


(EEAP) BOILER AND CHILLER STUDY

AT

FORT SAM HOUSTON

SAN ANTONIO, TEXAS

FINAL REPORT



**US Army Corps
of Engineers**

Fort Worth Division




CONDUCTED BY

HUITT-ZOLLARS, INC.

CONSULTING ENGINEERS

FORT WORTH, TEXAS



9/18/95

19971016 233



DEPARTMENT OF THE ARMY
CONSTRUCTION ENGINEERING RESEARCH LABORATORIES, CORPS OF ENGINEERS
P.O. BOX 9005
CHAMPAIGN, ILLINOIS 61826-9005

REPLY TO
ATTENTION OF: TR-I Library

17 Sep 1997

Based on SOW, these Energy Studies are unclassified/unlimited.
Distribution A. Approved for public release.



Marie Wakefield,
Librarian Engineering

TABLE OF CONTENTS

| | |
|---|----|
| ABBREVIATIONS | i |
| I. EXECUTIVE SUMMARY | 1 |
| A. Introduction | 1 |
| B. Buildings Studied | 1 |
| C. Present Energy Consumption | 2 |
| Base Year Energy Consumption | 2 |
| Boiler & Chiller Systems Energy Consumption | 2 |
| D. Energy Conservation Opportunity (ECO) Analysis | 3 |
| ECOs Rejected | 3 |
| ECOs Recommended | 3 |
| ECOs Not Recommended | 3 |
| ECIP Projects Developed | 3 |
| Non-ECIP Projects Developed | 3 |
| Recommended Maintenance & Operations Practices | 4 |
| E. Energy And Cost Savings | 5 |
| Total Potential Energy and Cost Savings | 5 |
| Energy Use and Costs Before and After | 5 |
| Percentage Saved | 5 |
| TABLE 1. ECOs Recommended | 6 |
| TABLE 2. ECOs Not Recommended | 6 |
| II. NARRATIVE REPORT | 7 |
| A. Entry Interview | 7 |
| Work Plan | 7 |
| Data List | 7 |
| ECO List | 7 |
| B. Data Collection | 8 |
| Building Data | 8 |
| Central Plant & HVAC Systems Data | 9 |
| Maintenance Data | 12 |
| Utility Data | 12 |
| Replacement Boiler Selection | 14 |
| Replacement Chiller Selection | 14 |
| C. Plan To Implement Projects: | 15 |
| Funding | 15 |
| Programming | 15 |
| Construction | 16 |
| Project DD-1391 Forms & Life Cycle Cost Analysis Summary Sheets | 17 |
| APPENDICES | |
| A. Energy Cost Analysis | |
| B. Computer Modeling of Boiler and Chiller Systems | |
| C. Data Forms | |
| D. Recommended ECO Calculations | |
| E. Non-Recommended ECO Calculations | |
| F. (EEAP) Boiler & Chiller Study - Scope Of Work & Review Comments | |
| G. Sample Products | |

I. EXECUTIVE SUMMARY

A. Introduction

This energy conservation study was performed by Huitt-Zollars Inc, for the U.S. Army Engineer District (USAED), Fort Worth, under contract number DACAC63-94-D-0015. The study was conducted at Fort Sam Houston (FSH) in San Antonio, Texas, between November 28, 1994 and June 15, 1995. The site survey, data collection and analysis was performed by John Carter, E.I.T, Tom Holthaus, P.E., Walter H. Williams III, P.E., and C.A. Pieper, P.E..

The purpose of the study was to perform a limited site survey of specific buildings at the facility, identify specific Energy Conservation Opportunities (ECOs) that exist, and then evaluate these ECOs for technical and economic feasibility. These ECOs were limited to central boiler and chiller plant systems serving specific building groups at FSH.

This survey was conducted with the assistance of many individuals at the FSH facility. Special thanks are extended to all of them, including the following individuals:

Gerardo De La Pena, Energy Coordinator
Frank Carbonell, Engineering Service
Gene Rodriguez, Engineering Service
Ray Mendoza, Engineering Service
Mike Brynes, Operations and Maintenance
Henry Guerra, Operations and Maintenance
Al Mote, Energy Program Specialist

Other individuals who assisted in this study by providing equipment and cost data are listed as follows:

Tom McGreal, York International, Dallas, TX
John Neal, Sr., Neal and Associates, Dallas, TX
Joe Scolaro and Brian Mitchell, Mitchell Technical Sales, Dallas, TX
Preston Dickson, Timberlake and Woffard, Inc., Dallas, TX
Larry Carpenter, The Trane Company, Fort Worth, TX
David Recca, DynaService, Fort Worth, TX

Any questions concerning this report should be directed to the Project Manager at Huitt-Zollars Inc., 512 Main Street, Suite 1500, Fort Worth, Texas 76102. Phone 817-335-3000.

B. Buildings Studied

This study was performed on five separate groups of buildings at the Fort Sam Houston installation in San Antonio, Tx. These groups were identified as areas 100, 900, 1300, 2200 and Quadrangle. Buildings in each of these areas are briefly described as follows:

- Area 100: These twenty buildings are currently used as office buildings, barracks, and other miscellaneous things such as a band rehearsal hall.
- Area 900: These buildings consisted of sixteen barracks, four smaller support buildings and one large administrative building, all occupied by army personnel.

Area 1300: The buildings in this group consisted of six barracks, one dining hall and one administrative office building.

Area 2200: The four buildings in this group consisted of three barracks and one administrative office building, which were all approximately 25 years old.

Quadrangle: The four buildings in this group are all administrative offices, one of which serves as the headquarters of the 5th Army.

C. Present Energy Consumption

Base Year Energy Consumption: The total metered electrical and gas consumptions for 12 consecutive months, prior to this study, were obtained from the facility and are referred to as the 'base year'. These data are shown on page 12 and are summarized as follows:

Figure 1. Base Year Energy Usage By Source

| ENERGY SOURCE | ANNUAL USAGE | | COST \$ |
|---------------|---------------|---------------|-----------|
| Electricity | 153,580 MWH | 524,169 MMBTU | 6,567,101 |
| Natural Gas | 51,415 MCF | 51,415 MMBTU | 192,985 |
| Total | 575,584 MMBTU | | 6,760,086 |

Boiler & Chiller Systems Energy Consumption: The annual energy consumption for the boiler & chiller systems studied was calculated in Appendix B, using the Trace 600 computer program to model the buildings and HVAC systems. This consumption amounted to a total of 11.1% of the base year energy usage and 7.4% of the energy costs. These system energy consumptions are given as follows:

Figure 2. Annual Boiler & Chiller Systems Energy Consumption

| AREA | COOLING SYSTEM DEMAND \$/YR | COOLING SYSTEM ELECT. KWH/YR | COOLING SYSTEM ELECT. \$/YR | HEATING SYSTEM DEMAND \$/YR | HEATING SYSTEM ELECT. KWH/YR | HEATING SYSTEM ELECT. \$/YR | HEATING SYSTEM GAS MCF/YR | HEATING SYSTEM GAS \$/YR |
|--|-----------------------------|------------------------------|-----------------------------|-----------------------------|------------------------------|-----------------------------|---------------------------|--------------------------|
| 100 | 46,621 | 1,687,278 | 35,433 | 1,269 | 89,804 | 1,886 | 1,927 | 5,126 |
| 900 | 13,242 | 621,339 | 13,048 | 1,000 | 88,213 | 1,852 | 7,809 | 20,771 |
| 1300 | 67,861 | 3,019,253 | 63,404 | 2,687 | 259,249 | 5,444 | 18,751 | 49,878 |
| 2200 | 36,390 | 1,609,767 | 33,805 | 797 | 51,536 | 1,082 | 4,949 | 13,163 |
| QUAD | 51,292 | 1,633,303 | 34,299 | 221 | 6,096 | 128 | 1,210 | 3,220 |
| SUBTOTALS | 215,405 | 8,570,940 | 179,990 | 5,973 | 494,898 | 10,393 | 34,646 | 92,158 |
| ANNUAL BOILER & CHILLER SYSTEM ENERGY | | | | 63,898 MMBTU/YR | | | | |
| ANNUAL BOILER & CHILLER SYSTEM COST, \$/YR | | | | 503,919 \$/YR | | | | |

D. Energy Conservation Opportunity (ECO) Analysis

ECOs Rejected: After reviewing the data collected at the facility and considering all of the practical limitations involved, there were no potential ECOs which were rejected prior to performing calculations. Therefore, energy savings calculations were performed for all ECOs identified in the scope of work.

ECOs Recommended: Certain ECOs which were identified during the building survey have been evaluated for technical and economic feasibility and are recommended for implementation. Complete documentation of all calculations as well as information required for implementation is included in Appendix D. These recommended ECOs are summarized in order of descending Savings to Investment Ratio (SIR) in Table 1 on page 6.

ECOs Not Recommended: Certain ECOs which were identified during the building survey have been evaluated for technical and economic feasibility but are not recommended for implementation. Complete documentation of all calculations are included in Appendix E. These non-recommended ECOs are summarized in order of order of descending SIR in Table 2 on page 6.

ECIP Projects Developed: The facility will submit three projects for ECIP funding, from the recommended ECOs shown in Table 1. The DD-1391 forms needed to request ECIP funding for each project are included in this report. These projects are listed below in order of descending SIR.

| ECIP Project | Description | Cost \$ | Payback yrs | SIR |
|--------------|---|---------|-------------|------|
| 1 | Chiller Retrofits, Areas 2200 & 900, Boiler Retrofit, Area 1300 | 558,058 | 7.7 | 2.27 |
| 2 | Chiller Retrofit, Area 1300 | 479,191 | 8.4 | 1.98 |
| 3 | New Central Chiller Plant, Area 100 | 556,559 | 8.6 | 1.73 |

Non-ECIP Projects Developed: The facility will also submit all ECOs individually as projects for non-ECIP funding. The DD-1391 forms needed to request non-ECIP funding for each project are included in this report. These projects are listed below in order of descending SIR.

| Non-ECIP Project | Description | Cost \$ | Payback yrs | SIR |
|------------------|-------------------------------------|---------|-------------|------|
| 1 | Chiller Retrofit, Area 2200 | 237,078 | 6.3 | 2.73 |
| 2 | Chiller Retrofit, Area 900 | 157,256 | 8.9 | 2.08 |
| 3 | Chiller Retrofit, Area 1300 | 479,191 | 8.4 | 1.98 |
| 4 | Boiler Retrofit, Area 1300 | 163,724 | 9.6 | 1.79 |
| 5 | New Central Chiller Plant, Area 100 | 556,559 | 8.6 | 1.73 |

Recommended Maintenance & Operations Practices: The following maintenance and operations (M&O) practices are recommended to help conserve boiler and chiller plant energy at FSH.

1. The Energy Coordinator and the FSH Director of Public Works should develop a master plan specification for all future central boiler and chiller plant maintenance and renovation projects. All facility project managers, as well as any central plant maintenance contractors should be required to follow this specification. The energy coordinator should review all new central boiler and chiller plant designs to check for compliance with the specifications.
2. The energy coordinator should attend training seminars for building energy.
3. The installation should increase the size of their current maintenance staff by adding trained HVAC technicians.
4. The installation should provide technical training for it's current HVAC staff, especially in the area of HVAC controls.
5. Revise the current HVAC preventative maintenance program as needed to improve the overall condition of the existing systems and equipment. The Energy Manager should be involved in this process to ensure that energy conservation concerns are addressed.
6. Add status, alarm, start and stop capabilities for all central boiler and chiller systems and auxiliaries to the post's existing building automation system. This will allow the maintenance staff to have better monitoring and control capabilities than they currently have.
7. Repair or replace all building HVAC control systems to improve space temperature control and conserve heating and cooling system energy.

E. Energy And Cost Savings

Total Potential Energy and Cost Savings. The energy and cost savings from the implementation of all ECIP projects was calculated as follows:

| | | |
|---------------------------|-----------|----------|
| Electrical Energy Savings | 8,690 | MMBTU/yr |
| Electrical Demand Savings | 49,884 | \$/yr |
| Gas Energy Savings | 4,020 | MMBTU/yr |
| Total Energy Savings | 12,710 | MMBTU/yr |
| Total Cost Savings | 193,496 | \$/yr |
| Total Investment | 1,593,808 | \$ |
| Simple Payback | 8.2 | yrs |

Energy Use and Costs Before and After. Based on the base year electrical and gas energy consumptions and costs shown on page 12, and the calculated total potential savings above, the FSH energy and usage and costs before and after implementation of the 3 Non-ECIP projects is as follows:

| | <u>Before</u> | <u>After</u> |
|------------|---------------|--------------|
| Electrical | 153,580 MWH | 151,033 MWH |
| Gas | 51,415 MCF | 47,395 MCF |
| Total Cost | 6,760,086 \$ | 6,566,590 \$ |

Percentage Saved. Based on the base year electrical and gas energy consumptions and costs, the percentage of savings from the 3 projects is as follows:

$$\text{Electrical Energy Saved} = \left[\frac{2,546 \text{ MWH}}{153,580 \text{ MWH}} \right] = 1.6\%$$

$$\text{Gas Energy Savings} = \left[\frac{4,020 \text{ MCF}}{51,415 \text{ MCF}} \right] = 7.8\%$$

$$\text{Energy Cost Savings} = \left[\frac{193,496 \$}{6,760,086 \$} \right] = 2.8\%$$

| TABLE 1. ENERGY CONSERVATION OPPORTUNITIES (ECOs) RECOMMENDED | | | | | | | | | | |
|---|--|---|--|--------------------------------------|--|-----------------------------------|---------------------------|--------------------------|------|--|
| ECO | Description | Electrical Energy Savings MMBTU/yr | Electrical Demand Savings \$/yr | Gas Energy Savings MMBTU/yr | Total Energy Savings MMBTU/yr | Total Cost Savings \$/yr | Total Investment \$ | Simple Payback Yrs | SIR | |
| E | AREA 2200 Replace Existing Chiller With New Centrifugal Chiller | 1,304 | 11,822 | 0 | 1,304 | 37,433 | 237,078 | 6.3 | 2.73 | |
| A | AREA 900 Replace Existing Central Chiller with Screw Chiller | 434 | 2,520 | 0 | 434 | 17,650 | 157,256 | 8.9 | 2.08 | |
| C | AREA 1300 Replace Existing Chillers With Centrifugal Chillers | 3,424 | 13,914 | 0 | 3,424 | 56,936 | 479,191 | 8.4 | 1.98 | |
| D | AREA 1300 Replace Existing Boilers With High % Modular Boilers | 712 | 1,847 | 4,020 | 4,732 | 17,012 | 163,724 | 9.6 | 1.79 | |
| I | AREA 100 Replace Individual Chillers With Central Chiller Plant | 2,816 | 19,781 | 0 | 2,816 | 64,465 | 556,559 | 8.6 | 1.73 | |
| | Totals | 8,690 | 49,884 | 4,020 | 12,710 | 193,496 | 1,593,808 | 8.2 | | |

| TABLE 2. ENERGY CONSERVATION OPPORTUNITIES (ECOs) NOT RECOMMENDED | | | | | | | | | | |
|---|---|---|--|--------------------------------------|--|-----------------------------------|---------------------------|--------------------------|------|--|
| ECO | Description | Electrical Energy Savings MMBTU/yr | Electrical Demand Savings \$/yr | Gas Energy Savings MMBTU/yr | Total Energy Savings MMBTU/yr | Total Cost Savings \$/yr | Total Investment \$ | Simple Payback Yrs | SIR | |
| B | AREA 900 Replace Existing Boilers With High % Modular Boilers | 0 | 0 | 1,235 | 1,235 | 3,285 | 50,591 | 15.4 | 1.21 | |
| G | QUADRANGLE AREA Replace Existing Chillers With Central Chiller Plant | 2,212 | 14,116 | 0 | 2,212 | 39,257 | 824,178 | 20.9 | 0.71 | |
| F | AREA 2200 Replace Existing Boilers With High % Modular Boilers | 38 | 378 | 910 | 948 | 3,037 | 78,553 | 25.8 | 0.69 | |
| J | AREA 100 Replace Existing Boilers With Central Boiler Plant | 186 | 680 | 680 | 866 | 11,483 | 273,951 | 23.8 | 0.66 | |
| H | QUADRANGLE AREA Replace Existing Boilers With Central Boiler Plant | -12 | 122 | -434 | -446 | 5,542 | 394,910 | 71.2 | 0.20 | |
| | Totals | 18,066 | 100,722 | 10,431 | 28,497 | 394,513 | 4,415,465 | 11.2 | | |

II. NARRATIVE REPORT

A. Entry Interview

Work Plan: An entry interview meeting was conducted at the Fort Sam Houston (FSH) facility on October 27, 1994. Present at the meeting were representatives of Huitt Zollars Inc. (HZ), Tom Holthaus, P.E., *Project Manager*, and Walter H. Williams III, P.E., *Mechanical Engineer*, as well as representatives from FSH, Gerardo De La Pena, *Energy Coordinator* and others. At that time, a description of the work plan for this study was presented. The work plan was a summary of the individual tasks to be performed to complete the boiler & chiller study and the approximate date that each task was to begin. Each step of the work plan was described in detail to the FSH staff. The work plan is shown in Figure 3.

Figure 3. Work Plan

| | |
|----------|---------------------------------------|
| 10/3/94 | Entry Interview |
| 10/3/94 | Building & Systems Data Collection |
| 10/10/95 | Formulate ECOs & Perform Calculations |
| 6/15/95 | Interim Findings Submittal |
| 9/18/95 | Pre-Final Report Submittal |
| 10/30/95 | Final Report Submittal |

Data List: After discussing the work plan, the FSH staff was presented a list of data items to be collected by the study team, shown in Figure 4. This list was a summary of the information required by the surveyors. The study team and FSH staff discussed the methods by which all of the data on the list were to be obtained. The data concerning the existing boiler and chiller systems were to be collected from the buildings and recorded onto preprinted data forms. Building mechanical drawings were to be collected, information extracted and included on individual building data forms. All data forms are included in Appendix C. The FSH personnel provided direction as to where to obtain information on the list. They also provided useful information on past energy conservation efforts, as well as any ongoing or future planned energy conservation measures. One such project underway is the installation of a base wide building automation system, to control primary and secondary HVAC equipment in many buildings on the post.

Figure 4. Data Acquisition List

1. Existing central boiler and chiller systems.
2. Existing auxiliary systems in central plants.
3. Building HVAC system types and operational hours.
4. Building size, age and remaining useful life.
5. Existing building operational schedules and area usage.
6. Facility electricity, gas, other utility rates.
7. Facility electricity, gas, other utility consumptions.
8. Utility company rebate programs.
9. Past boiler and chiller energy conservation projects.
10. Proposed boiler and chiller energy conservation projects.
11. Typical boiler and chiller maintenance procedures and costs.
12. Typical boiler and chiller retrofit procedures.

ECO List: Following the discussion on the data list, the FSH personnel were presented a list of specific Energy Conservation Opportunities (ECOs) that were identified for evaluation in the Detailed Scope of Work (see pages F-11 through F-15). This list is shown in Figure 5. The first ECO specified was the upgrade or replacement of existing central chillers with more efficient systems. The scope specifically called for the evaluation of electric centrifugal chillers, electric centrifugals with variable frequency drives, electric screw chillers and gas driven centrifugal chillers. All of these types were evaluated as a means of saving energy and maintenance costs in the existing central chiller plants of areas 900, 1300 and 2200. The second ECO specified was the upgrade or replacement of existing central boilers with

more efficient systems. Since no specific types were identified, the most efficient alternatives were selected and evaluated as a means of saving energy and maintenance costs in the existing central boiler plants of areas 900, 1300 and 2200. The third ECO specified was the installation of new central chiller plants to replace the existing individual building chillers in areas 100 and the Quadrangle. These new central plant evaluations were similar to a 1986 central plant design for area 100 which was never implemented. The fourth ECO specified was the installation of new central boiler plants to replace the existing individual building boilers in areas 100 and the Quadrangle. In all ECOs, the annual energy consumption of the boilers, chillers and auxiliary equipment were calculated by computer simulations using the Trane Trace 600 program. Building data were used to accurately model each building such that a realistic load profile was created for simulating boiler and chiller operational patterns. In all ECO calculations, the required capacity of the existing central heating and cooling equipment was evaluated from the computer simulations and recommendations for proper sizing were made.

Figure 5. Specific ECOs List

1. Chiller replacement or retrofit.
2. Boiler upgrade or replacement.
3. Install central chiller plants.
4. Install central boiler plants.

B. Data Collection

Following the entry interview, the study team began the task of collecting the required data. First, building mechanical plans were studied and data was extracted. Then field surveys were made on all of the buildings in the study to verify and supplement data collected from the drawings. All of the data obtained from drawings and field survey were put onto data sheets and included in Appendix C. The following summarizes the data collection phase of this study.

Building Data: This study was performed on five separate groups of buildings and required two separate site visits to collect data. These groups were identified as areas 100, 900, 1300, 2200 and Quadrangle. Buildings in each of these areas are described as follows:

1. Area 900 - This area included buildings 902, 904, 905, 906, 907, 908, 915, 916, 917, 919, 920, 921, 922, 924, 925, 926, 928, 929, 930, 931 and 932. A map of this area is included in Appendix C along with the data sheets for these buildings. The buildings in this group were constructed approximately 21 years ago and are mainly steel and concrete structures with brick veneer exteriors and flat built-up roofs. These buildings consisted of 16 barracks, four smaller support buildings and one large administrative building, all occupied by army personnel. All of the barracks were three story structures while the others were single story structures.
2. Area 1300 - This area included buildings 1350, 1374, 1375, 1377, 1379, 1380, 1382 and 1385. A map of this area is included in Appendix C along with the data sheets for these buildings. The buildings in this group consisted of six barracks, one dining hall and one administrative office building. All buildings are approximately 24 years old except for 1350, which is only 12 years old. These buildings were all occupied by army personnel. All of these buildings are mainly steel and concrete structures with brick veneer exteriors and flat built-up roofs. All of the barracks were multi-story structures while the others were single story structures.
3. Area 2200 - This area included buildings 2263, 2264, 2265 and 2266. A map of this area is included in Appendix C along with the data sheets for these buildings. The buildings in this group consisted of three barracks and one administrative office building, which were all approximately 25 years old. These buildings were all occupied by regular army personnel. All of these buildings are mainly masonry structures with stucco exteriors and pitched red clay tile roofs. All of the buildings were three story structures with both attic and basement spaces. One

of the barracks buildings has a dining hall, while another has a museum.

4. Quadrangle - This area included buildings 16, 44, 56 and 4015. A map of this area is included in Appendix C along with the data sheets for these buildings. The four buildings in this group are all administrative offices, one of which serves as the headquarters of the 5th Army. All but one are multi-story, with construction ranging from wood frame and siding with pitched shingle roofs to masonry structure, limestone exterior and pitched metal roof on the Headquarters building. These buildings are between 40 and 45 years old, and are considered historically significant.
5. Area 100 - This area included buildings 122, 124, 125, 127, 128, 132, 133, 134, 135, 142, 143, 144, 145, 146, 147, 149, 197, 198, 199 and 250. A map of this area is included in Appendix C along with the data sheets for these buildings. The buildings in this group were constructed approximately 50 to 55 years ago and are mainly wood framed structures with brick veneer exteriors and pitched shingle roofs. Most all of these buildings were two story structures that had basement and attic spaces. These buildings are currently used as office buildings, barracks, and other miscellaneous things such as a band rehearsal hall. These buildings are occupied by both army and civilian personnel.

Central Plant & HVAC Systems Data:

1. Area 900 - The buildings in this area are served by a central plant in building 902. The primary cooling system consists of a single 300 ton, centrifugal, water cooled chiller which is ten years old and uses R-11 refrigerant. A sixteen year old packaged, single cell crossflow cooling tower serves the chiller. Both the chiller and cooling tower appear to be in fair condition with many years of useful life remaining. The computer simulations of this area verified that the installed tonnage was both adequate and required to meet the building cooling loads.

Primary heating systems consist of three gas fired, water tube, HW boilers. The combined output capacity of these sixteen year old boilers is approximately 4,995 MBH, and they appeared to be in fair condition with a few years of useful life remaining. The computer simulations of this area identified that the installed capacity was approximately 2 ½ times what is required to adequately meet the building heating loads.

The individual chilled water (CHW) and condenser water (CND) pumps and multiple heating water (HW) pumps are located within the plant. These primary systems distribute thermal energy to the buildings through a four-pipe distribution loop. The domestic hot water (DHW) for the area is generated in the buildings through individual shell and tube heat exchangers in mechanical rooms, using HW from the boilers. A single DHW circulation pump for buildings distributes the DHW to the plumbing fixtures. This design requires a boiler to operate year round to produce DHW. The other buildings have individual gas fired water heaters.

Secondary HVAC systems in these buildings consist of two pipe fan coil units (FCUs) in the barracks, while multizone (MZ) and single zone (SZ) air handling units are located within the support and administrative buildings. Each pair of barracks buildings has a secondary pump to circulate HW or CHW from the central loop to all the FCUs. Overall HVAC system performance in this area is poor due in part to faulty or inadequate system controls, making space temperatures difficult to maintain. Also, the two-pipe distribution loops in the buildings and the four-pipe distribution loop from the central plant to the buildings are in poor condition with corrosion, leaks and missing or unserviceable insulation.

2. Area 1300 - The buildings in this area are served by a central plant in the dining hall building 1377. The primary cooling systems consist of two centrifugal water cooled chillers, rated at a combined 1200 tons, which are 23 years old and use R-11 refrigerant. These two chillers are piped in series and serve all of the buildings except for 1350. This newer building is served by a single 438 ton, water cooled centrifugal chiller that is 12 years old and uses R-11 refrigerant. A twelve year old, single cell cooling tower serves this chiller while a 23 year old, two cell tower serves the other two chillers. The older chillers and tower appeared to be in poor condition and nearing the end of useful life. The newer chiller and tower were in fair condition with some years of useful life remaining. The computer simulations of this area identified that the installed capacity of 1,424 tons was around 14% higher than what is required to meet the building cooling loads.

The primary heating systems consisted of two firetube, HW boilers which are 23 years old and have a combined output capacity of 11,824 MBH. These two boilers serve all of the buildings except for 1350. This building is served by two watertube, HW boilers which are 12 years old and have a combined output capacity of 9,653 MBH. The older boilers appeared to be in poor condition and are near the end of their useful life. The newest boiler was in fair condition with some years of useful life remaining. The computer simulations of this area identified that the installed capacity of 21,477 MBH was approximately 3 times what is required to adequately meet the building heating loads.

The three CHW pumps, three CND pumps and three HW pumps are located within the plant in building 1377. These primary systems distribute thermal energy to the buildings through two four-pipe distribution loops, which appeared to be in good condition. One loop is for building 1350 and the other is for all other buildings in the area. DHW is generated by individual gas fired water heaters in each building.

Secondary HVAC systems in these buildings consist of some two pipe FCUs and SZ air handlers, and many four pipe MZ air handling units located within the buildings. Each building has secondary CHW and HW pumps to circulate water from the central loops to all the FCUs and air handlers. Overall HVAC system performance in this area is poor due in part to faulty or inadequate controls, making space temperatures difficult to maintain.

3. Area 2200 - The buildings in this area are served by a central CHW plant in the basement of building 2265. The primary cooling system consists of a single 650 ton centrifugal, water cooled chiller, which is 22 years old and uses R-11 refrigerant. A 23 year old, single cell, built-up cooling tower is outside to serve the chiller. The chiller and tower appear to be in poor condition and nearing the end of useful service. The computer simulations of this area identified that the installed capacity was around 18% higher than what is required to meet the building cooling loads.

The primary heating systems consist of three watertube, HW boilers which are seven years old and have a combined rated capacity of 6,720 MBH. These boilers are all located in a separate mechanical building behind 2265 and appeared to be in good condition with many years of useful life remaining. The computer simulations of this area identified that the installed capacity was approximately 2 ½ times what is required to adequately meet the building heating loads.

A single CHW pump, CND pump and three HW pumps are located within the plants. These primary systems distribute thermal energy to the 2200 area buildings through a four-pipe distribution loop which appears to be in good condition. DHW is generated by individual gas fired water heaters in each building.

Secondary HVAC systems in these buildings consist of SZ and MZ air handlers located within the buildings. Each building has secondary CHW and HW pumps to circulate water from the central loop to all the FCUs and air handlers. Overall HVAC system performance in this area is poor due in part to faulty or inadequate controls, making space temperatures difficult to maintain.

4. Quadrangle - The buildings in this area have no central boiler or chiller plant. All buildings have stand alone primary heating and cooling systems. The primary cooling systems consisted of one 12 year old, air cooled, reciprocating chiller, rated at 50 tons and serving building 4015. This chiller appears to be in fair condition with at least 10 years of useful life remaining. Another two year old, air cooled, reciprocating chiller, rated at 30 tons serves building 56. This chiller appears to be in good condition with many years of useful life remaining. Building 16 is served by two air cooled, reciprocating chillers. One is only a year old and is rated at 120 tons. The other is eight years old and is rated at 110 tons. Both of these chillers appeared to be in good condition with many years of useful life remaining. Finally, building 44 is served by three chillers which are 10 years old and rated at a combined 225 tons. All three of these chillers appeared to be in good condition with many years of useful life remaining. All of these chillers operate on the R-22 refrigerant. The computer simulations of this area verified that the installed capacity of 565 tons was both adequate and required to meet the building cooling loads. However in some areas, especially in building 44, temperature control problems are apparent.

The primary heating systems consist of an eight year old, firetube HW boiler, with an output rating of 741 MBH, serving building 4015. This boiler appeared to be in good condition with many years of useful life remaining. Building 16 has two watertube, steam boilers which are 16 years old. One is rated at 1,614 MBH output and serves approximately half of the building. The other is rated at 3,587 MBH output and serves the other half of building 16 as well as all of building 56. These two boilers appeared to be in fair condition with some useful life remaining. Building 44 has 12 modular steam boilers which are 25 years old and have a combined output of 3,028 MBH. These boilers appeared to be in poor condition and are at the end of their useful life. The computer simulations of this area identified that the installed capacity was approximately 2 ½ times what is required to adequately meet the building heating loads.

The CHW pumps for all the chillers in the Quadrangle area are located within the buildings they serve. A single HW pump is located within building 4015 to circulate water through the buildings secondary systems. All other buildings have steam and condensate return piping from the boilers to all secondary systems. DHW is generated by individual gas fired water heaters in each building.

Secondary HVAC systems in the Quadrangle area buildings consist of dual duct, MZ and SZ air handling units as well as FCUs located in some areas of the buildings. These units all have steam coils for heat, except for those in building 4015, which have hot water coils. Some areas of building 16 and building 44 are cooled by direct expansion (DX) terminal units, with small cooling towers outside for condensers. Overall HVAC system performance in this area is poor due in part to faulty or inadequate controls, making space temperatures difficult to maintain. Because of the historical significance of this area, there is little space for a central plant. However, one could be located nearby with a historically correct wall built around it to hide the equipment.

5. Area 100 - The buildings in this area have no central boiler or chiller plant. All buildings have stand alone primary heating and cooling systems. The primary cooling systems consist of 14

air cooled, reciprocating chillers, which are all ten years old and have a combined capacity of 540 tons. All chillers appeared to be in good condition with many years of useful life remaining. The computer simulations of this area identified that the installed capacity of 540 tons was around 28% higher than what is required to meet the building cooling loads.

The primary heating systems consisted of 14 watertube, HW boilers, which are all ten years old and have a combined capacity of 8,829 MBH. All boilers appeared to be in good condition with many years of useful life remaining. The computer simulations of this area identified that the installed capacity was approximately 4 ½ times what is required to adequately meet the building heating loads.

CHW and HW pumps are generally located within the buildings that they serve. DHW is generated by individual gas fired water heaters in each basement.

Secondary HVAC systems in these buildings consist of MZ and SZ air handling units located within the buildings. However, one building has window A/C units, a gas fired warm air furnace, and no boiler or chiller. Overall HVAC system performance in this area is poor due in part to faulty or inadequate controls, making space temperatures difficult to maintain.

Maintenance Data: Most HVAC system maintenance is performed by post civil service personnel, who maintain the central plants as well as building systems. In general, post maintenance is inadequate due to cutbacks in manpower, in conjunction with the addition of new buildings to maintain. For instance, some HVAC air filters appeared to be excessively dirty, and leaks were found in the HW coil of one air handler during data collection. Also, HVAC system controls appeared to be inoperable or missing, adding to the inability of the systems to maintain temperatures within the building spaces. Repair or replacement of these controls could save heating and cooling energy, but is beyond the scope of this study. In some buildings the outside air intakes to air handlers were blocked off with sheet metal. The existing preventative maintenance program is less effective than could be desired.


Utility Data: A 12 month utility billing history was obtained from the energy coordinator which covered the period from August, 1993 through July, 1994. This history included all of the metered electric consumption for the installation and gas consumption for only the FSH areas included in this study. This history is shown in Figure 6. The total cost of electricity for the base year was \$6.5 million and the total cost for gas was \$0.19 million.

Figure 6. 1993-94 Base Year Utility Data

| Billing Period | Electrical | | | Natural Gas | |
|----------------|------------|-----------------|-----------|-----------------|----------|
| | Demand KW | Consumption MWH | Cost \$ | Consumption MCF | Cost \$ |
| AUG | 30,576 | 16,464 | 785,463 | 1,826.4 | 7,880.0 |
| SEPT | 31,024 | 16,856 | 795,130 | 1,750.2 | 7,161.0 |
| OCT | 30,240 | 14,084 | 706,204 | 1,679.9 | 6,508.0 |
| NOV | 27,496 | 9,548 | 464,806 | 6,988.7 | 23,429.0 |
| DEC | 24,819 | 10,136 | 464,187 | 5,423.0 | 20,105.0 |
| JAN | 24,819 | 9,044 | 379,870 | 10,451.3 | 37,106.0 |
| FEB | 24,819 | 9,268 | 391,687 | 9,341.3 | 33,138.0 |
| MAR | 24,819 | 9,968 | 459,976 | 6,816.0 | 26,047.0 |
| APR | 24,819 | 10,416 | 376,714 | 2,177.0 | 9,736.0 |
| MAY | 27,160 | 13,216 | 447,478 | 1,750.6 | 7,774.0 |
| JUN | 31,752 | 16,716 | 620,912 | 1,519.0 | 6,600.0 |
| JUL | 32,872 | 17,864 | 674,674 | 1,691.1 | 7,501.0 |
| Total | 335,215 | 153,580 | 6,567,101 | 51,414.5 | 192,985 |


Charts of the base year energy usages were plotted and are shown in Figures 7 and 8. These charts give a visual representation of the installation's energy usage patterns for the year. Looking at Figure 7, it can be seen that the electrical usage never falls below 9,000 MWH per month. This is considered a 'baseline' of electrical energy use. It can be assumed that all energy usage above this baseline is consumed by cooling systems, based on the peaks and the months in which they occur.

Figure 7. Base Year Electrical Usage Profile



Similar observations can be made about gas energy usage, shown in Figure 8. The baseline usage here is around 1,800 MCF of gas per month. Since gas is the primary source of heating at FSH, the obvious peak during the winter months can be considered heating energy. Therefore, all gas energy usage below the baseline is used for DHW and cooking equipment. This is a large amount of energy usage and should be considered a large target for potential energy savings.

Figure 8. Base Year Gas Usage Profile



Based on the current gas and electric utility rates from the City Public Service (CPS) of San Antonio, the current avoided costs for electrical savings are \$0.021 per KWH, and \$7.50 to \$10.00 per KW demand savings, depending upon the time of year. For natural gas savings in area 100 only, the avoided cost is \$4.39 per MCF. For all other areas, the avoided cost of gas savings is \$2.66 per MCF. There are currently no rebates available from the CPS for boiler or chiller energy conservation projects.

Replacement Boiler Selection: Data on available replacement boilers were obtained from typical manufacturers in order to select representative boilers for ECO evaluations. This data included performance characteristics, physical dimensions and cost figures. The criteria for selecting new boiler systems for the ECOs are described below.

1. Efficiency. Replacement boilers that had the highest overall efficiency over the operating range were selected in each area. In most cases, this criteria was met by the high-efficiency modular boilers which were modeled in the ECOs. These are fully condensing, forced draft firetube units that have efficiencies in the 90s over the entire range of operation. No other boiler type was found to match this performance.
2. Turn-down ratio. In order to limit the thermal shock and efficiency losses associated with cycling, replacement boilers for the ECOs needed to have a high turn-down ratio. The 14:1 ratio associated with the modular boilers used in most ECOs was as good or better than other available boilers with lower efficiencies. And the modular concept of using multiple boilers to match the heating loads, combined with this high turn-down ratio, minimizes the negative impacts of cycling.
3. Controls. In order to closely match the heating load requirements at any given time, all new boilers were selected with fully modulating controls. Two-position or multi-stage controls would increase the possibility of boiler cycling, as well as reduce the part load efficiency.
4. Physical size. In order to fit the new boilers into the buildings without modifying the existing boiler room openings, the small footprint and overall size of the modular boilers was the best choice for the ECOs. Other types of boilers were larger and would require more effort and cost to install in the buildings. This criteria was not a factor in areas 100 and the Quadrangle, where completely new central boiler plants were being considered.
5. First cost. The first cost of the modular boilers was greater than other types available. However, the efficiency improvements of these units justified the higher initial first costs in the Life Cycle Cost Analysis. In areas 100 and the Quadrangle, the first cost of the boilers selected was equivalent to or lower than most of the other boiler types available for the ECOs.
6. Maintenance requirements and costs. All types of replacement boilers would require annual cleaning of the heat exchanger surfaces, as well as optimization of the combustion systems. The boilers used in the ECOs appeared to be as good or better than all other boiler types in ease of maintenance. This is due to their small physical size and construction features. Maintenance cost estimates obtained from the local contractor were independent of boiler type. Therefore, all new boiler types available were assumed to be approximately equal in the area of maintenance costs.

Replacement Chiller Selection: Data on available replacement chillers were obtained from typical manufacturers in order to select representative chillers for ECO evaluations. This data included performance characteristics, physical dimensions and cost figures. The criteria for selecting new chiller systems for the ECOs are described below.

1. Manufacturer. The facility maintenance personnel requested that York chillers be used in this study as they preferred them to other manufacturer's products. Therefore, most new chillers used for analysis in the ECOs were made by York. In areas 100 and the Quadrangle, McQuay chillers were selected for reasons mentioned in the following text.

2. Machine Type. The scope of work generally identified the specific types of chillers to be compared in each area. These were the centrifugal, centrifugal with variable speed drive, screw and gas-engine driven centrifugal. Therefore, all four of these chiller types were compared in each ECO to determine the most economically beneficial retrofit for each area. In areas 100 and the Quadrangle, where new central plants were under consideration, only packaged air-cooled type chillers were considered. This was done to minimize the implementation costs in these areas.
3. Drive configuration. The new machines selected for ECO analysis all had open drives on the compressors. This increases the first cost somewhat, but decreases the long term maintenance costs.
4. Refrigerant. Replacement chillers were to all use either R-123 or R-134 refrigerant, as per the scope of work. This requirement was met in the study.
5. Efficiency. The full and part load efficiencies for all machines selected for evaluation were used in the ECOs. The relative effects of these efficiency differences are illustrated in the Life Cycle Cost Analysis of each machine. In areas 100 and the Quadrangle, the most efficient type of air cooled packaged chiller found was the single-screw unit from McQuay. Therefore, this machine was used in the ECO evaluations.
6. First cost. The first cost data for all machines selected for evaluation were used in the ECOs. The relative effects of these cost differences are illustrated in the Life Cycle Cost Analysis of each machine.
7. Maintenance requirements and costs. All types of replacement chillers would require periodic cleaning of the heat exchanger surfaces, as well as optimization of the compressor systems and controls. Maintenance cost estimates obtained from the local contractor were independent of chiller type. Therefore, all new chiller types available were assumed to be approximately equal in the area of maintenance costs.

C. Plan To Implement Projects:

The analysis of all potential boiler & chiller ECOs at the facility has been completed and the grouping of individual ECOs into projects has been determined. These were detailed previously in the Executive Summary. Below is an abbreviated plan for implementation of the recommended projects.

Funding: The forms DD-1391 and life cycle cost analysis summary sheets for all three ECIP projects are provided on pages 17 to 27. These are to be submitted for project funding, along with the savings calculations and cost estimates in Appendix D. Check for the latest ECIP project documentation requirements prior to submitting these forms. The forms DD-1391 and life cycle cost analysis summary sheets for all five Non-ECIP projects are provided on pages 28 to 42. These are to be submitted for project funding, along with the savings calculations and cost estimates in Appendix D if required. Check for the particular project documentation requirements prior to submitting these forms.

Programming: An engineering design firm should be selected to produce construction contract drawings and specifications for all of the projects which are funded either through ECIP or by other means. All of the savings calculations and cost estimates for the recommended ECOs in Appendix D should be supplied to the designers in order to inform them of the intent and projected budget of each ECO. The designers should use the equipment sizing described in the ECOs as a guide only, and perform all calculations necessary to properly size all new equipment. These calculations should take into consideration all existing field conditions in the areas effected by the ECOs. It is recommended that

existing auxiliary equipment be reused wherever possible to reduce the first cost of each project. The designer should field verify the condition of all existing equipment before specifying its disposition. In the case of boiler retrofits, the designer should consider keeping some of the existing boilers in place to be as backups. Where equipment is to be removed, the specifications should include some provisions dealing with the possible salvage value of this equipment. The facility's project manager should ensure that all new central plant designs produced by the design firm do conform with the intent of each ECO, in order to realize the estimated savings. All construction drawings and specifications should be compared to the original ECOs to ensure compliance, prior to releasing for bids.

Construction: Once the plans and specifications have been reviewed and approved, the facility's project manager should release them for bids, using their normal construction procurement proceedings. Care should be taken to schedule all work at a time which would minimize the negative impact of projects on the buildings served by the central plant equipment. Prior to construction, the facility should review all shop drawings and Submittals to once again ensure compliance with the original intent of each ECO.

| | | | | | | |
|---|--|--|--|--------------------------|--------------------|----------------------------------|
| 1. COMPONENT ARMY | | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | | | 2. DATE 8/24/95 | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | 4. PROJECT TITLE ECIP | | |
| 5. PROGRAM ELEMENT | | 6. CATEGORY CODE | | 7. PROJECT NUMBER | | 8. PROJECT COST (\$000) 558.0 |
| 9. COST ESTIMATES | | | | | | |
| ITEM | | | | U/M | QUANTITY | COST (\$000) |
| Replace existing chiller with new centrifugal chiller in building 2265. | | | | EA | 1 | 237.0 |
| Replace existing chiller with new screw chiller in building 902. | | | | EA | 1 | 157.0 |
| Replace existing boilers with new high efficiency modular boilers in Area building 1377. | | | | EA | 1 | 164.0 |
| ESTIMATED CONTRACT COST | | | | | | 500.501 |
| CONTINGENCY (0%) | | | | | | 0.0 |
| SIOH | | | | | | 27.527 |
| DESIGN | | | | | | 30.030 |
| TOTAL REQUEST | | | | | | 558.058 |
| TOTAL REQUEST (ROUNDED) | | | | | | 558.000 |
| 10. DESCRIPTION OF PROPOSED CONSTRUCTION | | | | | | |
| <p><u>AREA 2200:</u></p> <p>Remove the existing 675 ton, R-11 centrifugal chiller in building 2265 and replace it with a 555 ton, R-134a centrifugal chiller. The existing 100 HP chilled water (CHW) pump, 50 HP condenser water (CND) pump and 40 HP cooling tower will be reused. The new chiller should be connected into the distribution piping at the existing chiller location. All existing controls and electrical services should be reconnected where possible. Specific requirements in all areas should be determined by the design engineer responsible for this project. To meet the current ASHRAE Standard 15, a refrigerant detection and ventilation system should be installed. This project will require engineering drawings and specifications, demolition and removal of the existing chiller and installation of the new chiller, associated wiring and controls.</p> <p><u>AREA 900:</u></p> <p>Remove the existing 300 ton, R-11 centrifugal chiller in building 902 and replace it with a 300 ton, R-134a screw chiller. The existing 25 HP chilled water (CHW) pump, 15 HP condenser water (CND) pump and 15 HP cooling tower will be reused. The new chiller should be connected into the distribution piping at the existing chiller location. All existing controls and electrical services should be reconnected where possible. Specific requirements in all areas should be determined by the design engineer responsible for this project. To meet</p> | | | | | | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|--|--------------------|---------------------------|-------|----------|---------------------------|--------|-------|--------------------|-------|----------|----------------------|-------|----------|--------------------|--------|-------|------------------|---------|----|----------------|-----|-----|-----|------|--|
| 1. COMPONENT ARMY | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | 2. DATE 8/24/95 | | | | | | | | | | | | | | | | | | | | | | | | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4. PROJECT TITLE ECIP | | 5. PROJECT NUMBER | | | | | | | | | | | | | | | | | | | | | | | | |
| 11. REQUIREMENT <p>the current ASHRAE Standard 15, a refrigerant detection and ventilation system should be installed. This project will require engineering drawings and specifications, demolition and removal of the existing chiller and installation of the new chiller, associated wiring and controls.</p> <p><u>AREA 1300:</u></p> <p>Remove the two existing watertube boilers and single 40 HP heating water (HW) distribution pump in building 1377, which are serving building 1350. Also remove the two existing firetube boilers and the two 15 HP distribution pumps in building 1377 which serve buildings 1374, 1375, 1379, 1380, 1382, 1377 and 1385. Connect the two separate distribution loops together in building 1377 with new HW supply and return headers to make a single HW distribution system. Install four new modular high efficiency boilers, rated at 1,830 MBH output each and four new 7 1/2 HP distribution pumps to serve this single system. The existing electrical service and controls should be reused as much as possible. Specific requirements in all areas should be determined by the design engineer responsible for this project. The boilers and pumps should be sequenced to operate only as needed to maintain the supply water temperature setpoint of approximately 180 F. This project will require engineering drawings and specifications, demolition and removal of the existing boilers and pumps, and installation of the new boilers, pumps, associated wiring and controls.</p> <p>ENERGY SAVINGS</p> <p>This project is required to reduce the cooling energy consumption in the 2200 and 900 area central plants, and the heating energy consumption in the 1300 area central plant. The project provides new, more efficient primary cooling and heating systems, which will save cooling and heating energy and cost. Additionally, this project will help protect the environment by replacing equipment which uses an ozone depleting refrigerant. All buildings included in this project will be active throughout the payback period. Installation of this new primary equipment will result in the following:</p> <table style="margin-left: auto; margin-right: auto;"> <tbody> <tr> <td>Electrical Energy Savings</td> <td style="text-align: right;">2,450</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Electrical Demand Savings</td> <td style="text-align: right;">16,189</td> <td style="text-align: right;">\$/yr</td> </tr> <tr> <td>Gas Energy Savings</td> <td style="text-align: right;">4,020</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Total Energy Savings</td> <td style="text-align: right;">6,470</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Total Cost Savings</td> <td style="text-align: right;">72,094</td> <td style="text-align: right;">\$/yr</td> </tr> <tr> <td>Total Investment</td> <td style="text-align: right;">558,058</td> <td style="text-align: right;">\$</td> </tr> <tr> <td>Simple Payback</td> <td style="text-align: right;">7.7</td> <td style="text-align: right;">yrs</td> </tr> <tr> <td>SIR</td> <td style="text-align: right;">2.27</td> <td></td> </tr> </tbody> </table> | | | Electrical Energy Savings | 2,450 | MMBTU/yr | Electrical Demand Savings | 16,189 | \$/yr | Gas Energy Savings | 4,020 | MMBTU/yr | Total Energy Savings | 6,470 | MMBTU/yr | Total Cost Savings | 72,094 | \$/yr | Total Investment | 558,058 | \$ | Simple Payback | 7.7 | yrs | SIR | 2.27 | |
| Electrical Energy Savings | 2,450 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Electrical Demand Savings | 16,189 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Gas Energy Savings | 4,020 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Energy Savings | 6,470 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Cost Savings | 72,094 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Investment | 558,058 | \$ | | | | | | | | | | | | | | | | | | | | | | | | |
| Simple Payback | 7.7 | yrs | | | | | | | | | | | | | | | | | | | | | | | | |
| SIR | 2.27 | | | | | | | | | | | | | | | | | | | | | | | | | |

| | | |
|--|--|--------------------|
| 1. COMPONENT ARMY | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | 2. DATE 8/24/95 |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | |
| 4. PROJECT TITLE ECIP | 5. PROJECT NUMBER | |
| <p>11. REQUIREMENT</p> <p>CURRENT SITUATION:</p> <p>AREA 2200:</p> <p>The existing water cooled, centrifugal chiller was installed in 1973 and serves as the primary cooling system for the four large buildings in the 2200 area. It appears to be in fair condition but uses the R-11 refrigerant, which will no longer be manufactured as of January 1, 1996. To avoid the anticipated increasing operational costs over the life of this machine, it should either be retrofitted to use an approved refrigerant or replaced with a new machine that operates on one. The existing centrifugal machine can be retrofitted with no loss of capacity by replacing the impeller with one designed for HCFC-123 refrigerant. A company which produces these new impellers for existing R-11 centrifugal machines has provided cost estimates. However, since the machine is already 22 years old, it is recommended that the facility replace it instead. A life cycle cost analysis performed on four different types of replacement chillers available determined that an electric centrifugal chiller using R-134a would be the most economical choice over the life of the new machine. Computer simulations of the buildings served by this machine determined that the current installed capacity of 657 tons is more than what is required to adequately cool the buildings. Therefore, the new chiller should only be sized for 555 tons to more closely match the cooling load of the four buildings.</p> <p>AREA 900:</p> <p>The existing water cooled, centrifugal chiller was installed in 1985 and serves as the primary cooling system for the 21 buildings in the 900 area. It appears to be in fair condition but uses the R-11 refrigerant, which will no longer be manufactured as of January 1, 1996. To avoid the anticipated increasing operational costs over the life of this machine, it should either be retrofitted to use an approved refrigerant or replaced with a new machine that operates on one. The existing centrifugal machine can be retrofitted with no loss of capacity by replacing the impeller with one designed for HCFC-123 refrigerant. A company which produces these new impellers for existing R-11 centrifugal machines has provided cost estimates. However, since the machine is already ten years old, it is recommended that the facility replace it instead. A life cycle cost analysis performed on four different types of replacement chillers available determined that a dual screw chiller using R-134a would be the most economical choice over the life of the new machine. Computer simulations of the buildings served by this machine determined that the current installed capacity of 300 tons is required to adequately cool the buildings. Therefore, no increase or decrease in the current chiller capacity is recommended at this time.</p> <p>AREA 1300:</p> <p>The two existing watertube boilers serving building 1350 were installed in 1983 and are rated at 5,317 MBH and 4,336 MBH output capacity. The single 40 HP pump circulates HW from these boilers through building 1350. The two existing firetube boilers serving the other buildings in the 1300 area were installed in 1972 and are rated at 5,912 MBH output capacity each. Two 15 HP pumps circulate HW from these boilers to the seven other buildings listed above. All these boilers appear to be in fair condition. Computer simulations of the eight buildings served by these boilers determined that the current combined capacity of 21,477 MBH is about three times the amount required to adequately heat the buildings. The existing boilers are therefore</p> | | |

| | | |
|--|--|--------------------|
| 1. COMPONENT ARMY | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | 2. DATE 8/24/95 |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | |
| 4. PROJECT TITLE ECIP | | 5. PROJECT NUMBER |
| 11. REQUIREMENT operating at an inefficient, low load condition most of the time. Also, because of the constant flow rate requirements of the large boilers, excessive pumping energy is expended. By combining the two distribution systems together and staging four new high efficiency modular boilers to operate only as needed, a substantial energy savings can be realized. Also, a decrease in the combined boiler output capacity to 7,320 MBH is recommended to more closely match the heating load in the eight buildings and reduce the associated pumping energy consumption. IMPACT IF NOT PROVIDED If this project is not provided, the above mentioned savings in cooling and heating energy and cost will continue to be wasted. There will be no contribution to the energy reduction goals established at the facility. | | |

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECIP-3

ANALYSIS DATE: 08-24-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|----|------------|
| A. CONSTRUCTION COST | \$ | 500501. | | |
| B. SIOH | \$ | 27527. | | |
| C. DESIGN COST | \$ | 30030. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 558058. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | | | | \$ 558058. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 2450. | \$ 15386. | 15.08 | \$ 232021. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 4020. | \$ 10693. | 18.58 | \$ 198680. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 16189. | 14.88 | \$ 240892. |
| N. TOTAL | | 6470. | \$ 42268. | | \$ 671593. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|----|
| A. ANNUAL RECURRING (+/-) | | \$ | 0. |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|--------------------|------------------------------|-----------------|------------------------|--|
| 1. REFRIG. UPGRADE | \$ 596520. | 0 | 1.00 | 596520. |
| d. TOTAL | \$ 596520. | | | 596520. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 596520.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 72094.

5. SIMPLE PAYBACK PERIOD (1G/4) 7.74 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 1268113.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 2.27
(IF < 1 PROJECT DOES NOT QUALIFY)

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): 7.32 %

| | | | | | | |
|--|--|--|--|--------------------------|--------------------|----------------------------------|
| 1. COMPONENT ARMY | | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | | | 2. DATE 8/24/95 | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | 4. PROJECT TITLE ECIP | | |
| 5. PROGRAM ELEMENT | | 6. CATAGORY CODE | | 7. PROJECT NUMBER | | 8. PROJECT COST (\$000) 479.0 |
| 9. COST ESTIMATES | | | | | | |
| ITEM | | | | U/M | QUANTITY | COST (\$000) |
| Replace two (2) existing chillers in building 1377 with one (1) new chiller. | | | | EA | 1 | 479.0 |
| ESTIMATED CONTRACT COST | | | | | | 429.768 |
| CONTINGENCY (0%) | | | | | | 0.0 |
| SIOH | | | | | | 23.673 |
| DESIGN | | | | | | 25.786 |
| TOTAL REQUEST | | | | | | 479.191 |
| TOTAL REQUEST (ROUNDED) | | | | | | 479.000 |
| 10. DESCRIPTION OF PROPOSED CONSTRUCTION | | | | | | |
| <p>Remove the two 600 ton, R-11 centrifugal chillers in building 1377 which were installed in 1972, and replace them with one R-134 centrifugal chiller, rated at 827 tons. The two existing chilled water pumps and condenser water pumps serving the existing chillers should be removed. Install a new chilled water pump and a new condenser water pump, each rated at 75 HP, to serve the new chiller. The new chiller should be connected into the distribution piping at the existing location. New chilled water supply and return headers should be installed to join together the existing distribution systems serving building 1350 and the other seven buildings in the 1300 area. This will create a single chilled water distribution system to be served by the new chiller and the existing 438 ton chiller which was installed in 1983 to serve building 1350. All existing controls and electrical services should be reconnected where possible. Specific requirements in all areas should be determined by the design engineer responsible for this project. To meet the current ASHRAE Standard 15, a refrigerant detection and ventilation system should be installed. This project will require engineering drawings and specifications, demolition and removal of the existing chillers and pumps, and installation of the new chillers, pumps, associated wiring and controls.</p> | | | | | | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|--|--------------------|---------------------------|-------|----------|---------------------------|--------|-------|--------------------|---|----------|----------------------|-------|----------|--------------------|--------|-------|------------------|---------|----|----------------|-----|-----|-----|------|--|
| 1. COMPONENT ARMY | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | 2. DATE 8/24/95 | | | | | | | | | | | | | | | | | | | | | | | | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4. PROJECT TITLE ECIP | | 5. PROJECT NUMBER | | | | | | | | | | | | | | | | | | | | | | | | |
| 11. REQUIREMENT <p>This project is required to reduce the cooling energy consumption in the 1300 Area central plant, building 1377. The project provides a new, more efficient primary cooling system, which will save cooling energy and cost. Additionally, this project will help protect the environment by replacing equipment which uses an ozone depleting refrigerant. All buildings included in this project will be active throughout the payback period. Installation of this cooling equipment will result in the following:</p> <table style="margin-left: auto; margin-right: auto;"> <tbody> <tr> <td>Electrical Energy Savings</td> <td style="text-align: right;">3,424</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Electrical Demand Savings</td> <td style="text-align: right;">13,914</td> <td style="text-align: right;">\$/yr</td> </tr> <tr> <td>Gas Energy Savings</td> <td style="text-align: right;">0</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Total Energy Savings</td> <td style="text-align: right;">3,424</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Total Cost Savings</td> <td style="text-align: right;">56,936</td> <td style="text-align: right;">\$/yr</td> </tr> <tr> <td>Total Investment</td> <td style="text-align: right;">479,191</td> <td style="text-align: right;">\$</td> </tr> <tr> <td>Simple Payback</td> <td style="text-align: right;">8.4</td> <td style="text-align: right;">yrs</td> </tr> <tr> <td>SIR</td> <td style="text-align: right;">1.98</td> <td></td> </tr> </tbody> </table> <p>CURRENT SITUATION:</p> <p>There are currently two independent chilled water distribution systems serving the 1300 area, one for building 1350 and the other for seven other buildings. These two systems should be combined into one system to conserve energy in the central plant. This can be accomplished by installing common CHW supply and return headers in the central plant. The existing centrifugal chiller serving building 1350 was installed in 1983, is rated at 438 tons and appears to be in good condition. The two existing centrifugal chillers serving the other seven buildings were installed in 1972, are rated at 600 tons each, and appear to be near the end of their useful life. Also, all three chillers use the R-11 refrigerant, which will no longer be manufactured as of January 1, 1996. To avoid the anticipated increasing operational costs over the life of these machines, they should either be retrofitted to use an approved refrigerant or replaced with new machines that operate on one. The existing centrifugal machines can be retrofitted with no loss of capacity by replacing the impellers with new ones designed for HCFC-123 refrigerant. A company which produces these new impellers for existing R-11 centrifugal machines has provided cost estimates. However, since the older machines are already over twenty years old, it is recommended that the facility replace them instead. A life cycle cost analysis performed on four different types of replacement chillers available determined that a single electric centrifugal chiller using R-134 would be the most economical choice over the life of the machine. Computer simulations of the buildings served by this machine determined that the current installed capacity of 1,638 tons is more than what is required to adequately cool the buildings. Therefore, the new combined capacity is recommended to be 1,265 tons to more nearly match the building cooling load.</p> <p>IMPACT IF NOT PROVIDED</p> <p>If this project is not provided, the above mentioned savings in cooling energy and cost will continue to be wasted. There will be no contribution to the energy reduction goals established at the facility.</p> | | | Electrical Energy Savings | 3,424 | MMBTU/yr | Electrical Demand Savings | 13,914 | \$/yr | Gas Energy Savings | 0 | MMBTU/yr | Total Energy Savings | 3,424 | MMBTU/yr | Total Cost Savings | 56,936 | \$/yr | Total Investment | 479,191 | \$ | Simple Payback | 8.4 | yrs | SIR | 1.98 | |
| Electrical Energy Savings | 3,424 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Electrical Demand Savings | 13,914 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Gas Energy Savings | 0 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Energy Savings | 3,424 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Cost Savings | 56,936 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Investment | 479,191 | \$ | | | | | | | | | | | | | | | | | | | | | | | | |
| Simple Payback | 8.4 | yrs | | | | | | | | | | | | | | | | | | | | | | | | |
| SIR | 1.98 | | | | | | | | | | | | | | | | | | | | | | | | | |

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-C1

ANALYSIS DATE: 08-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|----|---------|
| A. CONSTRUCTION COST | \$ | 429768. | | |
| B. SIOH | \$ | 23637. | | |
| C. DESIGN COST | \$ | 25786. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 479191. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | | | \$ | 479191. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 3424. | \$ 21503. | 15.08 | \$ 324261. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 13914. | 14.88 | \$ 207040. |
| N. TOTAL | | 3424. | \$ 35417. | | \$ 531301. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-----------|
| A. ANNUAL RECURRING (+/-) | | \$ 2275. |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 33852. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTOR (3) | DISCOUNTED SAVINGS(+) / COST(-) (4) |
|-------------------|------------------------------|-----------------|-------------------------|---|
| 1. REFRIG UPGRADE | \$ 384882. | 0 | 1.00 | 384882. |
| d. TOTAL | \$ 384882. | | | 384882. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 418734.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 56936.

5. SIMPLE PAYBACK PERIOD (1G/4) 8.42 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 950035.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.98
(IF < 1 PROJECT DOES NOT QUALIFY)

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): 6.59 %

| | | | | | | |
|--|--|--|--|--------------------------|--------------------|----------------------------------|
| 1. COMPONENT ARMY | | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | | | 2. DATE 8/24/95 | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | 4. PROJECT TITLE ECIP | | |
| 5. PROGRAM ELEMENT | | 6. CATEGORY CODE | | 7. PROJECT NUMBER | | 8. PROJECT COST (\$000) 557.0 |
| 9. COST ESTIMATES | | | | | | |
| ITEM | | | | U/M | QUANTITY | COST (\$000) |
| Replace individual building chillers with central chiller plant in Area 100. | | | | EA | 1 | 557.0 |
| ESTIMATED CONTRACT COST | | | | | | |
| CONTINGENCY (0%) | | | | | | 499.156 |
| SIOH | | | | | | 0.0 |
| DESIGN | | | | | | 27.454 |
| | | | | | | 29.949 |
| TOTAL REQUEST | | | | | | 556.559 |
| TOTAL REQUEST (ROUNDED) | | | | | | 557.000 |
| 10. DESCRIPTION OF PROPOSED CONSTRUCTION | | | | | | |
| <p>Remove the 14 existing air cooled, reciprocating chillers serving buildings 122, 124, 125, 128, 133, 134, 135, 142, 143, 144, 146, 147, 149, 197, 198, 199 and 250. Install 6" chilled water supply and return piping loop between the buildings in this area and terminate loop behind building 250, near the existing air cooled chiller installation. Install two new 210 ton, air cooled screw chillers behind building 250. Install two new 30 HP chilled water distribution pumps to circulate water from new chillers through new distribution loop. The existing chilled water pumps that serve buildings where chillers were removed will be reused to circulate chilled water from the new loop through the buildings. These existing pumps should be connected into the new distribution piping at the existing chiller locations. All new controls and electrical services should be installed at building 250 to serve the new chillers and pumps. All 54ER specific requirements should be determined by the design engineer responsible for this project. This project will require engineering drawings and specifications, demolition and removal of the existing chiller and installation of the new chiller, associated wiring and controls.</p> | | | | | | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|--|--------------------|---------------------------|-------|----------|---------------------------|--------|-------|--------------------|---|----------|----------------------|-------|----------|--------------------|--------|-------|------------------|---------|----|----------------|-----|-----|-----|------|--|
| 1. COMPONENT ARMY | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | 2. DATE 8/24/95 | | | | | | | | | | | | | | | | | | | | | | | | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4. PROJECT TITLE ECIP | | 5. PROJECT NUMBER | | | | | | | | | | | | | | | | | | | | | | | | |
| 11. REQUIREMENT <p>This project is required to reduce the cooling energy consumption in the 100 Area buildings. The project provides new, more efficient primary cooling systems, which will save cooling energy and cost. Additionally, this project will help protect the environment by replacing equipment which uses an ozone depleting refrigerant. All buildings included in this project will be active throughout the payback period. Installation of this cooling equipment will result in the following:</p> <table style="margin-left: auto; margin-right: auto;"> <tbody> <tr> <td>Electrical Energy Savings</td> <td style="text-align: right;">2,816</td> <td>MMBTU/yr</td> </tr> <tr> <td>Electrical Demand Savings</td> <td style="text-align: right;">19,781</td> <td>\$/yr</td> </tr> <tr> <td>Gas Energy Savings</td> <td style="text-align: right;">0</td> <td>MMBTU/yr</td> </tr> <tr> <td>Total Energy Savings</td> <td style="text-align: right;">2,816</td> <td>MMBTU/yr</td> </tr> <tr> <td>Total Cost Savings</td> <td style="text-align: right;">64,465</td> <td>\$/yr</td> </tr> <tr> <td>Total Investment</td> <td style="text-align: right;">556,559</td> <td>\$</td> </tr> <tr> <td>Simple Payback</td> <td style="text-align: right;">8.6</td> <td>yrs</td> </tr> <tr> <td>SIR</td> <td style="text-align: right;">1.73</td> <td></td> </tr> </tbody> </table> <p>CURRENT SITUATION:</p> <p>The 14 existing air cooled, reciprocating chillers in the 100 area were installed in 1985 and serve as the primary cooling systems for 17 buildings. They generally appear to be in fair condition at this time. However, the cost of maintaining so many chillers is excessive and difficult for the maintenance staff. It is recommended that a central chiller plant, consisting of two air cooled screw machines be installed to serve all these buildings. This will not only save energy but will also greatly reduce the maintenance costs to the installation. Computer simulations of the buildings in this area determined that the current installed capacity of 540 tons is more than is required to adequately cool the buildings. Therefore, it is recommended that the two new chillers be rated at a combined 420 tons to more closely match the cooling load of the buildings.</p> <p>IMPACT IF NOT PROVIDED</p> <p>If this project is not provided, the above mentioned savings in cooling energy and cost will continue to be wasted. There will be no contribution to the energy reduction goals established at the facility.</p> | | | Electrical Energy Savings | 2,816 | MMBTU/yr | Electrical Demand Savings | 19,781 | \$/yr | Gas Energy Savings | 0 | MMBTU/yr | Total Energy Savings | 2,816 | MMBTU/yr | Total Cost Savings | 64,465 | \$/yr | Total Investment | 556,559 | \$ | Simple Payback | 8.6 | yrs | SIR | 1.73 | |
| Electrical Energy Savings | 2,816 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Electrical Demand Savings | 19,781 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Gas Energy Savings | 0 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Energy Savings | 2,816 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Cost Savings | 64,465 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Investment | 556,559 | \$ | | | | | | | | | | | | | | | | | | | | | | | | |
| Simple Payback | 8.6 | yrs | | | | | | | | | | | | | | | | | | | | | | | | |
| SIR | 1.73 | | | | | | | | | | | | | | | | | | | | | | | | | |

LIFE CYCLE COST ANALYSIS SUMMARY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: FSH
 INSTALLATION & LOCATION: FSH LCCID FY95 (92)
 PROJECT NO. & TITLE: 03018504 REGION NOS. 6 CENSUS: 3
 FISCAL YEAR 96 EEAP BOILER CHILLER STUDY
 ANALYSIS DATE: 06-16-95 DISCRETE PORTION NAME: ECO-I
 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|----|---------|
| A. CONSTRUCTION COST | \$ | 499156. | | |
| B. SIOH | \$ | 27454. | | |
| C. DESIGN COST | \$ | 29949. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 556559. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | | | \$ | 556559. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 2816. | \$ 17684. | 15.08 | \$ 266682. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 19781. | 14.88 | \$ 294341. |
| N. TOTAL | | 2816. | \$ 37465. | | \$ 561023. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|-------|----|---------|
| A. ANNUAL RECURRING (+/-) | | \$ | 27000. |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 401760. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+) / COST(-) (4) |
|----------|------------------------------|-----------------|------------------------|---|
| d. TOTAL | \$ 0. | | | 0. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 401760.

4. FIRST YEAR DOLLAR SAVINGS 2N3+3A+(3Bd1/(YRS ECONOMIC LIFE)) \$ 64465.

5. SIMPLE PAYBACK PERIOD (1G/4) 8.63 YEAF

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 962783.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.73
 (IF < 1 PROJECT DOES NOT QUALIFY)

| | | | | | | |
|--|--|--|--|-------------------|--------------------|----------------------------------|
| 1. COMPONENT ARMY | | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | | | 2. DATE 8/24/95 | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | 4. PROJECT TITLE | | |
| 5. PROGRAM ELEMENT | | 6. CATEGORY CODE | | 7. PROJECT NUMBER | | 8. PROJECT COST (\$000) 237.0 |
| 9. COST ESTIMATES | | | | | | |
| ITEM | | | | U/M | QUANTITY | COST (\$000) |
| Replace existing chiller with new centrifugal chiller in building 2265. | | | | EA | 1 | 237.0 |
| ESTIMATED CONTRACT COST | | | | | | 212.626 |
| CONTINGENCY (0%) | | | | | | 0.0 |
| SIOH | | | | | | 11.694 |
| DESIGN | | | | | | 12.758 |
| TOTAL REQUEST | | | | | | 237.078 |
| TOTAL REQUEST (ROUNDED) | | | | | | 237.000 |
| 10. DESCRIPTION OF PROPOSED CONSTRUCTION | | | | | | |
| <p>Remove the existing 675 ton, R-11 centrifugal chiller in building 2265 and replace it with a 555 ton, R-134a centrifugal chiller. The existing 100 HP chilled water (CHW) pump, 50 HP condenser water (CND) pump and 40 HP cooling tower will be reused. The new chiller should be connected into the distribution piping at the existing chiller location. All existing controls and electrical services should be reconnected where possible. Specific requirements in all areas should be determined by the design engineer responsible for this project. To meet the current ASHRAE Standard 15, a refrigerant detection and ventilation system should be installed. This project will require engineering drawings and specifications, demolition and removal of the existing chiller and installation of the new chiller, associated wiring and controls.</p> | | | | | | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|---|---------------------------|---------------------------|-------|----------|---------------------------|--------|-------|--------------------|---|----------|----------------------|-------|----------|--------------------|--------|-------|------------------|---------|----|----------------|-----|-----|-----|------|--|
| 1. COMPONENT ARMY | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | 2. DATE 8/24/95 | | | | | | | | | | | | | | | | | | | | | | | | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4. PROJECT TITLE | | 5. PROJECT NUMBER | | | | | | | | | | | | | | | | | | | | | | | | |
| <p>11. REQUIREMENT</p> <p>This project is required to reduce the cooling energy consumption in the 2200 Area central plant. The project provides new, more efficient primary cooling systems, which will save cooling energy and cost. Additionally, this project will help protect the environment by replacing equipment which uses an ozone depleting refrigerant. All buildings included in this project will be active throughout the payback period. Installation of this cooling equipment will result in the following:</p> <table style="margin-left: auto; margin-right: auto;"> <tbody> <tr> <td>Electrical Energy Savings</td> <td style="text-align: right;">1,304</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Electrical Demand Savings</td> <td style="text-align: right;">11,822</td> <td style="text-align: right;">\$/yr</td> </tr> <tr> <td>Gas Energy Savings</td> <td style="text-align: right;">0</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Total Energy Savings</td> <td style="text-align: right;">1,304</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Total Cost Savings</td> <td style="text-align: right;">37,433</td> <td style="text-align: right;">\$/yr</td> </tr> <tr> <td>Total Investment</td> <td style="text-align: right;">237,078</td> <td style="text-align: right;">\$</td> </tr> <tr> <td>Simple Payback</td> <td style="text-align: right;">6.3</td> <td style="text-align: right;">yrs</td> </tr> <tr> <td>SIR</td> <td style="text-align: right;">2.73</td> <td></td> </tr> </tbody> </table> <p>CURRENT SITUATION:</p> <p>The existing water cooled, centrifugal chiller was installed in 1973 and serves as the primary cooling system for the four large buildings in the 2200 area. It appears to be in fair condition but uses the R-11 refrigerant, which will no longer be manufactured as of January 1, 1996. To avoid the anticipated increasing operational costs over the life of this machine, it should either be retrofitted to use an approved refrigerant or replaced with a new machine that operates on one. The existing centrifugal machine can be retrofitted with no loss of capacity by replacing the impeller with one designed for HCFC-123 refrigerant. A company which produces these new impellers for existing R-11 centrifugal machines has provided cost estimates. However, since the machine is already 22 years old, it is recommended that the facility replace it instead. A life cycle cost analysis performed on four different types of replacement chillers available determined that an electric centrifugal chiller using R-134a would be the most economical choice over the life of the new machine. Computer simulations of the buildings served by this machine determined that the current installed capacity of 657 tons is more than what is required to adequately cool the buildings. Therefore, the new chiller should only be sized for 555 tons to more closely match the cooling load of the four buildings.</p> <p>IMPACT IF NOT PROVIDED</p> <p>If this project is not provided, the above mentioned savings in cooling energy and cost will continue to be wasted. There will be no contribution to the energy reduction goals established at the facility.</p> | | | Electrical Energy Savings | 1,304 | MMBTU/yr | Electrical Demand Savings | 11,822 | \$/yr | Gas Energy Savings | 0 | MMBTU/yr | Total Energy Savings | 1,304 | MMBTU/yr | Total Cost Savings | 37,433 | \$/yr | Total Investment | 237,078 | \$ | Simple Payback | 6.3 | yrs | SIR | 2.73 | |
| Electrical Energy Savings | 1,304 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Electrical Demand Savings | 11,822 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Gas Energy Savings | 0 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Energy Savings | 1,304 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Cost Savings | 37,433 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Investment | 237,078 | \$ | | | | | | | | | | | | | | | | | | | | | | | | |
| Simple Payback | 6.3 | yrs | | | | | | | | | | | | | | | | | | | | | | | | |
| SIR | 2.73 | | | | | | | | | | | | | | | | | | | | | | | | | |

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-E1

ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|---------|--|
| A. CONSTRUCTION COST | \$ | 212626. | | |
| B. SIOH | \$ | 11694. | | |
| C. DESIGN COST | \$ | 12758. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 237078. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | 237078. | |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 1304. | \$ 8189. | 15.08 | \$ 123492. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 11822. | 14.88 | \$ 175911. |
| N. TOTAL | | 1304. | \$ 20011. | | \$ 299403. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|----|
| A. ANNUAL RECURRING (+/-) | | \$ | 0. |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) | YR OC | DISCNT FACTR | DISCOUNTED SAVINGS(+) COST(-) (4) |
|-------------------|-----------------------|----------|-----------------|---|
| | (1) | (2) | (3) | (4) |
| 1. REFRIG UPGRADE | \$ 348435. | 0 | 1.00 | 348435. |
| d. TOTAL | \$ 348435. | | | 348435. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 348435.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 37433.

5. SIMPLE PAYBACK PERIOD (1G/4) 6.33 YEAR

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 647838.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 2.73
 (IF < 1 PROJECT DOES NOT QUALIFY)

| | | | | | | |
|--|--|--|--|-------------------|--------------------|----------------------------------|
| 1. COMPONENT ARMY | | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | | | 2. DATE 8/24/95 | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | 4. PROJECT TITLE | | |
| 5. PROGRAM ELEMENT | | 6. CATEGORY CODE | | 7. PROJECT NUMBER | | 8. PROJECT COST (\$000) 157.0 |
| 9. COST ESTIMATES | | | | | | |
| ITEM | | | | U/M | QUANTITY | COST (\$000) |
| Replace existing chiller with new screw chiller in building 902. | | | | EA | 1 | 157.0 |
| ESTIMATED CONTRACT COST | | | | | | 141.037 |
| CONTINGENCY (0%) | | | | | | 0.0 |
| SIOH | | | | | | 7.757 |
| DESIGN | | | | | | 8.462 |
| TOTAL REQUEST | | | | | | 157.256 |
| TOTAL REQUEST (ROUNDED) | | | | | | 157.000 |
| 10. DESCRIPTION OF PROPOSED CONSTRUCTION | | | | | | |
| <p>Remove the existing 300 ton, R-11 centrifugal chiller in building 902 and replace it with a 300 ton, R-134a screw chiller. The existing 25 HP chilled water (CHW) pump, 15 HP condenser water (CND) pump and 15 HP cooling tower will be reused. The new chiller should be connected into the distribution piping at the existing chiller location. All existing controls and electrical services should be reconnected where possible. Specific requirements in all areas should be determined by the design engineer responsible for this project. To meet the current ASHRAE Standard 15, a refrigerant detection and ventilation system should be installed. This project will require engineering drawings and specifications, demolition and removal of the existing chiller and installation of the new chiller, associated wiring and controls.</p> | | | | | | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|--|--------------------|---------------------------|-----|----------|---------------------------|-------|-------|--------------------|---|----------|----------------------|-----|----------|--------------------|--------|-------|------------------|---------|----|----------------|-----|-----|-----|------|--|
| 1. COMPONENT ARMY | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | 2. DATE 8/24/95 | | | | | | | | | | | | | | | | | | | | | | | | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4. PROJECT TITLE | | 5. PROJECT NUMBER | | | | | | | | | | | | | | | | | | | | | | | | |
| <p>11. REQUIREMENT</p> <p>This project is required to reduce the cooling energy consumption in the 900 Area central plant. The project provides new, more efficient primary cooling systems, which will save cooling energy and cost. Additionally, this project will help protect the environment by replacing equipment which uses an ozone depleting refrigerant. All buildings included in this project will be active throughout the payback period. Installation of this cooling equipment will result in the following:</p> <table style="margin-left: auto; margin-right: auto;"> <tbody> <tr> <td>Electrical Energy Savings</td> <td style="text-align: right;">434</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Electrical Demand Savings</td> <td style="text-align: right;">2,520</td> <td style="text-align: right;">\$/yr</td> </tr> <tr> <td>Gas Energy Savings</td> <td style="text-align: right;">0</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Total Energy Savings</td> <td style="text-align: right;">434</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Total Cost Savings</td> <td style="text-align: right;">17,650</td> <td style="text-align: right;">\$/yr</td> </tr> <tr> <td>Total Investment</td> <td style="text-align: right;">157,256</td> <td style="text-align: right;">\$</td> </tr> <tr> <td>Simple Payback</td> <td style="text-align: right;">8.9</td> <td style="text-align: right;">yrs</td> </tr> <tr> <td>SIR</td> <td style="text-align: right;">2.08</td> <td></td> </tr> </tbody> </table> <p>CURRENT SITUATION:</p> <p>The existing water cooled, centrifugal chiller was installed in 1985 and serves as the primary cooling system for the 21 buildings in the 900 area. It appears to be in fair condition but uses the R-11 refrigerant, which will no longer be manufactured as of January 1, 1996. To avoid the anticipated increasing operational costs over the life of this machine, it should either be retrofitted to use an approved refrigerant or replaced with a new machine that operates on one. The existing centrifugal machine can be retrofitted with no loss of capacity by replacing the impeller with one designed for HCFC-123 refrigerant. A company which produces these new impellers for existing R-11 centrifugal machines has provided cost estimates. However, since the machine is already ten years old, it is recommended that the facility replace it instead. A life cycle cost analysis performed on four different types of replacement chillers available determined that a dual screw chiller using R-134a would be the most economical choice over the life of the new machine. Computer simulations of the buildings served by this machine determined that the current installed capacity of 300 tons is required to adequately cool the buildings. Therefore, no increase or decrease in the current chiller capacity is recommended at this time.</p> <p>IMPACT IF NOT PROVIDED</p> <p>If this project is not provided, the above mentioned savings in cooling energy and cost will continue to be wasted. There will be no contribution to the energy reduction goals established at the facility.</p> | | | Electrical Energy Savings | 434 | MMBTU/yr | Electrical Demand Savings | 2,520 | \$/yr | Gas Energy Savings | 0 | MMBTU/yr | Total Energy Savings | 434 | MMBTU/yr | Total Cost Savings | 17,650 | \$/yr | Total Investment | 157,256 | \$ | Simple Payback | 8.9 | yrs | SIR | 2.08 | |
| Electrical Energy Savings | 434 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Electrical Demand Savings | 2,520 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Gas Energy Savings | 0 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Energy Savings | 434 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Cost Savings | 17,650 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Investment | 157,256 | \$ | | | | | | | | | | | | | | | | | | | | | | | | |
| Simple Payback | 8.9 | yrs | | | | | | | | | | | | | | | | | | | | | | | | |
| SIR | 2.08 | | | | | | | | | | | | | | | | | | | | | | | | | |

LIFE CYCLE COST ANALYSIS SUMMARY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: FSH
 INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3
 PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY
 FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-A3
 ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|--|
| A. CONSTRUCTION COST | \$ | 141037. | |
| B. SIOH | \$ | 7757. | |
| C. DESIGN COST | \$ | 8462. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 157256. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | 157256. | |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 434. | \$ 2726. | 15.08 | \$ 41101. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 2520. | 14.88 | \$ 37498. |
| N. TOTAL | | 434. | \$ 5246. | | \$ 78598. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|----|
| A. ANNUAL RECURRING (+/-) | | \$ | 0. |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) | YR OC | DISCNT FACTOR | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|-------------------|-----------------------|----------|------------------|--|
| | (1) | (2) | (3) | |
| 1. REFRIG UPGRADE | \$ 248085. | 0 | 1.00 | 248085. |
| d. TOTAL | \$ 248085. | | | 248085. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 248085.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 17650.

5. SIMPLE PAYBACK PERIOD (1G/4) 8.91 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 326683.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 2.08
 (IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

| | | | | | | |
|--|--|--|--|-------------------|--------------------|----------------------------------|
| 1. COMPONENT ARMY | | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | | | 2. DATE 8/24/95 | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | 4. PROJECT TITLE | | |
| 5. PROGRAM ELEMENT | | 6. CATEGORY CODE | | 7. PROJECT NUMBER | | 8. PROJECT COST (\$000) 479.0 |
| 9. COST ESTIMATES | | | | | | |
| ITEM | | | | U/M | QUANTITY | COST (\$000) |
| Replace two (2) existing chillers in building 1377 with one (1) new chiller. | | | | EA | 1 | 479.0 |
| ESTIMATED CONTRACT COST | | | | | | 429.768 |
| CONTINGENCY (0%) | | | | | | 0.0 |
| SIOH | | | | | | 23.673 |
| DESIGN | | | | | | 25.786 |
| TOTAL REQUEST | | | | | | 479.191 |
| TOTAL REQUEST (ROUNDED) | | | | | | 479.000 |
| 10. DESCRIPTION OF PROPOSED CONSTRUCTION | | | | | | |
| <p>Remove the two 600 ton, R-11 centrifugal chillers in building 1377 which were installed in 1972, and replace them with one R-134 centrifugal chiller, rated at 827 tons. The two existing chilled water pumps and condenser water pumps serving the existing chillers should be removed. Install a new chilled water pump and a new condenser water pump, each rated at 75 HP, to serve the new chiller. The new chiller should be connected into the distribution piping at the existing location. New chilled water supply and return headers should be installed to join together the existing distribution systems serving building 1350 and the other seven buildings in the 1300 area. This will create a single chilled water distribution system to be served by the new chiller and the existing 438 ton chiller which was installed in 1983 to serve building 1350. All existing controls and electrical services should be reconnected where possible. Specific requirements in all areas should be determined by the design engineer responsible for this project. To meet the current ASHRAE Standard 15, a refrigerant detection and ventilation system should be installed. This project will require engineering drawings and specifications, demolition and removal of the existing chillers and pumps, and installation of the new chillers, pumps, associated wiring and controls.</p> | | | | | | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|--|--------------------|---------------------------|-------|----------|---------------------------|--------|-------|--------------------|---|----------|----------------------|-------|----------|--------------------|--------|-------|------------------|---------|----|----------------|-----|-----|-----|------|--|
| 1. COMPONENT ARMY | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | 2. DATE 8/24/95 | | | | | | | | | | | | | | | | | | | | | | | | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4. PROJECT TITLE | | 5. PROJECT NUMBER | | | | | | | | | | | | | | | | | | | | | | | | |
| 11. REQUIREMENT <p>This project is required to reduce the cooling energy consumption in the 1300 Area central plant, building 1377. The project provides a new, more efficient primary cooling system, which will save cooling energy and cost. Additionally, this project will help protect the environment by replacing equipment which uses an ozone depleting refrigerant. All buildings included in this project will be active throughout the payback period. Installation of this cooling equipment will result in the following:</p> <table style="margin-left: auto; margin-right: auto;"> <tbody> <tr> <td>Electrical Energy Savings</td> <td style="text-align: right;">3,424</td> <td>MMBTU/yr</td> </tr> <tr> <td>Electrical Demand Savings</td> <td style="text-align: right;">13,914</td> <td>\$/yr</td> </tr> <tr> <td>Gas Energy Savings</td> <td style="text-align: right;">0</td> <td>MMBTU/yr</td> </tr> <tr> <td>Total Energy Savings</td> <td style="text-align: right;">3,424</td> <td>MMBTU/yr</td> </tr> <tr> <td>Total Cost Savings</td> <td style="text-align: right;">56,936</td> <td>\$/yr</td> </tr> <tr> <td>Total Investment</td> <td style="text-align: right;">479,191</td> <td>\$</td> </tr> <tr> <td>Simple Payback</td> <td style="text-align: right;">8.4</td> <td>yrs</td> </tr> <tr> <td>SIR</td> <td style="text-align: right;">1.98</td> <td></td> </tr> </tbody> </table> <p>CURRENT SITUATION:</p> <p>There are currently two independent chilled water distribution systems serving the 1300 area, one for building 1350 and the other for seven other buildings. These two systems should be combined into one system to conserve energy in the central plant. This can be accomplished by installing common CHW supply and return headers in the central plant. The existing centrifugal chiller serving building 1350 was installed in 1983, is rated at 438 tons and appears to be in good condition. The two existing centrifugal chillers serving the other seven buildings were installed in 1972, are rated at 600 tons each, and appear to be near the end of their useful life. Also, all three chillers use the R-11 refrigerant, which will no longer be manufactured as of January 1, 1996. To avoid the anticipated increasing operational costs over the life of these machines, they should either be retrofitted to use an approved refrigerant or replaced with new machines that operate on one. The existing centrifugal machines can be retrofitted with no loss of capacity by replacing the impellers with new ones designed for HCFC-123 refrigerant. A company which produces these new impellers for existing R-11 centrifugal machines has provided cost estimates. However, since the older machines are already over twenty years old, it is recommended that the facility replace them instead. A life cycle cost analysis performed on four different types of replacement chillers available determined that a single electric centrifugal chiller using R-134 would be the most economical choice over the life of the machine. Computer simulations of the buildings served by this machine determined that the current installed capacity of 1,638 tons is more than what is required to adequately cool the buildings. Therefore, the new combined capacity is recommended to be 1,265 tons to more nearly match the building cooling load.</p> <p>IMPACT IF NOT PROVIDED</p> <p>If this project is not provided, the above mentioned savings in cooling energy and cost will continue to be wasted. There will be no contribution to the energy reduction goals established at the facility.</p> | | | Electrical Energy Savings | 3,424 | MMBTU/yr | Electrical Demand Savings | 13,914 | \$/yr | Gas Energy Savings | 0 | MMBTU/yr | Total Energy Savings | 3,424 | MMBTU/yr | Total Cost Savings | 56,936 | \$/yr | Total Investment | 479,191 | \$ | Simple Payback | 8.4 | yrs | SIR | 1.98 | |
| Electrical Energy Savings | 3,424 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Electrical Demand Savings | 13,914 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Gas Energy Savings | 0 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Energy Savings | 3,424 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Cost Savings | 56,936 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Investment | 479,191 | \$ | | | | | | | | | | | | | | | | | | | | | | | | |
| Simple Payback | 8.4 | yrs | | | | | | | | | | | | | | | | | | | | | | | | |
| SIR | 1.98 | | | | | | | | | | | | | | | | | | | | | | | | | |

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-C1

ANALYSIS DATE: 08-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|----|------------|
| A. CONSTRUCTION COST | \$ | 429768. | | |
| B. SIOH | \$ | 23637. | | |
| C. DESIGN COST | \$ | 25786. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 479191. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | | | | \$ 479191. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 3424. | \$ 21503. | 15.08 | \$ 324261. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 13914. | 14.88 | \$ 207040. |
| N. TOTAL | | 3424. | \$ 35417. | | \$ 531301. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-----------|
| A. ANNUAL RECURRING (+/-) | | \$ 2275. |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 33852. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) | YR OC | DISCNT FACTR | DISCOUNTED SAVINGS(+) COST(-) (4) |
|-------------------|-----------------------|----------|-----------------|---|
| | (1) | (2) | (3) | |
| 1. REFRIG UPGRADE | \$ 384882. | 0 | 1.00 | 384882. |
| d. TOTAL | \$ 384882. | | | 384882. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 418734.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 56936.

5. SIMPLE PAYBACK PERIOD (1G/4) 8.42 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 950035.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.98
(IF < 1 PROJECT DOES NOT QUALIFY)

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): 6.59 %

| | | | | | | |
|---|--|--|--|-------------------|--------------------|----------------------------------|
| 1. COMPONENT ARMY | | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | | | 2. DATE 8/24/95 | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | 4. PROJECT TITLE | | |
| 5. PROGRAM ELEMENT | | 6. CATEGORY CODE | | 7. PROJECT NUMBER | | 8. PROJECT COST (\$000) 164.0 |
| 9. COST ESTIMATES | | | | | | |
| ITEM | | | | U/M | QUANTITY | COST (\$000) |
| Replace existing boilers with new high efficiency modular boilers in building 1377. | | | | EA | 1 | 164.0 |
| ESTIMATED CONTRACT COST | | | | | | |
| CONTINGENCY (0%) | | | | | | 146.838 |
| SIOH | | | | | | 0.0 |
| DESIGN | | | | | | 8.076 |
| | | | | | | 8.810 |
| TOTAL REQUEST | | | | | | 163.724 |
| TOTAL REQUEST (ROUNDED) | | | | | | 164.000 |
| 10. DESCRIPTION OF PROPOSED CONSTRUCTION | | | | | | |
| <p>Remove the two existing watertube boilers and single 40 HP heating water (HW) distribution pump in building 1377, which are serving building 1350. Also remove the two existing firetube boilers and the two 15 HP distribution pumps in building 1377 which serve buildings 1374, 1375, 1379, 1380, 1382, 1377 and 1385. Connect the two separate distribution loops together in building 1377 with new HW supply and return headers to make a single HW distribution system. Install four new modular high efficiency boilers, rated at 1,830 MBH output each and four new 7 1/2 HP distribution pumps to serve this single system. The existing electrical service and controls should be reused as much as possible. Specific requirements in all areas should be determined by the design engineer responsible for this project. The boilers and pumps should be sequenced to operate only as needed to maintain the supply water temperature setpoint of approximately 180 F. This project will require engineering drawings and specifications, demolition and removal of the existing boilers and pumps, and installation of the new boilers, pumps, associated wiring and controls.</p> | | | | | | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|--|---------------------------|---------------------------|-----|----------|---------------------------|-------|-------|--------------------|-------|----------|----------------------|-------|----------|--------------------|--------|-------|------------------|---------|----|----------------|-----|----|-----|------|--|
| 1. COMPONENT ARMY | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | 2. DATE 8/24/95 | | | | | | | | | | | | | | | | | | | | | | | | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4. PROJECT TITLE | | 5. PROJECT NUMBER | | | | | | | | | | | | | | | | | | | | | | | | |
| 11. REQUIREMENT <p>This project is required to reduce the heating energy consumption in the 1300 Area central plant. The project provides new, more efficient primary heating systems, which will save heating energy and cost. All buildings included in this project will be active throughout the payback period. Installation of this cooling equipment will result in the following:</p> <table style="margin-left: auto; margin-right: auto;"> <tr> <td>Electrical Energy Savings</td> <td style="text-align: right;">712</td> <td>MMBTU/yr</td> </tr> <tr> <td>Electrical Demand Savings</td> <td style="text-align: right;">1,847</td> <td>\$/yr</td> </tr> <tr> <td>Gas Energy Savings</td> <td style="text-align: right;">4,020</td> <td>MMBTU/yr</td> </tr> <tr> <td>Total Energy Savings</td> <td style="text-align: right;">4,732</td> <td>MMBTU/yr</td> </tr> <tr> <td>Total Cost Savings</td> <td style="text-align: right;">17,012</td> <td>\$/yr</td> </tr> <tr> <td>Total Investment</td> <td style="text-align: right;">163,724</td> <td>\$</td> </tr> <tr> <td>Simple Payback</td> <td style="text-align: right;">9.6</td> <td>yr</td> </tr> <tr> <td>SIR</td> <td style="text-align: right;">1.79</td> <td></td> </tr> </table> <p>CURRENT SITUATION:</p> <p>The two existing watertube boilers serving building 1350 were installed in 1983 and are rated at 5,317 MBH and 4,336 MBH output capacity. The single 40 HP pump circulates HW from these boilers through building 1350. The two existing firetube boilers serving the other buildings in the 1300 area were installed in 1972 and are rated at 5,912 MBH output capacity each. Two 15 HP pumps circulate HW from these boilers to the seven other buildings listed above. All these boilers appear to be in fair condition. Computer simulations of the eight buildings served by these boilers determined that the current combined capacity of 21,477 MBH is about three times the amount required to adequately heat the buildings. The existing boilers are therefore operating at an inefficient, low load condition most of the time. Also, because of the constant flow rate requirements of the large boilers, excessive pumping energy is expended. By combining the two distribution systems together and staging four new high efficiency modular boilers to operate only as needed, a substantial energy savings can be realized. Also, a decrease in the combined boiler output capacity to 7,320 MBH is recommended to more closely match the heating load in the eight buildings and reduce the associated pumping energy consumption.</p> <p>IMPACT IF NOT PROVIDED</p> <p>If this project is not provided, the above mentioned savings in heating energy and cost will continue to be wasted. There will be no contribution to the energy reduction goals established at the facility.</p> | | | Electrical Energy Savings | 712 | MMBTU/yr | Electrical Demand Savings | 1,847 | \$/yr | Gas Energy Savings | 4,020 | MMBTU/yr | Total Energy Savings | 4,732 | MMBTU/yr | Total Cost Savings | 17,012 | \$/yr | Total Investment | 163,724 | \$ | Simple Payback | 9.6 | yr | SIR | 1.79 | |
| Electrical Energy Savings | 712 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Electrical Demand Savings | 1,847 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Gas Energy Savings | 4,020 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Energy Savings | 4,732 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Cost Savings | 17,012 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Investment | 163,724 | \$ | | | | | | | | | | | | | | | | | | | | | | | | |
| Simple Payback | 9.6 | yr | | | | | | | | | | | | | | | | | | | | | | | | |
| SIR | 1.79 | | | | | | | | | | | | | | | | | | | | | | | | | |

LIFE CYCLE COST ANALYSIS SUMMARY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: FSH
 INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3
 PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY
 FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-D
 ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|---------|
| A. CONSTRUCTION COST | \$ | 146838. | |
| B. SIOH | \$ | 8076. | |
| C. DESIGN COST | \$ | 8810. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 163724. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | 163724. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 712. | \$ 4471. | 15.08 | \$ 67428. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 4020. | \$ 10693. | 18.58 | \$ 198680. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 1847. | 14.88 | \$ 27483. |
| N. TOTAL | | 4732. | \$ 17012. | | \$ 293591. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-------|
| A. ANNUAL RECURRING (+/-) | | |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | \$ 0. |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|----------|------------------------------|-----------------|------------------------|--|
| d. TOTAL | \$ 0. | | | 0. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 0.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 17012.

5. SIMPLE PAYBACK PERIOD (1G/4) 9.62 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 293591.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.79
 (IF < 1 PROJECT DOES NOT QUALIFY)

| | | | | | | |
|--|--|--|--|-------------------|--------------------|----------------------------------|
| 1. COMPONENT ARMY | | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | | | 2. DATE 8/24/95 | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | 4. PROJECT TITLE | | |
| 5. PROGRAM ELEMENT | | 6. CATAGORY CODE | | 7. PROJECT NUMBER | | 8. PROJECT COST (\$000) 557.0 |
| 9. COST ESTIMATES | | | | | | |
| ITEM | | | | U/M | QUANTITY | COST (\$000) |
| Replace individual building chillers with central chiller plant in Area 100. | | | | EA | 1 | 557.0 |
| ESTIMATED CONTRACT COST | | | | | | |
| CONTINGENCY (0%) | | | | | | 499.156 |
| SIOH | | | | | | 0.0 |
| DESIGN | | | | | | 27.454 |
| | | | | | | 29.949 |
| TOTAL REQUEST | | | | | | 556.559 |
| TOTAL REQUEST (ROUNDED) | | | | | | 557.000 |
| 10. DESCRIPTION OF PROPOSED CONSTRUCTION | | | | | | |
| <p>Remove the 14 existing air cooled, reciprocating chillers serving buildings 122, 124, 125, 128, 133, 134, 135, 142, 143, 144, 146, 147, 149, 197, 198, 199 and 250. Install 6" chilled water supply and return piping loop between the buildings in this area and terminate loop behind building 250, near the existing air cooled chiller installation. Install two new 210 ton, air cooled screw chillers behind building 250. Install two new 30 HP chilled water distribution pumps to circulate water from new chillers through new distribution loop. The existing chilled water pumps that serve buildings where chillers were removed will be reused to circulate chilled water from the new loop through the buildings. These existing pumps should be connected into the new distribution piping at the existing chiller locations. All new controls and electrical services should be installed at building 250 to serve the new chillers and pumps. All 54ER specific requirements should be determined by the design engineer responsible for this project. This project will require engineering drawings and specifications, demolition and removal of the existing chiller and installation of the new chiller, associated wiring and controls.</p> | | | | | | |

| | | | | | | | | | | | | | | | | | | | | | | | | | | |
|--|--|---------------------------|---------------------------|-------|----------|---------------------------|--------|-------|--------------------|---|----------|----------------------|-------|----------|--------------------|--------|-------|------------------|---------|----|----------------|-----|-----|-----|------|--|
| 1. COMPONENT ARMY | FY 1997 MILITARY CONSTRUCTION PROJECT DATA | 2. DATE 8/24/95 | | | | | | | | | | | | | | | | | | | | | | | | |
| 3. INSTALLATION AND LOCATION FORT SAM HOUSTON, SAN ANTONIO, TX. | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 4. PROJECT TITLE | | 5. PROJECT NUMBER | | | | | | | | | | | | | | | | | | | | | | | | |
| <p>11. REQUIREMENT</p> <p>This project is required to reduce the cooling energy consumption in the 100 Area buildings. The project provides new, more efficient primary cooling systems, which will save cooling energy and cost. Additionally, this project will help protect the environment by replacing equipment which uses an ozone depleting refrigerant. All buildings included in this project will be active throughout the payback period. Installation of this cooling equipment will result in the following:</p> <table style="margin-left: auto; margin-right: auto;"> <tbody> <tr> <td>Electrical Energy Savings</td> <td style="text-align: right;">2,816</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Electrical Demand Savings</td> <td style="text-align: right;">19,781</td> <td style="text-align: right;">\$/yr</td> </tr> <tr> <td>Gas Energy Savings</td> <td style="text-align: right;">0</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Total Energy Savings</td> <td style="text-align: right;">2,816</td> <td style="text-align: right;">MMBTU/yr</td> </tr> <tr> <td>Total Cost Savings</td> <td style="text-align: right;">64,465</td> <td style="text-align: right;">\$/yr</td> </tr> <tr> <td>Total Investment</td> <td style="text-align: right;">556,559</td> <td style="text-align: right;">\$</td> </tr> <tr> <td>Simple Payback</td> <td style="text-align: right;">8.6</td> <td style="text-align: right;">yrs</td> </tr> <tr> <td>SIR</td> <td style="text-align: right;">1.73</td> <td></td> </tr> </tbody> </table> <p>CURRENT SITUATION:</p> <p>The 14 existing air cooled, reciprocating chillers in the 100 area were installed in 1985 and serve as the primary cooling systems for 17 buildings. They generally appear to be in fair condition at this time. However, the cost of maintaining so many chillers is excessive and difficult for the maintenance staff. It is recommended that a central chiller plant, consisting of two air cooled screw machines be installed to serve all these buildings. This will not only save energy but will also greatly reduce the maintenance costs to the installation. Computer simulations of the buildings in this area determined that the current installed capacity of 540 tons is more than is required to adequately cool the buildings. Therefore, it is recommended that the two new chillers be rated at a combined 420 tons to more closely match the cooling load of the buildings.</p> <p>IMPACT IF NOT PROVIDED</p> <p>If this project is not provided, the above mentioned savings in cooling energy and cost will continue to be wasted. There will be no contribution to the energy reduction goals established at the facility.</p> | | | Electrical Energy Savings | 2,816 | MMBTU/yr | Electrical Demand Savings | 19,781 | \$/yr | Gas Energy Savings | 0 | MMBTU/yr | Total Energy Savings | 2,816 | MMBTU/yr | Total Cost Savings | 64,465 | \$/yr | Total Investment | 556,559 | \$ | Simple Payback | 8.6 | yrs | SIR | 1.73 | |
| Electrical Energy Savings | 2,816 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Electrical Demand Savings | 19,781 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Gas Energy Savings | 0 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Energy Savings | 2,816 | MMBTU/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Cost Savings | 64,465 | \$/yr | | | | | | | | | | | | | | | | | | | | | | | | |
| Total Investment | 556,559 | \$ | | | | | | | | | | | | | | | | | | | | | | | | |
| Simple Payback | 8.6 | yrs | | | | | | | | | | | | | | | | | | | | | | | | |
| SIR | 1.73 | | | | | | | | | | | | | | | | | | | | | | | | | |

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-I

ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|--|
| A. CONSTRUCTION COST | \$ | 499156. | |
| B. SIOH | \$ | 27454. | |
| C. DESIGN COST | \$ | 29949. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 556559. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | 556559. | |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 2816. | \$ 17684. | 15.08 | \$ 266682. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 19781. | 14.88 | \$ 294341. |
| N. TOTAL | | 2816. | \$ 37465. | | \$ 561023. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|------------|
| A. ANNUAL RECURRING (+/-) | | \$ 27000. |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 401760. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+) COST(-) (4) |
|----------|------------------------------|-----------------|------------------------|---|
| d. TOTAL | \$ 0. | | | 0. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 401760.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 64465.

5. SIMPLE PAYBACK PERIOD (1G/4) 8.63 YEAR

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 962783.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.73
(IF < 1 PROJECT DOES NOT QUALIFY)

APPENDIX A
ENERGY COST ANALYSIS

APPENDIX A
ENERGY COST ANALYSIS

TABLE OF CONTENTS

| | | |
|----|--|-----|
| A. | Electrical Energy Cost Analysis | A-1 |
| | Electrical Rate Schedule | A-1 |
| | Avoided Costs | A-1 |
| B. | Natural Gas Energy Cost Analysis | A-2 |
| | Gas Rate Schedules | A-2 |
| | Avoided Cost | A-3 |

APPENDIX A ENERGY COST ANALYSIS

A. Electrical Energy Cost Analysis

Electrical Rate Schedule: The post purchases its electrical power from the City Public Service (CPS) of San Antonio, and is billed under the Super Large Power (SLP) rate. Service is provided through a single substation on the post, owned by the Army. The SLP rate has been in effect since January of 1994, and was created by the utility company to lower military base charges, thereby helping to avoid base closures. This rate has resulted in substantial cost decreases, even though the electrical usage on the post has increased. The monthly SLP billing rate components are as follows:

Service Availability Charge: \$1,000

Energy Charge: \$0.024/KWH

Demand Charge: \$10.00/KW billing demand (June through September)
\$7.50/KW billing demand (October through May)

where: billing demand is the highest 15 minute metered KW demand during the month, or 5000 KW, or 80% of highest billing demand from previous June through September (applicable only from October through May), whichever is greatest

Fuel Cost Adjustment: calculated monthly, difference between actual fuel cost and \$0.016/KWH (average variance from base year data is -\$0.002566/KWH)

Avoided Costs: In order to convert electric demand and energy savings into dollar savings, the avoided costs of demand and energy are determined. These are the marginal cost savings to be realized by the post, per unit of demand or energy saved. Using the above billing components, the *Avoided Cost of Demand* (C_{SD} & C_{WD}) and the *Avoided Cost of Energy* (C_E) are determined as follows:

$$C_{SD} = \frac{\$10.00}{KW} \quad (\text{June through September})$$

$$C_{WD} = \frac{\$7.50}{KW} \quad (\text{October through May})$$

$$C_E = (E + F) \times \frac{KWH}{3413 BTU} \times \frac{1,000,000 BTU}{MMBTU} \times \frac{\$}{MMBTU}$$

$$C_E = (0.024 - 0.002566) \times \frac{1,000,000}{3413} = \frac{\$6.28}{MMBTU}$$

Rebate Program: The City Public Service of San Antonio currently offers no cash incentives for energy conservation retrofits.

B. Natural Gas Energy Cost Analysis

Gas Rate Schedules: FSH is currently supplied natural gas by CPS through many meters distributed throughout the post. However, the meters serving areas 900, 1300, 2200 and the quadrangle are all billed under the Large Volume Gas (LVG) rate. The monthly LVG billing rate components are as follows:

| | | |
|------------------------------|--|--------------------------|
| Service Availability Charge: | \$325 | |
| Energy Charge: | \$2.65/MCF | |
| Fuel Adjustment: | calculated monthly, difference between actual gas cost and \$2.20/MCF (average variance from base year data is \$0.0142/MCF) | |
| Demand Charge: | \$0.080/(MCF/day) | (December through March) |
| | \$0.064/(MCF/day) | (April through November) |

where: billing demand is the monthly gas consumption (MCF) divided by the number of days in the month, or 60 MCF/day, or the maximum billing demand established during the period of December through March (applicable only during April through November), whichever is greatest

The buildings in the area 100 have individual gas meters and are billed under the Residential Gas (RG) rate #4. The monthly RG billing rate components are as follows:

| | | |
|------------------------------|--|--|
| Service Availability Charge: | \$3.85 | |
| Energy Charge: | \$4.38/MCF | |
| Fuel Adjustment: | calculated monthly, difference between actual gas cost and \$2.20/MCF (average variance from base year data is \$0.0142/MCF) | |

Avoided Costs: In order to convert gas energy savings or penalties into cost savings or penalties, the *Avoided Cost of Gas* (C_G) is determined for each rate schedule described above as follows:

Areas 900, 1300, 2200 and Quadrangle,

$$C_G = (E + F) \times \frac{1 \text{ MCF}}{\text{MMBTU}} \quad \frac{\$}{\text{MMBTU}}$$

where,

E = energy charge = \$2.65 per MCF

F = fuel adjustment = \$0.0142 per MCF (average from base year data)

$$C_G = (2.65 + 0.0142) = 2.66 \quad \frac{\$}{\text{MMBTU}}$$

Area 100,

$$C_G = (E + F) \times \frac{1 \text{ MCF}}{\text{MMBTU}} \quad \frac{\$}{\text{MMBTU}}$$

where,

E = energy charge = \$4.38 per MCF

F = fuel adjustment = \$0.0142 per MCF (average from base year data)

$$C_G = (4.38 + 0.0142) = 4.39 \quad \frac{\$}{\text{MMBTU}}$$

APPENDIX B

COMPUTER MODELING OF BOILER & CHILLER SYSTEMS

APPENDIX B
COMPUTER MODELING OF BOILER & CHILLER SYSTEMS

TABLE OF CONTENTS

| | | |
|----|--|-------|
| A. | General Parameters | B-1 |
| B. | People, Lights and Miscellaneous Equipment Schedules | B-2 |
| C. | HVAC Equipment Schedules | B-2 |
| D. | Building HVAC Systems | B-3 |
| E. | Boiler & Chiller Systems | B-3 |
| | Area 900 - Trace 600 Input Data | B-5 |
| | Area 900 - Trace 600 Model Header & System Load Profile | B-23 |
| | Area 900 - Trace 600 Existing Equipment Energy Consumption Output Sheets | B-25 |
| | Area 900 - Trace 600 Proposed Equipment Energy Consumption Output Sheets | B-27 |
| | Area 1300 - Trace 600 Input Data | B-37 |
| | Area 1300 - Trace 600 Model Header & System Load Profile | B-55 |
| | Area 1300 - Trace 600 Existing Equipment Energy Consumption Output Sheets | B-57 |
| | Area 1300 - Trace 600 Proposed Equipment Energy Consumption Output Sheets | B-60 |
| | Area 2200 - Trace 600 Input Data | B-70 |
| | Area 2200 - Trace 600 Model Header & System Load Profile | B-84 |
| | Area 2200 - Trace 600 Existing Equipment Energy Consumption Output Sheets | B-86 |
| | Area 2200 - Trace 600 Proposed Equipment Energy Consumption Output Sheets | B-89 |
| | Quadrangle Area - Trace 600 Input Data | B-99 |
| | Quadrangle Area- Trace 600 Model Header & System Load Profile | B-109 |
| | Quadrangle Area- Trace 600 Existing Equipment Energy Consumption Output Sheets | B-111 |
| | Quadrangle Area- Trace 600 Proposed Equipment Energy Consumption Output Sheets | B-118 |
| | Area 100 - Trace 600 Input Data | B-121 |
| | Area 100 - Trace 600 Model Header & System Load Profile | B-139 |
| | Area 100 - Trace 600 Existing Equipment Energy Consumption Output Sheets | B-141 |
| | Area 100 - Trace 600 Proposed Equipment Energy Consumption Output Sheets | B-155 |

APPENDIX B

COMPUTER MODELING OF BOILER & CHILLER SYSTEMS

- A. General Parameters. The following assumptions and estimates were used in the modeling of the existing buildings which are served by the boilers and chillers included in this study.
1. The Trace 600 weather data for San Antonio, Texas was used in all of the computer simulations.
 2. The Trace 600 computer simulations were performed for the months of January through December to determine annual HVAC equipment energy consumptions.
 3. A special holiday schedule was created to incorporate the additional holidays that military personnel living in the area 900 and 1300 barracks buildings receive. This schedule includes the seven standard holidays plus the period from December 17 through 31. The standard seven day holiday schedule was used for all other areas.
 4. All building dimensions and construction data were determined from as-built drawings when available, or from field measurements taken during the site visit.
 5. Design room temperatures (thermostat setpoints) were obtained from CEMP-E (9 December 1991) Chapter 13, Section 3. These temperatures were 78°F for cooling and 70°F for heating. No cooling or heating temperature setback control was included in the simulations.
 6. The shading coefficient for all windows with interior blinds was estimated at 0.67 per ASHRAE data.
 7. The number of people in each building or room was estimated from interviews with post personnel. The sensible and latent heat gain rates used for the people in each room were taken from ASHRAE data.
 8. Building and room lighting loads were obtained from as-built drawings when available, or from field notes taken during the site visit.
 9. Building and room miscellaneous equipment loads were estimated from field notes taken during the site visit. These loads represent the internal heat gains generated from equipment in the rooms, such as computers, televisions, cooking equipment, etc. Heat gain data for the various types of internal loads was taken from ASHRAE.
 10. For all building areas with forced ventilation, the rates were taken from ASHRAE Standard 62-1989 or from schedule data on the existing air handlers, whichever was greater.
 11. For all barracks buildings with operable windows and no forced ventilation, infiltration rates were assumed to be equal to building or room exhaust rates.
 12. Building and room exhaust rates were taken from as-built drawings.

B. People, Lights and Miscellaneous Equipment Schedules. The following assumptions and estimates were used in the modeling of the existing buildings which are served by the boilers and chillers included in this study.

1. Offices and Classrooms: During the weekdays, all people, lights and miscellaneous equipment were scheduled at 100% from 8 am until 12 pm, and from 1 pm until 5 pm. During the lunch hour, from 12 pm until 1 pm, all internal loads were scheduled at 10%. On the weekends and holidays, all loads were scheduled at 0%.
2. Barracks:
 - a. People - During the weekdays, all people were scheduled at 5% between 8 am and 5 pm. Between 5 pm and 10 pm, they were scheduled at 80%, and between 10 pm and 8 am, they were scheduled at 100%. During the weekends and holidays, the people were scheduled at 50% all day long.
 - b. Lights and Miscellaneous Equipment - During the weekdays, the lights and miscellaneous equipment (TVs, radios, etc.) were scheduled at 5% between 8 am and 5 pm. Between 5 pm and 10 pm, they were scheduled at 80%, and between 10 pm and 8 am, they were scheduled at 5%. During the weekends and holidays, the lights and miscellaneous equipment were scheduled at 50% from 8 am until 10 pm, and 5% from 10 pm until 8 am.
3. Dining Areas:
 - a. People - During the weekdays, weekends and holidays, all people were scheduled at 100% between 6 am and 9 am, between 11 am and 2 pm, and between 5 pm and 7 pm. They were scheduled at 0% at all other times.
 - b. Lights and Miscellaneous Equipment - During the weekdays, weekends and holidays, all lights and miscellaneous equipment were scheduled at 100% between 5 am and 7 pm. They were scheduled at 0% at all other times.
4. Kitchen Areas: During the weekdays, weekends and holidays, all people, lights and miscellaneous equipment were scheduled at 100% from 4 am until 9 pm. They were scheduled at 0% at all other times.

C. HVAC Equipment Schedules. The following assumptions and estimates were used in the modeling of the existing buildings which are served by the boilers and chillers included in this study.

1. All fan coil and air handler fans were scheduled to operate 100% of the day, 12 months of the year, as required by room thermostats to maintain building setpoint temperatures.
2. All fan coil and air handler cooling coils were scheduled to operate 100% of the day, from May through October, as required by room thermostats to maintain building setpoint temperatures.
3. All fan coil and air handler heating coils were scheduled to operate 100% of the day, from November through April, as required by room thermostats to maintain building setpoint temperatures.
4. All building infiltration and ventilation air is scheduled to be introduced into the buildings at a fixed rate 100% of the day, 12 months per year.

5. All building and room thermostats were scheduled to maintain the design setpoints 24 hours per day, 12 months per year with no setback periods.

D. **Building HVAC Systems.** The following assumptions and estimates were used in the modeling of the existing buildings which are served by the boilers and chillers included in this study.

1. HVAC air system types were taken from building as-built drawings when available, or from field notes taken during the site visit.
2. In order to simplify the calculations, most buildings were modeled as a single 'zone' served by a single HVAC air system. Other buildings with more diverse occupancies were zoned as shown on as-built drawings and served by individual HVAC air systems in order to generate a more realistic load profile for the boilers and chillers.
3. Each building HVAC air system was assumed to have a chilled water coil for cooling and a heating water coil for heating. These coils were assumed to be served by two-pipe distribution systems within the buildings.

E. **Boiler & Chiller Systems.** The following assumptions and estimates were used in the modeling of the boiler and chiller systems included in this study.

1. Existing boiler and chiller systems types were identified during the field inspection and used in the computer simulations. They're full load capacity and energy consumption rates were input to match the existing systems. The Trace 600 models were used for part load performance of the existing boilers and chillers.
2. It was assumed that all existing chillers had a full load KW/ton increase of 1% over their original rating for each year of service up to ten years. For all service over ten years, 0.25% per year was added to the full load KW/ton rating. This was done to account for natural efficiency losses due to tube fouling and compressor wear.
3. It was assumed that all existing boilers had a full load efficiency decrease of 1% under their original rating for each year of service up to ten years. For all service over ten years, 0.25% per year was deducted from the full load efficiency rating. This was done to account for natural efficiency losses due to tube fouling and burner wear.
4. The existing pumping horsepower for all associated pumps was also input to simulate the existing systems.
5. In area 900, a base load of 565 MBH per hour was imposed on the existing and proposed boilers to account for the generation of domestic hot water in the barracks buildings. This base load increases the required boiler capacity and shows up as 'base utility' in the equipment energy consumption output sheets.
6. Proposed boiler and chiller alternatives were selected for comparison in the computer simulations. Full load capacity and energy consumption rates were obtained from manufacturer's data and input into the computer simulations. When available, part load energy consumption data from the manufactures was used in the simulations.
7. All new chillers were selected from the top 25% of their class in terms of efficiency (KW/ton), and also were at least 10% more efficient than current design standards.

8. New pumping horsepower for all associated pumps was estimated for all proposed boilers and chillers and input to simulate the new systems.
9. Existing cooling tower systems were identified during the field inspection and used in the computer simulations. They're existing fan horsepower was also input to simulate the existing towers.
10. In all areas, a base load was added to the chillers and boilers to account for heat loss or gain from circulating pumps and piping insulation. These base loads increased the required capacity of the boilers and chillers and show up as 'base utility' in the equipment energy consumption output sheets.

01 Card - Job Information

Project: 030185.04 EEAP BOILER-CHILLER STUDY
 Location: FT. SAM HOUSTON - SAN ANTONIO, TX.
 Client: CORPS. OF ENGINEERS - FORT WORTH, TX.
 Program User: HUITT-ZOLLARS INC.
 Comments: AREA 900

Card 08----- Climatic Information -----

| | Summer | Winter | Summer | Summer | Winter | | Summer | Winter |
|----------|-----------|-----------|----------|----------|----------|-------------|---------|---------|
| Weather | Clearness | Clearness | Design | Design | Design | Building | Ground | Ground |
| Code | Number | Number | Dry Bulb | Wet Bulb | Dry Bulb | Orientation | Reflect | Reflect |
| SANANTON | | | | | | | | |

Card 11----- Energy Simulation Parameters -----

| 1st Month | Last Month | Level | | Building |
|------------|------------|-------------|----------|----------|
| Energy | Energy | Of | Holiday | Calendar |
| Simulation | Simulation | Calculation | Code | Code |
| | | | ARMY1994 | Area |

----- Load Section Alternative #1 -----

Card 19- Load Alternative -

| Number | Description |
|--------|--------------------|
| 1 | EXISTING BUILDINGS |

Card 20----- General Room Parameters -----

| Room | Zone | Reference | Room | Floor | Floor | Const | Plenum | Acoustic | Floor to | Duplicate | Duplicate | Perimeter |
|--------|--------|-----------|------|--------|-------|-------|--------|------------|----------|------------|-----------|-----------|
| Number | Number | Descrip | | Length | Width | Type | Height | Ceiling | Floor | Floors | Rooms per | Depth |
| | | | | | | | | Resistance | Height | Multiplier | Zone | |
| 5 | 5 | BLDG 904 | | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 10 | 10 | BLDG 907 | | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 15 | 15 | BLDG 920 | | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 20 | 20 | BLDG 926 | | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 25 | 25 | BLDG 915 | | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 30 | 30 | BLDG 921 | | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 35 | 35 | BLDG 929 | | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 40 | 40 | BLDG 932 | | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 45 | 45 | BLDG 905 | | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |

| Card 20----- General Room Parameters ----- | | | | | | | | | | | |
|--|-----------------------|--------------|--------------|-------------|------------|---------------|-----------------------------|-----------------------|-----------------------------|--------------------------|-----------------|
| Room Number | Zone Reference Number | Room Descrip | Floor Length | Floor Width | Const Type | Plenum Height | Acoustic Ceiling Resistance | Floor to Floor Height | Duplicate Floors Multiplier | Duplicate Rooms per Zone | Perimeter Depth |
| 50 | 50 | BLDG 906 | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 55 | 55 | BLDG 924 | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 60 | 60 | BLDG 925 | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 65 | 65 | BLDG 916 | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 70 | 70 | BLDG 917 | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 75 | 75 | BLDG 930 | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 80 | 80 | BLDG 931 | 103 | 103 | 3 | 0 | 2.54 | 9.5 | | | |
| 85 | 85 | BLDG 908 | 46 | 46 | 3 | 1.5 | 2.54 | 10 | | | |
| 90 | 90 | BLDG 919 | 46 | 46 | 3 | 1.5 | 2.54 | 10 | | | |
| 95 | 95 | BLDG 922 | 46 | 46 | 3 | 1.5 | 2.54 | 10 | | | |
| 100 | 100 | BLDG 928 | 46 | 46 | 3 | 1.5 | 2.54 | 10 | | | |
| 105 | 105 | BLDG 902 | 136 | 137 | 3 | 4 | 2.54 | 13 | | | |

| Card 21----- | | | Thermostat Parameters ----- | | | | | | | |
|--------------|--------------|-------------|-----------------------------|----------------|--------------|----------------|----------------|----------|---------|--------|
| Room | Cooling Room | Room Design | Cooling T'stat | Cooling T'stat | Heating Room | Heating T'stat | Heating T'stat | T'stat | Mass / | Carpet |
| Number | Design DB | RH | Driftpoint | Schedule | Design DB | Driftpoint | Schedule | Location | No. Hrs | On |
| 5 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 10 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 15 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 20 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 25 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 30 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 35 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 40 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 45 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 50 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 55 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 60 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 65 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 70 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 75 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 80 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 85 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 90 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 95 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 100 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 105 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |

| Card 22----- Roof Parameters ----- | | | | | | | | | |
|------------------------------------|-------------|----------------------|-------------|------------|--------------|------------|----------------|-----------|------------|
| Room Number | Roof Number | Roof Equal to Floor? | Roof Length | Roof Width | Roof U-Value | Const Type | Roof Direction | Roof Tilt | Roof Alpha |
| 5 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |

Card 22----- Roof Parameters -----

| Roof | | | | | | | | | |
|-------------|-------------|-----------------|-------------|------------|--------------|------------|----------------|-----------|------------|
| Room Number | Roof Number | Equal to Floor? | Roof Length | Roof Width | Roof U-Value | Const Type | Roof Direction | Roof Tilt | Roof Alpha |
| 10 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 15 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 20 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 25 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 30 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 35 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 40 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 45 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 50 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 55 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 60 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 65 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 70 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 75 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 80 | 1 | | 59 | 60 | .08 | 26 | 0 | 90 | .74 |
| 85 | 1 | YES | | | .07 | 48 | 0 | 90 | .9 |
| 90 | 1 | YES | | | .07 | 48 | 0 | 90 | .9 |
| 95 | 1 | YES | | | .07 | 48 | 0 | 90 | .9 |
| 100 | 1 | YES | | | .07 | 48 | 0 | 90 | .9 |
| 105 | 1 | YES | | | .07 | 48 | 0 | 90 | .9 |

Card 24----- Wall Parameters -----

| Wall | | | | | | | | | | Ground |
|-------------|-------------|-------------|-------------|--------------|-------------------|----------------|-----------|------------|------------------|------------|
| Room Number | Wall Number | Wall Length | Wall Height | Wall U-Value | Wall Constuc Type | Wall Direction | Wall Tilt | Wall Alpha | Wall Reflectance | Multiplier |
| 5 | 1 | 275 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 5 | 2 | 108 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 5 | 3 | 275 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 5 | 4 | 108 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 10 | 1 | 275 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 10 | 2 | 108 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 10 | 3 | 275 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 10 | 4 | 108 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 15 | 1 | 275 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 15 | 2 | 108 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 15 | 3 | 275 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 15 | 4 | 108 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 20 | 1 | 275 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 20 | 2 | 108 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 20 | 3 | 275 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 20 | 4 | 108 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 25 | 1 | 275 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 25 | 2 | 108 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 25 | 3 | 275 | 9.5 | .11 | 58 | 180 | | .74 | | |

| Card 24----- Wall Parameters ----- | | | | | | | | | | |
|------------------------------------|--------|--------|--------|---------|---------|-----------|------|-------|-------------|------------|
| Room | Wall | Wall | Wall | Wall | Wall | Wall | Wall | Wall | Ground | |
| Number | Number | Length | Height | U-Value | Constuc | Direction | Tilt | Alpha | Reflectance | Multiplier |
| 25 | 4 | 108 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 30 | 1 | 275 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 30 | 2 | 108 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 30 | 3 | 275 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 30 | 4 | 108 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 35 | 1 | 275 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 35 | 2 | 108 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 35 | 3 | 275 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 35 | 4 | 108 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 40 | 1 | 275 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 40 | 2 | 108 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 40 | 3 | 275 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 40 | 4 | 108 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 45 | 1 | 275 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 45 | 2 | 108 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 45 | 3 | 275 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 45 | 4 | 108 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 50 | 1 | 275 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 50 | 2 | 108 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 50 | 3 | 275 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 50 | 4 | 108 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 55 | 1 | 275 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 55 | 2 | 108 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 55 | 3 | 275 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 55 | 4 | 108 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 60 | 1 | 275 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 60 | 2 | 108 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 60 | 3 | 275 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 60 | 4 | 108 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 65 | 1 | 275 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 65 | 2 | 108 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 65 | 3 | 275 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 65 | 4 | 108 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 70 | 1 | 275 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 70 | 2 | 108 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 70 | 3 | 275 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 70 | 4 | 108 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 75 | 1 | 275 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 75 | 2 | 108 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 75 | 3 | 275 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 75 | 4 | 108 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 80 | 1 | 275 | 9.5 | .11 | 58 | 90 | | .74 | | |
| 80 | 2 | 108 | 9.5 | .11 | 58 | 180 | | .74 | | |
| 80 | 3 | 275 | 9.5 | .11 | 58 | 270 | | .74 | | |
| 80 | 4 | 108 | 9.5 | .11 | 58 | 0 | | .74 | | |
| 85 | 1 | 46 | 10 | .10 | 58 | 0 | | .74 | | |
| 85 | 2 | 46 | 10 | .10 | 58 | 90 | | .74 | | |

Card 24----- Wall Parameters -----

| Room Number | Wall Number | Wall Length | Wall Height | Wall U-Value | Wall | | Wall Direction | Wall Tilt | Wall Alpha | Ground Reflectance Multiplier |
|-------------|-------------|-------------|-------------|--------------|---------|------|----------------|-----------|------------|-------------------------------|
| | | | | | Constuc | Type | | | | |
| 85 | 3 | 46 | 10 | .10 | 58 | | 180 | | .74 | |
| 85 | 4 | 46 | 10 | .10 | 58 | | 270 | | .74 | |
| 90 | 1 | 46 | 10 | .10 | 58 | | 0 | | .74 | |
| 90 | 2 | 46 | 10 | .10 | 58 | | 90 | | .74 | |
| 90 | 3 | 46 | 10 | .10 | 58 | | 180 | | .74 | |
| 90 | 4 | 46 | 10 | .10 | 58 | | 270 | | .74 | |
| 95 | 1 | 46 | 10 | .10 | 58 | | 0 | | .74 | |
| 95 | 2 | 46 | 10 | .10 | 58 | | 90 | | .74 | |
| 95 | 3 | 46 | 10 | .10 | 58 | | 180 | | .74 | |
| 95 | 4 | 46 | 10 | .10 | 58 | | 270 | | .74 | |
| 100 | 1 | 46 | 10 | .10 | 58 | | 0 | | .74 | |
| 100 | 2 | 46 | 10 | .10 | 58 | | 90 | | .74 | |
| 100 | 3 | 46 | 10 | .10 | 58 | | 180 | | .74 | |
| 100 | 4 | 46 | 10 | .10 | 58 | | 270 | | .74 | |
| 105 | 1 | 188 | 13 | .21 | 52 | | 0 | | .9 | |
| 105 | 2 | 188 | 13 | .21 | 52 | | 180 | | .9 | |
| 105 | 3 | 125 | 13 | .21 | 52 | | 270 | | .9 | |

Card 25----- Wall/Glass Parameters -----

| Room Number | Wall Number | Glass Length | Glass Width | Pct Glass | | Shading Coefficient | External Shading Type | Internal Shading Type | Percent Solar Ret. | Visible Air Transmittance | Inside Visible Reflectance |
|-------------|-------------|--------------|-------------|-------------------|---------------|---------------------|-----------------------|-----------------------|--------------------|---------------------------|----------------------------|
| | | | | or No. of Windows | Glass U-Value | | | | | | |
| 10 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 10 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 15 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 15 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 20 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 20 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 25 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 25 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 30 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 35 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 40 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 45 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 50 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 50 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 55 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 55 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 60 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 60 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 65 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 65 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 70 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 70 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 75 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |

| Card 25----- Wall/Glass Parameters ----- | | | | | | | | | | | |
|--|--------|--------|-------|-----------|---------|-------------|----------|----------|----------|---------------|-------------|
| Room | Wall | Glass | Glass | Pct Glass | Glass | Shading | External | Internal | Percent | Visible | Inside |
| Number | Number | Length | Width | or No. of | U-Value | Coefficient | Shading | Shading | Solar to | Transmittance | Visible |
| | | | | Windows | | | Type | Type | Ret. Air | | Reflectance |
| 75 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 80 | 1 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 80 | 3 | 4 | 2 | 54 | 1.1 | .67 | | | | | |
| 85 | 1 | 8 | 10 | 1 | 1.1 | .67 | | | | | |
| 85 | 2 | 8 | 4 | 2 | 1.1 | .67 | 3 | | | | |
| 85 | 4 | 8 | 4 | 2 | 1.1 | .67 | 3 | | | | |
| 90 | 1 | 8 | 10 | 1 | 1.1 | .67 | 3 | | | | |
| 90 | 2 | 8 | 4 | 2 | 1.1 | .67 | 3 | | | | |
| 90 | 4 | 8 | 4 | 2 | 1.1 | .67 | 3 | | | | |
| 95 | 1 | 8 | 10 | 1 | 1.1 | .67 | 3 | | | | |
| 95 | 2 | 8 | 4 | 2 | 1.1 | .67 | 3 | | | | |
| 95 | 4 | 8 | 4 | 2 | 1.1 | .67 | 3 | | | | |
| 100 | 1 | 8 | 10 | 1 | 1.1 | .67 | 3 | | | | |
| 100 | 2 | 8 | 4 | 2 | 1.1 | .67 | 3 | | | | |
| 100 | 4 | 8 | 4 | 2 | 1.1 | .67 | 3 | | | | |
| 105 | 1 | 2 | 4 | 7 | 1.1 | .67 | | | | | |
| 105 | 2 | 2 | 4 | 7 | 1.1 | .67 | | | | | |
| 105 | 3 | 2 | 4 | 2 | 1.1 | .67 | | | | | |

| Card 26----- Schedules ----- | | | | | | | | | | |
|------------------------------|----------|----------|-------------|--------------|---------|---------|---------|-----------|---------|-------------|
| Room | People | Lights | Ventilation | Infiltration | Reheat | Cooling | Heating | Auxiliary | Room | Daylighting |
| Number | | | | | Minimum | Fans | Fan | Fan | Exhaust | Controls |
| 5 | FSHBARRP | FSHBARRL | | | | | | | | |
| 10 | FSHBARRP | FSHBARRL | | | | | | | | |
| 15 | FSHBARRP | FSHBARRL | | | | | | | | |
| 20 | FSHBARRP | FSHBARRL | | | | | | | | |
| 25 | FSHBARRP | FSHBARRL | | | | | | | | |
| 30 | FSHBARRP | FSHBARRL | | | | | | | | |
| 35 | FSHBARRP | FSHBARRL | | | | | | | | |
| 40 | FSHBARRP | FSHBARRL | | | | | | | | |
| 45 | FSHBARRP | FSHBARRL | | | | | | | | |
| 50 | FSHBARRP | FSHBARRL | | | | | | | | |
| 55 | FSHBARRP | FSHBARRL | | | | | | | | |
| 60 | FSHBARRP | FSHBARRL | | | | | | | | |
| 65 | FSHBARRP | FSHBARRL | | | | | | | | |
| 70 | FSHBARRP | FSHBARRL | | | | | | | | |
| 75 | FSHBARRP | FSHBARRL | | | | | | | | |
| 80 | FSHBARRP | FSHBARRL | | | | | | | | |
| 85 | FSHOFFIC | FSHOFFIC | | | | | | | | |
| 90 | FSHOFFIC | FSHOFFIC | | | | | | | | |
| 95 | FSHBARRP | FSHBARRL | | | | | | | | |
| 100 | FSHBARRP | FSHBARRL | | | | | | | | |
| 105 | FSHOFFIC | FSHOFFIC | | | | | | | | |

Card 27----- People and Lights -----

| Room Number | People Value | People Units | People Sensible | People Latent | Lighting Value | Lighting Units | Lighting | | Ballast Factor | Percent Lights to Ret. Air | --- Daylighting --- | |
|-------------|--------------|--------------|-----------------|---------------|----------------|----------------|-----------------|--|----------------|----------------------------|---------------------|-------------------|
| | | | | | | | Fixture Type | | | | Reference Point 1 | Reference Point 2 |
| 5 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 10 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 15 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 20 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 25 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 30 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 35 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 40 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 45 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 50 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 55 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 60 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 65 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 70 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 75 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 80 | 53 | PEOPLE | 250 | 200 | 1 | | WATT-SF INCAND | | | | | |
| 85 | 10 | PEOPLE | 250 | 200 | 2.5 | | WATT-SF ASHRAE2 | | | | | |
| 90 | 10 | PEOPLE | 250 | 200 | 2.5 | | WATT-SF ASHRAE2 | | | | | |
| 95 | 10 | PEOPLE | 250 | 200 | 2.5 | | WATT-SF ASHRAE2 | | | | | |
| 100 | 10 | PEOPLE | 250 | 200 | 2.5 | | WATT-SF ASHRAE2 | | | | | |
| 105 | 96 | PEOPLE | 250 | 200 | 2.75 | | WATT-SF ASHRAE2 | | | | | |

Card 28----- Miscellaneous Equipment -----

| Room Number | Misc Equipment | | Energy Consump Value | Energy Consump Units | Schedule Code | Energy | | Percent of Load Sensible | Percent Misc. Load to Room | Percent Misc. Sens to Ret. Air | Radiant Fraction | Optional Air Path |
|-------------|----------------|----------|----------------------|----------------------|---------------|------------|--|--------------------------|----------------------------|--------------------------------|------------------|-------------------|
| | Number | Descrip | | | | Meter Code | | | | | | |
| 5 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 10 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 15 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 20 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 25 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 30 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 35 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 40 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 45 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 50 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 55 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 60 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 65 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 70 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 75 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 80 | 1 | BARREQ | .75 | | FSHBARRL | | | | | | | |
| 85 | 1 | COMPUTER | 1 | | FSHOFFIC | | | | | | | |
| 90 | 1 | COMPUTER | 1 | | FSHOFFIC | | | | | | | |
| 95 | 1 | COMPUTER | 1 | | FSHBARRL | | | | | | | |
| 100 | 1 | COMPUTER | 1 | | FSHBARRL | | | | | | | |
| 105 | 1 | COMPUTER | 1 | | FSHOFFIC | | | | | | | |

| Card 29-----Room Airflows----- | | | | | | | | | | |
|--------------------------------|-----------------|-------|-----------------|-------|------------------------|-------|-----------------|-------|--------------------|-------|
| -----Ventilation----- | | | | | -----Infiltration----- | | | | | |
| Room Number | ----Cooling---- | | ----Heating---- | | ----Cooling---- | | ----Heating---- | | --Reheat Minimum-- | |
| | Value | Units | Value | Units | Value | Units | Value | Units | Value | Units |
| 5 | | | | | 1440 | CFM | 1440 | CFM | | |
| 10 | | | | | 1440 | CFM | 1440 | CFM | | |
| 15 | | | | | 1440 | CFM | 1440 | CFM | | |
| 20 | | | | | 1440 | CFM | 1440 | CFM | | |
| 25 | | | | | 1440 | CFM | 1440 | CFM | | |
| 30 | | | | | 1440 | CFM | 1440 | CFM | | |
| 35 | | | | | 1440 | CFM | 1440 | CFM | | |
| 40 | | | | | 1440 | CFM | 1440 | CFM | | |
| 45 | | | | | 1440 | CFM | 1440 | CFM | | |
| 50 | | | | | 1440 | CFM | 1440 | CFM | | |
| 55 | | | | | 1440 | CFM | 1440 | CFM | | |
| 60 | | | | | 1440 | CFM | 1440 | CFM | | |
| 65 | | | | | 1440 | CFM | 1440 | CFM | | |
| 70 | | | | | 1440 | CFM | 1440 | CFM | | |
| 75 | | | | | 1440 | CFM | 1440 | CFM | | |
| 80 | | | | | 1440 | CFM | 1440 | CFM | | |
| 85 | 340 | CFM | 340 | CFM | | | | | | |
| 90 | 340 | CFM | 340 | CFM | | | | | | |
| 95 | 340 | CFM | 340 | CFM | | | | | | |
| 100 | 340 | CFM | 340 | CFM | | | | | | |
| 105 | 3580 | CFM | 3580 | CFM | | | | | | |

| Card 30-----Fan Airflows----- | | | | | | | | | | |
|-------------------------------|-----------------|-------|-----------------|-------|---------------------|-------|-----------------|-------|------------------|-------|
| -----Main----- | | | | | -----Auxiliary----- | | | | | |
| Room Number | ----Cooling---- | | ----Heating---- | | ----Cooling---- | | ----Heating---- | | --Room Exhaust-- | |
| | Value | Units | Value | Units | Value | Units | Value | Units | Value | Units |
| 5 | | | | | | | | | 1440 | CFM |
| 10 | | | | | | | | | 1440 | CFM |
| 15 | | | | | | | | | 1440 | CFM |
| 20 | | | | | | | | | 1440 | CFM |
| 25 | | | | | | | | | 1440 | CFM |
| 30 | | | | | | | | | 1440 | CFM |
| 35 | | | | | | | | | 1440 | CFM |
| 40 | | | | | | | | | 1440 | CFM |
| 45 | | | | | | | | | 1440 | CFM |
| 50 | | | | | | | | | 1440 | CFM |
| 55 | | | | | | | | | 1440 | CFM |
| 60 | | | | | | | | | 1440 | CFM |
| 65 | | | | | | | | | 1440 | CFM |
| 70 | | | | | | | | | 1440 | CFM |
| 75 | | | | | | | | | 1440 | CFM |
| 80 | | | | | | | | | 1440 | CFM |
| 85 | | | | | | | | | 325 | CFM |
| 90 | | | | | | | | | 325 | CFM |
| 95 | | | | | | | | | 325 | CFM |

Card 30----- Fan Airflows -----
 -----Main----- Auxiliary-----
 Room ---Cooling--- ---Heating--- ---Cooling--- ---Heating--- --Room Exhaust--
 Number Value Units Value Units Value Units Value Units Value Units
 100 325 CFM
 105 850 CFM

Card 31----- Partition Parameters -----
 Room Partition Partition Partition Partition Const Temp Cooling Heating Adjacent
 Number Number Length Height U-Value Type Flag Temp Temp Room No
 105 1 125 13 .09 101 HRLYOAD8

Card 33----- External Shading -----
 -----OVERHANG----- VERTICAL FINS-----
 Height Left Right Adjacent
 Shading Glass Above Projection Glass Projection Projection Projection Projection Building
 Type Height Glass Out Width Left Out Right Out Out Flag
 3 8 1 7 4 .5 7 .5 7

----- System Section Alternative #1 -----

Card 39- System Alternative
 Number Description
 1 EXISTING BUILDINGS

Card 40----- System Type -----
 -----OPTIONAL VENTILATION SYSTEM-----
 System Ventil Fan
 Set System Deck Cooling Heating Cooling Heating Static
 Number Type Location SADBvh SADBvh Schedule Schedule Pressure
 1 FC

Card 41----- Zone Assignment -----
 System
 Set Ref #1 Ref #2 Ref #3 Ref #4 Ref #5 Ref #6
 Number Begin End Begin End Begin End Begin End Begin End Begin End
 1 5 105

Card 42----- Fan SP and Duct Parameters-----
 System Cool Heat Return Mn Exh Aux Rm Exh Cool Return Supply Supply Return
 Set Fan Fan Fan Fan Fan Fan Fan Mtr Fan Mtr Duct Duct Air
 Number SP SP SP SP SP SP Loc Loc Ht Gn Loc Path
 1 .75 .75

Card 45----- Equipment Schedules -----
 System Main Direct Indirect Auxiliary Main Main Auxiliary
 Set Cooling Evap Evap Cooling Heating Preheat Reheat Mech. Heating
 Number Coil Economizer Coil Coil Coil Coil Coil Coil Humidity Coil
 1 FTSAMCLG FTSAMHTG FTSAMHTG FTSAMHTG

----- Equipment Section Alternative #1 -----

Card 59----- Equipment Description / TOD Schedules -----
 Elec Consump Elec Demand Demand ---- Demand Limit ---
 Alternative Time of Day Time of Day Limit Temperature
 Number Schedule Schedule Max KW Alternative Description Schedule Drift
 1 BASE CASE

Card 60----- Cooling Load Assignment-----
 Load All Coil Cooling
 Asgn Loads To Equipment -Group 1- -Group 2- -Group 3- -Group 4- -Group 5- -Group 6- -Group 7- -Group 8- -Group 9-
 Ref Cool Ref Sizing Begin End Begin End Begin End Begin End Begin End Begin End Begin End Begin End
 1 1 BLKPLANT 1 1

Card 62----- Cooling Equipment Parameters -----
 Cool Equip Num -----COOLING----- -----HEAT RECOVERY----- Seq Demand
 Ref Code Of --Capacity-- ----Energy---- --Capacity-- ----Energy---- Order Seq Limit
 Num Name Units Value Units Value Units Value Units Value Units Num Type Number
 1 EQ1001S 1 304 TONS 225 KW

Card 63----- Cooling Pumps and References -----
 Cool ---CHILLED WATER--- ----CONDENSER----- ---HT REC or AUX--- Switch-
 Ref Full Load Full Load Full Load Full Load Full Load Full Load over Cold Cooling Misc.
 Num Value Units Value Units Value Units Control Storage Tower Access.
 1 18.65 KW 11.19 KW 1

Card 65----- Heating Load Assignment -----
 Load All Coil
 Assignment Loads To -Group 1- -Group 2- -Group 3- -Group 4- -Group 5- -Group 6- -Group 7- -Group 8- -Group 9-
 Reference Heating Ref Begin End Begin End Begin End Begin End Begin End Begin End Begin End Begin End

Card 67----- Heating Equipment Parameters -----

| Heat Ref | Equip Code | Number Of | HW Pmp Full Ld | Cap'y | Energy Rate | Seq Order | Switch over | Hot Strg | Misc. Acc. | Cogen | Demand Limit |
|----------|------------|-----------|----------------|-------|-------------|-----------|-------------|----------|------------|---------|--------------|
| Number | Name | Units | Value | Units | Value | Units | Value | Units | Number | Control | Number |
| 1 | 900HEXIS | 1 | 3.73 | KW | 1665 | MBH | 2250 | MBH | 1 | | 1 |
| 2 | 900HEXIS | 1 | | | 1665 | MBH | 2250 | MBH | 2 | | |
| 3 | 900HEXIS | 1 | | | 1665 | MBH | 2250 | MBH | 3 | | |

Card 71----- Base Utility Parameters -----

| Base Utility | Base Utility | Hourly Demand | Hourly Demand | Schedule | Energy | Equip Reference | Demand Limiting | Entering Temp | Leaving Temp |
|--------------|------------------|---------------|---------------|----------|----------|-----------------|-----------------|---------------|--------------|
| Number | Descrip | Value | Units | Code | Type | Number | Number | Temp | Temp |
| 1 | DHW USE-LINE LOS | 608.2 | MBH | AVAIL | HOT-LD | 1 | | | |
| 2 | HT-PUMP LOSS CHL | 33.4 | TONS | FTSAMCLG | CHILL-LD | 1 | | | |

Card 74----- Condenser / Cooling Tower Parameters -----

| Tower Ref | Cooling Tower | Capacity Value | Capacity Units | Energy Consump | Energy Consump | Fluid Type | Tower Type | Number Of Cells | Percent Airflow | Low Spd Energy | Low Spd Energy |
|-----------|---------------|----------------|----------------|----------------|----------------|------------|------------|-----------------|-----------------|----------------|----------------|
| Ref | Code | Value | Units | Value | Units | Type | Type | Cells | Low Spd | Value | Units |
| 1 | EQ5100 | | | 11.19 | KW | | | 1 | | | |

Card 75----- Miscellaneous Accessory -----

| #1 | | | | #2 | | | | #3 | | | | |
|----------|------------|--------------|--------------|------------|------------|--------------|--------------|------------|------------|--------------|--------------|------------|
| Misc Ref | Equip Code | Energy Value | Energy Units | Sched Code | Equip Code | Energy Value | Energy Units | Sched Code | Equip Code | Energy Value | Energy Units | Sched Code |
| 1 | EQ5013 | 3.73 | KW | | EQ5013 | 1.49 | KW | | EQ5013 | 1.12 | KW | |

----- Equipment Section Alternative #2 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Time of Day | Time of Day | Limit | Alternative Description | Schedule | Temperature Drift |
|-------------|--------------|-------------|--------|-------------|-------------|--------|--|----------|-------------------|
| Number | Time of Day | Time of Day | Max KW | Schedule | Schedule | Max KW | Alternative Description | Schedule | Temperature Drift |
| 2 | | | | | | | GAS ENGINE DRIVEN CHILLER, EXIST. BOILER | | |

Card 60----- Cooling Load Assignment-----

| Load Ref | All Coil | Cooling | Equipment | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|----------|----------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Ref | Coil Ref | Sizing | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | BLKPLANT | 1 1 | | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | -----COOLING----- | | | | -----HEAT RECOVERY----- | | | | Seq | Demand | | |
|------------|----------|-------------------|-------|----------------|-------|-------------------------|-------|----------------|-------|-------|--------|-------|--------|
| Ref Code | Of | --Capacity-- | | ----Energy---- | | --Capacity-- | | ----Energy---- | | Order | Seq | Limit | |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Value | Units | Num | Type | Number |
| 1 | YENGDRIV | 1 | | | 1980 | MBH | | | | | | | |

Card 63----- Cooling Pumps and References -----

| Cool | ---CHILLED WATER--- | -----CONDENSER----- | ---HT REC or AUX--- | Switch- |
|------|---------------------|---------------------|---------------------|-----------|
| Ref | Full Load | Full Load | Full Load | Full Load |
| Num | Value | Units | Value | Units |
| 1 | 18.65 | KW | 11.19 | KW |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Equipment | Demand |
|---------|------------------|--------|--------|-----------|------------|
| Utility | Utility | Demand | Demand | Reference | Limiting |
| Number | Descrip | Value | Units | Code | Number |
| 1 | HT-PUMP LOSS CHL | 33.4 | TONS | FTSAMCLG | CHILL-LD 1 |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | Capacity | Capacity | Energy | Energy | Number | Percent | Low Spd | Low Spd |
|---------|----------|----------|--------|--------|--------|---------|---------|---------|
| Tower | Tower | Value | Units | Value | Units | Of | Airflow | Energy |
| Ref | Code | Value | Units | Value | Units | Type | Low Spd | Value |
| 1 | EQ5100 | | | 11.19 | KW | 1 | | |

----- Equipment Section Alternative #3 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | --- Demand Limit --- |
|-------------|--------------|-------------|--------|--|
| Number | Time of Day | Time of Day | Limit | Temperature |
| Number | Schedule | Schedule | Max KW | Schedule |
| 3 | | | | WATER COOLED SCREW CHILLER, EXIST BOILER |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling |
|------|----------|-----------|
| Asgn | Loads To | Equipment |
| Ref | Cool Ref | Sizing |
| 1 | 1 | BLKPLANT |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | COOLING | | | | HEAT RECOVERY | | | | Seq | Demand | | |
|------------|---------|----------|--------|----------|--------|---------------|-------|-------|-------|-------|--------|------|--------|
| Ref Code | Of | Capacity | Energy | Capacity | Energy | Order | Seq | Limit | | | | | |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Value | Units | Num | Type | Number |
| 1 | YSCRW22 | 1 | | | 186 | KW | | | | | | | |

Card 63----- Cooling Pumps and References -----

| Cool | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | over | Cold | Cooling | Misc. |
|------|-----------|-----------|-----------|-----------|-----------|-----------|---------|---------|---------|---------|
| Num | Value | Units | Value | Units | Value | Units | Control | Storage | Tower | Access. |
| 1 | 18.65 | KW | 11.19 | KW | | | | | 1 | |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Schedule | Energy | Equip | Demand | Limiting | Entering | Leaving |
|---------|------------------|--------|--------|----------|----------|-----------|----------|----------|----------|---------|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting | Entering | Leaving | |
| Number | Descrip | Units | Code | Type | Number | Number | Temp | Temp | | |
| 1 | HT-PUMP LOSS CHL | 33.4 | TONS | FTSAMCLG | CHILL-LD | 1 | | | | |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | Energy | Energy | Number | Percent | Low Spd | Low Spd |
|---------|---------|---------|--------|---------|---------|---------|
| Tower | Consump | Consump | Fluid | Tower | Of | Airflow |
| Ref | Code | Value | Units | Value | Units | Type |
| 1 | Eq5100 | 11.19 | KW | | | 1 |

----- Equipment Section Alternative #4 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Demand Limit | Temperature |
|-------------|--------------|-------------|--------|--------------|-------------|
| Number | Time of Day | Time of Day | Limit | Schedule | Drift |
| 4 | | | | | |

W. C. R-123 CENTR. CHILLER, EXIST BOILER

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Asgn | Loads To | Equipment | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| Ref | Cool Ref | Sizing | 1 | 1 | | | | | | | |
| 1 | 1 | BLKPLANT | 1 | 1 | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | -----COOLING----- | | | | -----HEAT RECOVERY----- | | | | Seq | Demand | |
|------------|----------|-------------------|----------------|-------|-------|-------------------------|----------------|-------|-------|-------|-----------|-------------|
| Ref Code | Of | --Capacity-- | ----Energy---- | | | --Capacity-- | ----Energy---- | | | Order | Seq Limit | |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Value | Units | Num | Type Number |
| 1 | YCENT123 | 1 | | | 177 | KW | | | | | | |

Card 63----- Cooling Pumps and References -----

| Cool | ---CHILLED WATER--- | | -----CONDENSER----- | | ---HT REC or AUX--- | | Switch- | | | | |
|------|---------------------|-----------|---------------------|-----------|---------------------|-----------|---------|---------|---------|---------|---|
| Ref | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | over | Cold | Cooling | Misc. | |
| Num | Value | Units | Value | Units | Value | Units | Control | Storage | Tower | Access. | |
| 1 | 18.65 | KW | 11.19 | KW | | | | | | | 1 |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | | Equip | Demand | | | |
|---------|------------------|--------|--------|----------|----------|-----------|----------|----------|---------|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting | Entering | Leaving |
| Number | Descrip | Value | Units | Code | Type | Number | Number | Temp | Temp |
| 1 | HT-PUMP LOSS CHL | 33.4 | TONS | FTSAMCLG | CHILL-LD | 1 | | | |

Card 74----- Condenser / Cooling Tower Parameters -----

| | Cooling | | | Energy | Energy | | | Number | Percent | Low Spd | Low Spd |
|-------|---------|----------|----------|---------|---------|-------|-------|--------|---------|---------|---------|
| Tower | Tower | Capacity | Capacity | Consump | Consump | Fluid | Tower | Of | Airflow | Energy | Energy |
| Ref | Code | Value | Units | Value | Units | Type | Type | Cells | Low Spd | Value | Units |
| 1 | EQ5100 | | | 11.19 | KW | | | 1 | | | |

Card 42----- Fan SP and Duct Parameters-----

| System | Cool | Heat | Return | Mn Exh | Aux | Rm Exh | Cool | Return | Supply | Supply | Return |
|--------|------|------|--------|--------|-----|--------|---------|---------|--------|--------|--------|
| Set | Fan | Fan | Fan | Fan | Fan | Fan | Fan Mtr | Fan Mtr | Duct | Duct | Air |
| Number | SP | SP | SP | SP | SP | SP | Loc | Loc | Ht Gn | Loc | Path |
| 1 | .75 | .75 | | | | | | | | | |

Card 45----- Equipment Schedules -----

| System | Main | Direct | Indirect | Auxiliary | Main | Main | Auxiliary |
|--------|----------|------------|----------|-----------|----------|----------|-----------|
| Set | Cooling | Evap | Evap | Cooling | Heating | Preheat | Reheat |
| Number | Coil | Economizer | Coil | Coil | Coil | Coil | Coil |
| 1 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG |

----- Equipment Section Alternative #1 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Time of Day | Time of Day | Limit | Temperature |
|-------------|--------------|-------------|--------|-------------------------|-------------|-------|-------------|
| Number | Schedule | Schedule | Max KW | Alternative Description | Schedule | Drift | |
| 1 | | | | BASE CASE | | | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | Asgn | Loads To | Equipment | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------|----------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Ref | Cool Ref | Sizing | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | BLKPLANT | 1 | 1 | | | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | ---COOLING--- | ---HEAT RECOVERY--- | Seq | Demand |
|------------|---------|---------------|---------------------|--------------|--------------|
| Ref Code | Of | --Capacity-- | ---Energy--- | --Capacity-- | ---Energy--- |
| Num | Name | Units | Value | Units | Value |
| 1 | E01001S | 1 | 304 | TONS | 225 |

Card 63----- Cooling Pumps and References -----

| Cool | ---CHILLED WATER--- | ---CONDENSER--- | ---HT REC or AUX--- | Switch- |
|------|---------------------|-----------------|---------------------|-----------|
| Ref | Full Load | Full Load | Full Load | Full Load |
| Num | Value | Units | Value | Units |
| 1 | 18.65 | KW | 11.19 | KW |

Card 65----- Heating Load Assignment -----

| Load | All Coil | Assignment | Loads To | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|-----------|-------------|------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Reference | Heating Ref | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| | | | | | | | | | | | | |

| Card 67----- Heating Equipment Parameters ----- | | | | | | | | | | | | | | |
|---|------------|-----------|----------------|-------|-------|-------|-------------|-------|-----------|-------------|------|------------|-------|---------------------|
| Heat Ref | Equip Code | Number Of | HW Pmp Full Ld | | Cap'y | | Energy Rate | | Seq Order | Switch over | Hot | Misc. Acc. | Cogen | Demand Limit Number |
| Number | Name | Units | Value | Units | Value | Units | Value | Units | Number | Control | Strg | | | |
| 1 | 900HEXIS | 1 | 3.73 | KW | 1665 | MBH | 2250 | MBH | 1 | | | 1 | | |
| 2 | 900HEXIS | 1 | | | 1665 | MBH | 2250 | MBH | 2 | | | | | |
| 3 | 900HEXIS | 1 | | | 1665 | MBH | 2250 | MBH | 3 | | | | | |

| Card 71----- Base Utility Parameters ----- | | | | | | | | | |
|--|------------------|---------------|---------------|---------------|-------------|-----------------|-----------------|---------------|--------------|
| Base Utility | Base Utility | Hourly Demand | Hourly Demand | Schedule Code | Energy Type | Equip Reference | Demand Limiting | Entering Temp | Leaving Temp |
| Number | Descrip | Value | Units | Code | Type | Number | Number | | |
| 1 | DHW USE-LINE LOS | 608.2 | MBH | AVAIL | HOT-LD | 1 | | | |
| 2 | HT-PUMP LOSS CHL | 33.4 | TONS | FTSAMCLG | CHILL-LD | 1 | | | |

| Card 74----- Condenser / Cooling Tower Parameters ----- | | | | | | | | | | | |
|---|--------|-------|----------|-------|-------|----------------|-------|------|------------|-----------------|-----------------|
| Cooling Tower | | | Capacity | | | Energy Consump | | | Fluid | | |
| Ref | Code | Value | Units | Value | Units | Value | Units | Type | Tower Type | Number Of Cells | Percent Airflow |
| 1 | EQ5100 | | | 11.19 | KW | | | | | 1 | |

| Card 75----- Miscellaneous Accessory ----- | | | | | | | | | | | |
|--|------------|--------------|--------------|------------|------------|--------------|--------------|------------|------------|--------------|--------------|
| #1 | | | | #2 | | | | #3 | | | |
| Misc Ref | Equip Code | Energy Value | Energy Units | Sched Code | Equip Code | Energy Value | Energy Units | Sched Code | Equip Code | Energy Value | Energy Units |
| 1 | EQ5013 | 3.73 | KW | | EQ5013 | 1.49 | KW | | EQ5013 | 1.12 | KW |

----- Equipment Section Alternative #2 -----

| Card 59----- Equipment Description / TOO Schedules ----- | | | | | | | | | |
|--|--------------|-------------|--------|--------|--|----------|-------------------|-----------------------|--|
| Alternative | Elec Consump | Elec Demand | Demand | | | | | ---- Demand Limit --- | |
| Number | Time of Day | Time of Day | Limit | Max KW | Alternative Description | Schedule | Temperature Drift | | |
| 2 | | | | | EXIST CHILLER, FORCE DRAFT HIGH BOILER | | | | |

| Card 65----- Heating Load Assignment ----- | | | | | | | | | | |
|--|----------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|---------------------|
| Load | All Coil | | | | | | | | | |
| Assignment Reference | Loads To Heating Ref | -Group 1- Begin End | -Group 2- Begin End | -Group 3- Begin End | -Group 4- Begin End | -Group 5- Begin End | -Group 6- Begin End | -Group 7- Begin End | -Group 8- Begin End | -Group 9- Begin End |
| 1 | 1 | 1 1 | | | | | | | | |

Card 67----- Heating Equipment Parameters -----

| Heat | Equip | Number | HW Pmp | Energy | Seq | Switch | Demand |
|--------|----------|--------|---------|--------|-------|--------|--------|
| Ref | Code | Of | Full Ld | Cap'y | Order | over | Limit |
| Number | Name | Units | Value | Units | Value | Units | Number |
| 1 | BOILHEFT | 1 | 3.73 | KW | 1758 | MBH | 2000 |
| | | | | | | | 1 |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Energy | Equip | Demand |
|---------|------------------|--------|--------|----------|-----------|----------|
| Utility | Utility | Demand | Demand | Schedule | Reference | Limiting |
| Number | Descrip | Value | Units | Code | Type | Number |
| 1 | DHW USE-LINE LOS | 608.2 | MBH | AVAIL | HOT-LD | 1 |

Card 75----- Miscellaneous Accessory -----

| #1 | | | | #2 | | | | #3 | | | | |
|------|--------|--------|--------|-------|--------|--------|--------|-------|--------|--------|--------|-------|
| Misc | Equip | Energy | Energy | Sched | Equip | Energy | Energy | Sched | Equip | Energy | Energy | Sched |
| Ref | Code | Value | Units | Code | Code | Value | Units | Code | Code | Value | Units | Code |
| 1 | E05013 | 3.73 | KW | | E05013 | 1.49 | KW | | E05013 | 1.12 | KW | |

----- Equipment Section Alternative #3 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Time of Day | Time of Day | Limit | Temperature |
|-------------|--------------|-------------|--------|--|-------------|-------|-------------|
| Number | Schedule | Schedule | Max KW | Alternative Description | Schedule | Drift | |
| 3 | | | | W. C. V.F.D. CENTR. CHILLER, EXIST BOILR | | | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Asgn | Loads To | Equipment | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| Ref | Cool Ref | Sizing | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | BLKPLANT | 1 | 1 | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | -----COOLING----- | -----HEAT RECOVERY----- | Seq | Demand |
|------------|---------|-------------------|-------------------------|-------|--------|
| Ref | Code | Of | Cap'y | Order | Seq |
| Num | Name | Units | Value | Units | Value |
| 1 | YCENVFD | 1 | 177 | KW | |

Card 63----- Cooling Pumps and References -----
Cool ---CHILLED WATER--- -----CONDENSER----- ---HT REC or AUX--- Switch-
Ref Full Load Full Load Full Load Full Load Full Load Full Load over Cold Cooling Misc.
Num Value Units Value Units Value Units Control Storage Tower Access.
1 18.65 KW 11.19 KW 1

Card 71----- Base Utility Parameters -----
Base Base Hourly Hourly Equip Demand
Utility Utility Demand Demand Schedule Energy Reference Limiting Entering Leaving
Number Descrip Value Units Code Type Number Number Temp Temp
1 HT-PUMP LOSS CHL 33.4 TONS FTSAMCLG CHILL-LD 1

Card 74----- Condenser / Cooling Tower Parameters -----
Cooling Energy Energy Number Percent Low Spd Low Spd
Tower Tower Capacity Capacity Consump Consump Fluid Tower Of Airflow Energy Energy
Ref Code Value Units Value Units Type Type Cells Low Spd Value Units
1 EQ5100 11.19 KW 1

```
*****
*****
**                                     **
**          TRACE 600 ANALYSIS          **
**                                     **
**          by HUITT & ZOLLARS          **
**                                     **
*****
*****
```

030185.04 EEAP BOILER-CHILLER STUDY
FT. SAM HOUSTON - SAN ANTONIO, TX.
CORPS. OF ENGINEERS - FORT WORTH, TX.
HUITT-ZOLLARS INC.

AREA 900

Weather File Code:

Location: SAN ANTONIO, TEXAS
Latitude: 29.0 (deg)
Longitude: 98.0 (deg)
Time Zone: 6
Elevation: 792 (ft)
Barometric Pressure: 29.0 (in. Hg)

Summer Clearness Number: 0.90
Winter Clearness Number: 0.90
Summer Design Dry Bulb: 97 (F)
Summer Design Wet Bulb: 76 (F)
Winter Design Dry Bulb: 30 (F)
Summer Ground Relectance: 0.20
Winter Ground Relectance: 0.20

Air Density: 0.0738 (Lbm/cuft)
Air Specific Heat: 0.2444 (Btu/lbm/F)
Density-Specific Heat Prod: 1.0818 (Btu-min./hr/cuft/F)
Latent Heat Factor: 4,761.9 (Btu-min./hr/cuft)
Enthalpy Factor: 4.4255 (Lb-min./hr/cuft)

Design Simulation Period: June To November
System Simulation Period: January To December
Cooling Load Methodology: TETD/Time Averaging

Time/Date Program was Run: 14:25:17 5/31/95
Dataset Name: FSH900 .TM

STEM TOTALS LOAD PROFILE - ALTERNATIVE 1
EXISTING BUILDINGS

----- SYSTEM LOAD PROFILE -----

System Totals

| Percent Design Load | ---- Cooling Load ---- | | | ----- Heating Load ----- | | |
|---------------------------|------------------------|--------------|-------|--------------------------|--------------|-------|
| | Cap. (Ton) | Hours (%) | Hours | Capacity (Btuh) | Hours (%) | Hours |
| 0 - 5 | 15.5 | 7 | 276 | -127,751 | 41 | 728 |
| 5 - 10 | 31.0 | 8 | 317 | -255,502 | 24 | 432 |
| 10 - 15 | 46.5 | 8 | 313 | -383,253 | 11 | 199 |
| 15 - 20 | 62.0 | 7 | 288 | -511,003 | 8 | 146 |
| 20 - 25 | 77.5 | 8 | 307 | -638,754 | 5 | 89 |
| 25 - 30 | 93.0 | 9 | 353 | -766,505 | 4 | 79 |
| 30 - 35 | 108.5 | 6 | 257 | -894,256 | 4 | 76 |
| 35 - 40 | 124.0 | 4 | 168 | -1,022,007 | 1 | 16 |
| 40 - 45 | 139.5 | 5 | 202 | -1,149,758 | 1 | 16 |
| 45 - 50 | 155.0 | 4 | 173 | -1,277,509 | 0 | 0 |
| 50 - 55 | 170.5 | 5 | 207 | -1,405,259 | 0 | 0 |
| 55 - 60 | 186.0 | 6 | 235 | -1,533,010 | 0 | 0 |
| 60 - 65 | 201.5 | 5 | 188 | -1,660,761 | 0 | 0 |
| 65 - 70 | 217.0 | 4 | 143 | -1,788,512 | 0 | 0 |
| 70 - 75 | 232.5 | 3 | 124 | -1,916,263 | 0 | 0 |
| 75 - 80 | 247.9 | 4 | 147 | -2,044,014 | 0 | 0 |
| 80 - 85 | 263.4 | 8 | 332 | -2,171,765 | 0 | 0 |
| 85 - 90 | 278.9 | 0 | 0 | -2,299,516 | 0 | 0 |
| 90 - 95 | 294.4 | 0 | 0 | -2,427,266 | 0 | 0 |
| 95 - 100 | 309.9 | 0 | 0 | -2,555,017 | 0 | 0 |
| Hours Off | 0.0 | 0 | 4,730 | 0 | 0 | 6,979 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|-------------------------------------|---------------------|-------|-------|-------|-------|-------|-------|--------|-------|-------|-------|-------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| | | | | | | | | | | | | | |
| 0 | LIGHTS | | | | | | | | | | | | |
| | ELEC | 42784 | 38686 | 42866 | 41391 | 42825 | 41473 | 42743 | 42866 | 41391 | 42825 | 41473 | 42375 |
| | PK | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 |
| | | | | | | | | | | | | | |
| 1 | MISC LD | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | |
| 2 | MISC LD | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | |
| 3 | MISC LD | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | |
| 4 | MISC LD | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | |
| 5 | MISC LD | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | |
| 6 | MISC LD | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | |
| 1 | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 4525 | 4087 | 4525 | 4379 | 4525 | 4379 | 4525 | 4525 | 4379 | 4525 | 4379 | 4525 |
| | PK | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 |
| | | | | | | | | | | | | | |
| 2 | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 24850 | 24048 | 24850 | 24850 | 24048 | 24850 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 33.4 | 33.4 | 33.4 | 33.4 | 33.4 | 33.4 | 0.0 | 0.0 |
| | | | | | | | | | | | | | |
| 1 | 2-STG CENTRIFUGAL CHILLER <550 TONS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 62585 | 78816 | 95844 | 100025 | 69899 | 36888 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 202.4 | 202.7 | 223.5 | 225.8 | 208.0 | 115.8 | 0.0 | 0.0 |
| | | | | | | | | | | | | | |
| 1 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 8325 | 8057 | 8325 | 8325 | 8057 | 4420 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | | |
|------------------------------|--------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|--------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 337 | 432 | 526 | 544 | 381 | 183 | 0 | 0 | 2,403 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.2 | 1.1 | 1.2 | 1.2 | 1.1 | 0.7 | 0.0 | 0.0 | 1.2 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13876 | 13428 | 13876 | 13876 | 13428 | 13876 | 0 | 0 | 82,358 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 0.0 | 0.0 | 18.6 |
| 1 | EQ5010 | CONDENSER WATER PUMP-CV(HIGH EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 8325 | 8057 | 8325 | 8325 | 8057 | 8325 | 0 | 0 | 49,415 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 11.2 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 1 | | NATURAL DRAFT, WATER TUBE BOILER | | | | | | | | | | | | |
| | GAS | 7875 | 7951 | 6205 | 5921 | 6115 | 5918 | 6115 | 6115 | 5918 | 6115 | 6024 | 7815 | 78,086 |
| | PK | 19.1 | 22.5 | 10.2 | 8.8 | 8.2 | 8.2 | 8.2 | 8.2 | 8.2 | 8.2 | 10.1 | 19.7 | 22.5 |
| 1 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 2775 | 2507 | 2775 | 2686 | 2775 | 2686 | 2775 | 2775 | 2686 | 2775 | 2686 | 2775 | 32,675 |
| | PK | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 |
| 1 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 93 | 90 | 93 | 93 | 90 | 93 | 90 | 93 | 1,095 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 |
| 1 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 2775 | 2507 | 2775 | 2686 | 2775 | 2686 | 2775 | 2775 | 2686 | 2775 | 2686 | 2775 | 32,675 |
| | PK | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 |
| 1 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 1109 | 1001 | 1109 | 1073 | 1109 | 1073 | 1109 | 1109 | 1073 | 1109 | 1073 | 1109 | 13,052 |
| | PK | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 |
| 1 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 833 | 753 | 833 | 806 | 833 | 806 | 833 | 833 | 806 | 833 | 806 | 833 | 9,811 |
| | PK | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 |
| 2 | | NATURAL DRAFT, WATER TUBE BOILER | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
GAS ENGINE DRIVEN CHILLER, EXIST. BOILER

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|----------|----------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 42784 | 38686 | 42866 | 41391 | 42825 | 41473 | 42743 | 42866 | 41391 | 42825 | 41473 | 42375 | 503,698 |
| | PK | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 24850 | 24048 | 24850 | 24850 | 24048 | 24850 | 0 | 0 | 147,494 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 33.4 | 33.4 | 33.4 | 33.4 | 33.4 | 33.4 | 0.0 | 0.0 | 33.4 |
| 1 | | YORK ENGINE DRIVEN CHILLER | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 4756 | 5968 | 7287 | 7671 | 5326 | 2853 | 0 | 0 | 33,862 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 16.1 | 15.6 | 18.7 | 19.6 | 16.0 | 8.1 | 0.0 | 0.0 | 19.6 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 8325 | 8057 | 8325 | 8325 | 8057 | 4262 | 0 | 0 | 45,352 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 11.2 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 365 | 467 | 569 | 591 | 412 | 200 | 0 | 0 | 2,604 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.3 | 1.2 | 1.4 | 1.4 | 1.2 | 0.8 | 0.0 | 0.0 | 1.4 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
3 ENGINE DRIVEN CHILLER, EXIST. BOILER

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|--------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13876 | 13428 | 13876 | 13876 | 13428 | 13876 | 0 | 0 | 82,358 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 0.0 | 0.0 | 18.6 |
| 1 | EQ5011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 8325 | 8057 | 8325 | 8325 | 8057 | 8325 | 0 | 0 | 49,415 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 11.2 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
WATER COOLED SCREW CHILLER, EXIST BOILER

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | | |
|------------------------------|----------|------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 42784 | 38686 | 42866 | 41391 | 42825 | 41473 | 42743 | 42866 | 41391 | 42825 | 41473 | 42375 | 503,698 |
| | PK | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 24850 | 24048 | 24850 | 24850 | 24048 | 24850 | 0 | 0 | 147,494 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 33.4 | 33.4 | 33.4 | 33.4 | 33.4 | 33.4 | 0.0 | 0.0 | 33.4 |
| 1 | YSCRW22 | YORK W.C. SCREW CHILL. | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 44600 | 56032 | 67754 | 70890 | 48770 | 28993 | 0 | 0 | 317,039 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 163.7 | 150.3 | 176.9 | 184.9 | 154.6 | 76.2 | 0.0 | 0.0 | 184.9 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 8325 | 8057 | 8325 | 8325 | 8057 | 4354 | 0 | 0 | 45,444 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 11.2 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 320 | 411 | 501 | 518 | 361 | 175 | 0 | 0 | 2,287 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.2 | 1.1 | 1.2 | 1.2 | 1.1 | 0.7 | 0.0 | 0.0 | 1.2 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
WATER COOLED SCREW CHILLER, EXIST BOILER

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|--------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13876 | 13428 | 13876 | 13876 | 13428 | 13876 | 0 | 0 | 82,358 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 0.0 | 0.0 | 18.6 |
| 1 | EQ5011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 8325 | 8057 | 8325 | 8325 | 8057 | 8325 | 0 | 0 | 49,415 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 11.2 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 4
C. R-123 CENTR. CHILLER, EXIST BOILER

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | | |
|------------------------------|--------------------------|---------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 42784 | 38686 | 42866 | 41391 | 42825 | 41473 | 42743 | 42866 | 41391 | 42825 | 41473 | 42375 | 503,698 |
| | PK | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | BASE UTILITY | | | | | | | | | | | | | |
| | CHILLO | 0 | 0 | 0 | 0 | 24850 | 24048 | 24850 | 24850 | 24048 | 24850 | 0 | 0 | 147,494 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 33.4 | 33.4 | 33.4 | 33.4 | 33.4 | 33.4 | 0.0 | 0.0 | 33.4 |
| 1 | YORK CENT. R-123 CHILLER | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 45712 | 56332 | 67955 | 70957 | 50302 | 28814 | 0 | 0 | 320,072 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 155.7 | 143.0 | 168.4 | 175.9 | 147.1 | 80.7 | 0.0 | 0.0 | 175.9 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 8325 | 8057 | 8325 | 8325 | 8057 | 4351 | 0 | 0 | 45,441 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 11.2 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 321 | 411 | 501 | 518 | 363 | 175 | 0 | 0 | 2,290 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.2 | 1.1 | 1.2 | 1.2 | 1.1 | 0.7 | 0.0 | 0.0 | 1.2 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 4
C. R-123 CENTR. CHILLER, EXIST BOILER

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|--------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 1 | E05001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13876 | 13428 | 13876 | 13876 | 13428 | 13876 | 0 | 0 | 82,358 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 0.0 | 0.0 | 18.6 |
| 1 | E05011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 8325 | 8057 | 8325 | 8325 | 8057 | 8325 | 0 | 0 | 49,415 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 11.2 |
| 1 | E05300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
C. V.F.D. CENTR. CHILLER, EXIST BOILR

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | | |
|------------------------------|----------|---------------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 42784 | 38686 | 42866 | 41391 | 42825 | 41473 | 42743 | 42866 | 41391 | 42825 | 41473 | 42375 | 503,698 |
| | PK | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTW2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 24850 | 24048 | 24850 | 24850 | 24048 | 24850 | 0 | 0 | 147,494 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 33.4 | 33.4 | 33.4 | 33.4 | 33.4 | 33.4 | 0.0 | 0.0 | 33.4 |
| 1 | YCENVFD | YORK TURBO MODULATOR VAR. FREQ. DRIVE | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 40210 | 51150 | 62895 | 66342 | 45212 | 23500 | 0 | 0 | 289,309 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 144.1 | 138.0 | 166.7 | 175.3 | 141.8 | 69.5 | 0.0 | 0.0 | 175.3 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 8325 | 8057 | 8325 | 8325 | 8057 | 4311 | 0 | 0 | 45,401 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 11.2 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 316 | 407 | 496 | 514 | 358 | 170 | 0 | 0 | 2,262 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.2 | 1.0 | 1.2 | 1.2 | 1.1 | 0.7 | 0.0 | 0.0 | 1.2 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
C. V.F.D. CENTR. CHILLER, EXIST BOILR

| ----- E Q U I P M E N T E N E R G Y C O N S U M P T I O N ----- | | | | | | | | | | | | | | |
|---|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|--------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13876 | 13428 | 13876 | 13876 | 13428 | 13876 | 0 | 0 | 82,358 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 0.0 | 0.0 | 18.6 |
| 1 | EQ5011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 8325 | 8057 | 8325 | 8325 | 8057 | 8325 | 0 | 0 | 49,415 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 11.2 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
WATER CHILLER, FORCE DRAFT HIGH % BOILER

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | | |
|------------------------------|----------|--|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 42784 | 38686 | 42866 | 41391 | 42825 | 41473 | 42743 | 42866 | 41391 | 42825 | 41473 | 42375 | 503,698 |
| | PK | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 | 152.0 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 4525 | 4087 | 4525 | 4379 | 4525 | 4379 | 4525 | 4525 | 4379 | 4525 | 4379 | 4525 | 53,278 |
| | PK | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 | 6.1 |
| 1 | | HIGH EFFICIENCY MODULAR FIRETUBE BOIL. | | | | | | | | | | | | |
| | GAS | 6629 | 6694 | 5224 | 4985 | 5148 | 4982 | 5148 | 5148 | 4982 | 5148 | 5071 | 6579 | 65,738 |
| | PK | 16.1 | 19.2 | 8.6 | 7.4 | 6.9 | 6.9 | 6.9 | 6.9 | 6.9 | 6.9 | 8.5 | 16.6 | 19.2 |
| 1 | | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 2775 | 2507 | 2775 | 2686 | 2775 | 2686 | 2775 | 2775 | 2686 | 2775 | 2686 | 2775 | 32,675 |
| | PK | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 |
| 1 | | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 93 | 90 | 93 | 93 | 90 | 93 | 90 | 93 | 1,095 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
WATER CHILLER, FORCE DRAFT HIGH % BOILER

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|------|------|------|------|------|------|------|------|------|------|------|--------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 1 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 2775 | 2507 | 2775 | 2686 | 2775 | 2686 | 2775 | 2775 | 2686 | 2775 | 2686 | 2775 | 32,675 |
| | PK | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 |
| 1 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 1109 | 1001 | 1109 | 1073 | 1109 | 1073 | 1109 | 1109 | 1073 | 1109 | 1073 | 1109 | 13,052 |
| | PK | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 |
| 1 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 833 | 753 | 833 | 806 | 833 | 806 | 833 | 833 | 806 | 833 | 806 | 833 | 9,811 |
| | PK | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 |

01 Card - Job Information

Project: 03018504 BOILER-CHILLER STUDY
 Location: FT. SAM HOUSTON - SAN ANTONIO, TX.
 Client: CORPS OF ENGINEERS - FT. WORTH, TEXAS
 Program User: HUITT - ZOLLARS INC.
 Comments: AREA 1300

Card 08----- Climatic Information -----

| Weather | Summer Clearness | Winter Clearness | Summer Design | Summer Design | Winter Design | Building Orientation | Summer Ground Reflect | Winter Ground Reflect |
|---------|---------------------|---------------------|------------------|------------------|------------------|-------------------------|-----------------------------|-----------------------------|
| Code | Number | Number | Dry Bulb | Wet Bulb | Dry Bulb | | | |

SANANTON

Card 11----- Energy Simulation Parameters -----

| 1st Month | Last Month | Level | Building |
|------------|------------|-------------|------------------------|
| Energy | Energy | Of | Holiday Calendar Floor |
| Simulation | Simulation | Calculation | Code Code Area |

ARMY1994

----- Load Section Alternative #1 -----

Card 19- Load Alternative -

| Number | Description |
|--------|------------------------------|
| 1 | AREA 1300 EXISTING BUILDINGS |

Card 20----- General Room Parameters -----

| Room Number | Zone Reference Number | Room Descrip | Floor Length | Floor Width | Const Type | Plenum Height | Acoustic Ceiling Resistance | Floor to Floor Height | Duplicate Floors Multiplier | Duplicate Rooms per Zone | Perimeter Depth |
|----------------|-----------------------------|-----------------|-----------------|----------------|---------------|------------------|-----------------------------------|-----------------------------|-----------------------------------|--------------------------------|--------------------|
| 5 | 5 | ADMIN 1350 | 179 | 180 | 3 | 3 | 2.54 | 12.5 | | | |
| 10 | 10 | DINING 1350 | 107 | 108 | 3 | 3 | 2.54 | 12.5 | | | |
| 15 | 15 | KITCHEN 1350 | 69 | 69 | 3 | 3 | 2.54 | 12.5 | | | |
| 20 | 20 | BARR 1350 | 398 | 399 | 3 | 3 | 2.54 | 12.5 | | | |
| 25 | 25 | ADMIN 1374 | 100 | 100 | 3 | 4 | 2.54 | 13 | | | |
| 30 | 30 | BARR 1374 | 240 | 240 | 3 | 4 | 2.54 | 13 | | | |
| 35 | 35 | ADMIN 1375 | 100 | 100 | 3 | 4 | 2.54 | 13 | | | |
| 40 | 40 | BARR 1375 | 240 | 240 | 3 | 4 | 2.54 | 13 | | | |
| 45 | 45 | ADMIN 1379 | 100 | 100 | 3 | 4 | 2.54 | 13 | | | |

| Card 20----- General Room Parameters ----- | | | | | | | | | | | |
|--|-----------------------|--------------|--------------|-------------|------------|---------------|-----------------------------|-------------------------|-----------------------------|--------------------------|-----------------|
| Room Number | Zone Reference Number | Room Descrip | Floor Length | Floor Width | Const Type | Plenum Height | Acoustic Ceiling Resistance | Floor to Ceiling Height | Duplicate Floors Multiplier | Duplicate Rooms per Zone | Perimeter Depth |
| 50 | 50 | BARR 1379 | 240 | 240 | 3 | 4 | 2.54 | 13 | | | |
| 55 | 55 | ADMIN 1380 | 100 | 100 | 3 | 4 | 2.54 | 13 | | | |
| 60 | 60 | BARR 1380 | 240 | 240 | 3 | 4 | 2.54 | 13 | | | |
| 65 | 65 | BLDG. 1385 | 82 | 62 | 3 | 3.5 | 2.54 | 12 | | | |
| 70 | 70 | ADMIN 1382 | 60 | 60 | 3 | 4 | 2.54 | 12 | | | |
| 75 | 75 | BARR 1382 | 161 | 161 | 3 | 2 | 2.54 | 10.5 | | | |
| 80 | 80 | KITCH 1377 | 100 | 100 | 3 | 3 | 2.54 | 12 | | | |
| 85 | 85 | DIN 1377 | 116 | 116 | 3 | 3 | 2.54 | 12 | | | |

| Card 21----- Thermostat Parameters ----- | | | | | | | | | | | |
|--|------------------------|----------------|---------------------------|-------------------------|------------------------|---------------------------|-------------------------|----------------------|----------------|-----------|-------|
| Room Number | Cooling Room Design DB | Room Design RH | Cooling T'stat Driftpoint | Cooling T'stat Schedule | Heating Room Design DB | Heating T'stat Driftpoint | Heating T'stat Schedule | T'stat Location Flag | Mass / No. Hrs | Carpet On | Floor |
| 5 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | YES | |
| 10 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 15 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 20 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 25 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 30 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 35 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 40 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 45 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 50 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 55 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 60 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 65 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 70 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 75 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 80 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 85 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |

| Card 22----- Roof Parameters ----- | | | | | | | | | |
|------------------------------------|-------------|----------------------|-------------|------------|--------------|------------|----------------|-----------|------------|
| Room Number | Roof Number | Roof Equal to Floor? | Roof Length | Roof Width | Roof U-Value | Const Type | Roof Direction | Roof Tilt | Roof Alpha |
| 5 | 1 | NO | 164 | 163 | 0.05 | 21 | | | |
| 10 | 1 | YES | | | 0.05 | 21 | | | |
| 15 | 1 | YES | | | 0.05 | 21 | | | |
| 20 | 1 | NO | 282 | 282 | 0.05 | 21 | | | |
| 25 | 1 | NO | 88 | 30 | 0.07 | 43 | | | |
| 30 | 1 | NO | 164 | 164 | 0.07 | 43 | | | |
| 35 | 1 | NO | 88 | 30 | 0.07 | 43 | | | |
| 40 | 1 | NO | 164 | 164 | 0.07 | 43 | | | |

Card 22----- Roof Parameters -----

| Room Number | Roof Number | Roof | | Roof Width | Roof U-Value | Const Type | Roof Direction | Roof Tilt | Roof Alpha |
|----------------|----------------|--------------------|--------|---------------|-----------------|---------------|-------------------|--------------|---------------|
| | | Equal to Floor? | Length | | | | | | |
| 45 | 1 | NO | 88 | 30 | .07 | 43 | | | |
| 50 | 1 | NO | 164 | 164 | 0.07 | 43 | | | |
| 55 | 1 | NO | 83 | 30 | 0.07 | 43 | | | |
| 60 | 1 | NO | 164 | 164 | 0.07 | 43 | | | |
| 65 | 1 | YES | | | 0.08 | 47 | | | |
| 70 | 1 | YES | | | 0.07 | 37 | | | |
| 75 | 1 | NO | 114 | 114 | 0.07 | 37 | | | |
| 80 | 1 | YES | | | 0.11 | 47 | | | |
| 85 | 1 | YES | | | 0.11 | 47 | | | |

Card 24----- Wall Parameters -----

| Room Number | Wall Number | Wall Length | Wall Height | Wall U-Value | Wall Constuc Type | Wall Direction | Wall Tilt | Wall Alpha | Ground Reflectance |
|----------------|----------------|----------------|----------------|-----------------|-------------------------|-------------------|--------------|---------------|-----------------------|
| | | | | | | | | | Multiplier |
| 5 | 1 | 128 | 12.5 | .15 | 29 | 0 | | | |
| 20 | 1 | 1130 | 12.5 | .15 | 29 | 0 | | | |
| 20 | 2 | 1400 | 12.5 | .15 | 29 | 90 | | | |
| 20 | 3 | 1130 | 12.5 | .15 | 29 | 180 | | | |
| 20 | 4 | 1400 | 12.5 | .15 | 29 | 270 | | | |
| 25 | 1 | 88 | 13 | .15 | 94 | 180 | | | |
| 25 | 2 | 40 | 13 | .20 | 61 | 270 | | | |
| 25 | 3 | 40 | 13 | .20 | 61 | 90 | | | |
| 30 | 1 | 912 | 13 | .13 | 80 | 180 | | .74 | |
| 30 | 2 | 768 | 13 | .13 | 80 | 270 | | .74 | |
| 30 | 3 | 912 | 13 | .13 | 80 | 0 | | .74 | |
| 30 | 4 | 768 | 13 | .13 | 80 | 90 | | .74 | |
| 35 | 1 | 88 | 13 | .15 | 94 | 180 | | | |
| 35 | 2 | 40 | 13 | .20 | 61 | 270 | | | |
| 35 | 3 | 40 | 13 | .20 | 61 | 90 | | | |
| 40 | 1 | 912 | 13 | .13 | 80 | 180 | | .74 | |
| 40 | 2 | 768 | 13 | .13 | 80 | 270 | | .74 | |
| 40 | 3 | 912 | 13 | .13 | 80 | 0 | | .74 | |
| 40 | 4 | 768 | 13 | .13 | 80 | 90 | | .74 | |
| 45 | 1 | 88 | 13 | .15 | 94 | 0 | | | |
| 45 | 2 | 40 | 13 | .20 | 61 | 90 | | | |
| 45 | 3 | 40 | 13 | .20 | 61 | 270 | | | |
| 50 | 1 | 912 | 13 | .13 | 80 | 0 | | .74 | |
| 50 | 2 | 768 | 13 | .13 | 80 | 90 | | .74 | |
| 50 | 3 | 912 | 13 | .13 | 80 | 180 | | .74 | |
| 50 | 4 | 768 | 13 | .13 | 80 | 270 | | .74 | |
| 55 | 1 | 88 | 13 | .15 | 94 | 0 | | | |
| 55 | 2 | 40 | 13 | .20 | 61 | 90 | | | |
| 55 | 3 | 40 | 13 | .20 | 61 | 270 | | | |
| 60 | 1 | 912 | 13 | .13 | 80 | 0 | | .74 | |
| 60 | 2 | 768 | 13 | .13 | 80 | 90 | | .74 | |

Card 24----- Wall Parameters -----

| Room | Wall | Wall | Wall | Wall | Wall | Wall | Wall | Wall | Ground |
|--------|--------|--------|--------|---------|------|-----------|------|-------|------------------------|
| Number | Number | Length | Height | U-Value | Type | Direction | Tilt | Alpha | Reflectance Multiplier |
| 60 | 3 | 912 | 13 | .13 | 80 | 180 | | .74 | |
| 60 | 4 | 768 | 13 | .13 | 80 | 270 | | .74 | |
| 65 | 1 | 82 | 12 | .22 | 58 | 0 | | | |
| 65 | 2 | 62 | 12 | .22 | 58 | 90 | | | |
| 65 | 3 | 82 | 12 | .22 | 58 | 180 | | | |
| 65 | 4 | 62 | 12 | .22 | 58 | 270 | | | |
| 70 | 1 | 44 | 12 | .22 | 58 | 0 | | | |
| 70 | 2 | 52 | 12 | .22 | 58 | 90 | | | |
| 70 | 3 | 68 | 12 | .22 | 58 | 270 | | | |
| 75 | 1 | 360 | 10.5 | .22 | 58 | 0 | | | |
| 75 | 2 | 312 | 10.5 | .22 | 58 | 90 | | | |
| 75 | 3 | 412 | 10.5 | .22 | 58 | 180 | | | |
| 75 | 4 | 312 | 10.5 | .22 | 58 | 270 | | | |
| 80 | 1 | 62 | 12 | .10 | 58 | 90 | | | |
| 80 | 2 | 32 | 12 | .10 | 58 | 270 | | | |
| 85 | 1 | 82 | 12 | .10 | 58 | 0 | | | |
| 85 | 2 | 160 | 12 | .10 | 58 | 90 | | | |
| 85 | 3 | 82 | 12 | .10 | 58 | 180 | | | |
| 85 | 4 | 124 | 12 | .10 | 58 | 270 | | | |

Card 25----- Wall/Glass Parameters -----

| Room | Wall | Glass | Glass | Pct Glass | Glass | Shading | External | Internal | Percent | Visible | Inside |
|--------|--------|--------|-------|-----------|---------|-------------|--------------|--------------|-------------------|---------------|---------------------|
| Number | Number | Length | Width | or No. of | U-Value | Coefficient | Shading Type | Shading Type | Solar to Ret. Air | Transmittance | Visible Reflectance |
| 5 | 1 | 4 | 5.5 | 12 | .73 | 1 | | | | | |
| 20 | 1 | 4 | 5.5 | 272 | .73 | 1 | 3 | | | | |
| 20 | 2 | 4 | 5.5 | 84 | .73 | 1 | 3 | | | | |
| 20 | 3 | 4 | 5.5 | 272 | .73 | 1 | 3 | | | | |
| 20 | 4 | 4 | 5.5 | 84 | .73 | 1 | 3 | | | | |
| 25 | 1 | 4 | 7 | 16 | 1.1 | .67 | 4 | | | | |
| 30 | 1 | 2 | 4 | 144 | 1.1 | .67 | 4 | | | | |
| 30 | 2 | 2 | 4 | 72 | 1.1 | .67 | 4 | | | | |
| 30 | 3 | 2 | 4 | 116 | 1.1 | .67 | 4 | | | | |
| 30 | 4 | 2 | 4 | 72 | 1.1 | .67 | 4 | | | | |
| 35 | 1 | 4 | 7 | 16 | 1.1 | .67 | 4 | | | | |
| 40 | 1 | 2 | 4 | 144 | 1.1 | .67 | 4 | | | | |
| 40 | 2 | 2 | 4 | 72 | 1.1 | .67 | 4 | | | | |
| 40 | 3 | 2 | 4 | 116 | 1.1 | .67 | 4 | | | | |
| 40 | 4 | 2 | 4 | 72 | 1.1 | .67 | 4 | | | | |
| 45 | 1 | 4 | 7 | 16 | 1.1 | .67 | 4 | | | | |
| 50 | 1 | 2 | 4 | 144 | 1.1 | .67 | 4 | | | | |
| 50 | 2 | 2 | 4 | 72 | 1.1 | .67 | 4 | | | | |
| 50 | 3 | 2 | 4 | 116 | 1.1 | .67 | 4 | | | | |
| 50 | 4 | 2 | 4 | 72 | 1.1 | .67 | 4 | | | | |
| 55 | 1 | 4 | 7 | 16 | 1.1 | .67 | 4 | | | | |

| Card 25----- Wall/Glass Parameters ----- | | | | | | | | | | | | |
|--|----------------|-----------------|----------------|----------------------|------------------|------------------------|-----------------------------|-----------------------------|----------------------|---------|--------------------------|----------------------------------|
| Room Number | Wall Number | Glass Length | Glass Width | Pct Glass | | Shading Coefficient | External Shading Type | Internal Shading Type | Percent | | Visible Transmittance | Inside Visible Reflectance |
| | | | | or No. of Windows | Glass U-Value | | | | Solar to Ret. Air | Visible | | |
| 60 | 1 | 2 | 4 | 144 | 1.1 | .67 | 4 | | | | | |
| 60 | 2 | 2 | 4 | 72 | 1.1 | .67 | 4 | | | | | |
| 60 | 3 | 2 | 4 | 116 | 1.1 | .67 | 4 | | | | | |
| 60 | 4 | 2 | 4 | 72 | 1.1 | .67 | 4 | | | | | |
| 65 | 1 | 4 | 4 | 8 | 1.1 | 1 | 5 | | | | | |
| 65 | 2 | 4 | 4 | 8 | 1.1 | 1 | 5 | | | | | |
| 65 | 3 | 4 | 4 | 6 | 1.1 | 1 | 5 | | | | | |
| 65 | 4 | 4 | 4 | 8 | 1.1 | 1 | 5 | | | | | |
| 70 | 1 | 5 | 3 | 7 | 1.1 | 1 | | | | | | |
| 70 | 2 | 5 | 3 | 1 | 1.1 | 1 | | | | | | |
| 75 | 1 | 6 | 3 | 23 | 1.1 | 1 | | | | | | |
| 75 | 2 | 6 | 3 | 16 | 1.1 | 1 | | | | | | |
| 75 | 3 | 6 | 3 | 24 | 1.1 | 1 | | | | | | |
| 75 | 4 | 6 | 3 | 14 | 1.1 | 1 | | | | | | |
| 85 | 2 | 5 | 5 | 6 | 1.1 | 1 | | | | | | |
| 85 | 4 | 5 | 5 | 6 | 1.1 | 1 | | | | | | |

| Card 26----- Schedules ----- | | | | | | | | | | | |
|------------------------------|----------|----------|-------------|--------------|-------------------|-----------------|----------------|------------------|-----------------|-------------------------|--|
| Room Number | People | Lights | Ventilation | Infiltration | Reheat Minimum | Cooling Fans | Heating Fan | Auxiliary Fan | Room Exhaust | Daylighting Controls | |
| 5 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 10 | FSHDINP | FSHDINL | | | | | | | | | |
| 15 | FSHKITCH | FSHKITCH | | | | | | | | | |
| 20 | FSHBARRP | FSHBARRL | | | | | | | | | |
| 25 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 30 | FSHBARRP | FSHBARRL | | | | | | | | | |
| 35 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 40 | FSHBARRP | FSHBARRL | | | | | | | | | |
| 45 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 50 | FSHBARRP | FSHBARRP | | | | | | | | | |
| 55 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 60 | FSHBARRP | FSHBARRL | | | | | | | | | |
| 65 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 70 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 75 | FSHBARRP | FSHBARRL | | | | | | | | | |
| 80 | FSHKITCH | FSHKITCH | | | | | | | | | |
| 85 | FSHDINP | FSHDINL | | | | | | | | | |

| Card 27----- People and Lights ----- | | | | | | | | | | | | |
|--------------------------------------|-----------------|-----------------|--------------------|------------------|-------------------|-------------------|-----------------|-------------------|----------------------------------|----------------------|----------------------|--|
| Room Number | People Value | People Units | People Sensible | People Latent | Lighting Value | Lighting Units | Lighting | | Percent Lights to Ret. Air | --- Daylighting --- | | |
| | | | | | | | Fixture Type | Ballast Factor | | Reference Point 1 | Reference Point 2 | |
| 5 | 175 | SF-PERS | 250 | 200 | 2.25 | WATT-SF | ASHRAE2 | | | | | |

Card 27----- People and Lights -----

| Room Number | People Value | People Units | People Sensible | People Latent | Lighting Value | Lighting Units | Lighting | | Ballast Factor | Percent | | --- Daylighting --- | |
|-------------|--------------|--------------|-----------------|---------------|----------------|----------------|--------------|--|----------------|--------------------|--|---------------------|-------------------|
| | | | | | | | Fixture Type | | | Lights to Ret. Air | | Reference Point 1 | Reference Point 2 |
| 10 | 300 | PEOPLE | 275 | 275 | 1.7 | WATT-SF | ASHRAE2 | | | | | | |
| 15 | 20 | PEOPLE | 275 | 475 | 1.5 | WATT-SF | ASHRAE2 | | | | | | |
| 20 | 1538 | PEOPLE | 250 | 200 | 1 | WATT-SF | ASHRAE2 | | | | | | |
| 25 | 35 | SF-PERS | 250 | 200 | 3.5 | WATT-SF | ASHRAE2 | | | | | | |
| 30 | 420 | PEOPLE | 250 | 200 | 2.6 | WATT-SF | SUSINCAN | | | | | | |
| 35 | 35 | SF-PERS | 250 | 200 | 3.5 | WATT-SF | ASHRAE2 | | | | | | |
| 40 | 420 | PEOPLE | 250 | 200 | 2.6 | WATT-SF | SUSINCAN | | | | | | |
| 45 | 35 | SF-PERS | 250 | 200 | 3.5 | WATT-SF | ASHRAE2 | | | | | | |
| 50 | 420 | PEOPLE | 250 | 200 | 2.6 | WATT-SF | SUSINCAN | | | | | | |
| 55 | 35 | SF-PERS | 250 | 200 | 3.5 | WATT-SF | ASHRAE2 | | | | | | |
| 60 | 420 | PEOPLE | 250 | 200 | 2.6 | WATT-SF | SUSINCAN | | | | | | |
| 65 | 16 | PEOPLE | 250 | 200 | 2.0 | WATT-SF | ASHRAE2 | | | | | | |
| 70 | 8 | PEOPLE | 250 | 200 | 3.0 | WATT-SF | ASHRAE2 | | | | | | |
| 75 | 232 | PEOPLE | 250 | 200 | .65 | WATT-SF | ASHRAE2 | | | | | | |
| 80 | 30 | PEOPLE | 250 | 200 | 2.6 | WATT-SF | ASHRAE2 | | | | | | |
| 85 | 800 | PEOPLE | 250 | 200 | 1.22 | WATT-SF | ASHRAE2 | | | | | | |

Card 28----- Miscellaneous Equipment -----

| Room Number | Misc Equipment | | Energy Consump Value | Energy Consump Units | Schedule Code | Energy Meter Code | Percent of Load Sensible | Percent Misc. Load to Room | Percent Misc. Sens to Ret. Air | Radiant Fraction | Optional Air Path |
|-------------|----------------|------------|----------------------|----------------------|---------------|-------------------|--------------------------|----------------------------|--------------------------------|------------------|-------------------|
| | Number | Descrip | | | | | | | | | |
| 5 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 10 | 1 | DIN. EQPT. | 1 | WATT-SF | FSHDINL | | | | | | |
| 15 | 1 | KITCHEN | 16 | WATT-SF | FSHKITCH | | | | | | |
| 20 | 1 | TV ETC. | 1 | WATT-SF | FSHBARRL | | | | | | |
| 25 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 30 | 1 | PERS APP. | .5 | WATT-SF | FSHBARRL | | | | | | |
| 35 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 40 | 1 | PERS APP. | .5 | WATT-SF | FSHBARRL | | | | | | |
| 45 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 50 | 1 | PERS APP. | .5 | WATT-SF | FSHBARRL | | | | | | |
| 55 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 60 | 1 | PERS APP. | .5 | WATT-SF | FSHBARRL | | | | | | |
| 65 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 70 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 75 | 1 | PERS APP. | .5 | WATT-SF | FSHBARRL | | | | | | |
| 80 | 1 | KITCHEN | 16 | WATT-SF | FSHKITCH | | | | | | |
| 85 | 1 | DINING | 1 | WATT-SF | FSHDINL | | | | | | |

Card 29----- Room Airflows -----

| Room Number | Ventilation | | | | Infiltration | | | | --Reheat Minimum-- | |
|-------------|-------------|-------|-------|-------|--------------|-------|-------|-------|--------------------|-------|
| | Value | Units | Value | Units | Value | Units | Value | Units | Value | Units |
| 5 | 3975 | CFM | 3975 | CFM | | | | | | |

| Card 29----- Room Airflows ----- | | | | | | | | | |
|----------------------------------|-------|-------------------|-------|-------------------|------------------------|-------------------|-------|-------------------|--------------------|
| -----Ventilation----- | | | | | -----Infiltration----- | | | | |
| Room | | -----Cooling----- | | -----Heating----- | | -----Cooling----- | | -----Heating----- | |
| Number | Value | Units | Value | Units | Value | Units | Value | Units | --Reheat Minimum-- |
| 10 | 20 | CFM-P | 20 | CFM-P | | | | | |
| 15 | 3000 | CFM | 3000 | CFM | | | | | |
| 20 | 17385 | CFM | 17385 | CFM | | | | | |
| 25 | 7700 | CFM | 7700 | CFM | | | | | |
| 30 | 12000 | CFM | 12000 | CFM | | | | | |
| 35 | 7700 | CFM | 7700 | CFM | | | | | |
| 40 | 12000 | CFM | 12000 | CFM | | | | | |
| 45 | 7700 | CFM | 7700 | CFM | | | | | |
| 50 | 12000 | CFM | 12000 | CFM | | | | | |
| 55 | 7700 | CFM | 7700 | CFM | | | | | |
| 60 | 12000 | CFM | 12000 | CFM | | | | | |
| 65 | 900 | CFM | 900 | CFM | | | | | |
| 70 | 20 | CFM-P | 20 | CFM-P | | | | | |
| 75 | 20 | CFM-P | 20 | CFM-P | | | | | |
| 80 | 12700 | CFM | 12700 | CFM | | | | | |
| 85 | 12200 | CFM | 12200 | CFM | | | | | |

| Card 31----- Partition Parameters ----- | | | | | | | | | |
|---|------------------|------------------|------------------|-------------------|------------|-----------|--------------|--------------|------------------|
| Room Number | Partition Number | Partition Length | Partition Height | Partition U-Value | Const Type | Temp Flag | Cooling Temp | Heating Temp | Adjacent Room No |
| 5 | 1 | 264 | 12.5 | .23 | 103 | HRLYOADB | | | |
| 5 | 2 | 264 | 12.5 | .23 | 103 | HRLYOADB | | | |
| 5 | 3 | 680 | 12.5 | .15 | 103 | HRLYOADB | | | |
| 10 | 1 | 220 | 12.5 | .44 | 107 | HRLYOADB | | | |
| 25 | 1 | 244 | 13 | .20 | 107 | HRLYOADB | | | |
| 30 | 1 | 244 | 13 | .20 | 107 | HRLYOADB | | | |
| 35 | 1 | 244 | 13 | .20 | 107 | HRLYOADB | | | |
| 40 | 1 | 244 | 13 | .20 | 107 | HRLYOADB | | | |
| 45 | 1 | 244 | 13 | .20 | 107 | HRLYOADB | | | |
| 50 | 1 | 244 | 13 | .20 | 107 | HRLYOADB | | | |
| 55 | 1 | 244 | 13 | .20 | 107 | HRLYOADB | | | |
| 60 | 1 | 244 | 13 | .20 | 107 | HRLYOADB | | | |
| 80 | 1 | 30 | 12 | .10 | 107 | HRLYOADB | | | |

| Card 33----- External Shading ----- | | | | | | | | | |
|-------------------------------------|--------------|-------------|----------------|-------------------------|-----------------|----------------|------------------|----------------------|------------------------|
| -----OVERHANG----- | | | | -----VERTICAL FINS----- | | | | | |
| Shading Type | Glass Height | Above Glass | Projection Out | Glass Width | Projection Left | Projection Out | Projection Right | Right Projection Out | Adjacent Building Flag |
| 3 | 5.5 | 1 | 2 | | | | | | |
| 4 | 4 | 1 | 5 | | | | | | |
| 5 | 4 | 1 | 3 | | | | | | |

----- System Section Alternative #1 -----

Card 39- System Alternative

| Number | Description |
|--------|-----------------|
| 1 | EXISTING SYSTEM |

Card 40----- System Type -----

| -----OPTIONAL VENTILATION SYSTEM----- | | | | | | | |
|---------------------------------------|--------|----------|---------|---------|----------|----------|----------|
| System | | Ventil | | | | | Fan |
| Set | System | Deck | Cooling | Heating | Cooling | Heating | Static |
| Number | Type | Location | SADBVh | SADBVh | Schedule | Schedule | Pressure |
| 1 | VAV | | | | | | |
| 2 | MZ | | | | | | |

Card 41----- Zone Assignment -----

| System | Ref #1 | | Ref #2 | | Ref #3 | | Ref #4 | | Ref #5 | | Ref #6 | |
|--------|--------|-----|--------|-----|--------|-----|--------|-----|--------|-----|--------|-----|
| Set | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End |
| Number | | | | | | | | | | | | |
| 1 | 5 | 20 | | | | | | | | | | |
| 2 | 25 | 85 | | | | | | | | | | |

Card 42----- Fan SP and Duct Parameters-----

| System | Cool | Heat | Return | Mn Exh | Aux | Rm Exh | Cool | Return | Supply | Supply | Return |
|--------|------|------|--------|--------|-----|--------|---------|---------|--------|--------|--------|
| Set | Fan | Fan | Fan | Fan | Fan | Fan | Fan Mtr | Fan Mtr | Duct | Duct | Air |
| Number | SP | SP | SP | SP | SP | SP | Loc | Loc | Ht Gn | Loc | Path |
| 1 | 1.5 | 1.5 | | | | | | | | | |
| 2 | 1.5 | 1.5 | | | | | | | | | |

Card 45----- Equipment Schedules -----

| System | Main | | Direct | Indirect | Auxiliary | Main | Main | | | Auxiliary |
|--------|----------|------------|--------|----------|-----------|----------|----------|----------|----------|-----------|
| Set | Cooling | | Evap | Evap | Cooling | Heating | Preheat | Reheat | Mech. | Heating |
| Number | Coil | Economizer | Coil | Coil | Coil | Coil | Coil | Coil | Humidity | Coil |
| 1 | FTSAMCLG | | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 2 | FTSAMCLG | | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |

----- Equipment Section Alternative #1 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Limit | Temperature |
|-------------|--------------|-------------|--------|-------------------------|----------------|
| Number | Schedule | Schedule | Max KW | Alternative Description | Schedule Drift |
| 1 | | | | BASE CASE | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | Asgn | Loads To | Equipment | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------|----------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Ref | Cool Ref | Sizing | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | BLKPLANT | 1 | 1 | | | | | | | | | | |
| 2 | 2 | BLKPLANT | 2 | 2 | | | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | Seq | Demand |
|------------|---------|-------|--------|
| Ref Code | Of | Order | Seq |
| Num | Name | Units | Type |
| 1 | EQ1001S | 1 | 1 |
| 2 | EQ1001S | 1 | 1 |
| 3 | EQ1001S | 1 | 1 |

Card 63----- Cooling Pumps and References -----

| Cool | ---CHILLED WATER--- | ---CONDENSER--- | ---HT REC or AUX--- | Switch- |
|------|---------------------|-----------------|---------------------|-----------|
| Ref | Full Load | Full Load | Full Load | Full Load |
| Num | Value | Units | Value | Units |
| 1 | 29.84 | KW | 22.38 | KW |
| 2 | 18.65 | KW | 29.84 | KW |
| 3 | | | 29.84 | KW |

Card 65----- Heating Load Assignment -----

| Load | All Coil | Assignment | Loads To | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|-----------|-------------|------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Reference | Heating Ref | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | 1 | 1 | | | | | | | | | |
| 2 | 3 | 2 | 2 | | | | | | | | | |

Card 67----- Heating Equipment Parameters -----

| Heat Equip | Number | HW Pmp | Energy | Seq | Switch | Demand |
|------------|----------|---------|--------|-------|--------|--------|
| Ref Code | Of | Full Ld | Cap'y | Order | over | Limit |
| Number | Name | Units | Value | Units | Value | Units |
| 1 | 1350HWB1 | 1 | 29.84 | KW | 5317 | MBH |
| 2 | 1350HWB2 | 1 | | | 4336 | MBH |
| 3 | 1300HWHB | 1 | 11.19 | KW | 5912 | MBH |
| 4 | 1300HWHB | 1 | 11.19 | KW | 5912 | MBH |

Card 71----- Base Utility Parameters -----

| Base Utility Number | Base Utility Descrip | Hourly Demand Value | Hourly Demand Units | Schedule Code | Energy Type | Equip Reference Number | Demand Limiting Number | Entering Temp | Leaving Temp |
|---------------------------|----------------------------|---------------------------|---------------------------|------------------|----------------|------------------------------|------------------------------|------------------|-----------------|
| 1 | PIPE-PUMP HT LOS | 19.45 | TOWS | FTSAMCLG | CHILL-LD | 1 | | | |
| 2 | PIPE HT LOSS | 482.9 | MBH | FTSAMHTG | HOT-LD | 1 | | | |
| 3 | PIPE-PUMP HT LOS | 45.56 | TOWS | FTSAMCLG | CHILL-LD | 2 | | | |
| 4 | PIPE HT LOSS | 1312.5 | MBH | FTSAMHTG | HOT-LD | 3 | | | |

Card 74----- Condenser / Cooling Tower Parameters -----

| Tower Ref | Cooling Tower Code | Capacity Value | Capacity Units | Energy Consump Value | Energy Consump Units | Fluid Type | Tower Type | Number Of Cells | Percent Airflow Low Spd | Low Spd Energy Value | Low Spd Energy Units |
|--------------|--------------------------|-------------------|-------------------|----------------------------|----------------------------|---------------|---------------|-----------------------|-------------------------------|----------------------------|----------------------------|
| 1 | EQ5100 | | | 14.92 | KW | | | 1 | 50 | 7.46 | KW |
| 2 | EQ5100 | | | 52.22 | KW | | | 2 | | | |

Card 75----- Miscellaneous Accessory -----

| #1 | | | | | #2 | | | | | #3 | | | | |
|-------------|---------------|-----------------|-----------------|---------------|-------------|---------------|-----------------|-----------------|---------------|-------------|---------------|-----------------|-----------------|---------------|
| Misc Ref | Equip Code | Energy Value | Energy Units | Sched Code | Misc Ref | Equip Code | Energy Value | Energy Units | Sched Code | Misc Ref | Equip Code | Energy Value | Energy Units | Sched Code |
| 1 | EQ5020 | 11.19 | KW | | | EQ5240 | 7.46 | KW | | | | | | |
| 2 | EQ5001 | 18.65 | KW | | | | | | | | | | | |
| 3 | EQ5240 | 7.46 | KW | | | | | | | | | | | |

----- Equipment Section Alternative #2 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Time of Day | Time of Day | Limit | Max KW | Alternative Description | Demand Limit | Temperature |
|-------------|--------------|-------------|--------|-------------|-------------|-------|--------|---|--------------|-------------|
| Number | Schedule | Schedule | Max KW | Schedule | Drift | | | | | |
| 2 | | | | | | | | EXISTING CHILLERS, HIGH MODULAR BOILERS | | |

Card 65----- Heating Load Assignment -----

| Load | All Coil | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------------|-------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Assignment | Loads To | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| Reference | Heating Ref | | | | | | | | | |
| 1 | 1 | 1 2 | | | | | | | | |

Card 67----- Heating Equipment Parameters -----

| Heat Ref | Equip Code | Number Of | HW Pmp Full Ld | Cap'y | Energy Rate | Seq Order | Switch over | Hot Strg | Misc. Acc. | Cogen | Demand Limit Number |
|-------------|---------------|--------------|-------------------|-------|----------------|--------------|----------------|-------------|---------------|---------|---------------------------|
| Number | Name | Units | Value | Units | Value | Units | Value | Units | Number | Control | Number |
| 1 | BOILLEFT | 1 | 5.6 | KW | 1830 | MBH | 2000 | MBH | 1 | | |

Card 67----- Heating Equipment Parameters -----

| Heat Ref | Equip Code | Number Of | HW Pmp Full Ld | Cap'y | Energy Rate | Seq Order | Switch over | Demand Limit |
|----------|------------|-----------|----------------|-------|-------------|-----------|-------------|--------------|
| Number | Name | Units | Value | Units | Value | Units | Value | Number |
| 2 | BOILHEFT | 1 | 5.6 | KW | 1830 | MBH | 2000 | 2 |
| 3 | BOILHEFT | 1 | 5.6 | KW | 1830 | MBH | 2000 | 3 |
| 4 | BOILHEFT | 1 | 5.6 | KW | 1830 | MBH | 2000 | 4 |

Card 71----- Base Utility Parameters -----

| Base Utility | Base Utility | Hourly Demand | Hourly Demand | Schedule | Energy Reference | Equip Reference | Demand Limiting | Entering Temp | Leaving Temp |
|--------------|--------------|---------------|---------------|----------|------------------|-----------------|-----------------|---------------|--------------|
| Number | Descrip | Value | Units | Code | Type | Number | Number | Temp | Temp |
| 1 | PIPE HT LOSS | 1795.4 | MBH | FTSAMHTG | HOT-LD | 1 | | | |

----- Equipment Section Alternative #3 -----

Card 59----- Equipment Description / TOU Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Temperature |
|-------------|--------------|-------------|--------|--|
| Number | Time of Day | Time of Day | Limit | Drift |
| 3 | Schedule | Schedule | Max KW | Alternative Description |
| | | | | WATER COOLED CENTR. CHILLER, EXIST BOILR |

Card 60----- Cooling Load Assignment-----

| Load Ref | All Coil | Cooling | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|----------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Ref | Loads To | Equipment | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | BLKPLANT | 1 | 2 | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Ref | Equip Code | Num Of | COOLING--Capacity-- | COOLING--Energy-- | HEAT RECOVERY--Capacity-- | HEAT RECOVERY--Energy-- | Seq Order | Demand Seq |
|----------|------------|--------|---------------------|-------------------|---------------------------|-------------------------|-----------|------------|
| Num | Name | Units | Value | Units | Value | Units | Value | Number |
| 1 | YCENT134 | 1 | 425 | TONS | 264 | KW | 1 | PAR |
| 2 | YCENT134 | 1 | 840 | TONS | 487 | KW | 2 | PAR |

Card 63----- Cooling Pumps and References -----

| Cool Ref | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | Switch over | Cold Storage | Cooling Tower | Misc. Access. |
|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-------------|--------------|---------------|---------------|
| Num | Value | Units | Value | Units | Value | Units | Value | Control | Storage | Tower | Access. |
| 1 | 29.84 | KW | 29.84 | KW | | | | 1 | | 1 | |

Card 63----- Cooling Pumps and References -----
Cool ---CHILLED WATER---- ----CONDENSER----- ---HT REC or AUX---- Switch-
Ref Full Load Full Load Full Load Full Load Full Load Full Load over Cold Cooling Misc.
Num Value Units Value Units Value Units Control Storage Tower Access.
2 55.95 KW 55.95 KW 1 2

Card 71----- Base Utility Parameters -----
Base Base Hourly Hourly Equip Demand
Utility Utility Demand Demand Schedule Energy Reference Limiting Entering Leaving
Number Descrip Value Units Code Type Number Number Temp Temp
1 PIPE-PUMP HT LOS 22 TONS FTSAMCLG CHILL-LD 1
2 PIPE-PUMP HT LOS 43 TONS FTSAMCLG CHILL-LD 2

Card 72-- Switchover Controls -----
Outside
Control Load Load Air Sched
Reference Value Units DB Code
1 425 TONS

Card 74----- Condenser / Cooling Tower Parameters -----
Cooling
Tower Tower Capacity Capacity Energy Energy
Ref Code Value Units Consump Consump Fluid Tower Number Percent Low Spd Low Spd
Cells Low Spd Value Units
1 EQ5100 14.92 KW 1 50 7.46 KW
2 EQ5100 52.2 KW 2

----- Equipment Section Alternative #4 -----

Card 59----- Equipment Description / TOO Schedules -----
Elec Consump Elec Demand Demand ---- Demand Limit ----
Alternative Time of Day Time of Day Limit Temperature
Number Schedule Schedule Max KW Alternative Description Schedule Drift
4 WAT. COOLED DUAL SCREW CHILR, EXIST BLR

Card 60----- Cooling Load Assignment-----
Load All Coil Cooling
Asgn Loads To Equipment -Group 1- -Group 2- -Group 3- -Group 4- -Group 5- -Group 6- -Group 7- -Group 8- -Group 9-
Ref Cool Ref Sizing Begin End Begin End Begin End Begin End Begin End Begin End Begin End Begin End
1 1 BLKPLANT 1 2

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | -----COOLING----- | | | | -----HEAT RECOVERY----- | | | | Seq | Demand |
|------------|-------|-------------------|-------|--------------|-------|-------------------------|-------|--------------|-------|-------|-------------|
| Ref Code | Of | --Capacity-- | | ---Energy--- | | --Capacity-- | | ---Energy--- | | Order | Seq Limit |
| Num Name | Units | Value | Units | Value | Units | Value | Units | Value | Units | Num | Type Number |
| 1 YSCRW22 | 1 | 425 | TONS | 272 | KW | | | | | 1 | PAR |
| 2 YSCRW22 | 1 | 840 | TONS | 538 | KW | | | | | 2 | PAR |

Card 63----- Cooling Pumps and References -----

| Cool | ---CHILLED WATER--- | | ---CONDENSER--- | | ---HT REC or AUX--- | | Switch- | | | | | |
|------|---------------------|-----------|-----------------|-----------|---------------------|-----------|-----------|---------|---------|---------|---------|--|
| Ref | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | over | Cold | Cooling | Misc. | |
| Num | Value | Units | Value | Units | Value | Units | Value | Control | Storage | Tower | Access. | |
| 1 | 29.84 | KW | 29.84 | KW | | | | 1 | | 1 | | |
| 2 | 55.95 | KW | 55.95 | KW | | | | 1 | | 2 | | |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | | Equip | Demand | | | |
|---------|------------------|--------|--------|----------|----------|-----------|----------|----------|---------|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting | Entering | Leaving |
| Number | Descrip | Value | Units | Code | Type | Number | Number | Temp | Temp |
| 1 | PIPE-PUMP HT LOS | 22 | TONS | FTSAMCLG | CHILL-LD | 1 | | | |
| 2 | PIPE-PUMP HT LOS | 43 | TONS | FTSAMCLG | CHILL-LD | 2 | | | |

Card 72-- Switchover Controls -----

| Control | Load | Load | Air | Sched |
|-----------|-------|-------|-----|-------|
| Reference | Value | Units | DB | Code |
| 1 | 425 | TONS | | |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | Energy | | Energy | | Fluid | | Tower | | Number | Percent | Low Spd | Low Spd |
|---------|--------|----------|----------|---------|---------|------|-------|-------|---------|---------|---------|---------|
| Tower | Tower | Capacity | Capacity | Consump | Consump | Type | Type | Of | Cells | Airflow | Energy | Energy |
| Ref | Code | Value | Units | Value | Units | Type | Type | Cells | Low Spd | Value | Units | Units |
| 1 | E05100 | | | 14.92 | KW | | | 1 | 50 | 7.46 | KW | |
| 2 | E05100 | | | 52.22 | KW | | | 2 | | | | |

Utility Description Reference Table

Schedules:

FSHBARRL F.S.H. BARRACKS LIGHT/MISC. SCHEDULE
FSHBARRP F.S.H. BARRACKS PEOPLE SCHEDULE
FSHDINL F.S.H. DINING LIGHTING/MISC. LOAD SCHED.
FSHDINP F.S.H. DINING PEOPLE SCHEDULE
FSHKITCH F.S.H. KITCHEN INTERNAL LOAD SCHEDULE
FSHOFFIC F.S.H. OFFICE INTERNAL LOAD SCHEDULE
FTSAMCLG EEAP BOILER/CHILLER STUDY
FTSAMHTG EEAP BOILER/CHILLER STUDY

System:

MZ MULTIZONE
VAV VARIABLE AIR VOLUME

Equipment:

Cooling:

EQ1001S 2-STG CENTRIFUGAL CHILLER <550 TONS
YCENT134 YORK CENT. R-134A CHILL
YSCRW22 YORK W.C. SCREW CHILL.

Heating:

1300HMB EXISTING FORCE DRAFT C.B. HWH BOILER
1350HMB1 EXISTING NAT. DRAFT RITE HWH BOILER
1350HMB2 EXISTING NAT. DRAFT AJAX HWH BOILER
BOILHEFT HIGH EFFICIENCY MODULAR FIRETUBE BOIL.

Tower:

EQ5100 COOLING TOWER FANS

Misc:

EQ5001 CHILLED WATER PUMP - CONSTANT VOLUME
EQ5020 HEATING WATER CIRCULATION PUMP
EQ5240 BOILER FORCED DRAFT FAN

Card 59----- Equipment Description / TOO Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Time of Day | Time of Day | Limit | Temperature |
|-------------|--------------|-------------|--------|-------------------------|-------------|-------|-------------|
| Number | Schedule | Schedule | Max KW | Alternative Description | Schedule | Drift | |
| 1 | | | | BASE CASE | | | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | Asgn | Loads To | Equipment | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------|----------|----------|-------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Ref | Cool Ref | Sizing | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End |
| 1 | 1 | BLKPLANT | 1 | 1 | | | | | | | | | | |
| 2 | 2 | BLKPLANT | 2 | 2 | | | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | Of | Capacity | Energy | Capacity | Energy | Seq | Demand |
|------------|---------|-------|----------|--------|----------|--------|-------|--------|
| Ref | Code | Units | Value | Units | Value | Units | Order | Seq |
| Num | Name | Units | Value | Units | Value | Units | Num | Type |
| 1 | EQ1001S | 1 | 438 | TONS | 329 | KW | | |
| 2 | EQ1001S | 1 | 544 | TONS | 517 | KW | | |
| 3 | EQ1001S | 1 | 442 | TONS | 517 | KW | 1 | SER |
| | | | | | | | 2 | SER |

Card 63----- Cooling Pumps and References -----

| Cool | CHILLED WATER | CONDENSER | HT REC or AUX | Switch | Cold | Cooling | Misc. |
|------|---------------|-----------|---------------|-----------|-----------|-----------|---------|
| Ref | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | Access. |
| Num | Value | Units | Value | Units | Value | Units | |
| 1 | 29.84 | KW | 22.38 | KW | | | 1 |
| 2 | 18.65 | KW | 29.84 | KW | | | 2 |
| 3 | | | 29.84 | KW | | | 2 |

Card 65----- Heating Load Assignment -----

| Load | All Coil | Assignment | Loads To | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|-----------|-------------|------------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Reference | Heating Ref | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End | Begin |
| 1 | 1 | 1 | 1 | | | | | | | | | |
| 2 | 3 | 2 | 2 | | | | | | | | | |

Card 67----- Heating Equipment Parameters -----

| Heat | Equip | Number | HW Pmp | Energy | Seq | Switch | Hot | Misc. | Demand |
|--------|-----------|--------|---------|--------|-------|--------|--------|-------|--------|
| Ref | Code | Of | Full Ld | Cap'y | Rate | Order | over | Acc. | Limit |
| Number | Name | Units | Value | Units | Value | Units | Number | Strg | Cogen |
| 1 | 1350HWHB1 | 1 | 29.84 | KW | 5317 | MBH | 7500 | MBH | 1 |
| 2 | 1350HWHB2 | 1 | | | 4336 | MBH | 5800 | MBH | 2 |
| 3 | 1300HWHB | 1 | 11.19 | KW | 5912 | MBH | 8369 | MBH | 1 |
| 4 | 1300HWHB | 1 | 11.19 | KW | 5912 | MBH | 8369 | MBH | 2 |

Card 71----- Base Utility Parameters -----

| Base Utility Number | Base Utility Descrip | Hourly Demand Value | Hourly Demand Units | Schedule Code | Energy Type | Equip Reference Number | Demand Limiting Number | Entering Temp | Leaving Temp |
|---------------------------|----------------------------|---------------------------|---------------------------|------------------|----------------|------------------------------|------------------------------|------------------|-----------------|
| 1 | PIPE-PUMP HT LOS | 19.45 | TONS | FTSAMCLG | CHILL-LD | 1 | | | |
| 2 | PIPE HT LOSS | 482.9 | MBH | FTSAMHTG | HOT-LD | 1 | | | |
| 3 | PIPE-PUMP HT LOS | 45.56 | TONS | FTSAMCLG | CHILL-LD | 2 | | | |
| 4 | PIPE HT LOSS | 1312.5 | MBH | FTSAMHTG | HOT-LD | 3 | | | |

Card 74----- Condenser / Cooling Tower Parameters -----

| Tower Ref | Cooling Tower Code | Capacity Value | Capacity Units | Energy | | Fluid Type | Tower Type | Number Of Cells | Percent Airflow Low Spd | Low Spd Energy Value | Low Spd Energy Units |
|--------------|--------------------------|-------------------|-------------------|------------------|------------------|---------------|---------------|-----------------------|-------------------------------|----------------------------|----------------------------|
| | | | | Consump Value | Consump Units | | | | | | |
| 1 | EQ5100 | | | 14.92 | KW | | | 1 | 50 | 7.46 | KW |
| 2 | EQ5100 | | | 52.22 | KW | | | 2 | | | |

Card 75----- Miscellaneous Accessory -----

| #1 | | | | | #2 | | | | | #3 | | | | |
|-------------|---------------|-----------------|-----------------|---------------|---------------|-----------------|-----------------|---------------|---------------|-----------------|-----------------|---------------|--|--|
| Misc Ref | Equip Code | Energy Value | Energy Units | Sched Code | Equip Code | Energy Value | Energy Units | Sched Code | Equip Code | Energy Value | Energy Units | Sched Code | | |
| 1 | EQ5020 | 11.19 | KW | | EQ5240 | 7.46 | KW | | | | | | | |
| 2 | EQ5001 | 18.65 | KW | | | | | | | | | | | |
| 3 | EQ5240 | 7.46 | KW | | | | | | | | | | | |

----- Equipment Section Alternative #2 -----

Card 59----- Equipment Description / T00 Schedules -----

| Alternative Number | Elec Consump Time of Day Schedule | Elec Demand Time of Day Schedule | Demand Limit Max KW | Alternative Description | Demand Limit Temperature Schedule | Drift |
|-----------------------|---|--|---------------------------|--|---|-------|
| 2 | | | | WAT. COOLED GAS ENGINE CHLR, EXIST BOILR | | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | Asgn | Loads To | Equipment | -Group 1- Begin End | -Group 2- Begin End | -Group 3- Begin End | -Group 4- Begin End | -Group 5- Begin End | -Group 6- Begin End | -Group 7- Begin End | -Group 8- Begin End | -Group 9- Begin End |
|------|----------|----------|------|----------|-----------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|
| Ref | Cool Ref | Sizing | | | | | | | | | | | | |
| 1 | 1 | BLKPLANT | 1 | 2 | | | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Ref | Equip Code | Num Of | COOLING | | | | HEAT RECOVERY | | | | Seq Order | Demand Seq Limit | |
|-------------|---------------|-----------|-----------------------------|-------------|-------------|-------------|-----------------------------|-------------|-------------|-------------|--------------|------------------------|-----|
| | | | --Capacity-- Value Units | Value Units | Value Units | Value Units | --Capacity-- Value Units | Value Units | Value Units | Value Units | | | |
| 1 | YENGDRIV | 1 | 425 | TONS | 2805 | MBH | | | | | | 1 | PAR |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | | COOLING | | | | HEAT RECOVERY | | | | Seq | Demand |
|------------|----------|---------|----------|--------|----------|---------------|----------|--------|-------|------|--------|
| Ref | Code | Of | Capacity | Energy | Capacity | Energy | Capacity | Energy | Order | Seq | Limit |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Num | Type | Number |
| 2 | YENGDRIV | 1 | 840 | TONS | 5208 | MBH | | | | | |
| | | | | | | | | | 2 | PAR | |

Card 63----- Cooling Pumps and References -----

| Cool | | CHILLED WATER | | CONDENSER | | HT REC or AUX | | Switch | Cold | Cooling | Misc. |
|------|-----------|---------------|-----------|-----------|-----------|---------------|-----------|---------|---------|---------|---------|
| Ref | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | over | Storage | Tower | Access. |
| Num | Value | Units | Value | Units | Value | Units | Value | Control | | | |
| 1 | 29.84 | KW | 29.84 | KW | | | | 1 | | 1 | |
| 2 | 55.95 | KW | 55.95 | KW | | | | 1 | | 2 | |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Schedule | | Equip | Demand | | |
|---------|------------------|--------|--------|----------|----------|-----------|----------|----------|---------|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting | Entering | Leaving |
| Number | Descrip | Value | Units | Code | Type | Number | Number | Temp | Temp |
| 1 | PIPE-PUMP HT LOS | 22 | TONS | FTSAMCLG | CHILL-LD | 1 | | | |
| 2 | PIPE-PUMP HT LOS | 43 | TONS | FTSAMCLG | CHILL-LD | 2 | | | |

Card 72-- Switchover Controls -----

| Control | Load | Load | Air | Sched |
|-----------|-------|-------|-----|-------|
| Reference | Value | Units | DB | Code |
| 1 | 425 | TONS | | |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | | Capacity | | Energy | Energy | Fluid | | Tower | Number | Percent | Low Spd | Low Spd |
|---------|--------|----------|----------|---------|---------|-------|-------|-------|--------|---------|---------|---------|
| Tower | Tower | Capacity | Capacity | Consump | Consump | Fluid | Tower | Of | Cells | Airflow | Energy | Energy |
| Ref | Code | Value | Units | Value | Units | Type | Type | | | Low Spd | Value | Units |
| 1 | EQ5100 | | | 14.92 | KW | | | 1 | 50 | 7.46 | KW | |
| 2 | EQ5100 | | | 52.2 | KW | | | 2 | | | | |

----- Equipment Section Alternative #3 -----

Card 59----- Equipment Description / TOD Schedules -----

| Elec Consump | | Elec Demand | | Demand | Demand Limit | |
|--------------|-------------|-------------|--------|---|--------------|-------------------|
| Alternative | Time of Day | Time of Day | Limit | | | |
| Number | Schedule | Schedule | Max KW | Alternative Description | Schedule | Temperature Drift |
| 3 | | | | W.C. CENTRIFUGAL VFD CHILLER, EXIST BLR | | |

Card 60----- Cooling Load Assignment-----
 Load All Coil Cooling
 Asgn Loads To Equipment -Group 1- -Group 2- -Group 3- -Group 4- -Group 5- -Group 6- -Group 7- -Group 8- -Group 9-
 Ref Cool Ref Sizing Begin End Begin End Begin End Begin End Begin End Begin End Begin End Begin End
 1 1 BLKPLANT 1 2

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | COOLING----- | | | | -----HEAT RECOVERY----- | | | | Seq | Demand | | |
|------------|---------|--------------|-------|----------------|-------|-------------------------|-------|----------------|-------|-------|--------|-------|--------|
| Ref Code | Of | --Capacity-- | | ----Energy---- | | --Capacity-- | | ----Energy---- | | Order | Seq | Limit | |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Value | Units | Num | Type | Number |
| 1 | YCENVFD | 1 | 425 | TONS | 264 | KW | | | | | 1 | PAR | |
| 2 | YCENVFD | 1 | 840 | TONS | 487 | KW | | | | | 2 | PAR | |

Card 63----- Cooling Pumps and References -----

| Cool | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | over | Cold | Cooling | Misc. | |
|------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-------|---------|---------|-------|---------|
| Num | Value | Units | Value | Units | Value | Units | Value | Units | Control | Storage | Tower | Access. |
| 1 | 29.84 | KW | 29.84 | KW | | | | | 1 | | 1 | |
| 2 | 55.95 | KW | 55.95 | KW | | | | | 1 | | 2 | |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | | Equip | Demand | | | |
|---------|------------------|--------|--------|----------|----------|-----------|----------|----------|---------|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting | Entering | Leaving |
| Number | Descrip | Value | Units | Code | Type | Number | Number | Temp | Temp |
| 1 | PIPE-PUMP HT LOS | 22 | TONS | FTSAMCLG | CHILL-LD | 1 | | | |
| 2 | PIPE-PUMP HT LOS | 43 | TONS | FTSAMCLG | CHILL-LD | 2 | | | |

Card 72-- Switchover Controls -----

| Control | Load | Load | Air | Sched |
|-----------|-------|-------|-----|-------|
| Reference | Value | Units | DB | Code |
| 1 | 425 | TONS | | |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | Capacity | Capacity | Energy | Energy | Fluid | Tower | Number | Percent | Low Spd | Low Spd |
|---------|----------|----------|--------|---------|---------|-------|--------|---------|---------|---------|
| Tower | Tower | Value | Units | Consump | Consump | Type | Type | Of | Airflow | Energy |
| Ref | Code | Value | Units | Value | Units | Type | Type | Cells | Low Spd | Value |
| 1 | EQ5100 | | | 14.92 | KW | | | 1 | 50 | 7.46 |
| 2 | EQ5100 | | | 52.22 | KW | | | 2 | | |

**
** TRACE 600 ANALYSIS **
**
** by HUITT & ZOLLARS **
**

03018504 BOILER-CHILLER STUDY
FT. SAM HOUSTON - SAN ANTONIO, TX.
CORPS OF ENGINEERS - FT. WORTH, TEXAS
HUITT - ZOLLARS INC.
AREA 1300

Weather File Code:

Location: SAN ANTONIO, TEXAS
Latitude: 29.0 (deg)
Longitude: 98.0 (deg)
Time Zone: 6
Elevation: 792 (ft)
Barometric Pressure: 29.0 (in. Hg)

Summer Clearness Number: 0.90
Winter Clearness Number: 0.90
Summer Design Dry Bulb: 97 (F)
Summer Design Wet Bulb: 76 (F)
Winter Design Dry Bulb: 30 (F)
Summer Ground Relectance: 0.20
Winter Ground Relectance: 0.20

Air Density: 0.0738 (Lbm/cuft)
Air Specific Heat: 0.2444 (Btu/lbm/F)
Density-Specific Heat Prod: 1.0818 (Btu-min./hr/cuft/F)
Latent Heat Factor: 4,761.9 (Btu-min./hr/cuft)
Enthalpy Factor: 4.4255 (Lb-min./hr/cuft)

Design Simulation Period: June To November
System Simulation Period: January To December
Cooling Load Methodology: TETD/Time Averaging

Time/Date Program was Run: 20: 5:15 6/ 8/95
Dataset Name: FSH1300 .TM

SYSTEM TOTALS LOAD PROFILE - ALTERNATIVE 1
EXISTING SYSTEM

----- SYSTEM LOAD PROFILE -----

System Totals

| Percent Design Load | ---- Cooling Load ---- | | | ----- Heating Load ----- | | |
|---------------------------|------------------------|--------------|-------|--------------------------|--------------|-------|
| | Cap. (Ton) | Hours (%) | Hours | Capacity (Btuh) | Hours (%) | Hours |
| 0 - 5 | 69.8 | 4 | 160 | -534,786 | 18 | 516 |
| 5 - 10 | 139.5 | 5 | 206 | -1,069,572 | 20 | 576 |
| 10 - 15 | 209.3 | 5 | 198 | -1,604,358 | 9 | 270 |
| 15 - 20 | 279.1 | 8 | 316 | -2,139,144 | 9 | 247 |
| 20 - 25 | 348.8 | 9 | 362 | -2,673,930 | 10 | 274 |
| 25 - 30 | 418.6 | 6 | 269 | -3,208,716 | 6 | 173 |
| 30 - 35 | 488.4 | 9 | 396 | -3,743,502 | 10 | 295 |
| 35 - 40 | 558.2 | 6 | 263 | -4,278,288 | 14 | 398 |
| 40 - 45 | 627.9 | 6 | 234 | -4,813,074 | 4 | 109 |
| 45 - 50 | 697.7 | 6 | 265 | -5,347,860 | 0 | 0 |
| 50 - 55 | 767.5 | 5 | 226 | -5,882,647 | 0 | 0 |
| 55 - 60 | 837.2 | 8 | 321 | -6,417,432 | 0 | 0 |
| 60 - 65 | 907.0 | 7 | 296 | -6,952,219 | 0 | 0 |
| 65 - 70 | 976.8 | 8 | 336 | -7,487,004 | 0 | 0 |
| 70 - 75 | 1,046.5 | 5 | 202 | -8,021,791 | 0 | 0 |
| 75 - 80 | 1,116.3 | 3 | 126 | -8,556,577 | 0 | 0 |
| 80 - 85 | 1,186.1 | 1 | 23 | -9,091,363 | 0 | 0 |
| 85 - 90 | 1,255.9 | 0 | 0 | -9,626,149 | 0 | 0 |
| 90 - 95 | 1,325.6 | 0 | 0 | -10,160,935 | 0 | 0 |
| 95 - 100 | 1,395.4 | 0 | 0 | -10,695,720 | 0 | 0 |
| Hours Off | 0.0 | 0 | 4,561 | 0 | 0 | 5,902 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|---------|--------------------------------------|-----|-----|-----|--------|--------|--------|--------|--------|-------|-----|-----|-----------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 1 | EQ1001S | 2-STG CENTRIFUGAL CHILLER <550 TONS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 89514 | 103432 | 122331 | 127030 | 103190 | 50187 | 0 | 0 | 595,685 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 286.9 | 267.5 | 299.6 | 319.9 | 290.4 | 193.8 | 0.0 | 0.0 | 319.9 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 11100 | 10742 | 11100 | 11100 | 10742 | 5429 | 0 | 0 | 60,215 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 0.0 | 0.0 | 14.9 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 483 | 569 | 673 | 694 | 561 | 270 | 0 | 0 | 3,251 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.6 | 1.5 | 1.6 | 1.7 | 1.6 | 1.2 | 0.0 | 0.0 | 1.7 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 22201 | 21485 | 22201 | 22201 | 21485 | 22201 | 0 | 0 | 131,773 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 29.8 |
| 1 | EQ5010 | CONDENSER WATER PUMP-CV(HIGH EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 16651 | 16114 | 16651 | 16651 | 16114 | 16651 | 0 | 0 | 98,830 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 0.0 | 0.0 | 22.4 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 2 | EQ1001S | 2-STG CENTRIFUGAL CHILLER <550 TONS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 216416 | 259295 | 314252 | 325517 | 256609 | 91916 | 0 | 0 | 1,464,005 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 524.9 | 541.9 | 549.8 | 556.5 | 540.7 | 371.9 | 0.0 | 0.0 | 556.5 |
| 2 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 38852 | 37598 | 38852 | 38852 | 37598 | 19065 | 0 | 0 | 210,817 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 0.0 | 0.0 | 52.2 |
| 2 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 1007 | 1274 | 1584 | 1663 | 1224 | 387 | 0 | 0 | 7,140 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.1 | 3.3 | 3.8 | 4.0 | 3.5 | 1.9 | 0.0 | 0.0 | 4.0 |
| 2 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13876 | 13428 | 13876 | 13876 | 13428 | 13876 | 0 | 0 | 82,358 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 0.0 | 0.0 | 18.6 |
| 2 | EQ5010 | CONDENSER WATER PUMP-CV(HIGH EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 22201 | 21485 | 22201 | 22201 | 21485 | 22201 | 0 | 0 | 131,773 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 29.8 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|---------|--------------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|---------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 2 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 2 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13876 | 13428 | 13876 | 13876 | 13428 | 13876 | 0 | 0 | 82,358 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 0.0 | 0.0 | 18.6 |
| 3 | EQ1001S | 2-STG CENTRIFUGAL CHILLER <550 TONS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 6503 | 20559 | 38934 | 48240 | 16050 | 0 | 0 | 0 | 130,286 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 165.4 | 210.0 | 305.1 | 347.3 | 234.0 | 0.0 | 0.0 | 0.0 | 347.3 |
| 3 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | EQ5010 | CONDENSER WATER PUMP-CV(HIGH EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 2626 | 4715 | 9250 | 9489 | 5073 | 0 | 0 | 0 | 31,153 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 0.0 | 29.8 |
| 3 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 88 | 158 | 310 | 318 | 170 | 0 | 0 | 0 | 1,044 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 0.0 | 1.0 |
| 1 | | 030185.04 BLDG 1350 HWH BOILER 1 | | | | | | | | | | | | |
| | GAS | 5565 | 5263 | 5068 | 4904 | 0 | 0 | 0 | 0 | 0 | 0 | 4904 | 5696 | 31,400 |
| | PK | 13.2 | 13.9 | 6.8 | 6.8 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 6.8 | 11.4 | 13.9 |
| 1 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 22201 | 20052 | 22201 | 21485 | 0 | 0 | 0 | 0 | 0 | 0 | 21485 | 22201 | 129,625 |
| | PK | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 |
| 1 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 | 543 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 2 | | 030185.04 BLDG 1350 HWH BOILER 2 | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

----- EQUIPMENT ENERGY CONSUMPTION -----

| Ref Num | Equip Code | Monthly Consumption | | | | | | | | | | | | Total |
|------------|---------------|-----------------------------------|-------|-------|-------|-----|------|------|-----|-----|-----|-------|-------|---------|
| | | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 3 | | 030185.04 AREA 1300 HWH BOILER(S) | | | | | | | | | | | | |
| | GAS | 36755 | 35443 | 18831 | 11935 | 0 | 0 | 0 | 0 | 0 | 0 | 17631 | 35518 | 156,112 |
| | PK | 81.9 | 79.4 | 53.4 | 19.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 52.2 | 76.6 | 81.9 |
| 3 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 8325 | 7520 | 8325 | 8057 | 0 | 0 | 0 | 0 | 0 | 0 | 8057 | 8325 | 48,609 |
| | PK | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 |
| 3 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 | 543 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 3 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 8325 | 7520 | 8325 | 8057 | 0 | 0 | 0 | 0 | 0 | 0 | 8057 | 8325 | 48,609 |
| | PK | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 |
| 3 | EQ5240 | BOILER FORCED DRAFT FAN | | | | | | | | | | | | |
| | ELEC | 5550 | 5013 | 5550 | 5371 | 0 | 0 | 0 | 0 | 0 | 0 | 5371 | 5550 | 32,406 |
| | PK | 7.5 | 7.5 | 7.5 | 7.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 7.5 | 7.5 | 7.5 |
| 4 | | 030185.04 AREA 1300 HWH BOILER(S) | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | EQ5240 | BOILER FORCED DRAFT FAN | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
WATER COOLED CENTR. CHILLER, EXIST BOILR

----- EQUIPMENT ENERGY CONSUMPTION -----

| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
|-----|----------|-------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 248076 | 224754 | 249404 | 239859 | 248740 | 241188 | 247411 | 249404 | 239859 | 248740 | 241187 | 241432 | 2,920,053 |
| | PK | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 16368 | 15840 | 16368 | 16368 | 15840 | 16368 | 0 | 0 | 97,152 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.0 | 22.0 | 22.0 | 22.0 | 22.0 | 22.0 | 0.0 | 0.0 | 22.0 |
| 2 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 31992 | 30960 | 31992 | 31992 | 30960 | 31992 | 0 | 0 | 189,888 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 43.0 | 43.0 | 43.0 | 43.0 | 43.0 | 43.0 | 0.0 | 0.0 | 43.0 |
| 1 | EQ1001S | 2-STG CENTRIFUGAL CHILLER <550 TONS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 70092 | 85728 | 108560 | 96704 | 93491 | 62989 | 0 | 0 | 517,565 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 268.8 | 287.1 | 326.8 | 330.2 | 307.2 | 276.6 | 0.0 | 0.0 | 330.2 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 6863 | 6058 | 6669 | 5804 | 7311 | 4499 | 0 | 0 | 37,204 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 0.0 | 0.0 | 14.9 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
WATER COOLED CENTR. CHILLER, EXIST BOILER

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|--------|--------|--------|--------|--------|-------|-----|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| Total | | | | | | | | | | | | | |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 397 | 484 | 600 | 528 | 527 | 354 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.5 | 1.5 | 1.7 | 1.7 | 1.6 | 1.6 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 2,891 |
| | | | | | | | | | | | | | 1.7 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13726 | 12115 | 13338 | 11608 | 14622 | 19694 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 85,104 |
| | | | | | | | | | | | | | 29.8 |
| 1 | EQ5010 | CONDENSER WATER PUMP-CV(HIGH EFFIC.) | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 10295 | 9086 | 10004 | 8706 | 10966 | 14771 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 63,828 |
| | | | | | | | | | | | | | 22.4 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 460 | 406 | 447 | 389 | 490 | 660 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 2,852 |
| | | | | | | | | | | | | | 1.0 |
| 2 | | YORK CENTRIFUGAL R-134A CHILLER | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 124154 | 158702 | 198246 | 223687 | 144780 | 18405 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 437.4 | 453.1 | 475.2 | 479.0 | 446.8 | 373.4 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 867,974 |
| | | | | | | | | | | | | | 479.0 |
| 2 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 19418 | 26204 | 31685 | 35131 | 24534 | 4385 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 141,358 |
| | | | | | | | | | | | | | 52.2 |
| 2 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 884 | 1133 | 1401 | 1562 | 1034 | 146 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.0 | 3.0 | 3.1 | 3.1 | 3.0 | 2.7 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 6,160 |
| | | | | | | | | | | | | | 3.1 |
| 2 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 20813 | 28087 | 33962 | 37654 | 26297 | 4700 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 151,513 |
| | | | | | | | | | | | | | 56.0 |
| 2 | EQ5011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 20813 | 28087 | 33962 | 37654 | 26297 | 4700 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 151,513 |
| | | | | | | | | | | | | | 56.0 |
| 2 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 372 | 502 | 607 | 673 | 470 | 84 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 2,708 |
| | | | | | | | | | | | | | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
WAT. COOLED GAS ENGINE CHLR, EXIST BOILR

----- EQUIPMENT ENERGY CONSUMPTION -----

| Ref Num | Equip Code | Monthly Consumption | | | | | | | | | | | | Total |
|------------|---------------|-------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|
| | | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 248076 | 224754 | 249404 | 239859 | 248740 | 241188 | 247411 | 249404 | 239859 | 248740 | 241187 | 241432 | 2,920,053 |
| | PK | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 16368 | 15840 | 16368 | 16368 | 15840 | 16368 | 0 | 0 | 97,152 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.0 | 22.0 | 22.0 | 22.0 | 22.0 | 22.0 | 0.0 | 0.0 | 22.0 |
| 2 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 31992 | 30960 | 31992 | 31992 | 30960 | 31992 | 0 | 0 | 189,888 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 43.0 | 43.0 | 43.0 | 43.0 | 43.0 | 43.0 | 0.0 | 0.0 | 43.0 |
| 1 | EQ1001S | 2-STG CENTRIFUGAL CHILLER <550 TONS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 70092 | 85728 | 108560 | 96704 | 93491 | 62989 | 0 | 0 | 517,565 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 268.8 | 287.1 | 326.8 | 330.2 | 307.2 | 276.6 | 0.0 | 0.0 | 330.2 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 6863 | 6058 | 6669 | 5804 | 7311 | 4499 | 0 | 0 | 37,204 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 0.0 | 0.0 | 14.9 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
WAT. COOLED GAS ENGINE CHLR, EXIST BOILR

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|---------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| Total | | | | | | | | | | | | | |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 397 | 484 | 600 | 528 | 527 | 354 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.5 | 1.5 | 1.7 | 1.7 | 1.6 | 1.6 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 2,891 |
| | | | | | | | | | | | | | 1.7 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13726 | 12115 | 13338 | 11608 | 14622 | 19694 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 85,104 |
| | | | | | | | | | | | | | 29.8 |
| 1 | EQ5010 | CONDENSER WATER PUMP-CV(HIGH EFFIC.) | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 10295 | 9086 | 10004 | 8706 | 10966 | 14771 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 63,828 |
| | | | | | | | | | | | | | 22.4 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 460 | 406 | 447 | 389 | 490 | 660 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 2,852 |
| | | | | | | | | | | | | | 1.0 |
| 2 | | YORK ENGINE DRIVEN CHILLER | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 12610 | 16173 | 20369 | 23139 | 14796 | 1774 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 45.0 | 47.4 | 50.6 | 51.3 | 47.0 | 36.7 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 88,860 |
| | | | | | | | | | | | | | 51.3 |
| 2 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 19418 | 26204 | 31685 | 35131 | 24534 | 4385 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 141,358 |
| | | | | | | | | | | | | | 52.2 |
| 2 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 996 | 1278 | 1584 | 1772 | 1166 | 160 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.4 | 3.5 | 3.6 | 3.6 | 3.4 | 3.1 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 6,957 |
| | | | | | | | | | | | | | 3.6 |
| 2 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 20813 | 28087 | 33962 | 37654 | 26297 | 4700 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 151,513 |
| | | | | | | | | | | | | | 56.0 |
| 2 | EQ5011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 20813 | 28087 | 33962 | 37654 | 26297 | 4700 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 151,513 |
| | | | | | | | | | | | | | 56.0 |
| 2 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 372 | 502 | 607 | 673 | 470 | 84 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 2,708 |
| | | | | | | | | | | | | | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
W.C. CENTRIFUGAL VFD CHILLER, EXIST BLR

----- EQUIPMENT ENERGY CONSUMPTION -----

| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
|-----|----------|-------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 248076 | 224754 | 249404 | 239859 | 248740 | 241188 | 247411 | 249404 | 239859 | 248740 | 241187 | 241432 | 2,920,053 |
| | PK | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 16368 | 15840 | 16368 | 16368 | 15840 | 16368 | 0 | 0 | 97,152 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.0 | 22.0 | 22.0 | 22.0 | 22.0 | 22.0 | 0.0 | 0.0 | 22.0 |
| 2 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 31992 | 30960 | 31992 | 31992 | 30960 | 31992 | 0 | 0 | 189,888 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 43.0 | 43.0 | 43.0 | 43.0 | 43.0 | 43.0 | 0.0 | 0.0 | 43.0 |
| 1 | EQ1001S | 2-STG CENTRIFUGAL CHILLER <550 TONS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 70092 | 85728 | 108560 | 96704 | 93491 | 62989 | 0 | 0 | 517,565 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 268.8 | 287.1 | 326.8 | 330.2 | 307.2 | 276.6 | 0.0 | 0.0 | 330.2 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 6863 | 6058 | 6669 | 5804 | 7311 | 4499 | 0 | 0 | 37,204 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 0.0 | 0.0 | 14.9 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
W.C. CENTRIFUGAL VFD CHILLER, EXIST BLR

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|--------|--------|--------|--------|--------|-------|-----|-----|---------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 397 | 484 | 600 | 528 | 527 | 354 | 0 | 0 | 2,891 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.5 | 1.5 | 1.7 | 1.7 | 1.6 | 1.6 | 0.0 | 0.0 | 1.7 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13726 | 12115 | 13338 | 11608 | 14622 | 19694 | 0 | 0 | 85,104 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 29.8 |
| 1 | EQ5010 | CONDENSER WATER PUMP-CV(HIGH EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 10295 | 9086 | 10004 | 8706 | 10966 | 14771 | 0 | 0 | 63,828 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 0.0 | 0.0 | 22.4 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 460 | 406 | 447 | 389 | 490 | 660 | 0 | 0 | 2,852 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 2 | YCNVFD | YORK TURBO MODULATOR VAR. FREQ. DRIVE | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 115650 | 147760 | 186147 | 211694 | 134793 | 15891 | 0 | 0 | 811,935 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 419.5 | 441.7 | 472.9 | 479.0 | 437.2 | 340.0 | 0.0 | 0.0 | 479.0 |
| 2 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 19426 | 26214 | 31698 | 35144 | 24543 | 4386 | 0 | 0 | 141,412 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 0.0 | 0.0 | 52.2 |
| 2 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 876 | 1123 | 1390 | 1551 | 1025 | 143 | 0 | 0 | 6,109 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.0 | 3.0 | 3.1 | 3.1 | 3.0 | 2.7 | 0.0 | 0.0 | 3.1 |
| 2 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 20813 | 28087 | 33962 | 37654 | 26297 | 4700 | 0 | 0 | 151,513 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 0.0 | 0.0 | 56.0 |
| 2 | EQ5011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 20813 | 28087 | 33962 | 37654 | 26297 | 4700 | 0 | 0 | 151,513 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 0.0 | 0.0 | 56.0 |
| 2 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 372 | 502 | 607 | 673 | 470 | 84 | 0 | 0 | 2,708 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 4
WAT. COOLED DUAL SCREW CHILR, EXIST BLR

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|----------|-------------------------------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 248076 | 224754 | 249404 | 239859 | 248740 | 241188 | 247411 | 249404 | 239859 | 248740 | 241187 | 241432 | 2,920,053 |
| | PK | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 16368 | 15840 | 16368 | 16368 | 15840 | 16368 | 0 | 0 | 97,152 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.0 | 22.0 | 22.0 | 22.0 | 22.0 | 22.0 | 0.0 | 0.0 | 22.0 |
| 2 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 31992 | 30960 | 31992 | 31992 | 30960 | 31992 | 0 | 0 | 189,888 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 43.0 | 43.0 | 43.0 | 43.0 | 43.0 | 43.0 | 0.0 | 0.0 | 43.0 |
| 1 | EQ1001S | 2-STG CENTRIFUGAL CHILLER <550 TONS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 70092 | 85728 | 108560 | 96704 | 93491 | 62989 | 0 | 0 | 517,565 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 268.8 | 287.1 | 326.8 | 330.2 | 307.2 | 276.6 | 0.0 | 0.0 | 330.2 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 6863 | 6058 | 6669 | 5804 | 7311 | 4499 | 0 | 0 | 37,204 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 0.0 | 0.0 | 14.9 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 4
WAT. COOLED DUAL SCREW CHILR, EXIST BLR

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | | |
|--|---------|--|-----|-----|-----|--------|--------|--------|--------|--------|-------|-----|-----|---------|--|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | | |
| | | | | | | | | | | | | | | | |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 397 | 484 | 600 | 528 | 527 | 354 | 0 | 0 | 2,891 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.5 | 1.5 | 1.7 | 1.7 | 1.6 | 1.6 | 0.0 | 0.0 | 1.7 | |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 13726 | 12115 | 13338 | 11608 | 14622 | 19694 | 0 | 0 | 85,104 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 29.8 | |
| 1 | EQ5010 | CONDENSER WATER PUMP-CV(HIGH EFFIC.) | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 10295 | 9086 | 10004 | 8706 | 10966 | 14771 | 0 | 0 | 63,828 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 0.0 | 0.0 | 22.4 | |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 460 | 406 | 447 | 389 | 490 | 660 | 0 | 0 | 2,852 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 | |
| 2 | YSCRW22 | YORK W.C. SCREW CHILLER | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 131905 | 167567 | 210224 | 238248 | 150736 | 18266 | 0 | 0 | 916,945 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 483.0 | 500.4 | 524.8 | 529.0 | 493.4 | 412.3 | 0.0 | 0.0 | 529.0 | |
| 2 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 19426 | 26214 | 31698 | 35144 | 24543 | 4386 | 0 | 0 | 141,412 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 0.0 | 0.0 | 52.2 | |
| 2 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 891 | 1142 | 1412 | 1576 | 1039 | 145 | 0 | 0 | 6,204 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.0 | 3.1 | 3.1 | 3.1 | 3.0 | 2.8 | 0.0 | 0.0 | 3.1 | |
| 2 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 20813 | 28087 | 33962 | 37654 | 26297 | 4700 | 0 | 0 | 151,513 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 0.0 | 0.0 | 56.0 | |
| 2 | EQ5011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 20813 | 28087 | 33962 | 37654 | 26297 | 4700 | 0 | 0 | 151,513 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 0.0 | 0.0 | 56.0 | |
| 2 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 372 | 502 | 607 | 673 | 470 | 84 | 0 | 0 | 2,708 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 | |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
EXISTING CHILLERS, HIGH % MODULAR BOILERS

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|----------|--|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|-----------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 248076 | 224754 | 249404 | 239859 | 248740 | 241188 | 247411 | 249404 | 239859 | 248740 | 241187 | 241432 | 2,920,053 |
| | PK | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 | 689.0 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 13358 | 12065 | 13358 | 12927 | 0 | 0 | 0 | 0 | 0 | 0 | 12927 | 13358 | 77,992 |
| | PK | 18.0 | 18.0 | 18.0 | 18.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 18.0 | 18.0 | 18.0 |
| 1 | | HIGH EFFICIENCY MODULAR FIRETUBE BOIL. | | | | | | | | | | | | |
| | GAS | 14880 | 13440 | 14725 | 14142 | 0 | 0 | 0 | 0 | 0 | 0 | 14257 | 14880 | 86,323 |
| | PK | 20.0 | 20.0 | 20.0 | 20.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 20.0 | 20.0 | 20.0 |
| 1 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 4166 | 3763 | 4166 | 4032 | 0 | 0 | 0 | 0 | 0 | 0 | 4032 | 4166 | 24,326 |
| | PK | 5.6 | 5.6 | 5.6 | 5.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 5.6 | 5.6 | 5.6 |
| 1 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 | 543 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
EXISTING CHILLERS, HIGH % MODULAR BOILRS

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|-------|------|-----|-----|------|------|-----|-----|-----|------|-------|--------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 2 | | HIGH EFFICIENCY MODULAR FIRETUBE BOIL. | | | | | | | | | | | | |
| | GAS | 10665 | 11051 | 4016 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 3581 | 10438 | 39,761 |
| | PK | 20.0 | 20.0 | 20.0 | 0.7 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 20.0 | 20.0 | 20.0 |
| 2 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 4166 | 3763 | 1870 | 84 | 0 | 0 | 0 | 0 | 0 | 0 | 1691 | 4166 | 15,742 |
| | PK | 5.6 | 5.6 | 5.6 | 5.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 5.6 | 5.6 | 5.6 |
| 2 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 93 | 84 | 42 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 38 | 93 | 351 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 3 | | HIGH EFFICIENCY MODULAR FIRETUBE BOIL. | | | | | | | | | | | | |
| | GAS | 6138 | 6228 | 383 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 234 | 6204 | 19,188 |
| | PK | 20.0 | 20.0 | 6.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 5.5 | 20.0 | 20.0 |
| 3 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 2195 | 2150 | 510 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 342 | 2307 | 7,504 |
| | PK | 5.6 | 5.6 | 5.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 5.6 | 5.6 | 5.6 |
| 3 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 49 | 48 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 52 | 167 |
| | PK | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 4 | | HIGH EFFICIENCY MODULAR FIRETUBE BOIL. | | | | | | | | | | | | |
| | GAS | 1004 | 722 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 313 | 2,039 |
| | PK | 9.9 | 6.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 4.4 | 9.9 |
| 4 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 1086 | 1053 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 818 | 2,957 |
| | PK | 5.6 | 5.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 5.6 | 5.6 |
| 4 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 24 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 18 | 66 |
| | PK | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |

01 Card - Job Information

Project: 03018504 EEAP BOILER-CHILLER STUDY
 Location: FT. SAM HOUSTON - SAN ANTONIO, TX.
 Client: CORPS OF ENGINEERS - FORT WORTH, TEXAS
 Program User: HUITT - ZOLLARS INC.
 Comments: AREA 2200

Card 08----- Climatic Information -----

| | Summer | Winter | Summer | Summer | Winter | | Summer | Winter |
|----------|-----------|-----------|----------|----------|----------|-------------|---------|---------|
| Weather | Clearness | Clearness | Design | Design | Design | Building | Ground | Ground |
| Code | Number | Number | Dry Bulb | Wet Bulb | Dry Bulb | Orientation | Reflect | Reflect |
| SANANTON | | | | | | | | |

----- Load Section Alternative #1 -----

Card 19- Load Alternative -

| Number | Description |
|--------|-------------|
| 1 | AREA 2200 |

Card 20----- General Room Parameters -----

| Zone | | General Room Parameters | | | | | | | Acoustic | Floor to | Duplicate | Duplicate | Perimeter |
|--------|-----------|-------------------------|--------|-------|-------|--------|------------|--------|------------|-----------|-----------|-----------|-----------|
| Room | Reference | Room | Floor | Floor | Const | Plenum | Ceiling | Floor | Floors | Rooms per | Depth | | |
| Number | Number | Descrip | Length | Width | Type | Height | Resistance | Height | Multiplier | Zone | | | |
| 5 | 5 | BLDG 2263 | 264 | 265 | 3 | 3 | 2.54 | 11 | | | | | |
| 15 | 15 | DINING 2265 | 77 | 77 | 3 | 2.5 | 2.54 | 11 | | | | | |
| 20 | 20 | BARR 2265 | 299 | 299 | 3 | 2.5 | 2.54 | 11 | | | | | |
| 25 | 25 | ADMIN 2264 | 221 | 222 | 3 | 2.5 | 2.54 | 11 | | | | | |
| 30 | 30 | BARR 2264 | 221 | 222 | 3 | 2.5 | 2.54 | 11 | | | | | |
| 35 | 35 | ADMIN 2266 | 221 | 222 | 3 | 2.5 | 2.54 | 11 | | | | | |
| 40 | 40 | BARR 2266 | 221 | 222 | 3 | 2.5 | 2.54 | 11 | | | | | |

Card 21----- Thermostat Parameters -----

| Cooling | | Room | Cooling | Cooling | Heating | Heating | Heating | T'stat | Mass / | Carpet |
|---------|--------|--------|---------|------------|----------|---------|---------|------------|----------|--------|
| Room | Room | Design | T'stat | T'stat | Room | T'stat | T'stat | Location | No. Hrs | On |
| Number | Design | DB | RH | Driftpoint | Schedule | Design | DB | Driftpoint | Schedule | Flag |
| 5 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | YES |
| 15 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 20 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | YES |

Card 21----- Thermostat Parameters -----

| Room | Cooling Room | Room Design | Cooling T'stat | Cooling T'stat | Heating Room | Heating T'stat | Heating T'stat | T'stat Location | Mass / No. Hrs | Carpet On |
|--------|--------------|-------------|----------------|----------------|--------------|----------------|----------------|-----------------|----------------|-----------|
| Number | Design DB | RH | Driftpoint | Schedule | Design DB | Driftpoint | Schedule | Flag | Average | Floor |
| 25 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | YES |
| 30 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | YES |
| 35 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | YES |
| 40 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | YES |

Card 22----- Roof Parameters -----

| Room | Roof | Roof | Roof | Roof | Roof | Const | Roof | Roof | Roof |
|--------|--------|-----------------|--------|-------|---------|-------|-----------|------|-------|
| Number | Number | Equal to Floor? | Length | Width | U-Value | Type | Direction | Tilt | Alpha |
| 5 | 1 | NO | 164 | 164 | .09 | 37 | | 80 | |
| 20 | 1 | NO | 165 | 166 | .09 | 37 | | 80 | |
| 30 | 1 | NO | 165 | 166 | .09 | 37 | | 80 | |
| 40 | 1 | NO | 165 | 166 | .09 | 37 | | 80 | |

Card 24----- Wall Parameters -----

| Room | Wall | Wall | Wall | Wall | Wall | Constuc | Wall | Wall | Wall | Ground |
|--------|--------|--------|--------|---------|------|---------|-----------|------|-------|------------------------|
| Number | Number | Length | Height | U-Value | Type | Type | Direction | Tilt | Alpha | Reflectance Multiplier |
| 5 | 1 | 924 | 11 | .49 | 74 | 0 | | | .74 | |
| 5 | 2 | 414 | 11 | .49 | 74 | 90 | | | .74 | |
| 5 | 3 | 924 | 11 | .49 | 74 | 180 | | | .74 | |
| 5 | 4 | 414 | 11 | .49 | 74 | 270 | | | .74 | |
| 15 | 1 | 309 | 11 | .41 | 94 | 0 | | | .74 | |
| 20 | 1 | 810 | 11 | .41 | 94 | 0 | | | .74 | |
| 20 | 2 | 243 | 11 | .41 | 94 | 90 | | | .74 | |
| 20 | 3 | 810 | 11 | .41 | 94 | 180 | | | .74 | |
| 20 | 4 | 243 | 11 | .41 | 94 | 270 | | | .74 | |
| 25 | 1 | 357 | 11 | .41 | 94 | 0 | | | .74 | |
| 25 | 2 | 81 | 11 | .41 | 94 | 90 | | | .74 | |
| 25 | 3 | 357 | 11 | .41 | 94 | 180 | | | .74 | |
| 25 | 4 | 81 | 11 | .41 | 94 | 270 | | | .74 | |
| 30 | 1 | 714 | 11 | .41 | 94 | 0 | | | .74 | |
| 30 | 2 | 162 | 11 | .41 | 94 | 90 | | | .74 | |
| 30 | 3 | 714 | 11 | .41 | 94 | 180 | | | .74 | |
| 30 | 4 | 162 | 11 | .41 | 94 | 270 | | | .74 | |
| 35 | 1 | 357 | 11 | .41 | 94 | 0 | | | .74 | |
| 35 | 2 | 81 | 11 | .41 | 94 | 90 | | | .74 | |
| 35 | 3 | 357 | 11 | .41 | 94 | 180 | | | .74 | |
| 35 | 4 | 81 | 11 | .41 | 94 | 270 | | | .74 | |
| 40 | 1 | 714 | 11 | .41 | 94 | 0 | | | .74 | |
| 40 | 2 | 162 | 11 | .41 | 94 | 90 | | | .74 | |
| 40 | 3 | 714 | 11 | .41 | 94 | 180 | | | .74 | |
| 40 | 4 | 162 | 11 | .41 | 94 | 270 | | | .74 | |

Card 25----- Wall/Glass Parameters -----

| Room Number | Wall Number | Glass Length | Glass Width | Pct Glass | | Shading Coefficient | External Shading Type | Internal Shading Type | Percent | | Inside Visible Reflectance |
|----------------|----------------|-----------------|----------------|----------------------|------------------|------------------------|-----------------------------|-----------------------------|----------------------|--------------------------|----------------------------------|
| | | | | or No. of Windows | Glass U-Value | | | | Solar to Ret. Air | Visible Transmittance | |
| 5 | 1 | 3 | 6 | 97 | 1.1 | .67 | | | | | |
| 5 | 2 | | | 16 | .63 | 1 | | | | | |
| 5 | 3 | | | 32 | .57 | 1 | | | | | |
| 5 | 4 | | | 16 | .63 | 1 | | | | | |
| 15 | 1 | 3 | 6 | 35 | 1.1 | .67 | | | | | |
| 20 | 1 | 3 | 6 | 82 | 1.1 | .67 | | | | | |
| 20 | 2 | 3 | 6 | 27 | 1.1 | .67 | | | | | |
| 20 | 3 | 3 | 6 | 96 | 1.1 | .67 | 3 | | | | |
| 20 | 4 | 3 | 6 | 27 | 1.1 | .67 | | | | | |
| 25 | 1 | 3 | 6 | 41 | 1.1 | .67 | | | | | |
| 25 | 2 | 3 | 6 | 9 | 1.1 | .67 | | | | | |
| 25 | 3 | 3 | 6 | 48 | 1.1 | .67 | 3 | | | | |
| 25 | 4 | 3 | 6 | 9 | 1.1 | .67 | | | | | |
| 30 | 1 | 3 | 6 | 82 | 1.1 | .67 | | | | | |
| 30 | 2 | 3 | 6 | 18 | 1.1 | .67 | | | | | |
| 30 | 3 | 3 | 6 | 96 | 1.1 | .67 | 3 | | | | |
| 30 | 4 | 3 | 6 | 18 | 1.1 | .67 | | | | | |
| 35 | 1 | 3 | 6 | 41 | 1.1 | .67 | | | | | |
| 35 | 2 | 3 | 6 | 9 | 1.1 | .67 | | | | | |
| 35 | 3 | 3 | 6 | 48 | 1.1 | .67 | 3 | | | | |
| 35 | 4 | 3 | 6 | 9 | 1.1 | .67 | | | | | |
| 40 | 1 | 3 | 6 | 82 | 1.1 | .67 | | | | | |
| 40 | 2 | 3 | 6 | 18 | 1.1 | .67 | | | | | |
| 40 | 3 | 3 | 6 | 96 | 1.1 | .67 | 3 | | | | |
| 40 | 4 | 3 | 6 | 18 | 1.1 | .67 | | | | | |

Card 26----- Schedules -----

| Room Number | People | Lights | Ventilation | Infiltration | Reheat Minimum | Cooling Fans | Heating Fan | Auxiliary Fan | Room Exhaust | Daylighting Controls |
|----------------|----------|----------|-------------|--------------|-------------------|-----------------|----------------|------------------|-----------------|-------------------------|
| 5 | FSHOFFIC | FSHOFFIC | | | | | | | | |
| 15 | FSHDINP | FSHDINL | | | | | | | | |
| 20 | FSHBARRP | FSHBARRL | | | | | | | | |
| 25 | FSHOFFIC | FSHOFFIC | | | | | | | | |
| 30 | FSHBARRP | FSHBARRL | | | | | | | | |
| 35 | FSHOFFIC | FSHOFFIC | | | | | | | | |
| 40 | FSHBARRP | FSHBARRL | | | | | | | | |

Card 27----- People and Lights -----

| Room Number | People Value | People Units | People Sensible | People Latent | Lighting Value | Lighting Units | Lighting | | Ballast Factor | Percent Lights to Ret. Air | --- Daylighting --- | |
|----------------|-----------------|-----------------|--------------------|------------------|-------------------|-------------------|-----------------|--|-------------------|----------------------------------|----------------------|----------------------|
| | | | | | | | Fixture Type | | | | Reference Point 1 | Reference Point 2 |
| 5 | 250 | PEOPLE | 250 | 200 | 2.5 | WATT-SF | ASHRAE2 | | | | | |
| 15 | 400 | PEOPLE | 275 | 275 | 1.3 | WATT-SF | ASHRAE2 | | | | | |

Card 27----- People and Lights -----

| Room Number | People | | | | Lighting | | Lighting Fixture Type | Ballast Factor | Percent Lights to Ret. Air | | --- Daylighting --- | |
|-------------|--------|--------|----------|--------|----------|-------|-----------------------|----------------|----------------------------|--|---------------------|-------------------|
| | Value | Units | Sensible | Latent | Value | Units | | | Ret. Air | | Reference Point 1 | Reference Point 2 |
| 20 | 215 | PEOPLE | 250 | 200 | .8 | | WATT-SF ASHRAE2 | | | | | |
| 25 | 40 | PEOPLE | 250 | 200 | 2.0 | | WATT-SF ASHRAE2 | | | | | |
| 30 | 350 | PEOPLE | 250 | 200 | .8 | | WATT-SF ASHRAE2 | | | | | |
| 35 | 40 | PEOPLE | 250 | 200 | 2.0 | | WATT-SF ASHRAE2 | | | | | |
| 40 | 350 | PEOPLE | 250 | 200 | .8 | | WATT-SF ASHRAE2 | | | | | |

Card 28----- Miscellaneous Equipment -----

| Room Number | Misc Equipment | | Energy Consump | | Schedule Code | Energy Meter Code | Percent of Load Sensible | Percent Misc. Load to Room | Percent Misc. Sens to Ret. Air | Radiant Fraction | Optional Air Path |
|-------------|----------------|-----------|----------------|---------|---------------|-------------------|--------------------------|----------------------------|--------------------------------|------------------|-------------------|
| | Number | Descrip | Value | Units | | | | | | | |
| 5 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 15 | 1 | DIN. EQ. | 1 | WATT-SF | FSHDINL | | | | | | |
| 20 | 1 | T.V. ETC. | 1 | WATT-SF | FSHBARRL | | | | | | |
| 25 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 30 | 1 | T.V. ETC. | 1 | WATT-SF | FSHBARRL | | | | | | |
| 35 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 40 | 1 | T.V. ETC. | 1 | WATT-SF | FSHBARRL | | | | | | |

Card 29----- Room Airflows -----

| Room Number | Ventilation | | | | Infiltration | | | | --Reheat Minimum-- | |
|-------------|-------------|-------|---------|-------|--------------|--|---------|--|--------------------|-------|
| | Cooling | | Heating | | Cooling | | Heating | | Value | Units |
| 5 | 20 | CFM-P | 20 | CFM-P | | | | | | |
| 15 | 20 | CFM-P | 20 | CFM-P | | | | | | |
| 20 | 20 | CFM-P | 20 | CFM-P | | | | | | |
| 25 | 20 | CFM-P | 20 | CFM-P | | | | | | |
| 30 | 20 | CFM-P | 20 | CFM-P | | | | | | |
| 35 | 20 | CFM-P | 20 | CFM-P | | | | | | |
| 40 | 20 | CFM-P | 20 | CFM-P | | | | | | |

Card 33----- External Shading -----

| Shading Type | OVERHANG | | | | VERTICAL FINS | | | | Adjacent Building Flag |
|--------------|--------------|-------------|----------------|-------------|-----------------|------------------|----------------|------------------|------------------------|
| | Glass Height | Above Glass | Projection Out | Glass Width | Projection Left | Projection Right | Projection Out | Projection Right | |
| 3 | 6 | 1 | 5 | | | | | | |

----- System Section Alternative #1 -----

Card 39- System Alternative

| Number | Description |
|--------|-----------------|
| 1 | EXISTING SYSTEM |

Card 40----- System Type -----

| -----OPTIONAL VENTILATION SYSTEM----- | | | | | | | | |
|---------------------------------------|------|----------|-------------|---------|----------|----------|----------|--------|
| System | Set | System | Ventil Deck | Cooling | Heating | Cooling | Heating | Static |
| Number | Type | Location | SADBVh | SADBVh | Schedule | Schedule | Pressure | |
| 1 | SZ | | | | | | | |

Card 41----- Zone Assignment -----

| System | Set | Ref #1 | Ref #2 | Ref #3 | Ref #4 | Ref #5 | Ref #6 |
|--------|-----|--------|--------|--------|--------|--------|--------|
| | | Begin | End | Begin | End | Begin | End |
| 1 | | 5 | 40 | | | | |

Card 42----- Fan SP and Duct Parameters-----

| System | Cool | Heat | Return | Mn Exh | Aux | Rm Exh | Cool | Return | Supply | Supply | Return |
|--------|------|------|--------|--------|-----|--------|---------|---------|--------|--------|--------|
| Set | Fan | Fan | Fan | Fan | Fan | Fan | Fan Mtr | Fan Mtr | Duct | Duct | Air |
| Number | SP | SP | SP | SP | SP | SP | Loc | Loc | Ht Gn | Loc | Path |
| 1 | 2 | 2 | | | | | | | | | |

Card 45----- Equipment Schedules -----

| System | Main | Direct | Indirect | Auxiliary | Main | Main | Auxiliary |
|--------|----------|------------|----------|-----------|----------|----------|-----------|
| Set | Cooling | Evap | Evap | Cooling | Heating | Preheat | Reheat |
| Number | Coil | Economizer | Coil | Coil | Coil | Coil | Coil |
| 1 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG |

----- Equipment Section Alternative #1 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Temperature |
|-------------|--------------|-------------|--------|-------------|
| Number | Time of Day | Time of Day | Limit | Drift |
| 1 | Schedule | Schedule | Max KW | BASE CASE |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------|----------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Ref | Cool Ref | Sizing | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | BLKPLANT | 1 | 1 | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | -----COOLING----- | | | | -----HEAT RECOVERY----- | | | | Seq | Demand |
|------------|-------|-------------------|-------|----------------|-------|-------------------------|-------|----------------|-------|-------|-------------|
| Ref Code | Of | --Capacity-- | | ----Energy---- | | --Capacity-- | | ----Energy---- | | Order | Seq Limit |
| Num Name | Units | Value | Units | Value | Units | Value | Units | Value | Units | Num | Type Number |
| 1 EQ1001L | 1 | 657 | TONS | 595 | KW | | | | | | |

Card 63----- Cooling Pumps and References -----

| Cool | ---CHILLED WATER---- | | | | | | | | | | ---CONDENSER----- | | ---HT REC or AUX---- | | Switch- |
|------|----------------------|-----------|-----------|-----------|-----------|-----------|-----------|-------|---------|---------|-------------------|---------|----------------------|--|---------|
| Ref | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | over | Cold | Cooling | Misc. | | | | |
| Num | Value | Units | Value | Units | Value | Units | Value | Units | Control | Storage | Tower | Access. | | | |
| 1 | 74.6 | KW | 37.3 | KW | | | | | | | 1 | | | | |

Card 65----- Heating Load Assignment -----

| Load | All Coil | | | | | | | | | | |
|------------|-------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|--|
| Assignment | Loads To | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- | |
| Reference | Heating Ref | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | |
| 1 | 1 | 1 | 1 | | | | | | | | |

Card 67----- Heating Equipment Parameters -----

| Heat | Equip | Number | HW Pmp | Energy | | Seq | Switch | Demand | | |
|--------|----------|--------|---------|--------|-------|-------|---------|--------|-------|-------|
| Ref | Code | Of | Full Ld | Cap'y | Rate | Order | over | Hot | Misc. | Limit |
| Number | Name | Units | Value | Units | Value | Units | Control | Strg | Acc. | Cogen |
| 1 | 2200EXST | 1 | 11.19 | KW | 2240 | MBH | 3000 | MBH | 1 | |
| 2 | 2200EXST | 1 | 11.19 | KW | 2240 | MBH | 3000 | MBH | 2 | |
| 3 | 2200EXST | 1 | 11.19 | KW | 2240 | MBH | 3000 | MBH | 3 | |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Energy | | Equip | Demand |
|---------|------------------|--------|--------|----------|----------|-----------|----------|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting |
| Number | Descrip | Value | Units | Code | Type | Number | Number |
| 1 | PIPE-PUMP HT LOS | 39.1 | TONS | FTSAMCLG | CHILL-LD | 1 | |
| 2 | PIPE HT LOSS | 612.2 | MBH | FTSAMHTG | HOT-LD | 1 | |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | Capacity | | Energy | Energy | Fluid | Tower | Number | Percent | Low Spd | Low Spd |
|---------|----------|----------|---------|---------|-------|-------|--------|---------|---------|---------|
| Tower | Tower | Capacity | Consump | Consump | Type | Type | Of | Airflow | Energy | Energy |
| Ref | Code | Value | Value | Units | Type | Type | Cells | Low Spd | Value | Units |
| 1 | EQ5100 | | 29.84 | KW | | | 2 | | | |

Card 75----- Miscellaneous Accessory -----

| #1 | | | | #2 | | | | #3 | | | | |
|------|--------|--------|--------|-------|-------|--------|--------|-------|-------|--------|--------|-------|
| Misc | Equip | Energy | Energy | Sched | Equip | Energy | Energy | Sched | Equip | Energy | Energy | Sched |
| Ref | Code | Value | Units | Code | Code | Value | Units | Code | Code | Value | Units | Code |
| 1 | EQ5013 | .56 | KW | | | | | | | | | |
| 2 | EQ5013 | .56 | KW | | | | | | | | | |
| 3 | EQ5013 | .56 | KW | | | | | | | | | |

----- Equipment Section Alternative #2 -----

Card 59----- Equipment Description / TOU Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Temperature |
|-------------|--------------|-------------|--------|---|
| Number | Time of Day | Time of Day | Limit | Drift |
| Number | Schedule | Schedule | Max KW | Alternative Description |
| 2 | | | | GAS ENGINE DRIVEN CHILLER, EXISTING BLR |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------|----------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Ref | Cool Ref | Sizing | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | BLKPLANT | 1 1 | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | COOLING | HEAT RECOVERY | Seq | Demand |
|------------|----------|---------|---------------|-------|--------|
| Ref | Code | Of | Capacity | Order | Seq |
| Num | Name | Units | Value | Units | Value |
| 1 | YENGDRIV | 1 | 555 | TONS | 3663 |

Card 63----- Cooling Pumps and References -----

| Cool | CHILLED WATER | CONDENSER | HT REC or AUX | Switch |
|------|---------------|-----------|---------------|-----------|
| Ref | Full Load | Full Load | Full Load | Full Load |
| Num | Value | Units | Value | Units |
| 1 | 74.6 | KW | 37.3 | KW |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Equip | Demand |
|---------|------------------|--------|--------|----------|----------|
| Utility | Utility | Demand | Demand | Schedule | Energy |
| Number | Descrip | Value | Units | Code | Type |
| 1 | PIPE-PUMP HT LOS | 39.1 | TONS | FTSAMCLG | CHILL-LD |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | | | | Energy | | Energy | | Number | | Percent | | Low Spd | | Low Spd | |
|---------|--------|----------|----------|---------|---------|--------|-------|--------|---------|---------|--------|---------|--|---------|--|
| Tower | Tower | Capacity | Capacity | Consump | Consump | Fluid | Tower | Of | Airflow | Energy | Energy | | | | |
| Ref | Code | Value | Units | Value | Units | Type | Type | Cells | Low Spd | Value | Units | | | | |
| 1 | EQ5100 | | | 29.84 | KW | | | 2 | | | | | | | |

----- Equipment Section Alternative #3 -----

Card 59----- Equipment Description / TOU Schedules -----

| Elec Consump | | | | Elec Demand | | Demand Limit | | Demand Limit | |
|--------------|-------------|-------------|--------|--|-------------|--------------|-------|--------------|--|
| Alternative | Time of Day | Time of Day | Limit | Alternative | Description | Schedule | Drift | Temperature | |
| Number | Schedule | Schedule | Max KW | Alternative | Description | Schedule | Drift | Temperature | |
| 3 | | | | W. C. DUAL SCREW CHILLER, EXIST BOILER | | | | | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | | | | | | | | | | | | | |
|------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|--|--|--|--|
| Asgn | Loads To | Equipment | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- | | | | |
| Ref | Cool Ref | Sizing | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | | | | |
| 1 | 1 | BLKPLANT | 1 1 | | | | | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | | Num | COOLING----- | | | | HEAT RECOVERY----- | | | | Seq | Demand | |
|------------|---------|-------|--------------|-------|------------|--------------|--------------------|------------|-------|-------|-------|--------|--------|
| Ref | Code | Of | --Capacity-- | ---- | Energy---- | --Capacity-- | ---- | Energy---- | Order | Seq | Limit | | |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Value | Units | Num | Type | Number |
| 1 | YSCRW22 | 1 | 555 | TONS | 355 | KW | | | | | | | |

Card 63----- Cooling Pumps and References -----

| Cool | CHILLED WATER---- | CONDENSER----- | HT REC or AUX---- | Switch- | | | | | | | | |
|------|-------------------|----------------|-------------------|-----------|-----------|-----------|---------|---------|---------|---------|--|--|
| Ref | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | over | Cold | Cooling | Misc. | | |
| Num | Value | Units | Value | Units | Value | Units | Control | Storage | Tower | Access. | | |
| 1 | 74.6 | KW | 37.3 | KW | | | | | 1 | | | |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Equip | Demand | | | | | | |
|---------|------------------|--------|--------|----------|----------|-----------|----------|----------|---------|--|--|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting | Entering | Leaving | | |
| Number | Descrip | Value | Units | Code | Type | Number | Number | Temp | Temp | | |
| 1 | PIPE-PUMP HT LOS | 39.1 | TONS | FTSAMCLG | CHILL-LD | 1 | | | | | |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | | | | Energy | | Energy | | Number | | Percent | | Low Spd | | Low Spd | |
|---------|--------|----------|----------|---------|---------|--------|-------|--------|---------|---------|--------|---------|--|---------|--|
| Tower | Tower | Capacity | Capacity | Consump | Consump | Fluid | Tower | Of | Airflow | Energy | Energy | | | | |
| Ref | Code | Value | Units | Value | Units | Type | Type | Cells | Low Spd | Value | Units | | | | |
| 1 | EQ5100 | | | 29.84 | KW | | | 2 | | | | | | | |

----- Equipment Section Alternative #4 -----

Card 59----- Equipment Description / TOD Schedules -----

| Elec Consump | | | | Elec Demand | | Demand | | Demand Limit | | Temperature | |
|--------------|-------------|-------------|--------|--|----------|--------|--|--------------|--|-------------|--|
| Alternative | Time of Day | Time of Day | Limit | | | | | | | | |
| Number | Schedule | Schedule | Max KW | Alternative Description | Schedule | Drift | | | | | |
| 4 | | | | W.C. CENTRIFUGAL CHILLER, EXISTING BOILR | | | | | | | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | | | | | | | | | | | | | |
|------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|--|--|--|--|
| Asgn | Loads To | Equipment | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- | | | | |
| Ref | Cool Ref | Sizing | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | | | | |
| 1 | | BLKPLANT | 1 | 1 | | | | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | | | | COOLING | | | | HEAT RECOVERY | | | | Seq | | Demand | |
|------------|----------|-------|--------------|------------|-------|--------------|-------|---------------|-------|-------|-----|-------|--------|--------|--|
| Ref | Code | Of | --Capacity-- | --Energy-- | | --Capacity-- | | --Energy-- | | Order | Seq | Limit | | | |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Value | Units | Num | Type | Number | | |
| 1 | YCENT134 | 1 | 555 | TONS | 322 | KW | | | | | | | | | |

Card 63----- Cooling Pumps and References -----

| Cool ---CHILLED WATER---- | | -----CONDENSER----- | | ---HT REC or AUX--- | | Switch- | | | | | | | |
|---------------------------|-----------|---------------------|-----------|---------------------|-----------|-----------|-----------|---------|-------|---------|-------|--|--|
| Ref | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | over | Cold | Cooling | Misc. | | |
| Num | Value | Units | Value | Units | Value | Units | Control | Storage | Tower | Access. | | | |
| 1 | 74.6 | KW | 37.3 | KW | | | | | | | | | |

Card 71----- Base Utility Parameters -----

| Base | | Hourly | | Hourly | | Equip | | Demand | | | | | |
|---------|------------------|--------|--------|----------|----------|-----------|----------|----------|---------|--|--|--|--|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting | Entering | Leaving | | | | |
| Number | Descrip | Value | Units | Code | Type | Number | Number | Temp | Temp | | | | |
| 1 | PIPE-PUMP HT LOS | 39.1 | TONS | FTSAMCLG | CHILL-LD | 1 | | | | | | | |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | | | | Energy | | Energy | | Number | | Percent | | Low Spd | | Low Spd | |
|---------|-------|----------|----------|---------|---------|--------|-------|--------|---------|---------|--------|---------|--|---------|--|
| Tower | Tower | Capacity | Capacity | Consump | Consump | Fluid | Tower | Of | Airflow | Energy | Energy | | | | |
| Ref | Code | Value | Units | Value | Units | Type | Type | Cells | Low Spd | Value | Units | | | | |
| | | | | | | | | | | | | | | | |

Utility Description Reference Table

Schedules:

FSHBARRL F.S.H. BARRACKS LIGHT/MISC. SCHEDULE
FSHBARRP F.S.H. BARRACKS PEOPLE SCHEDULE
FSHDINL F.S.H. DINING LIGHTING/MISC. LOAD SCHED.
FSHDINP F.S.H. DINING PEOPLE SCHEDULE
FSHOFFIC F.S.H. OFFICE INTERNAL LOAD SCHEDULE
FTSAMCLG EEAP BOILER/CHILLER STUDY
FTSAMHTG EEAP BOILER/CHILLER STUDY

System:

SZ SINGLE ZONE

Equipment:

Cooling:

EQ1001L 2-STG CENTRIFUGAL CHILLER >550 TONS
YCENT134 YORK CENT. R-134A CHILL
YENGDRIV YORK ENGINE DRIVEN CHILLER
YSCRW22 YORK W.C. SCREW CHILL.

Heating:

2200EXST EXISTING NAT. DRAFT AJAX HWH BOILER

Tower:

EQ5100 COOLING TOWER FANS

Misc:

EQ5013 WATER CIRCULATING PUMP - CONSTANT VOLUME

Card 39- System Alternative

| Number | Description |
|--------|-----------------|
| 1 | EXISTING SYSTEM |

Card 40----- System Type -----

| -----OPTIONAL VENTILATION SYSTEM----- | | | | | | | |
|---------------------------------------|------|----------|--------|--------|----------|----------|----------|
| System | Set | System | Ventil | Deck | Cooling | Heating | Static |
| Number | Type | Location | SADBvh | SADBvh | Schedule | Schedule | Pressure |
| 1 | SZ | | | | | | |

Card 41----- Zone Assignment -----

| System | Set | Ref #1 | Ref #2 | Ref #3 | Ref #4 | Ref #5 | Ref #6 |
|--------|-----|--------|--------|--------|--------|--------|--------|
| | | Begin | End | Begin | End | Begin | End |
| 1 | | 5 | 40 | | | | |

Card 42----- Fan SP and Duct Parameters-----

| System | Cool | Heat | Return | Mn Exh | Aux | Rm Exh | Cool | Return | Supply | Supply | Return |
|--------|------|------|--------|--------|-----|--------|---------|---------|--------|--------|--------|
| Set | Fan | Fan | Fan | Fan | Fan | Fan | Fan Mtr | Fan Mtr | Duct | Duct | Air |
| Number | SP | SP | SP | SP | SP | SP | Loc | Loc | Ht Gn | Loc | Path |
| 1 | 2 | 2 | | | | | | | | | |

Card 45----- Equipment Schedules -----

| System | Main | Direct | Indirect | Auxiliary | Main | Main | Reheat | Mech. | Auxiliary |
|--------|----------|------------|----------|-----------|---------|----------|----------|----------|-----------|
| Set | Cooling | Evap | Evap | Cooling | Heating | Preheat | Reheat | Heating | Heating |
| Number | Coil | Economizer | Coil | Coil | Coil | Coil | Coil | Humidity | Coil |
| 1 | FTSAMCLG | | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | |

----- Equipment Section Alternative #1 -----

Card 59----- Equipment Description / TOU Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Time of Day | Time of Day | Limit | Max KW | Alternative Description | Schedule | Temperature | Drift |
|-------------|--------------|-------------|--------|-------------|-------------|-------|--------|-------------------------|----------|-------------|-------|
| 1 | | | | | | | | BASE CASE | | | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | Asgn | Loads To | Equipment | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------|----------|----------|-------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Ref | Cool Ref | Sizing | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End |
| 1 | 1 | BLKPLANT | 1 | 1 | | | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | -----COOLING----- | | | | -----HEAT RECOVERY----- | | | | Seq | Demand | | |
|------------|---------|-------------------|-------|--------------|-------|-------------------------|-------|--------------|-------|-------|--------|-------|--------|
| Ref Code | Of | --Capacity-- | | ---Energy--- | | --Capacity-- | | ---Energy--- | | Order | Seq | Limit | |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Value | Units | Num | Type | Number |
| 1 | EQ1001L | 1 | 657 | TONS | 595 | KW | | | | | | | |

Card 63----- Cooling Pumps and References -----

| Cool | ---CHILLED WATER---- | | | | | | | | | | ---CONDENSER----- | | ---HT REC or AUX---- | | Switch- |
|------|----------------------|-----------|-----------|-----------|-----------|-----------|-----------|-------|---------|---------|-------------------|---------|----------------------|--|---------|
| Ref | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | Full Load | over | Cold | Cooling | Misc. | | | | |
| Num | Value | Units | Value | Units | Value | Units | Value | Units | Control | Storage | Tower | Access. | | | |
| 1 | 74.6 | KW | 37.3 | KW | | | | | | | | | 1 | | |

Card 65----- Heating Load Assignment -----

| Load | All Coil | | | | | | | | | | | | |
|------------|-------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----|-------|-----|
| Assignment | Loads To | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- | | | |
| Reference | Heating Ref | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End |
| 1 | 1 | 1 | 1 | | | | | | | | | | |

Card 67----- Heating Equipment Parameters -----

| Heat | Equip | Number | HW Pmp | Energy | | | | Seq | Switch | Demand | | | | |
|--------|----------|--------|---------|--------|-------|-------|-------|-------|--------|---------|------|------|-------|--------|
| Ref | Code | Of | Full Ld | Cap'y | Rate | Order | over | Hot | Misc. | Limit | | | | |
| Number | Name | Units | Value | Units | Value | Units | Value | Units | Number | Control | Strg | Acc. | Cogen | Number |
| 1 | 2200EXST | 1 | 11.19 | KW | 2240 | MBH | 3000 | MBH | 1 | | | | 1 | |
| 2 | 2200EXST | 1 | 11.19 | KW | 2240 | MBH | 3000 | MBH | 2 | | | | 2 | |
| 3 | 2200EXST | 1 | 11.19 | KW | 2240 | MBH | 3000 | MBH | 3 | | | | 3 | |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Equip | Demand |
|---------|------------------|--------|--------|----------|----------|
| Utility | Utility | Demand | Demand | Schedule | Energy |
| Number | Descrip | Value | Units | Code | Type |
| 1 | PIPE-PUMP HT LOS | 39.1 | TONS | FTSAMCLG | CHILL-LD |
| 2 | PIPE HT LOSS | 612.2 | MBH | FTSAMHTG | HOT-LD |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | Energy | Energy | Number | Percent | Low Spd | Low Spd |
|---------|---------|---------|--------|---------|---------|---------|
| Tower | Consump | Consump | Of | Airflow | Energy | Energy |
| Ref | Value | Units | Cells | Low Spd | Value | Units |
| 1 | EQ5100 | 29.84 | KW | 2 | | |

Card 75----- Miscellaneous Accessory -----

| #1 | | | | | #2 | | | | | #3 | | | | |
|------|--------|--------|--------|-------|-------|--------|--------|-------|-------|--------|--------|-------|--|--|
| Misc | Equip | Energy | Energy | Sched | Equip | Energy | Energy | Sched | Equip | Energy | Energy | Sched | | |
| Ref | Code | Value | Units | Code | Code | Value | Units | Code | Code | Value | Units | Code | | |
| 1 | E05013 | .56 | KW | | | | | | | | | | | |
| 2 | E05013 | .56 | KW | | | | | | | | | | | |
| 3 | E05013 | .56 | KW | | | | | | | | | | | |

----- Equipment Section Alternative #2 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | Time of Day | Time of Day | Limit | Alternative Description | Temperature |
|-------------|--------------|-------------|--------|-------------|-------------|-------|---|-------------|
| Number | Schedule | Schedule | Max KW | Schedule | Schedule | Limit | Schedule | Drift |
| 2 | | | | | | | W.C. CENTRIFUGAL CHILLER-VFD, EXIST BLR | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | Asgn | Loads To | Equipment | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------|----------|----------|-------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Ref | Cool Ref | Sizing | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End |
| 1 | 1 | BLKPLANT | 1 | 1 | | | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | COOLING | HEAT RECOVERY | Seq | Demand | | | | |
|------------|---------|---------|---------------|--------|----------|--------|-------|------|--------|
| Ref | Code | Of | Capacity | Energy | Capacity | Energy | Order | Seq | Limit |
| Num | Name | Units | Value | Units | Value | Units | Num | Type | Number |
| 1 | YCENVFD | 1 | 555 | TONS | 322 | KW | | | |

Card 63----- Cooling Pumps and References -----

| Cool | CHILLED WATER | CONDENSER | HT REC or AUX | Switch |
|------|---------------|-----------|---------------|-----------|
| Ref | Full Load | Full Load | Full Load | Full Load |
| Num | Value | Units | Value | Units |
| 1 | 74.6 | KW | 37.3 | KW |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Equip | Demand |
|---------|------------------|--------|--------|----------|----------|
| Utility | Utility | Demand | Demand | Schedule | Energy |
| Number | Descrip | Value | Units | Code | Type |
| 1 | PIPE-PUMP HT LOS | 39.1 | TONS | FYSAMCLG | CHILL-LD |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | | | | Energy | | Energy | | Number | | Percent | | Low Spd | | Low Spd | |
|---------|--------|----------|----------|---------|---------|--------|-------|--------|---------|---------|--------|---------|--|---------|--|
| Tower | Tower | Capacity | Capacity | Consump | Consump | Fluid | Tower | Of | Airflow | Energy | Energy | | | | |
| Ref | Code | Value | Units | Value | Units | Type | Type | Cells | Low Spd | Value | Units | | | | |
| 1 | EQ5100 | | | 29.84 | KW | | | 2 | | | | | | | |

----- Equipment Section Alternative #3 -----

Card 59----- Equipment Description / TOU Schedules -----

| Elec Consump | | | | Elec Demand | | Demand | | ---- Demand Limit --- | |
|--------------|-------------|-------------|--------|---------------------------------------|--|--------|--|-----------------------|-------------|
| Alternative | Time of Day | Time of Day | Limit | | | | | | Temperature |
| Number | Schedule | Schedule | Max KW | Alternative Description | | | | Schedule | Drift |
| 3 | | | | EXIST CHILLER, NATURAL DRAFT HIGH BLR | | | | | |

Card 65----- Heating Load Assignment -----

| All Coil | | | | | | | | | | | |
|------------|-------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Assignment | Loads To | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- | |
| Reference | Heating Ref | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | 1 | 1 | | | | | | | | |

Card 67----- Heating Equipment Parameters -----

| Heat | Equip | Number | HW Pmp | Energy | | | | Seq | Switch | Demand | | | | |
|--------|----------|--------|---------|--------|-------|-------|-------|-------|--------|---------|-------|-------|-------|--------|
| Ref | Code | Of | Full Ld | Cap'y | Rate | | | Order | over | Hot | Misc. | Limit | | |
| Number | Name | Units | Value | Units | Value | Units | Value | Units | Number | Control | Strg | Acc. | Cogen | Number |
| 1 | BOILHEFT | 1 | 5.6 | KW | 1830 | MBH | 2000 | MBH | 1 | | | | 1 | |
| 2 | BOILHEFT | 1 | | | 915 | MBH | 1000 | MBH | 2 | | | | | |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Equip | | Demand | |
|---------|-------------|--------|--------|----------|--------|-----------|----------|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting |
| Number | Descrip | Value | Units | Code | Type | Number | Number |
| 1 | PIPE HT LOS | 612.2 | MBH | FTSAMHTG | HOT-LD | 1 | |

Card 75----- Miscellaneous Accessory -----

| #1 | | | | | #2 | | | | | #3 | | | | |
|------|--------|--------|--------|-------|-------|--------|--------|-------|-------|--------|--------|-------|--|--|
| Misc | Equip | Energy | Energy | Sched | Equip | Energy | Energy | Sched | Equip | Energy | Energy | Sched | | |
| Ref | Code | Value | Units | Code | Code | Value | Units | Code | Code | Value | Units | Code | | |
| 1 | EQ5020 | 3.73 | KW | | | | | | | | | | | |

```
*****  
*****  
**  
**          TRACE    600  ANALYSIS          **  
**  
**          by HUITT & ZOLLARS              **  
**  
*****  
*****
```

03018504 EEAP BOILER-CHILLER STUDY
FT. SAM HOUSTON - SAN ANTONIO, TX.
CORPS OF ENGINEERS - FORT WORTH, TEXAS
HUITT - ZOLLARS INC.
AREA 2200

Weather File Code:

| | |
|----------------------|--------------------|
| Location: | SAN ANTONIO, TEXAS |
| Latitude: | 29.0 (deg) |
| Longitude: | 98.0 (deg) |
| Time Zone: | 6 |
| Elevation: | 792 (ft) |
| Barometric Pressure: | 29.0 (in. Hg) |

| | |
|---------------------------|--------|
| Summer Clearness Number: | 0.90 |
| Winter Clearness Number: | 0.90 |
| Summer Design Dry Bulb: | 97 (F) |
| Summer Design Wet Bulb: | 76 (F) |
| Winter Design Dry Bulb: | 30 (F) |
| Summer Ground Relectance: | 0.20 |
| Winter Ground Relectance: | 0.20 |

| | |
|-----------------------------|-----------------------------|
| Air Density: | 0.0738 (Lbm/cuft) |
| Air Specific Heat: | 0.2444 (Btu/lbm/F) |
| Density-Specific Heat Prod: | 1.0818 (Btu-min./hr/cuft/F) |
| Latent Heat Factor: | 4,761.9 (Btu-min./hr/cuft) |
| Enthalpy Factor: | 4.4255 (Lb-min./hr/cuft) |

Design Simulation Period: June To November
System Simulation Period: January To December
Cooling Load Methodology: TETD/Time Averaging

Time/Date Program was Run: 19: 5: 7 6/ 8/95
Dataset Name: FSH2200 .TM

EM TOTALS LOAD PROFILE - ALTERNATIVE 1

----- SYSTEM LOAD PROFILE -----

System Totals

| Percent Design Load | ---- Cooling Load ---- | | | ----- Heating Load ----- | | |
|---------------------------|------------------------|--------------|-------|--------------------------|--------------|-------|
| | Cap. (Ton) | Hours (%) | Hours | Capacity (Btuh) | Hours (%) | Hours |
| 0 - 5 | 32.2 | 7 | 279 | -213,687 | 50 | 1,134 |
| 5 - 10 | 64.4 | 5 | 211 | -427,375 | 14 | 307 |
| 10 - 15 | 96.7 | 6 | 235 | -641,062 | 4 | 82 |
| 15 - 20 | 128.9 | 9 | 367 | -854,749 | 7 | 168 |
| 20 - 25 | 161.1 | 8 | 349 | -1,068,437 | 16 | 363 |
| 25 - 30 | 193.3 | 7 | 281 | -1,282,124 | 3 | 78 |
| 30 - 35 | 225.6 | 8 | 324 | -1,495,811 | 2 | 46 |
| 35 - 40 | 257.8 | 7 | 286 | -1,709,499 | 2 | 49 |
| 40 - 45 | 290.0 | 5 | 223 | -1,923,186 | 1 | 21 |
| 45 - 50 | 322.2 | 9 | 358 | -2,136,873 | 1 | 15 |
| 50 - 55 | 354.5 | 8 | 318 | -2,350,561 | 0 | 0 |
| 55 - 60 | 386.7 | 9 | 366 | -2,564,248 | 0 | 0 |
| 60 - 65 | 418.9 | 5 | 204 | -2,777,936 | 0 | 0 |
| 65 - 70 | 451.1 | 6 | 253 | -2,991,623 | 0 | 0 |
| 70 - 75 | 483.3 | 1 | 43 | -3,205,311 | 0 | 0 |
| 75 - 80 | 515.6 | 2 | 66 | -3,418,998 | 0 | 0 |
| 80 - 85 | 547.8 | 0 | 0 | -3,632,685 | 0 | 0 |
| 85 - 90 | 580.0 | 0 | 0 | -3,846,373 | 0 | 0 |
| 90 - 95 | 612.2 | 0 | 0 | -4,060,060 | 0 | 0 |
| 95 - 100 | 644.5 | 0 | 0 | -4,273,747 | 0 | 0 |
| Hours Off | 0.0 | 0 | 4,597 | 0 | 0 | 6,497 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|----------|-------------------------------------|-------|-------|-------|--------|--------|--------|--------|--------|-------|-------|-------|-----------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 93324 | 84377 | 98571 | 89467 | 95947 | 94714 | 90700 | 98571 | 89467 | 95947 | 89467 | 90700 | 1,111,251 |
| | PK | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 29090 | 28152 | 29090 | 29090 | 28152 | 29090 | 0 | 0 | 172,666 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 39.1 | 39.1 | 39.1 | 39.1 | 39.1 | 39.1 | 0.0 | 0.0 | 39.1 |
| 2 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 4555 | 4114 | 4555 | 4408 | 0 | 0 | 0 | 0 | 0 | 0 | 4408 | 4555 | 26,594 |
| | PK | 6.1 | 6.1 | 6.1 | 6.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 6.1 | 6.1 | 6.1 |
| 1 | EQ1001L | 2-STG CENTRIFUGAL CHILLER >550 TONS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 151580 | 173401 | 204346 | 211763 | 166768 | 86289 | 0 | 0 | 994,146 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 481.0 | 522.3 | 568.8 | 596.6 | 535.0 | 368.3 | 0.0 | 0.0 | 596.6 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 22201 | 21485 | 22201 | 22201 | 21485 | 11898 | 0 | 0 | 121,471 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 29.8 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

----- EQUIPMENT ENERGY CONSUMPTION -----

| Ref Num | Equip Code | Monthly Consumption | | | | | | | | | | | | Total |
|------------|---------------|--|-------|------|------|-------|-------|-------|-------|-------|-------|------|------|---------|
| | | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 699 | 804 | 952 | 980 | 757 | 378 | 0 | 0 | 4,569 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.3 | 2.4 | 2.6 | 2.6 | 2.5 | 1.9 | 0.0 | 0.0 | 2.6 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 55502 | 53712 | 55502 | 55502 | 53712 | 55502 | 0 | 0 | 329,433 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 0.0 | 0.0 | 74.6 |
| 1 | EQ5010 | CONDENSER WATER PUMP-CV(HIGH EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 27751 | 26856 | 27751 | 27751 | 26856 | 27751 | 0 | 0 | 164,717 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 0.0 | 0.0 | 37.3 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 1 | | EXISTING NAT. DRAFT AJAX HWH BOILER | | | | | | | | | | | | |
| | GAS | 10454 | 10246 | 6486 | 5991 | 0 | 0 | 0 | 0 | 0 | 0 | 6240 | 9940 | 49,358 |
| | PK | 30.0 | 30.0 | 10.9 | 9.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 10.4 | 30.0 | 30.0 |
| 1 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 8325 | 7520 | 8325 | 8057 | 0 | 0 | 0 | 0 | 0 | 0 | 8057 | 8325 | 48,609 |
| | PK | 11.2 | 11.2 | 11.2 | 11.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 | 11.2 |
| 1 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 | 543 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 1 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 417 | 376 | 417 | 403 | 0 | 0 | 0 | 0 | 0 | 0 | 403 | 417 | 2,433 |
| | PK | 0.6 | 0.6 | 0.6 | 0.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.6 | 0.6 | 0.6 |
| 2 | | EXISTING NAT. DRAFT AJAX HWH BOILER | | | | | | | | | | | | |
| | GAS | 17 | 91 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 19 | 127 |
| | PK | 2.4 | 5.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 3.2 | 5.1 |
| 2 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 134 | 269 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 67 | 470 |
| | PK | 11.2 | 11.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 |
| 2 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 2 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 5 |
| | PK | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-----|------|------|-----|-----|-----|-----|-----|-------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 2 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 7 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 24 |
| | PK | 0.6 | 0.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.6 | 0.6 |
| 3 | | EXISTING NAT. DRAFT AJAX HWH BOILER | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | EQ5013 | WATER CIRCULATING PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
GAS ENGINE DRIVEN CHILLER, EXISTING BLR

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | | |
|--|----------------------------|---------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-----------|--|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total | |
| 0 | LIGHTS | | | | | | | | | | | | | | |
| | ELEC | 93324 | 84377 | 98571 | 89467 | 95947 | 94714 | 90700 | 98571 | 89467 | 95947 | 89467 | 90700 | 1,111,251 | |
| | PK | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | |
| 1 | MISC LD | | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 2 | MISC LD | | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 3 | MISC LD | | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 4 | MISC LD | | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 5 | MISC LD | | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 6 | MISC LD | | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 1 | BASE UTILITY | | | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 29090 | 28152 | 29090 | 29090 | 28152 | 29090 | 0 | 0 | 172,666 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 39.1 | 39.1 | 39.1 | 39.1 | 39.1 | 39.1 | 0.0 | 0.0 | 39.1 | |
| 1 | YORK ENGINE DRIVEN CHILLER | | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 9807 | 11472 | 13818 | 14498 | 11113 | 5068 | 0 | 0 | 65,775 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 33.9 | 34.6 | 36.2 | 36.6 | 35.3 | 24.9 | 0.0 | 0.0 | 36.6 | |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 22201 | 21485 | 22201 | 22201 | 21485 | 11600 | 0 | 0 | 121,172 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 29.8 | |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 736 | 851 | 1013 | 1046 | 803 | 390 | 0 | 0 | 4,840 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.4 | 2.4 | 2.4 | 2.4 | 2.4 | 2.0 | 0.0 | 0.0 | 2.4 | |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
GAS ENGINE DRIVEN CHILLER, EXISTING BLR

| ----- E Q U I P M E N T E N E R G Y C O N S U M P T I O N ----- | | | | | | | | | | | | | | |
|---|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|---------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 55502 | 53712 | 55502 | 55502 | 53712 | 55502 | 0 | 0 | 329,433 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 0.0 | 0.0 | 74.6 |
| 1 | EQ5011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 27751 | 26856 | 27751 | 27751 | 26856 | 27751 | 0 | 0 | 164,717 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 0.0 | 0.0 | 37.3 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
W. C. DUAL SCREW CHILLER, EXIST BOILER

| ----- E Q U I P M E N T E N E R G Y C O N S U M P T I O N ----- | | | | | | | | | | | | | | |
|---|----------|------------------------|-------|-------|-------|-------|--------|--------|--------|--------|-------|-------|-------|-----------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 93324 | 84377 | 98571 | 89467 | 95947 | 94714 | 90700 | 98571 | 89467 | 95947 | 89467 | 90700 | 1,111,251 |
| | PK | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 29090 | 28152 | 29090 | 29090 | 28152 | 29090 | 0 | 0 | 172,666 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 39.1 | 39.1 | 39.1 | 39.1 | 39.1 | 39.1 | 0.0 | 0.0 | 39.1 |
| 1 | YSCRW22 | YORK W.C. SCREW CHILL. | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 94351 | 109968 | 131558 | 137516 | 106569 | 51609 | 0 | 0 | 631,571 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 338.4 | 343.0 | 352.2 | 355.0 | 347.1 | 264.5 | 0.0 | 0.0 | 355.0 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 22201 | 21485 | 22201 | 22201 | 21485 | 12459 | 0 | 0 | 122,031 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 29.8 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 647 | 746 | 886 | 912 | 702 | 346 | 0 | 0 | 4,239 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.1 | 2.1 | 2.1 | 2.1 | 2.1 | 1.8 | 0.0 | 0.0 | 2.1 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
W. C. DUAL SCREW CHILLER, EXIST BOILER

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|---------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 55502 | 53712 | 55502 | 55502 | 53712 | 55502 | 0 | 0 | 329,433 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 0.0 | 0.0 | 74.6 |
| 1 | EQ5011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 27751 | 26856 | 27751 | 27751 | 26856 | 27751 | 0 | 0 | 164,717 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 0.0 | 0.0 | 37.3 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 4
W.C. CENTRIFUGAL CHILLER, EXISTING BOILER

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|----------|---------------------------------|-------|-------|-------|-------|--------|--------|--------|--------|-------|-------|-------|-----------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 93324 | 84377 | 98571 | 89467 | 95947 | 94714 | 90700 | 98571 | 89467 | 95947 | 89467 | 90700 | 1,111,251 |
| | PK | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 29090 | 28152 | 29090 | 29090 | 28152 | 29090 | 0 | 0 | 172,666 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 39.1 | 39.1 | 39.1 | 39.1 | 39.1 | 39.1 | 0.0 | 0.0 | 39.1 |
| 1 | | YORK CENT. R-134A CHILL | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 92599 | 106789 | 126901 | 132023 | 103005 | 50227 | 0 | 0 | 611,543 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 306.9 | 311.1 | 319.4 | 322.0 | 314.8 | 240.0 | 0.0 | 0.0 | 322.0 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 22201 | 21485 | 22201 | 22201 | 21485 | 12467 | 0 | 0 | 122,039 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 29.8 |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 645 | 743 | 882 | 907 | 699 | 345 | 0 | 0 | 4,221 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.1 | 2.1 | 2.1 | 2.1 | 2.1 | 1.8 | 0.0 | 0.0 | 2.1 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 4
W.C. CENTRIFUGAL CHILLER, EXISTING BOILER

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|---------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 1 | E05001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 55502 | 53712 | 55502 | 55502 | 53712 | 55502 | 0 | 0 | 329,433 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 0.0 | 0.0 | 74.6 |
| 1 | E05011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 27751 | 26856 | 27751 | 27751 | 26856 | 27751 | 0 | 0 | 164,717 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 0.0 | 0.0 | 37.3 |
| 1 | E05300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
W.C. CENTRIFUGAL CHILLER-VFD, EXIST BLR

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | | |
|--|--------------|---------------------------------------|-------|-------|-------|-------|-------|--------|--------|-------|-------|-------|-------|-----------|--|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total | |
| 0 | LIGHTS | | | | | | | | | | | | | | |
| | ELEC | 93324 | 84377 | 98571 | 89467 | 95947 | 94714 | 90700 | 98571 | 89467 | 95947 | 89467 | 90700 | 1,111,251 | |
| | PK | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | |
| 1 | MISC LD | | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 2 | MISC LD | | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 3 | MISC LD | | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 4 | MISC LD | | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 5 | MISC LD | | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 6 | MISC LD | | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 1 | BASE UTILITY | | | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 29090 | 28152 | 29090 | 29090 | 28152 | 29090 | 0 | 0 | 172,666 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 39.1 | 39.1 | 39.1 | 39.1 | 39.1 | 39.1 | 0.0 | 0.0 | 39.1 | |
| 1 | YCENVFD | YORK TURBO MODULATOR VAR. FREQ. DRIVE | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 82189 | 96782 | 117375 | 123391 | 93614 | 41497 | 0 | 0 | 554,847 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 297.8 | 304.5 | 317.9 | 322.0 | 310.5 | 216.8 | 0.0 | 0.0 | 322.0 | |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 22201 | 21485 | 22201 | 22201 | 21485 | 12289 | 0 | 0 | 121,861 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 0.0 | 0.0 | 29.8 | |
| 1 | EQ5100 | COOLING TOWER FANS | | | | | | | | | | | | | |
| | WATER | 0 | 0 | 0 | 0 | 636 | 734 | 873 | 899 | 690 | 337 | 0 | 0 | 4,169 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.0 | 2.1 | 2.1 | 2.1 | 2.1 | 1.8 | 0.0 | 0.0 | 2.1 | |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
W.C. CENTRIFUGAL CHILLER-VFD, EXIST BLR

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|---------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 55502 | 53712 | 55502 | 55502 | 53712 | 55502 | 0 | 0 | 329,433 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 0.0 | 0.0 | 74.6 |
| 1 | EQ5011 | CONDENSER WATER PUMP-CV(MEDIUM EFFIC.) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 27751 | 26856 | 27751 | 27751 | 26856 | 27751 | 0 | 0 | 164,717 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 0.0 | 0.0 | 37.3 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
EXIST CHILLER, NATURAL DRAFT HIGH % BLR

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | | | |
|------------------------------|--|--------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-----------|--|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total | |
| 0 | LIGHTS | | | | | | | | | | | | | | |
| | ELEC | 93324 | 84377 | 98571 | 89467 | 95947 | 94714 | 90700 | 98571 | 89467 | 95947 | 89467 | 90700 | 1,111,251 | |
| | PK | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | 452.3 | |
| 1 | MISC LD | | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 2 | MISC LD | | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 3 | MISC LD | | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 4 | MISC LD | | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 5 | MISC LD | | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 6 | MISC LD | | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | |
| 1 | BASE UTILITY | | | | | | | | | | | | | | |
| | HOTLD | 4555 | 4114 | 4555 | 4408 | 0 | 0 | 0 | 0 | 0 | 0 | 4408 | 4555 | 26,594 | |
| | PK | 6.1 | 6.1 | 6.1 | 6.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 6.1 | 6.1 | 6.1 | |
| 1 | HIGH EFFICIENCY MODULAR FIRETUBE BOIL. | | | | | | | | | | | | | | |
| | GAS | 8361 | 8169 | 5293 | 4889 | 0 | 0 | 0 | 0 | 0 | 0 | 5092 | 8030 | 39,833 | |
| | PK | 20.0 | 20.0 | 8.9 | 7.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 8.5 | 20.0 | 20.0 | |
| 1 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | | |
| | ELEC | 4166 | 3763 | 4166 | 4032 | 0 | 0 | 0 | 0 | 0 | 0 | 4032 | 4166 | 24,326 | |
| | PK | 5.6 | 5.6 | 5.6 | 5.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 5.6 | 5.6 | 5.6 | |
| 1 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 | 543 | |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 | |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
EXIST CHILLER, NATURAL DRAFT HIGH % BLR

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|------|------|------|-----|------|------|-----|-----|-----|------|------|--------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 1 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 2775 | 2507 | 2775 | 2686 | 0 | 0 | 0 | 0 | 0 | 0 | 2686 | 2775 | 16,203 |
| | PK | 3.7 | 3.7 | 3.7 | 3.7 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 3.7 | 3.7 | 3.7 |
| 2 | | HIGH EFFICIENCY MODULAR FIRETUBE BOIL. | | | | | | | | | | | | |
| | GAS | 189 | 269 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 97 | 555 |
| | PK | 6.7 | 8.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 7.1 | 8.6 |
| 2 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 3 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 7 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 19 |
| | PK | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |

01 Card - Job Information

Project: 030185.04 EEAP BOILER-CHILLER STUDY
 Location: FT. SAM HOUSTON - SAN ANTONIO, TX.
 Client: CORPS OF ENGINEERS - FORT WORTH, TEXAS
 Program User: HUITT - ZOLLARS INC.
 Comments: QUADRANGLE AREA

Card 08----- Climatic Information -----

| | Summer | Winter | Summer | Summer | Winter | | Summer | Winter |
|----------|-----------|-----------|----------|----------|----------|-------------|---------|---------|
| Weather | Clearness | Clearness | Design | Design | Design | Building | Ground | Ground |
| Code | Number | Number | Dry Bulb | Wet Bulb | Dry Bulb | Orientation | Reflect | Reflect |
| SANANTON | | | | | | | | |

----- Load Section Alternative #1 -----

Card 19- Load Alternative -

| Number | Description |
|--------|-----------------------------|
| 1 | QUADRANGLE LOAD DESCRIPTION |

Card 20----- General Room Parameters -----

| Room | Zone | Room | Floor | Floor | Const | Plenum | Acoustic | Floor to | Duplicate | Duplicate | Perimeter |
|--------|-----------|-----------|--------|-------|-------|--------|------------|----------|------------|-----------|-----------|
| Number | Reference | Descrip | Length | Width | Type | Height | Ceiling | Floor | Floors | Rooms per | Depth |
| | Number | | | | | | Resistance | Height | Multiplier | Zone | |
| 5 | 5 | BLDG T56 | 181 | 45 | 3 | 3 | 2.54 | 15 | | | |
| 10 | 10 | BLDG 44 | 309 | 309 | 3 | 4.5 | 2.54 | 16 | | | |
| 15 | 15 | BLDG 4015 | 121 | 121 | 3 | 3 | 1.2 | 12 | | | |
| 20 | 20 | BLDG 16 | 276 | 276 | 3 | 6 | 2.54 | 17 | | | |

Card 21----- Thermostat Parameters -----

| Room | Cooling | Room | Cooling | Cooling | Heating | Heating | Heating | T'stat | Mass / | Carpet |
|--------|-----------|--------|------------|----------|-----------|------------|----------|----------|---------|--------|
| Number | Room | Design | T'stat | T'stat | Room | T'stat | T'stat | Location | No. Hrs | On |
| | Design DB | RH | Driftpoint | Schedule | Design DB | Driftpoint | Schedule | Flag | Average | Floor |
| 5 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 10 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 15 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |
| 20 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO |

Card 22----- Roof Parameters -----

| Room Number | Roof Number | Roof Equal to Floor? | Roof Length | Roof Width | Roof U-Value | Const Type | Roof Direction | Roof Tilt | Roof Alpha |
|-------------|-------------|----------------------|-------------|------------|--------------|------------|----------------|-----------|------------|
| 5 | 1 | YES | | | .10 | 47 | | 67 | .9 |
| 10 | 1 | NO | 221 | 221 | .09 | 23 | | 90 | .9 |
| 15 | 1 | NO | 245 | 39 | .22 | 47 | | 90 | .74 |
| 20 | 1 | NO | 1582 | 34 | .10 | 47 | | 60 | .74 |

Card 24----- Wall Parameters -----

| Room Number | Wall Number | Wall Length | Wall Height | Wall U-Value | Wall Constuc Type | Wall Direction | Wall Tilt | Wall Alpha | Ground Reflectance Multiplier |
|-------------|-------------|-------------|-------------|--------------|-------------------|----------------|-----------|------------|-------------------------------|
| 5 | 1 | 153 | 14 | .26 | 58 | 90 | | .74 | |
| 5 | 2 | 30 | 14 | .26 | 58 | 0 | | .74 | |
| 5 | 3 | 17 | 14 | .13 | 88 | 0 | | .74 | |
| 5 | 4 | 181 | 14 | .13 | 88 | 270 | | .74 | |
| 5 | 5 | 45 | 14 | .13 | 88 | 180 | | .74 | |
| 5 | 6 | 28 | 14 | .13 | 88 | 90 | | .74 | |
| 10 | 1 | 200 | 16 | .19 | 58 | 0 | | .9 | |
| 10 | 2 | 232 | 16 | .19 | 58 | 180 | | .9 | |
| 10 | 3 | 230 | 16 | .19 | 58 | 270 | | .9 | |
| 10 | 4 | 364 | 16 | .18 | 88 | 0 | | .74 | |
| 10 | 5 | 482 | 16 | .18 | 88 | 90 | | .74 | |
| 10 | 6 | 342 | 16 | .18 | 88 | 180 | | .74 | |
| 10 | 7 | 260 | 16 | .18 | 88 | 270 | | .74 | |
| 15 | 1 | 39 | 12 | .22 | 52 | 0 | | .74 | |
| 15 | 2 | 245 | 12 | .22 | 52 | 90 | | .74 | |
| 15 | 3 | 39 | 12 | .22 | 52 | 180 | | .74 | |
| 15 | 4 | 245 | 12 | .22 | 52 | 270 | | .74 | |
| 20 | 1 | 600 | 15.5 | .2 | 64 | 0 | | .74 | |
| 20 | 2 | 1016 | 15.5 | .2 | 64 | 90 | | .74 | |
| 20 | 3 | 600 | 15.5 | .2 | 64 | 180 | | .74 | |
| 20 | 4 | 1016 | 15.5 | .2 | 64 | 270 | | .74 | |

Card 25----- Wall/Glass Parameters -----

| Room Number | Wall Number | Glass Length | Glass Width | Pct Glass or No. of Windows | Glass U-Value | Shading Coefficient | External Shading Type | Internal Shading Type | Percent Solar Ret. | Visible Air Transmittance | Inside Visible Reflectance |
|-------------|-------------|--------------|-------------|-----------------------------|---------------|---------------------|-----------------------|-----------------------|--------------------|---------------------------|----------------------------|
| 5 | 1 | 3.5 | 6.5 | 16 | 1.1 | .67 | | | | | |
| 5 | 2 | 3.5 | 6.5 | 1 | 1.1 | .67 | | | | | |
| 5 | 4 | 2.5 | 3 | 12 | 1.1 | 1 | | | | | |
| 5 | 5 | 3.5 | 6.5 | 4 | 1.1 | .67 | | | | | |
| 10 | 1 | 5 | 8 | 17 | 1.1 | .67 | | | | | |
| 10 | 2 | 5 | 8 | 13 | 1.1 | .67 | | | | | |
| 10 | 3 | 5 | 8 | 17 | 1.1 | .67 | | | | | |
| 10 | 4 | 3.5 | 8 | 29 | 1.1 | .67 | | | | | |
| 10 | 5 | 3.5 | 8 | 51 | 1.1 | .67 | | | | | |
| 10 | 6 | 3.5 | 8 | 57 | 1.1 | .67 | | | | | |

Card 25----- Wall/Glass Parameters -----

| Room Number | Wall Number | Glass Length | Glass Width | Pct Glass or No. of Windows | Glass U-Value | Shading Coefficient | External Shading Type | Internal Shading Type | Percent Solar Ret. Air | Visible Transmittance | Inside Visible Reflectance |
|-------------|-------------|--------------|-------------|-----------------------------|---------------|---------------------|-----------------------|-----------------------|------------------------|-----------------------|----------------------------|
| 10 | 7 | 3.5 | 8 | 21 | 1.1 | .67 | | | | | |
| 15 | 1 | 3 | 6 | 11 | 1.1 | .67 | | | | | |
| 15 | 2 | 3 | 6 | 89 | 1.1 | .67 | | | | | |
| 15 | 3 | 3 | 6 | 10 | 1.1 | .67 | | | | | |
| 15 | 4 | 3 | 6 | 96 | 1.1 | .67 | | | | | |
| 20 | 1 | | | 48 | .56 | 1 | | | | | |
| 20 | 2 | 3 | 6 | 56 | 1.1 | .67 | | | | | |
| 20 | 3 | 3 | 6 | 84 | 1.1 | .67 | | | | | |
| 20 | 4 | 3 | 6 | 56 | 1.1 | .67 | | | | | |

Card 26----- Schedules -----

| Room Number | People | Lights | Ventilation | Infiltration | Reheat Minimum | Cooling Fans | Heating Fan | Auxiliary Fan | Room Exhaust | Daylighting Controls |
|-------------|----------|----------|-------------|--------------|----------------|--------------|-------------|---------------|--------------|----------------------|
| 5 | FSHOFFIC | FSHOFFIC | | | | | | | | |
| 10 | FSHOFFIC | FSHOFFIC | | | | | | | | |
| 15 | FSHOFFIC | FSHOFFIC | | | | | | | | |
| 20 | FSHOFFIC | FSHOFFIC | | | | | | | | |

Card 27----- People and Lights -----

| Room Number | People Value | People Units | People Sensible | People Latent | Lighting Value | Lighting Units | Lighting Fixture Type | Ballast Factor | Percent Lights to Ret. Air | --- Daylighting --- Reference Point 1 | Reference Point 2 |
|-------------|--------------|--------------|-----------------|---------------|----------------|----------------|-----------------------|----------------|----------------------------|--|-------------------|
| 5 | 64 | PEOPLE | 250 | 200 | 2 | WATT-SF | ASHRAE2 | | | | |
| 10 | 500 | PEOPLE | 250 | 200 | 2.5 | WATT-SF | SUSFLUOR | | | | |
| 15 | 110 | PEOPLE | 250 | 200 | 2 | WATT-SF | SUSFLUOR | | | | |
| 20 | 150 | SF-PERS | 250 | 200 | 2.25 | WATT-SF | ASHRAE2 | | | | |

Card 28----- Miscellaneous Equipment -----

| Room Number | Misc Equipment Number | Equipment Descrip | Energy Consump Value | Energy Consump Units | Schedule Code | Energy Meter Code | Percent of Load Sensible | Percent Misc. Load to Room | Percent Misc. Sens to Ret. Air | Radiant Fraction | Optional Air Path |
|-------------|-----------------------|-------------------|----------------------|----------------------|---------------|-------------------|--------------------------|----------------------------|--------------------------------|------------------|-------------------|
| 5 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | | | | | | |
| 10 | 1 | COMPUTER | 2 | WATT-SF | FSHOFFIC | | | | | | |
| 15 | 1 | COMPUTER | 2.5 | WATT-SF | FSHOFFIC | | | | | | |
| 20 | 1 | COMPUTER | 1.25 | WATT-SF | FSHOFFIC | | | | | | |

Card 29----- Room Airflows -----

| Room Number | -----Cooling----- Value | Units | -----Heating----- Value | Units | -----Cooling----- Value | Units | -----Heating----- Value | Units | ---Reheat Minimum--- Value | Units |
|-------------|----------------------------|-------|----------------------------|-------|----------------------------|-------|----------------------------|-------|-------------------------------|-------|
| 5 | 20 | CFM-P | 20 | CFM-P | | | | | | |

Card 29----- Room Airflows -----

| Room Number | -----Ventilation----- | | -----Heating----- | | -----Cooling----- | | -----Heating----- | | --Reheat Minimum-- | |
|-------------|-----------------------|-------|-------------------|-------|-------------------|-------|-------------------|-------|--------------------|-------|
| | Value | Units | Value | Units | Value | Units | Value | Units | Value | Units |
| 10 | 20 | CFM-P | 20 | CFM-P | | | | | | |
| 15 | 15 | CFM-P | 15 | CFM-P | | | | | | |
| 20 | 20 | CFM-P | 20 | CFM-P | | | | | | |

----- System Section Alternative #1 -----

Card 39- System Alternative

| Number | Description |
|--------|-----------------|
| 1 | EXISTING SYSTEM |

Card 40----- System Type -----

-----OPTIONAL VENTILATION SYSTEM-----

| System Set | System | Ventil Deck | Cooling SADBvh | Heating SADBvh | Cooling Schedule | Heating Schedule | Fan Static Pressure |
|------------|--------|-------------|----------------|----------------|------------------|------------------|---------------------|
| 1 | MZ | | | | | | |
| 2 | SZ | | | | | | |
| 3 | MZ | | | | | | |
| 4 | SZ | | | | | | |

Card 41----- Zone Assignment -----

| System Set | Ref #1 | | Ref #2 | | Ref #3 | | Ref #4 | | Ref #5 | | Ref #6 | |
|------------|--------|-----|--------|-----|--------|-----|--------|-----|--------|-----|--------|-----|
| | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End | Begin | End |
| 1 | 5 | 5 | | | | | | | | | | |
| 2 | 10 | 10 | | | | | | | | | | |
| 3 | 15 | 15 | | | | | | | | | | |
| 4 | 20 | 20 | | | | | | | | | | |

Card 42----- Fan SP and Duct Parameters-----

| System Set | Cool Fan | Heat Fan | Return Fan | Mn Exh Fan | Aux Fan | Rm Exh Fan | Cool Fan Mtr | Return Fan Mtr | Supply Duct | Supply Duct | Return Air Path |
|------------|----------|----------|------------|------------|---------|------------|--------------|----------------|-------------|-------------|-----------------|
| Number | SP | SP | SP | SP | SP | SP | Loc | Loc | Ht Gn | Loc | Path |
| 1 | 2.0 | | | | | | | | | | |
| 2 | 1.5 | | | | | | | | | | |
| 3 | 1.5 | | | | | | | | | | |

Card 42----- Fan SP and Duct Parameters-----

| System | Cool | Heat | Return | Mn Exh | Aux | Rm Exh | Cool | Return | Supply | Supply | Return |
|--------|------|------|--------|--------|-----|--------|---------|---------|--------|--------|--------|
| Set | Fan | Fan | Fan | Fan | Fan | Fan | Fan Mtr | Fan Mtr | Duct | Duct | Air |
| Number | SP | SP | SP | SP | SP | SP | Loc | Loc | Ht Gn | Loc | Path |
| 4 | 1.5 | | | | | | | | | | |

Card 45----- Equipment Schedules -----

| System | Main | Direct | Indirect | Auxiliary | Main | Main | | | Auxiliary |
|--------|----------|------------|----------|-----------|----------|---------|--------|----------|-----------|
| Set | Cooling | Evap | Evap | Cooling | Heating | Preheat | Reheat | Mech. | Heating |
| Number | Coil | Economizer | Coil | Coil | Coil | Coil | Coil | Humidity | Coil |
| 1 | FTSAMCLG | | | | FTSAMHTG | | | | |
| 2 | FTSAMCLG | | | | FTSAMHTG | | | | |
| 3 | FTSAMCLG | | | | FTSAMHTG | | | | |
| 4 | FTSAMCLG | | | | FTSAMHTG | | | | |

----- Equipment Section Alternative #1 -----

Card 59----- Equipment Description / T00 Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | | Demand Limit |
|-------------|--------------|-------------|--------|-------------------------|----------------|
| Number | Time of Day | Time of Day | Limit | Alternative Description | Temperature |
| Number | Schedule | Schedule | Max KW | Alternative Description | Schedule Drift |
| 1 | | | | BASE CASE | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | | | | | | | | | |
|------|----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Asgn | Loads To | Equipment | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
| Ref | Cool Ref | Sizing | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | BLKPLANT | 1 1 | | | | | | | | |
| 2 | 2 | BLKPLANT | 2 2 | | | | | | | | |
| 3 | 5 | BLKPLANT | 3 3 | | | | | | | | |
| 4 | 6 | BLKPLANT | 4 4 | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | COOLING----- | | | | HEAT RECOVERY----- | | | | Seq | Demand |
|------------|----------|--------------|------------|-------|--------------|--------------------|-------|-------|-----|-------|--------|
| Ref Code | Of | --Capacity-- | --Energy-- | | --Capacity-- | --Energy-- | | Order | Seq | Limit | |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Num | Type | Number |
| 1 | QUADACRE | 1 | 30 | TONS | 49 | KW | | | | | |
| 2 | QUADACRE | 1 | 65 | TONS | 114 | KW | | | 1 | PAR | |
| 3 | QUADACRE | 1 | 95 | TONS | 167 | KW | | | 2 | PAR | |
| 4 | QUADACRE | 1 | 95 | TONS | 167 | KW | | | 3 | PAR | |
| 5 | QUADACRE | 1 | 50 | TONS | 88.4 | KW | | | | | |
| 6 | QUADACRE | 1 | 120 | TONS | 194 | KW | | | 1 | PAR | |

Card 62----- Cooling Equipment Parameters -----

| Cool Equip | Num | -----COOLING----- | | | | -----HEAT RECOVERY----- | | | | Seq | Demand |
|------------|----------|-------------------|----------------|-------|--------------|-------------------------|-------|-------|-----|-------|--------|
| Ref Code | Of | --Capacity-- | ----Energy---- | | --Capacity-- | ----Energy---- | | Order | Seq | Limit | |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Num | Type | Number |
| 7 | QUADACRE | 1 | 110 | TONS | 190 | KW | | | 2 | PAR | |

Card 63----- Cooling Pumps and References -----

| Cool | ---CHILLED WATER--- | -----CONDENSER----- | ---HT REC or AUX--- | Switch- |
|------|---------------------|---------------------|---------------------|-----------|
| Ref | Full Load | Full Load | Full Load | Full Load |
| Num | Value | Units | Value | Units |
| 1 | 3.73 | KW | | |
| 2 | 14.92 | KW | | |
| 3 | 3.73 | KW | | |
| 4 | 3.73 | KW | | |
| 5 | 3.73 | KW | | |
| 6 | 5.6 | KW | | |

Card 65----- Heating Load Assignment -----

| Load | All Coil |
|------------|-------------|
| Assignment | Loads To |
| Reference | Heating Ref |
| 1 | 1 |
| 2 | 3 |
| 3 | 15 |

Card 67----- Heating Equipment Parameters -----

| Heat | Equip | Number | HW Pmp | Energy | Seq | Switch | Demand |
|--------|----------|--------|---------|--------|-------|--------|--------|
| Ref | Code | Of | Full Ld | Rate | Order | over | Limit |
| Number | Name | Units | Value | Units | Value | Units | Number |
| 1 | QUAEXIST | 1 | | | 3587 | MBH | 5000 |
| 2 | QUAEXIST | 1 | | | 1614 | MBH | 2250 |
| 3 | QUAEXIST | 1 | | | 264 | MBH | 385 |
| 4 | QUAEXIST | 1 | | | 264 | MBH | 385 |
| 5 | QUAEXIST | 1 | | | 264 | MBH | 385 |
| 6 | QUAEXIST | 1 | | | 264 | MBH | 385 |
| 7 | QUAEXIST | 1 | | | 264 | MBH | 385 |
| 8 | QUAEXIST | 1 | | | 264 | MBH | 385 |
| 9 | QUAEXIST | 1 | | | 264 | MBH | 385 |
| 10 | QUAEXIST | 1 | | | 236 | MBH | 335 |
| 11 | QUAEXIST | 1 | | | 236 | MBH | 335 |
| 12 | QUAEXIST | 1 | | | 236 | MBH | 335 |
| 13 | QUAEXIST | 1 | | | 236 | MBH | 335 |
| 14 | QUAEXIST | 1 | | | 236 | MBH | 335 |
| 15 | EQ2001 | 1 | 2.24 | KW | 741 | MBH | 1000 |

Card 71----- Base Utility Parameters -----

| Base Utility Number | Base Utility Descrip | Hourly Demand Value | Hourly Demand Units | Schedule Code | Energy Type | Equip Reference Number | Demand Limiting Number | Entering Temp | Leaving Temp |
|---------------------------|----------------------------|---------------------------|---------------------------|------------------|----------------|------------------------------|------------------------------|------------------|-----------------|
| 1 | PIPE PUMP HT LOS | 1.6 | TONS | FTSAMCLG | CHILL-LD | 1 | | | |
| 2 | PIPE HT LOSS | 68.1 | MBH | FTSAMHTG | HOT-LD | 1 | | | |
| 3 | PIPE PUMP HT LOS | 10.2 | TONS | FTSAMCLG | CHILL-LD | 2 | | | |
| 4 | PIPE HT LOSS | 54.5 | MBH | FTSAMHTG | HOT-LD | 2 | | | |
| 5 | PIPE PUMP HT LOS | 2.5 | TONS | FTSAMCLG | CHILL-LD | 5 | | | |
| 6 | PIPE HT LOSS | 17.71 | MBH | FTSAMHTG | HOT-LD | 14 | | | |
| 7 | PIPE PUMP HT LOS | 5.9 | TONS | FTSAMCLG | CHILL-LD | 6 | | | |

Card 75----- Miscellaneous Accessory -----

| #1 | | | | | #2 | | | | | #3 | | | | |
|-------------|---------------|-----------------|-----------------|---------------|---------------|-----------------|-----------------|---------------|---------------|-----------------|-----------------|---------------|--|--|
| Misc Ref | Equip Code | Energy Value | Energy Units | Sched Code | Equip Code | Energy Value | Energy Units | Sched Code | Equip Code | Energy Value | Energy Units | Sched Code | | |
| 1 | EQ5240 | 3.73 | KW | | | | | | | | | | | |
| 2 | EQ5001 | 5.6 | KW | | EQ5105 | 9.33 | KW | | | | | | | |
| 3 | EQ5001 | 3.73 | KW | | | | | | | | | | | |

----- Equipment Section Alternative #2 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative Number | Elec Consump Time of Day Schedule | Elec Demand Time of Day Schedule | Demand Limit Max KW | Alternative Description | Demand Limit | |
|-----------------------|---|--|---------------------------|-------------------------|--------------|----------------------|
| | | | | | Schedule | Temperature Drift |
| 2 | | | | A.C. SCREW CHILLERS | | |

Card 60----- Cooling Load Assignment -----

| Load | All Coil | Cooling | | | | | | | | | | |
|-------------|----------------------|---------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|--|
| Asgn Ref | Loads To Cool Ref | Equipment Sizing | -Group 1- Begin End | -Group 2- Begin End | -Group 3- Begin End | -Group 4- Begin End | -Group 5- Begin End | -Group 6- Begin End | -Group 7- Begin End | -Group 8- Begin End | -Group 9- Begin End | |
| 1 | 1 | BLKPLANT | 1 | 4 | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Ref | Equip Code | Num Of | COOLING | | | | HEAT RECOVERY | | | | Seq Order | Demand Seq Limit |
|-------------|---------------|-----------|-----------------------|-------|-------|-------|-----------------------|-------|-------|-------|--------------|---------------------|
| | | | --Capacity-- Value | Units | Value | Units | --Capacity-- Value | Units | Value | Units | | |
| 1 | EQ1510 | 1 | 275 | TONS | 351 | KW | | | | | 1 | PAR |
| 2 | EQ1510 | 1 | 275 | TONS | 351 | KW | | | | | 2 | PAR |

Card 63----- Cooling Pumps and References -----

| Cool | ---CHILLED WATER--- | -----CONDENSER----- | ---HT REC or AUX--- | Switch- |
|-------|---------------------|---------------------|---------------------|-----------|
| Ref | Full Load | Full Load | Full Load | Full Load |
| Value | Units | Value | Units | Value |
| 1 | 22.38 | KW | | |
| 2 | 22.38 | KW | | |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | Equip | Demand |
|---------|------------------|--------|--------|-----------|----------|
| Utility | Utility | Demand | Demand | Reference | Limiting |
| Number | Descrip | Value | Units | Code | Type |
| 1 | PIPE-PUMP HT LOS | 20.2 | TONS | FTSAMCLG | CHILL-LD |

Card 74----- Condenser / Cooling Tower Parameters -----

| Cooling | Capacity | Capacity | Consump | Consump | Fluid | Tower | Of | Percent | Low Spd | Low Spd |
|---------|----------|----------|---------|---------|-------|-------|------|---------|---------|---------|
| Tower | Tower | Value | Units | Value | Units | Type | Type | Cells | Low Spd | Value |
| Ref | Code | Value | Units | Value | Units | Type | Type | Cells | Low Spd | Units |
| 1 | EQ5200 | | | 0 | KW | | | | | |

----- Equipment Section Alternative #3 -----

Card 59----- Equipment Description / TDD Schedules -----

| Alternative | Elec Consump | Elec Demand | Demand | --- Demand Limit --- |
|-------------|--------------|-------------|--------|--|
| Number | Time of Day | Time of Day | Limit | Temperature |
| Number | Schedule | Schedule | Max KW | Schedule |
| 3 | | | | EXIST STEAM BLR WITH NEW HWH GENERATOR |

Card 65----- Heating Load Assignment -----

| Load | All Coil | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------------|-------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Assignment | Loads To | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| Reference | Heating Ref | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End | Begin End |
| 1 | 1 | 1 | 4 | | | | | | | |

Card 67----- Heating Equipment Parameters -----

| Heat | Equip | Number | HW Pmp | Energy | Seq | Switch | Demand |
|--------|----------|--------|---------|--------|-------|--------|--------|
| Ref | Code | Of | Full Ld | Cap'y | Order | over | Hot |
| Number | Name | Units | Value | Units | Value | Units | Value |
| 1 | QUAEXIST | 1 | | 3587 | MBH | 5000 | MBH |

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | | | Equip | Demand | | |
|---------|--------------|--------|--------|----------|--------|-----------|----------|----------|---------|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting | Entering | Leaving |
| Number | Descrip | Value | Units | Code | Type | Number | Number | Temp | Temp |
| 1 | PIPE HT LOSS | 140.3 | MBH | FTSAMHTG | HOT-LD | 1 | | | |

Card 75----- Miscellaneous Accessory -----

| #1 | | | | | #2 | | | | #3 | | | |
|------|--------|--------|--------|-------|-------|--------|--------|-------|-------|--------|--------|-------|
| Misc | Equip | Energy | Energy | Sched | Equip | Energy | Energy | Sched | Equip | Energy | Energy | Sched |
| Ref | Code | Value | Units | Code | Code | Value | Units | Code | Code | Value | Units | Code |
| 1 | EQ5020 | 2.24 | KW | | | | | | | | | |

Utility Description Reference Table

Schedules:

FSHOFFIC F.S.N. OFFICE INTERNAL LOAD SCHEDULE
FTSAMCLG EEAP BOILER/CHILLER STUDY
FTSAMHTG EEAP BOILER/CHILLER STUDY

System:

MZ MULTIZONE
SZ SINGLE ZONE

Equipment:

Cooling:

EQ1510 AIR COOLED SERIES R (RTAA)
QUADACRE QUAD AIR COOLED RECIP CHILLER(S)

Heating:

EQ2001 GAS FIRED HOT WATER BOILER
QUAEXIST QUAD AREA EXIST STEAM BOILER

Tower:

EQ5200 CONDENSER FANS

Misc:

EQ5001 CHILLED WATER PUMP - CONSTANT VOLUME
EQ5020 HEATING WATER CIRCULATION PUMP
EQ5105 EVAPORATIVE CONDENSER FANS
EQ5240 BOILER FORCED DRAFT FAN

**
** TRACE 600 ANALYSIS **
**
** by HUITT & ZOLLARS **
**

030185.04 EEAP BOILER-CHILLER STUDY
FT. SAM HOUSTON - SAN ANTONIO, TX.
CORPS OF ENGINEERS - FORT WORTH, TEXAS
HUITT - ZOLLARS INC.

QUADANGLE AREA

Weather File Code:

Location: SAN ANTONIO, TEXAS
Latitude: 29.0 (deg)
Longitude: 98.0 (deg)
Time Zone: 6
Elevation: 792 (ft)
Barometric Pressure: 29.0 (in. Hg)

Summer Clearness Number: 0.90
Winter Clearness Number: 0.90
Summer Design Dry Bulb: 97 (F)
Summer Design Wet Bulb: 76 (F)
Winter Design Dry Bulb: 30 (F)
Summer Ground Relectance: 0.20
Winter Ground Relectance: 0.20

Air Density: 0.0738 (Lbm/cuft)
Air Specific Heat: 0.2444 (Btu/lbm/F)
Density-Specific Heat Prod: 1.0818 (Btu-min./hr/cuft/F)
Latent Heat Factor: 4,761.9 (Btu-min./hr/cuft)
Enthalpy Factor: 4.4255 (Lb-min./hr/cuft)

Design Simulation Period: June To November
System Simulation Period: January To December
Cooling Load Methodology: TETD/Time Averaging

Time/Date Program was Run: 8:28:39 6/12/95
Dataset Name: FSH4ANGL .TM

SYSTEM TOTALS LOAD PROFILE - ALTERNATIVE 1

----- SYSTEM LOAD PROFILE -----

System Totals

| Percent Design Load | ---- Cooling Load ---- | | | ----- Heating Load ----- | | |
|---------------------------|------------------------|--------------|-------|--------------------------|--------------|-------|
| | Cap. (Ton) | Hours (%) | Hours | Capacity (Btuh) | Hours (%) | Hours |
| 0 - 5 | 27.8 | 14 | 569 | -140,290 | 57 | 907 |
| 5 - 10 | 55.5 | 9 | 371 | -280,581 | 8 | 124 |
| 10 - 15 | 83.3 | 11 | 430 | -420,871 | 6 | 100 |
| 15 - 20 | 111.1 | 8 | 307 | -561,161 | 5 | 80 |
| 20 - 25 | 138.8 | 9 | 351 | -701,452 | 3 | 48 |
| 25 - 30 | 166.6 | 9 | 346 | -841,742 | 4 | 60 |
| 30 - 35 | 194.3 | 6 | 246 | -982,032 | 5 | 81 |
| 35 - 40 | 222.1 | 2 | 73 | -1,122,323 | 2 | 25 |
| 40 - 45 | 249.9 | 3 | 129 | -1,262,613 | 0 | 6 |
| 45 - 50 | 277.6 | 4 | 141 | -1,402,904 | 3 | 54 |
| 50 - 55 | 305.4 | 3 | 108 | -1,543,194 | 6 | 99 |
| 55 - 60 | 333.2 | 3 | 131 | -1,683,484 | 1 | 16 |
| 60 - 65 | 360.9 | 2 | 86 | -1,823,775 | 0 | 0 |
| 65 - 70 | 388.7 | 3 | 131 | -1,964,065 | 0 | 0 |
| 70 - 75 | 416.5 | 3 | 128 | -2,104,355 | 0 | 0 |
| 75 - 80 | 444.2 | 4 | 168 | -2,244,646 | 0 | 0 |
| 80 - 85 | 472.0 | 4 | 172 | -2,384,936 | 0 | 0 |
| 85 - 90 | 499.8 | 1 | 43 | -2,525,227 | 0 | 0 |
| 90 - 95 | 527.5 | 1 | 43 | -2,665,517 | 0 | 0 |
| 95 - 100 | 555.3 | 0 | 0 | -2,805,807 | 0 | 0 |
| Hours Off | 0.0 | 0 | 4,787 | 0 | 0 | 7,160 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|----------|---------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|---------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 77510 | 70128 | 84891 | 73819 | 81200 | 81200 | 73819 | 84891 | 73819 | 81200 | 73819 | 73819 | 930,115 |
| | PK | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 1190 | 1152 | 1190 | 1190 | 1152 | 1190 | 0 | 0 | 7,066 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.6 | 1.6 | 1.6 | 1.6 | 1.6 | 1.6 | 0.0 | 0.0 | 1.6 |
| 2 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 507 | 458 | 507 | 490 | 0 | 0 | 0 | 0 | 0 | 0 | 490 | 507 | 2,958 |
| | PK | 0.7 | 0.7 | 0.7 | 0.7 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.7 | 0.7 | 0.7 |
| 3 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 7589 | 7344 | 7589 | 7589 | 7344 | 7589 | 0 | 0 | 45,043 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 10.2 | 10.2 | 10.2 | 10.2 | 10.2 | 10.2 | 0.0 | 0.0 | 10.2 |
| 4 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 405 | 366 | 405 | 392 | 0 | 0 | 0 | 0 | 0 | 0 | 392 | 405 | 2,367 |
| | PK | 0.5 | 0.5 | 0.5 | 0.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.5 | 0.5 | 0.5 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|--------|--------------------------------------|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| 5 | | BASE UTILITY | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 1860 | 1800 | 1860 | 1860 | 1800 | 1860 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.5 | 2.5 | 2.5 | 2.5 | 2.5 | 2.5 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 11,040 |
| | | | | | | | | | | | | | 2.5 |
| 6 | | BASE UTILITY | | | | | | | | | | | |
| | HOTLD | 132 | 119 | 132 | 128 | 0 | 0 | 0 | 0 | 0 | 0 | 128 | 132 |
| | PK | 0.2 | 0.2 | 0.2 | 0.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.2 | 0.2 |
| | | | | | | | | | | | | | 769 |
| | | | | | | | | | | | | | 0.2 |
| 7 | | BASE UTILITY | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 4390 | 4248 | 4390 | 4390 | 4248 | 4390 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 5.9 | 5.9 | 5.9 | 5.9 | 5.9 | 5.9 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 26,054 |
| | | | | | | | | | | | | | 5.9 |
| 1 | | QUAD AIR COOLED RECIP CHILLER(S) | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 11383 | 13937 | 16680 | 16889 | 12081 | 5786 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 36.9 | 40.4 | 43.9 | 44.1 | 37.5 | 27.4 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 76,755 |
| | | | | | | | | | | | | | 44.1 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 2775 | 2686 | 2775 | 2775 | 2686 | 2775 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 16,472 |
| | | | | | | | | | | | | | 3.7 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | 1.0 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 2775 | 2686 | 2775 | 2775 | 2686 | 2775 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 16,472 |
| | | | | | | | | | | | | | 3.7 |
| 2 | | QUAD AIR COOLED RECIP CHILLER(S) | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 46937 | 51983 | 56803 | 57761 | 50614 | 32096 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 98.2 | 106.1 | 113.6 | 115.1 | 103.4 | 93.6 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 296,194 |
| | | | | | | | | | | | | | 115.1 |
| 2 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 11100 | 10742 | 11100 | 11100 | 10742 | 11100 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 65,887 |
| | | | | | | | | | | | | | 14.9 |
| 2 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | 1.0 |
| 3 | | QUAD AIR COOLED RECIP CHILLER(S) | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 32997 | 43350 | 54743 | 56746 | 34944 | 20449 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 143.1 | 155.5 | 166.4 | 168.7 | 151.4 | 137.2 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 243,230 |
| | | | | | | | | | | | | | 168.7 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--------------------------------------|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 3 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1071 | 1417 | 1768 | 1790 | 1119 | 656 | 0 | 0 | 7,822 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 0.0 | 0.0 | 3.7 |
| 3 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 287 | 380 | 474 | 480 | 300 | 176 | 0 | 0 | 2,097 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 4 | | QUAD AIR COOLED RECIP CHILLER(S) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 16188 | 19446 | 21238 | 24712 | 17761 | 4890 | 0 | 0 | 104,234 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 143.1 | 155.5 | 166.4 | 168.7 | 151.4 | 121.0 | 0.0 | 0.0 | 168.7 |
| 4 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 492 | 574 | 597 | 686 | 522 | 164 | 0 | 0 | 3,036 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 0.0 | 0.0 | 3.7 |
| 4 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 132 | 154 | 160 | 184 | 140 | 44 | 0 | 0 | 814 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 5 | | QUAD AIR COOLED RECIP CHILLER(S) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 27434 | 32405 | 38181 | 38370 | 28141 | 15749 | 0 | 0 | 180,278 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 83.1 | 86.8 | 90.0 | 89.3 | 83.4 | 76.9 | 0.0 | 0.0 | 90.0 |
| 5 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 2775 | 2686 | 2775 | 2775 | 2686 | 2775 | 0 | 0 | 16,472 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 0.0 | 0.0 | 3.7 |
| 5 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 6 | | QUAD AIR COOLED RECIP CHILLER(S) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 56711 | 73757 | 86637 | 85892 | 62230 | 27804 | 0 | 0 | 393,031 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 159.0 | 185.9 | 188.5 | 189.2 | 166.5 | 157.2 | 0.0 | 0.0 | 189.2 |
| 6 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 4166 | 4032 | 4166 | 4166 | 4032 | 4166 | 0 | 0 | 24,730 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | 0.0 | 0.0 | 5.6 |
| 6 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--------------------------------------|------|-----|-----|-------|-------|-------|-------|-------|-------|-----|------|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 6 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 4166 | 4032 | 4166 | 4166 | 4032 | 4166 | 0 | 0 | 24,730 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | 0.0 | 0.0 | 5.6 |
| 6 | EQ5105 | EVAPORATIVE CONDENSER FANS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 6942 | 6718 | 6942 | 6942 | 6718 | 6942 | 0 | 0 | 41,201 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 9.3 | 9.3 | 9.3 | 9.3 | 9.3 | 9.3 | 0.0 | 0.0 | 9.3 |
| 7 | | QUAD AIR COOLED RECIP CHILLER(S) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 19262 | 20759 | 27811 | 31913 | 18382 | 4632 | 0 | 0 | 122,759 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 155.6 | 170.6 | 184.6 | 185.3 | 160.4 | 119.9 | 0.0 | 0.0 | 185.3 |
| 7 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 7 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 154 | 154 | 200 | 230 | 140 | 44 | 0 | 0 | 922 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 1 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | | |
| | GAS | 2063 | 1913 | 207 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 350 | 1977 | 6,509 |
| | PK | 11.5 | 12.0 | 6.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 6.0 | 11.4 | 12.0 |
| 1 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 57 | 53 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 17 | 55 | 192 |
| | PK | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 2 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | | |
| | GAS | 277 | 239 | 619 | 684 | 0 | 0 | 0 | 0 | 0 | 0 | 556 | 292 | 2,665 |
| | PK | 1.0 | 1.0 | 1.0 | 0.9 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 |
| 2 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 36 | 31 | 81 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 73 | 38 | 351 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 3 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | | |
| | GAS | 374 | 347 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 308 | 1,029 |
| | PK | 3.8 | 3.8 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 3.8 | 3.8 |
| 3 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 14 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 11 | 38 |
| | PK | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|--------|---------------------------------|-----|-----|-----|-----|------|------|-----|-----|-----|-----|-----|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| 4 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | |
| | GAS | 262 | 221 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 180 |
| | PK | 3.8 | 3.8 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 3.8 |
| 4 | E05311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 11 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 |
| | PK | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 |
| 5 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | |
| | GAS | 5 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 |
| | PK | 0.3 | 0.9 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.4 |
| 5 | E05311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 3 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 |
| | PK | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 |
| 6 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | E05311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 7 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 7 | E05311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 8 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 8 | E05311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 9 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|------------------------------|-----|-----|-----|-----|------|------|-----|-----|-----|-----|-----|-------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 9 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 10 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | | |
| | GAS | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| | PK | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 |
| 10 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| | PK | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 |
| 11 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 11 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 12 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 12 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 13 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 13 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 14 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 14 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|---------------------------------|-----|-----|-----|-----|------|------|-----|-----|-----|-----|-----|-------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 15 | EQ2001 | GAS FIRED HOT WATER BOILER | | | | | | | | | | | | |
| | GAS | 392 | 351 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 59 | 379 | 1,204 |
| | PK | 2.9 | 3.0 | 1.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.6 | 2.9 | 3.0 |
| 15 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 562 | 484 | 72 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 161 | 542 | 1,821 |
| | PK | 2.2 | 2.2 | 2.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 2.2 | 2.2 | 2.2 |
| 15 | EQ5240 | BOILER FORCED DRAFT FAN | | | | | | | | | | | | |
| | ELEC | 1361 | 806 | 358 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 828 | 921 | 4,275 |
| | PK | 3.7 | 3.7 | 3.7 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 3.7 | 3.7 | 3.7 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
A.C. SCREW CHILLERS

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|--------------|--------------------------------------|-------|-------|-------|-------|--------|--------|--------|-------|-------|-------|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| Total | | | | | | | | | | | | | |
| 0 | LIGHTS | | | | | | | | | | | | |
| | ELEC | 77510 | 70128 | 84891 | 73819 | 81200 | 81200 | 73819 | 84891 | 73819 | 81200 | 73819 | 73819 |
| | PK | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 |
| | | | | | | | | | | | | | 930,115 |
| | | | | | | | | | | | | | 455.7 |
| 1 | MISC LD | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 0 |
| | | | | | | | | | | | | | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 0 |
| | | | | | | | | | | | | | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 0 |
| | | | | | | | | | | | | | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 0 |
| | | | | | | | | | | | | | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 0 |
| | | | | | | | | | | | | | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 0 |
| | | | | | | | | | | | | | 0.0 |
| 1 | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 15029 | 14544 | 15029 | 15029 | 14544 | 15029 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 20.2 | 20.2 | 20.2 | 20.2 | 20.2 | 20.2 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 89,203 |
| | | | | | | | | | | | | | 20.2 |
| 1 | EQ1510 | AIR COOLED SERIES R (RTAA) | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 88155 | 109763 | 136458 | 139682 | 93439 | 39506 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 287.6 | 328.3 | 351.0 | 351.0 | 306.5 | 271.9 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 607,003 |
| | | | | | | | | | | | | | 351.0 |
| 1 | EQ5200 | CONDENSER FANS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 0 |
| | | | | | | | | | | | | | 0.0 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 16651 | 16114 | 16651 | 16651 | 16114 | 16651 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 98,830 |
| | | | | | | | | | | | | | 22.4 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
A.C. SCREW CHILLERS

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--------------------------------------|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|---------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 1 | E05302 | CONTROLS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 74 | 72 | 74 | 74 | 72 | 74 | 0 | 0 | 442 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.1 |
| 2 | E01510 | AIR COOLED SERIES R (RTAA) | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 37029 | 47686 | 52699 | 56867 | 42171 | 17101 | 0 | 0 | 253,553 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 287.6 | 328.3 | 351.0 | 351.0 | 306.5 | 216.4 | 0.0 | 0.0 | 351.0 |
| 2 | E05001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 3939 | 4924 | 4924 | 5147 | 4476 | 2350 | 0 | 0 | 25,759 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 0.0 | 0.0 | 22.4 |
| 2 | E05302 | CONTROLS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 18 | 22 | 22 | 23 | 20 | 11 | 0 | 0 | 115 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.1 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
EXIST STEAM BLR WITH NEW HWH GENERATOR

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|----------|---------------------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|---------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 77510 | 70128 | 84891 | 73819 | 81200 | 81200 | 73819 | 84891 | 73819 | 81200 | 73819 | 73819 | 930,115 |
| | PK | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 | 455.7 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 1044 | 943 | 1044 | 1010 | 0 | 0 | 0 | 0 | 0 | 0 | 1010 | 1044 | 6,095 |
| | PK | 1.4 | 1.4 | 1.4 | 1.4 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.4 | 1.4 | 1.4 |
| 1 | | QUAD AREA EXIST STEAM BOILER | | | | | | | | | | | | |
| | GAS | 4107 | 3752 | 1598 | 1408 | 0 | 0 | 0 | 0 | 0 | 0 | 1692 | 3883 | 16,440 |
| | PK | 23.0 | 24.3 | 8.2 | 2.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 8.7 | 23.1 | 24.3 |
| 1 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 | 543 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 1 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 1667 | 1505 | 1667 | 1613 | 0 | 0 | 0 | 0 | 0 | 0 | 1613 | 1667 | 9,731 |
| | PK | 2.2 | 2.2 | 2.2 | 2.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 2.2 | 2.2 | 2.2 |

01 Card - Job Information

 Project: 030185.04 EEAP BOILER-CHILLER STUDY
 Location: FT. SAM HOUSTON - SAN ANTONIO, TX.
 Client: CORPS. OF ENGINEERS - FORT WORTH, TX.
 Program User: HUITT-ZOLLARS INC.
 Comments: AREA 100

Card 08----- Climatic Information -----

| | Summer | Winter | Summer | Summer | Winter | | Summer | Winter |
|----------|-----------|-----------|----------|----------|----------|-------------|---------|---------|
| Weather | Clearness | Clearness | Design | Design | Design | Building | Ground | Ground |
| Code | Number | Number | Dry Bulb | Wet Bulb | Dry Bulb | Orientation | Reflect | Reflect |
| SANANTON | | | | | | | | |

----- Load Section Alternative #1 -----

Card 19- Load Alternative -

| Number | Description |
|--------|--------------------|
| 1 | EXISTING BUILDINGS |

Card 20----- General Room Parameters -----

| Room | Zone | Room | Floor | Floor | Const | Plenum | Acoustic | Floor to | Duplicate | Duplicate | Perimeter |
|--------|-----------|----------|--------|-------|-------|--------|------------|----------|------------|-----------|-----------|
| Number | Reference | Descrip | Length | Width | Type | Height | Ceiling | Floor | Floors | Rooms per | Depth |
| | Number | | | | | | Resistance | Height | Multiplier | Zone | |
| 5 | 5 | BLDG 122 | 113 | 113 | 3 | 3 | 2.54 | 11 | | | |
| 10 | 10 | BLDG 124 | 113 | 113 | 3 | 3 | 2.54 | 11 | | | |
| 15 | 15 | BLDG 128 | 119 | 119 | 3 | 8 | 2.54 | 18 | | | |
| 20 | 20 | BLDG 133 | 100 | 96 | 3 | 8 | 2.54 | 18 | | | |
| 25 | 25 | BLDG 134 | 102 | 102 | 3 | 3 | 2.54 | 12 | | | |
| 30 | 30 | BLDG 143 | 122 | 122 | 3 | 3 | 2.54 | 12 | | | |
| 35 | 35 | BLDG 144 | 122 | 122 | 3 | 3 | 2.54 | 12 | | | |
| 40 | 40 | BLDG 145 | 122 | 122 | 3 | 3 | 2.54 | 12 | | | |
| 45 | 45 | BLDG 146 | 122 | 122 | 3 | 3 | 2.54 | 12 | | | |
| 50 | 50 | BLDG 147 | 122 | 122 | 3 | 3 | 2.54 | 12 | | | |
| 55 | 55 | BLDG 149 | 122 | 122 | 3 | 3 | 2.54 | 12 | | | |
| 60 | 60 | BLDG 197 | 122 | 122 | 3 | 3 | 2.54 | 12 | | | |
| 65 | 65 | BLDG 198 | 68 | 68 | 3 | 5 | 2.54 | 14 | | | |
| 70 | 70 | BLDG 199 | 80 | 80 | 3 | 2 | 2.54 | 12 | | | |
| 75 | 75 | BLDG 125 | 50 | 26 | 3 | 5 | 2.54 | 15 | | | |
| 80 | 80 | BLDG 127 | 50 | 26 | 3 | 5 | 2.54 | 15 | | | |
| 85 | 85 | BLDG 135 | 50 | 26 | 3 | 5 | 2.54 | 15 | | | |

| Card 20----- General Room Parameters ----- | | | | | | | | | | | |
|--|-----------|------------|--------|-------|-------|--------|------------|----------|------------|-----------|-----------|
| Zone | | | | | | | | | | | |
| Room | Reference | Room | Floor | Floor | Const | Plenum | Acoustic | Floor to | Duplicate | Duplicate | Perimeter |
| Number | Number | Descrip | Length | Width | Type | Height | Ceiling | Floor | Floors | Rooms per | Depth |
| | | | | | | | Resistance | Height | Multiplier | Zone | |
| 90 | 90 | BLDG 250-1 | 142 | 34 | 3 | 2 | 2.54 | 10.5 | | | |
| 95 | 95 | BLDG 250-2 | 195 | 195 | 3 | 2 | 2.54 | 10.5 | | | |
| 100 | 100 | BLDG. 142 | 65 | 65 | 3 | 2 | 2.54 | 10 | 1 | 1 | |

| Card 21----- Thermostat Parameters ----- | | | | | | | | | | | |
|--|-----------|-----------|------------|----------|-----------|------------|----------|----------|---------|--------|--|
| Cooling | | | | | | | | | | | |
| Room | Room | Room | Cooling | Cooling | Heating | Heating | Heating | T'stat | Mass / | Carpet | |
| Number | Design DB | Design RH | T'stat | T'stat | Room | T'stat | T'stat | Location | No. Hrs | On | |
| | | | Driftpoint | Schedule | Design DB | Driftpoint | Schedule | Flag | Average | Floor | |
| 5 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 10 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 15 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 20 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 25 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 30 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 35 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 40 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 45 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 50 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 55 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 60 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 65 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 70 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 75 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 80 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 85 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 90 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 95 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | NO | |
| 100 | 78 | 50 | 78 | | 70 | 70 | | ROOM | LIGHT30 | YES | |

| Card 22----- Roof Parameters ----- | | | | | | | | | | |
|------------------------------------|--------|----------|--------|-------|---------|------|-----------|------|-------|--|
| Roof | | | | | | | | | | |
| Room | Roof | Roof | Roof | Roof | Const | Roof | Roof | Roof | Roof | |
| Number | Number | Equal to | Length | Width | U-Value | Type | Direction | Tilt | Alpha | |
| 5 | 1 | NO | 180 | 30 | .08 | 37 | 0 | 60 | .9 | |
| 10 | 1 | NO | 180 | 30 | .08 | 37 | 0 | 60 | .9 | |
| 15 | 1 | YES | | | .08 | 37 | 0 | 60 | .9 | |
| 20 | 1 | YES | | | .08 | 37 | 0 | 60 | .9 | |
| 25 | 1 | NO | 73 | 74 | .05 | 40 | 0 | 45 | .9 | |
| 30 | 1 | NO | 146 | 28 | .05 | 40 | 0 | 80 | .9 | |
| 35 | 1 | NO | 146 | 28 | .05 | 40 | 0 | 80 | .9 | |
| 40 | 1 | NO | 146 | 28 | .05 | 40 | 0 | 80 | .9 | |
| 45 | 1 | NO | 146 | 28 | .05 | 40 | 0 | 80 | .9 | |
| 50 | 1 | NO | 146 | 28 | .05 | 40 | 0 | 80 | .9 | |

Card 22----- Roof Parameters -----

| Room Number | Roof Number | Roof Equal to Floor? | Roof Length | Roof Width | Roof U-Value | Const Type | Roof Direction | Roof Tilt | Roof Alpha |
|-------------|-------------|----------------------|-------------|------------|--------------|------------|----------------|-----------|------------|
| 55 | 1 | NO | 146 | 28 | .05 | 40 | 0 | 80 | .9 |
| 60 | 1 | NO | 146 | 28 | .05 | 40 | 0 | 80 | .9 |
| 65 | 1 | NO | 39 | 39 | .08 | 37 | 0 | 60 | .9 |
| 70 | 1 | NO | 56 | 57 | .05 | 37 | 0 | 60 | .9 |
| 75 | 1 | YES | | | .08 | 37 | 0 | 60 | .9 |
| 80 | 1 | YES | | | .08 | 37 | 0 | 60 | .9 |
| 85 | 1 | YES | | | .08 | 37 | 0 | 60 | .9 |
| 90 | 1 | YES | | | .06 | 23 | 0 | 90 | .9 |
| 95 | 1 | NO | 113 | 113 | .06 | 23 | 0 | 90 | .9 |
| 100 | 1 | NO | 47 | 33 | 0.05 | 40 | 0 | 80 | .9 |

Card 24----- Wall Parameters -----

| Room Number | Wall Number | Wall Length | Wall Height | Wall U-Value | Wall Constuc Type | Wall Direction | Wall Tilt | Wall Alpha | Ground Reflectance Multiplier |
|-------------|-------------|-------------|-------------|--------------|-------------------|----------------|-----------|------------|-------------------------------|
| 5 | 1 | 360 | 11 | .17 | 58 | 330 | 0 | .74 | 1 |
| 5 | 2 | 60 | 11 | .17 | 58 | 60 | 0 | .74 | 1 |
| 5 | 3 | 360 | 11 | .17 | 58 | 150 | 0 | .74 | 1 |
| 5 | 4 | 60 | 11 | .17 | 58 | 240 | 0 | .74 | 1 |
| 10 | 1 | 360 | 11 | .17 | 58 | 315 | 0 | .74 | 1 |
| 10 | 2 | 60 | 11 | .17 | 58 | 45 | 0 | .74 | 1 |
| 10 | 3 | 360 | 11 | .17 | 58 | 135 | 0 | .74 | 1 |
| 10 | 4 | 60 | 11 | .17 | 58 | 225 | 0 | .74 | 1 |
| 15 | 1 | 100 | 18 | .10 | 58 | 315 | 0 | .9 | 1 |
| 15 | 2 | 96 | 18 | .10 | 58 | 45 | 0 | .9 | 1 |
| 15 | 3 | 100 | 18 | .10 | 52 | 135 | 0 | .9 | 1 |
| 15 | 4 | 96 | 18 | .10 | 58 | 225 | 0 | .9 | 1 |
| 20 | 1 | 100 | 18 | .10 | 58 | 330 | 0 | .9 | 1 |
| 20 | 2 | 96 | 18 | .10 | 58 | 60 | 0 | .9 | 1 |
| 20 | 3 | 100 | 18 | .10 | 52 | 150 | 0 | .9 | 1 |
| 20 | 4 | 96 | 18 | .10 | 58 | 240 | 0 | .9 | 1 |
| 25 | 1 | 280 | 12 | .11 | 88 | 315 | 0 | .9 | 1 |
| 25 | 2 | 60 | 12 | .11 | 88 | 45 | 0 | .9 | 1 |
| 25 | 3 | 280 | 12 | .11 | 88 | 135 | 0 | .9 | 1 |
| 25 | 4 | 60 | 12 | .11 | 88 | 225 | 0 | .9 | 1 |
| 30 | 1 | 292 | 12 | .10 | 58 | 0 | 0 | .9 | 1 |
| 30 | 2 | 56 | 12 | .10 | 58 | 90 | 0 | .9 | 1 |
| 30 | 3 | 292 | 12 | .10 | 58 | 180 | 0 | .9 | 1 |
| 30 | 4 | 56 | 12 | .10 | 58 | 270 | 0 | .9 | 1 |
| 35 | 1 | 292 | 12 | .10 | 58 | 0 | 0 | .9 | 1 |
| 35 | 2 | 56 | 12 | .10 | 58 | 90 | 0 | .9 | 1 |
| 35 | 3 | 292 | 12 | .10 | 58 | 180 | 0 | .9 | 1 |
| 35 | 4 | 56 | 12 | .10 | 58 | 270 | 0 | .9 | 1 |
| 40 | 1 | 292 | 12 | .10 | 58 | 0 | 0 | .9 | 1 |
| 40 | 2 | 56 | 12 | .10 | 58 | 90 | 0 | .9 | 1 |

Card 24----- Wall Parameters -----

| Room Number | Wall Number | Wall Length | Wall Height | Wall U-Value | Wall Constuc Type | Wall Direction | Wall Tilt | Wall Alpha | Ground Reflectance Multiplier |
|----------------|----------------|----------------|----------------|-----------------|-------------------------|-------------------|--------------|---------------|-------------------------------------|
| 40 | 3 | 292 | 12 | .10 | 58 | 180 | 0 | .9 | 1 |
| 40 | 4 | 56 | 12 | .10 | 58 | 270 | 0 | .9 | 1 |
| 45 | 1 | 292 | 12 | .10 | 58 | 0 | 0 | .9 | 1 |
| 45 | 2 | 56 | 12 | .10 | 58 | 90 | 0 | .9 | 1 |
| 45 | 3 | 292 | 12 | .10 | 58 | 180 | 0 | .9 | 1 |
| 45 | 4 | 56 | 12 | .10 | 58 | 270 | 0 | .9 | 1 |
| 50 | 1 | 292 | 12 | .10 | 58 | 90 | 0 | .9 | 1 |
| 50 | 2 | 56 | 12 | .10 | 58 | 180 | 0 | .9 | 1 |
| 50 | 3 | 292 | 12 | .10 | 58 | 270 | 0 | .9 | 1 |
| 50 | 4 | 56 | 12 | .10 | 58 | 0 | 0 | .9 | 1 |
| 55 | 1 | 292 | 12 | .10 | 58 | 90 | 0 | .9 | 1 |
| 55 | 2 | 56 | 12 | .10 | 58 | 180 | 0 | .9 | 1 |
| 55 | 3 | 292 | 12 | .10 | 58 | 270 | 0 | .9 | 1 |
| 55 | 4 | 56 | 12 | .10 | 58 | 0 | 0 | .9 | 1 |
| 60 | 1 | 292 | 12 | .10 | 58 | 320 | 0 | .9 | 1 |
| 60 | 2 | 56 | 12 | .10 | 58 | 50 | 0 | .9 | 1 |
| 60 | 3 | 292 | 12 | .10 | 58 | 140 | 0 | .9 | 1 |
| 60 | 4 | 56 | 12 | .10 | 58 | 230 | 0 | .9 | 1 |
| 65 | 1 | 27.5 | 14 | .12 | 74 | 0 | 0 | .74 | 1 |
| 65 | 2 | 59 | 14 | .12 | 74 | 90 | 0 | .74 | 1 |
| 65 | 3 | 27.5 | 14 | .12 | 74 | 180 | 0 | .74 | 1 |
| 65 | 4 | 59 | 14 | .12 | 74 | 270 | 0 | .74 | 1 |
| 70 | 1 | 126 | 12 | .12 | 74 | 315 | 0 | .74 | 1 |
| 70 | 2 | 31 | 12 | .12 | 74 | 45 | 0 | .74 | 1 |
| 70 | 3 | 126 | 12 | .12 | 74 | 135 | 0 | .74 | 1 |
| 70 | 4 | 31 | 12 | .12 | 74 | 225 | 0 | .74 | 1 |
| 75 | 1 | 50 | 15 | .17 | 58 | 315 | 0 | .74 | 1 |
| 75 | 2 | 26 | 15 | .17 | 58 | 45 | 0 | .74 | 1 |
| 75 | 3 | 50 | 15 | .17 | 58 | 135 | 0 | .74 | 1 |
| 75 | 4 | 26 | 15 | .17 | 58 | 225 | 0 | .74 | 1 |
| 80 | 1 | 50 | 15 | .17 | 58 | 315 | 0 | .74 | 1 |
| 80 | 2 | 26 | 15 | .17 | 58 | 45 | 0 | .74 | 1 |
| 80 | 3 | 50 | 15 | .17 | 58 | 135 | 0 | .74 | 1 |
| 80 | 4 | 26 | 15 | .17 | 58 | 225 | 0 | .74 | 1 |
| 85 | 1 | 50 | 15 | .17 | 58 | 315 | 0 | .74 | 1 |
| 85 | 2 | 26 | 15 | .17 | 58 | 45 | 0 | .74 | 1 |
| 85 | 3 | 50 | 15 | .17 | 58 | 135 | 0 | .74 | 1 |
| 85 | 4 | 26 | 15 | .17 | 58 | 225 | 0 | .74 | 1 |
| 90 | 1 | 142 | 10.5 | .12 | 74 | 0 | 0 | .74 | 1 |
| 90 | 2 | 58 | 10.5 | .12 | 74 | 90 | 0 | .74 | 1 |
| 90 | 3 | 52 | 10.5 | .12 | 74 | 180 | 0 | .74 | 1 |
| 90 | 4 | 58 | 10.5 | .12 | 74 | 270 | 0 | .74 | 1 |
| 95 | 1 | 20 | 10.5 | .12 | 74 | 0 | 0 | .74 | 1 |
| 95 | 2 | 798 | 10.5 | .12 | 74 | 90 | 0 | .74 | 1 |
| 95 | 3 | 60 | 10.5 | .12 | 74 | 180 | 0 | .74 | 1 |
| 95 | 4 | 798 | 10.5 | .12 | 74 | 270 | 0 | .74 | 1 |
| 100 | 1 | 118 | 10 | .16 | 64 | 0 | 0 | .74 | 1 |

Card 24----- Wall Parameters -----

| Room Number | Wall Number | Wall Length | Wall Height | Wall U-Value | Wall | | Wall Tilt | Wall Alpha | Ground | |
|-------------|-------------|-------------|-------------|--------------|---------|-----------|-----------|------------|-------------|------------|
| | | | | | Constuc | Direction | | | Reflectance | Multiplier |
| 100 | 2 | 83 | 10 | .16 | 64 | 0 | 0 | .74 | 1 | |
| 100 | 3 | 118 | 10 | .16 | 64 | 0 | 0 | .74 | 1 | |
| 100 | 4 | 83 | 10 | .16 | 64 | 0 | 0 | .74 | 1 | |

Card 25----- Wall/Glass Parameters -----

| Room Number | Wall Number | Glass Length | Glass Width | Pct Glass or No. of Windows | Glass U-Value | Shading Coefficient | External | | Internal | Percent Solar Ret. Air | Visible Transmittance | Inside Visible Reflectance |
|-------------|-------------|--------------|-------------|-----------------------------|---------------|---------------------|--------------|--------------|----------|------------------------|-----------------------|----------------------------|
| | | | | | | | Shading Type | Shading Type | | | | |
| 5 | 1 | 5 | 3 | 34 | 1.1 | .67 | | | | | | |
| 5 | 2 | 5 | 3 | 6 | 1.1 | .67 | | | | | | |
| 5 | 3 | 5 | 3 | 34 | 1.1 | .67 | | 3 | | | | |
| 5 | 4 | 5 | 3 | 6 | 1.1 | .67 | | | | | | |
| 10 | 1 | 5 | 3 | 34 | 1.1 | .67 | | | | | | |
| 10 | 2 | 5 | 3 | 6 | 1.1 | .67 | | | | | | |
| 10 | 3 | 5 | 3 | 34 | 1.1 | .67 | | 3 | | | | |
| 10 | 4 | 5 | 3 | 6 | 1.1 | .67 | | | | | | |
| 15 | 1 | 7 | 3 | 8 | 1.1 | .67 | | | | | | |
| 15 | 2 | 7 | 3 | 7 | 1.1 | .67 | | | | | | |
| 15 | 3 | 7 | 3 | 9 | 1.1 | .67 | | | | | | |
| 15 | 4 | 7 | 3 | 7 | 1.1 | .67 | | | | | | |
| 20 | 1 | 7 | 3 | 8 | 1.1 | .67 | | | | | | |
| 20 | 2 | 7 | 3 | 7 | 1.1 | .67 | | | | | | |
| 20 | 3 | 7 | 3 | 9 | 1.1 | .67 | | | | | | |
| 20 | 4 | 7 | 3 | 7 | 1.1 | .67 | | | | | | |
| 25 | 1 | 6 | 3 | 26 | .8 | .67 | | | | | | |
| 25 | 2 | 6 | 3 | 5 | .8 | .67 | | | | | | |
| 25 | 3 | | | 29 | .53 | 1 | | | | | | |
| 25 | 4 | 6 | 3 | 5 | .8 | .67 | | | | | | |
| 30 | 1 | 7 | 3.5 | 21 | 1.1 | .67 | | 3 | | | | |
| 30 | 2 | 7 | 3.5 | 6 | 1.1 | .67 | | | | | | |
| 30 | 3 | | | 35 | 1.1 | .67 | | 3 | | | | |
| 30 | 4 | 7 | 3.5 | 6 | 1.1 | .67 | | | | | | |
| 35 | 1 | 7 | 3.5 | 21 | 1.1 | .67 | | 3 | | | | |
| 35 | 2 | 7 | 3.5 | 6 | 1.1 | .67 | | | | | | |
| 35 | 3 | | | 35 | 1.1 | .67 | | 3 | | | | |
| 35 | 4 | 7 | 3.5 | 6 | 1.1 | .67 | | | | | | |
| 40 | 1 | 7 | 3.5 | 21 | 1.1 | .67 | | 3 | | | | |
| 40 | 2 | 7 | 3.5 | 6 | 1.1 | .67 | | | | | | |
| 40 | 3 | | | 35 | 1.1 | .67 | | 3 | | | | |
| 40 | 4 | 7 | 3.5 | 6 | 1.1 | .67 | | | | | | |
| 45 | 1 | 7 | 3.5 | 21 | 1.1 | .67 | | 3 | | | | |
| 45 | 2 | 7 | 3.5 | 6 | 1.1 | .67 | | | | | | |
| 45 | 3 | | | 35 | 1.1 | .67 | | 3 | | | | |
| 45 | 4 | 7 | 3.5 | 6 | 1.1 | .67 | | | | | | |
| 50 | 1 | 7 | 3.5 | 21 | 1.1 | .67 | | 3 | | | | |

| Card 25----- Wall/Glass Parameters ----- | | | | | | | | | | |
|--|--------|--------|-------|-----------|---------|-------------|----------|----------|----------|---------------|
| Room | Wall | Glass | Glass | Pct Glass | | Shading | External | Internal | Percent | Inside |
| Number | Number | Length | Width | or No. of | Glass | Coefficient | Shading | Shading | Solar to | Visible |
| | | | | Windows | U-Value | | Type | Type | Ret. Air | Transmittance |
| | | | | | | | | | | Reflectance |
| 50 | 2 | 7 | 3.5 | 6 | 1.1 | .67 | | | | |
| 50 | 3 | | | 35 | 1.1 | .67 | 3 | | | |
| 50 | 4 | 7 | 3.5 | 6 | 1.1 | .67 | | | | |
| 55 | 1 | 7 | 3.5 | 21 | 1.1 | .67 | 3 | | | |
| 55 | 2 | 7 | 3.5 | 6 | 1.1 | .67 | | | | |
| 55 | 3 | | | 35 | 1.1 | .67 | 3 | | | |
| 55 | 4 | 7 | 3.5 | 6 | 1.1 | .67 | | | | |
| 60 | 1 | 7 | 3.5 | 21 | 1.1 | .67 | 3 | | | |
| 60 | 2 | 7 | 3.5 | 6 | 1.1 | .67 | | | | |
| 60 | 3 | | | 35 | 1.1 | .67 | 3 | | | |
| 60 | 4 | 7 | 3.5 | 6 | 1.1 | .67 | | | | |
| 65 | 1 | 5 | 3 | 6 | 1.1 | .67 | | | | |
| 65 | 2 | 5 | 3 | 11 | 1.1 | .67 | 3 | | | |
| 65 | 3 | 5 | 3 | 6 | 1.1 | .67 | | | | |
| 65 | 4 | 5 | 3 | 11 | 1.1 | .67 | 3 | | | |
| 70 | 1 | 5 | 3 | 10 | 1.1 | .67 | 3 | | | |
| 70 | 2 | 5 | 3 | 2 | 1.1 | .67 | | | | |
| 70 | 3 | 5 | 3 | 10 | 1.1 | .67 | | | | |
| 70 | 4 | 5 | 3 | 2 | 1.1 | .67 | | | | |
| 75 | 1 | 8 | 3 | 4 | .73 | .67 | | | | |
| 75 | 2 | 8 | 3 | 2 | .73 | .67 | | | | |
| 75 | 3 | 8 | 3 | 4 | .73 | .67 | | | | |
| 75 | 4 | 8 | 3 | 2 | .73 | .67 | | | | |
| 80 | 1 | 8 | 3 | 4 | .73 | .67 | | | | |
| 80 | 2 | 8 | 3 | 2 | .73 | .67 | | | | |
| 80 | 3 | 8 | 3 | 4 | .73 | .67 | | | | |
| 80 | 4 | 8 | 3 | 2 | .73 | .67 | | | | |
| 85 | 1 | 8 | 3 | 4 | .73 | .67 | | | | |
| 85 | 2 | 8 | 3 | 2 | .73 | .67 | | | | |
| 85 | 3 | 8 | 3 | 4 | .73 | .67 | | | | |
| 85 | 4 | 8 | 3 | 2 | .73 | .67 | | | | |
| 90 | 1 | 4 | 2 | 3 | 1.1 | 1 | | | | |
| 90 | 3 | 7 | 5 | 3 | 1.1 | 1 | | | | |
| 90 | 4 | 7 | 5 | 3 | 1.1 | 1 | | | | |
| 95 | 2 | 4 | 2 | 114 | 1.1 | .67 | | | | |
| 95 | 3 | 4 | 2 | 6 | 1.1 | .67 | | | | |
| 95 | 4 | 4 | 2 | 114 | 1.1 | .67 | | | | |
| 100 | 1 | 5 | 3.5 | 5 | 1.1 | 0.67 | | | | |
| 100 | 2 | 5 | 3.5 | 6 | 1.1 | 0.67 | | | | |
| 100 | 3 | 5 | 3.5 | 7 | 1.1 | 0.67 | | | | |
| 100 | 4 | 5 | 3.5 | 6 | 1.1 | 0.67 | | | | |

| Card 26----- Schedules ----- | | | | | | | | | | |
|------------------------------|----------|----------|-------------|--------------|---------|---------|---------|-----------|---------|-------------|
| Room | People | Lights | Ventilation | Infiltration | Reheat | Cooling | Heating | Auxiliary | Room | Daylighting |
| Number | | | | | Minimum | Fans | Fan | Fan | Exhaust | Controls |
| 5 | FSHOFFIC | FSHOFFIC | | | | | | | | |

| Card 26----- Schedules ----- | | | | | | | | | | | |
|------------------------------|----------|----------|-------------|--------------|---------|---------|---------|-----------|---------|-------------|--|
| Room | People | Lights | Ventilation | Infiltration | Reheat | Cooling | Heating | Auxiliary | Room | Daylighting | |
| Number | | | | | Minimum | Fans | Fan | Fan | Exhaust | Controls | |
| 10 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 15 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 20 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 25 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 30 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 35 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 40 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 45 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 50 | FSHBARRP | FSHBARRL | | | | | | | | | |
| 55 | FSHBARRP | FSHBARRL | | | | | | | | | |
| 60 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 65 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 70 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 75 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 80 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 85 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 90 | FSHOFFIC | FSHOFFIC | | | | | | | | | |
| 95 | FSHBARRP | FSHBARRP | | | | | | | | | |
| 100 | FSHOFFIC | FSHOFFIC | | | | | | | | | |

| Card 27----- People and Lights ----- | | | | | | | | | | | |
|--------------------------------------|--------|---------|----------|--------|----------|----------|----------|---------|--------------------|---------------------|-------------------|
| Room | People | People | People | People | Lighting | Lighting | Lighting | Ballast | Percent | --- Daylighting --- | |
| Number | Value | Units | Sensible | Latent | Value | Units | Type | Factor | Lights to Ret. Air | Reference Point 1 | Reference Point 2 |
| 5 | 60 | PEOPLE | 250 | 200 | 2 | WATT-SF | ASHRAE2 | 1 | | | |
| 10 | 60 | PEOPLE | 250 | 200 | 2 | WATT-SF | ASHRAE2 | 1 | | | |
| 15 | 175 | SF-PERS | 250 | 200 | 2 | WATT-SF | ASHRAE2 | 1 | | | |
| 20 | 175 | SF-PERS | 250 | 200 | 2 | WATT-SF | ASHRAE2 | 1 | | | |
| 25 | 175 | SF-PERS | 250 | 200 | 2.25 | WATT-SF | ASHRAE2 | 1 | | | |
| 30 | 175 | SF-PERS | 250 | 200 | 3 | WATT-SF | ASHRAE2 | 1 | | | |
| 35 | 175 | SF-PERS | 250 | 200 | 3 | WATT-SF | ASHRAE2 | 1 | | | |
| 40 | 175 | SF-PERS | 250 | 200 | 3 | WATT-SF | ASHRAE2 | 1 | | | |
| 45 | 175 | SF-PERS | 250 | 200 | 3 | WATT-SF | ASHRAE2 | 1 | | | |
| 50 | 45 | PEOPLE | 250 | 200 | 1.5 | WATT-SF | ASHRAE2 | 1 | | | |
| 55 | 45 | PEOPLE | 250 | 200 | 1.5 | WATT-SF | ASHRAE2 | 1 | | | |
| 60 | 250 | SF-PERS | 250 | 200 | 3 | WATT-SF | ASHRAE2 | 1 | | | |
| 65 | 175 | SF-PERS | 250 | 200 | 2 | WATT-SF | ASHRAE2 | 1 | | | |
| 70 | 175 | SF-PERS | 250 | 200 | 2 | WATT-SF | ASHRAE2 | 1 | | | |
| 75 | 100 | SF-PERS | 250 | 200 | 2 | WATT-SF | ASHRAE2 | 1 | | | |
| 80 | 100 | SF-PERS | 250 | 200 | 2 | WATT-SF | ASHRAE2 | 1 | | | |
| 85 | 100 | SF-PERS | 250 | 200 | 2 | WATT-SF | ASHRAE2 | 1 | | | |
| 90 | 160 | SF-PERS | 250 | 200 | 2 | WATT-SF | INCAND | 1 | | | |
| 95 | 160 | SF-PERS | 250 | 200 | 1.5 | WATT-SF | INCAND | 1 | | | |
| 100 | 175 | SF-PERS | 250 | 200 | 2 | WATT-SF | ASHRAE2 | 1 | | | |

| Card 28----- Miscellaneous Equipment ----- | | | | | | | | | | | |
|--|-----------|-----------|---------|---------|----------|--------|----------|------------|-------------|----------|----------|
| Room | Misc | Equipment | Energy | Energy | Schedule | Energy | Percent | Percent | Percent | | |
| Number | Equipment | Descrip | Consump | Consump | Code | Meter | of Load | Misc. Load | Misc. Sens | Radiant | Optional |
| | Number | | Value | Units | | Code | Sensible | to Room | to Ret. Air | Fraction | Air Path |
| 5 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 10 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 15 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 20 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 25 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 30 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 35 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 40 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 45 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 50 | 1 | T.V.-ETC. | 1 | WATT-SF | FSHBARRL | NONE | 100 | 100 | | | |
| 55 | 1 | T.V.-ETC. | 1 | WATT-SF | FSHBARRL | NONE | 100 | 100 | | | |
| 60 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 65 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 70 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 75 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 80 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 85 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 90 | 1 | COMPUTER | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |
| 95 | 1 | COMPUTER | 1 | WATT-SF | FSHBARRL | NONE | 100 | 100 | | | |
| 100 | 1 | COMPUTERS | 1 | WATT-SF | FSHOFFIC | NONE | 100 | 100 | | | |

| Card 29----- Room Airflows ----- | | | | | | | | | | |
|----------------------------------|--|-------------------|-------|-------------------|------------------------|-------------------|-------|-------------------|-------|--------------------|
| -----Ventilation----- | | | | | -----Infiltration----- | | | | | |
| | | -----Cooling----- | | -----Heating----- | | -----Cooling----- | | -----Heating----- | | --Reheat Minimum-- |
| Room | | Value | Units | Value | Units | Value | Units | Value | Units | Value Units |
| 5 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 10 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 15 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 20 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 25 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 30 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 35 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 40 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 45 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 50 | | 15 | CFM-P | 15 | CFM-P | | | | | |
| 55 | | 15 | CFM-P | 15 | CFM-P | | | | | |
| 60 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 65 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 70 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 75 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 80 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 85 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 90 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 95 | | 20 | CFM-P | 20 | CFM-P | | | | | |
| 100 | | 20 | CFM-P | 20 | CFM-P | | | | | |

| Card 32----- Exposed Floor Parameters----- | | | | | | | | | | |
|--|--------|-----------|-------------|-------------------------|---------|-------|----------|---------|---------|----------|
| Exposed Slab----- | | | | -----Exposed Floor----- | | | | | | |
| Room | Floor | Perimeter | Loss | Floor | Floor | Const | Temp | Cooling | Heating | Adjacent |
| Number | Number | Length | Coefficient | Area | U-Value | Type | Flag | Temp | Temp | Room No |
| 5 | 1 | | | 5400 | .19 | 119 | HRLYQADB | | | |
| 10 | 1 | | | 5400 | .19 | 119 | HRLYQADB | | | |
| 15 | 1 | | | 14224 | .19 | 119 | HRLYQADB | | | |
| 20 | 1 | | | 9600 | .19 | 119 | HRLYQADB | | | |
| 50 | 1 | | | 5400 | .19 | 119 | HRLYQADB | | | |
| 55 | 1 | | | 5400 | .19 | 119 | HRLYQADB | | | |
| 70 | 1 | | | 3906 | .25 | 119 | HRLYQADB | | | |

| Card 33----- External Shading ----- | | | | | | | | | |
|-------------------------------------|--------|-------|------------|-------------------------|------------|------|------------|-------|----------|
| -----OVERHANG----- | | | | -----VERTICAL FINS----- | | | | | |
| Height | | | | Left | | | | | |
| Shading | Glass | Above | Projection | Glass | Projection | Left | Projection | Right | Adjacent |
| Type | Height | Glass | Out | Width | Left | Out | Right | Out | Building |
| 3 | 5 | 2 | 8 | | | | | | Flag |

----- System Section Alternative #1 -----

Card 39- System Alternative

| Number | Description |
|--------|---------------------------|
| 1 | AREA 100 EXISTING SYSTEMS |

| Card 40----- System Type ----- | | | | | | | |
|---------------------------------------|--------|----------|---------|---------|----------|----------|----------|
| -----OPTIONAL VENTILATION SYSTEM----- | | | | | | | |
| System | Ventil | Fan | | | | | |
| Set | System | Deck | Cooling | Heating | Cooling | Heating | Static |
| Number | Type | Location | SADBVh | SADBVh | Schedule | Schedule | Pressure |
| 1 | MZ | | | | | | |
| 2 | MZ | | | | | | |
| 3 | MZ | | | | | | |
| 4 | MZ | | | | | | |
| 5 | MZ | | | | | | |
| 6 | MZ | | | | | | |
| 7 | MZ | | | | | | |
| 8 | MZ | | | | | | |
| 9 | MZ | | | | | | |
| 10 | MZ | | | | | | |
| 11 | MZ | | | | | | |
| 12 | MZ | | | | | | |
| 13 | MZ | | | | | | |
| 14 | MZ | | | | | | |
| 15 | MZ | | | | | | |

Card 40----- System Type -----

```

-----OPTIONAL VENTILATION SYSTEM-----
System      Ventil      Fan
Set System  Deck      Cooling Heating Cooling Heating Static
Number Type   Location  SADBVh  SADBVh  Schedule Schedule Pressure
16      MZ
17      MZ
18      MZ
19      MZ
20      SZ

```

Card 41----- Zone Assignment -----

```

System
Set      Ref #1      Ref #2      Ref #3      Ref #4      Ref #5      Ref #6
Number   Begin   End   Begin   End   Begin   End   Begin   End   Begin   End   Begin   End
1         5       5
2        10      10
3        15      15
4        20      20
5        25      25
6        30      30
7        35      35
8        40      40
9        45      45
10       50      50
11       55      55
12       60      60
13       65      65
14       70      70
15       75      75
16       80      80
17       85      85
18       90      90
19       95      95
20      100     100

```

Card 42----- Fan SP and Duct Parameters-----

```

System Cool Heat Return Mn Exh Aux Rm Exh Cool Return Supply Supply Return
Set Fan Fan Fan Fan Fan Fan Fan Mtr Fan Mtr Duct Duct Air
Number SP SP SP SP SP SP Loc Loc Ht Gn Loc Path
1      1
2      1
3     2.25
4     2.25
5     1.5
6     1.4
7     1.4

```

Card 42----- Fan SP and Duct Parameters-----

| System | Cool | Heat | Return | Mn Exh | Aux | Rm Exh | Cool | Return | Supply | Supply | Return |
|--------|------|------|--------|--------|-----|--------|---------|---------|--------|--------|--------|
| Set | Fan | Fan | Fan | Fan | Fan | Fan | Fan Mtr | Fan Mtr | Duct | Duct | Air |
| Number | SP | SP | SP | SP | SP | SP | Loc | Loc | Ht Gn | Loc | Path |
| 8 | .5 | | | | | | | | | | |
| 9 | 1.4 | | | | | | | | | | |
| 10 | 1.4 | | | | | | | | | | |
| 11 | 1.4 | | | | | | | | | | |
| 12 | 1.4 | | | | | | | | | | |
| 13 | 1.5 | | | | | | | | | | |
| 14 | 1.5 | | | | | | | | | | |
| 15 | 1 | | | | | | | | | | |
| 16 | 1 | | | | | | | | | | |
| 17 | 1 | | | | | | | | | | |
| 18 | 2.5 | | | | | | | | | | |
| 19 | 2.5 | | | | | | | | | | |
| 20 | 1.0 | 1.0 | | | | | | | | | |

Card 45----- Equipment Schedules -----

| System | Main | Direct | Indirect | Auxiliary | Main | Main | | | Auxiliary |
|--------|----------|------------|----------|-----------|----------|----------|----------|----------|-----------|
| Set | Cooling | Evap | Evap | Cooling | Heating | Preheat | Reheat | Mech. | Heating |
| Number | Coil | Economizer | Coil | Coil | Coil | Coil | Coil | Humidity | Coil |
| 1 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 2 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 3 | OFF | | | | OFF | OFF | OFF | | |
| 4 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 5 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 6 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 7 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 8 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 9 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 10 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 11 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 12 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 13 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 14 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 15 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 16 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 17 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 18 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 19 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |
| 20 | FTSAMCLG | | | | FTSAMHTG | FTSAMHTG | FTSAMHTG | | |

----- Equipment Section Alternative #1 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative Number | Elec Consump Time of Day Schedule | Elec Demand Time of Day Schedule | Demand Limit Max KW | Alternative Description | ---- Demand Limit ---- Temperature Schedule | Drift |
|--------------------|---|--|---------------------------|-------------------------|---|-------|
| 1 | | | | BASE CASE | | |

Card 60----- Cooling Load Assignment-----

| Load Ref | All Coil Ref | Cooling Equipment Sizing | -Group 1- Begin End | -Group 2- Begin End | -Group 3- Begin End | -Group 4- Begin End | -Group 5- Begin End | -Group 6- Begin End | -Group 7- Begin End | -Group 8- Begin End | -Group 9- Begin End |
|----------|--------------|--------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|
| 1 | 1 | BLKPLANT | 1 1 | | | | | | | | |
| 2 | 2 | BLKPLANT | 2 2 | 15 15 | | | | | | | |
| 3 | 3 | BLKPLANT | 3 3 | | | | | | | | |
| 4 | 4 | BLKPLANT | 4 4 | | | | | | | | |
| 5 | 5 | BLKPLANT | 5 5 | 17 17 | | | | | | | |
| 6 | 6 | BLKPLANT | 6 6 | | | | | | | | |
| 7 | 7 | BLKPLANT | 7 7 | | | | | | | | |
| 8 | 9 | BLKPLANT | 8 8 | | | | | | | | |
| 9 | 10 | BLKPLANT | 9 9 | | | | | | | | |
| 10 | 11 | BLKPLANT | 10 11 | | | | | | | | |
| 11 | 12 | BLKPLANT | 12 12 | | | | | | | | |
| 12 | 13 | BLKPLANT | 13 13 | | | | | | | | |
| 13 | 14 | BLKPLANT | 14 14 | | | | | | | | |
| 14 | 15 | BLKPLANT | 16 16 | | | | | | | | |
| 15 | 16 | BLKPLANT | 18 19 | | | | | | | | |
| 16 | 17 | BLKPLANT | 20 20 | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Ref | Cool Equip Code | Num Of | -----COOLING----- | | | | -----HEAT RECOVERY----- | | | | Seq Order | Demand Seq Limit | |
|-----|-----------------|--------|-------------------|-------|----------------|-------|-------------------------|-------|----------------|-------|-----------|------------------|--------|
| | | | --Capacity-- | | ----Energy---- | | --Capacity-- | | ----Energy---- | | | | |
| Num | Name | Units | Value | Units | Value | Units | Value | Units | Value | Units | Num | Type | Number |
| 1 | 100ACREC | 1 | 40 | TONS | 70.4 | KW | | | | | | | |
| 2 | 100ACREC | 1 | 50 | TONS | 88 | KW | | | | | | | |
| 3 | 100ACREC | 1 | 40 | TONS | 70.4 | KW | | | | | | | |
| 4 | 100ACREC | 1 | 25 | TONS | 44 | KW | | | | | | | |
| 5 | 100ACREC | 1 | 30 | TONS | 52.8 | KW | | | | | | | |
| 6 | 100ACREC | 1 | 45 | TONS | 79.2 | KW | | | | | | | |
| 7 | 100ACREC | 1 | 45 | TONS | 79.2 | KW | | | | | 1 | PAR | |
| 8 | EQ1161 | 1 | 4 | TONS | 5.81 | KW | | | | | 2 | PAR | |
| 9 | EQ1161 | 1 | 46 | TONS | 67.6 | KW | | | | | | | |
| 10 | 100ACREC | 1 | 40 | TONS | 70.4 | KW | | | | | | | |
| 11 | 100ACREC | 1 | 50 | TONS | 88 | KW | | | | | | | |
| 12 | 100ACREC | 1 | 50 | TONS | 88 | KW | | | | | | | |
| 13 | 100ACREC | 1 | 10 | TONS | 17.6 | KW | | | | | | | |
| 14 | 100ACREC | 1 | 15 | TONS | 26.4 | KW | | | | | | | |
| 15 | EQ1161 | 1 | 4.5 | TONS | 8.48 | KW | | | | | | | |
| 16 | 100ACREC | 1 | 100 | TONS | 176 | KW | | | | | | | |
| 17 | 100ACREC | 1 | 10 | TONS | 17.6 | KW | | | | | | | |

Card 63----- Cooling Pumps and References -----

| Cool | ---CHILLED WATER--- | -----CONDENSER----- | ---HT REC or AUX--- | Switch- |
|-------|---------------------|---------------------|---------------------|-----------|
| Ref | Full Load | Full Load | Full Load | Full Load |
| Value | Units | Value | Units | Value |
| 1 | 2.24 | KW | | |
| 2 | 2.24 | KW | | |
| 3 | 1.12 | KW | | |
| 4 | 1.12 | KW | | |
| 5 | .37 | KW | | |
| 6 | 2.24 | KW | | |
| 7 | 2.24 | KW | | |
| 10 | 1.12 | KW | | |
| 11 | 3.73 | KW | | |
| 12 | 1.49 | KW | | |
| 13 | 1.12 | KW | | |
| 14 | 1.49 | KW | | |
| 16 | 5.6 | KW | | |
| 17 | .75 | KW | | |

Card 65----- Heating Load Assignment -----

| Load | All Coil | -Group 1- | -Group 2- | -Group 3- | -Group 4- | -Group 5- | -Group 6- | -Group 7- | -Group 8- | -Group 9- |
|------------|-------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Assignment | Loads To | Begin | End | Begin | End | Begin | End | Begin | End | Begin |
| Reference | Heating Ref | Begin | End | Begin | End | Begin | End | Begin | End | Begin |
| 1 | 1 | 1 | 1 | | | | | | | |
| 2 | 2 | 2 | 2 | 15 | 15 | | | | | |
| 3 | 3 | 3 | 3 | | | | | | | |
| 4 | 4 | 4 | 4 | | | | | | | |
| 5 | 5 | 5 | 5 | 17 | 17 | | | | | |
| 6 | 6 | 6 | 6 | | | | | | | |
| 7 | 7 | 7 | 7 | | | | | | | |
| 8 | 8 | 8 | 8 | | | | | | | |
| 9 | 9 | 9 | 9 | | | | | | | |
| 10 | 10 | 10 | 10 | | | | | | | |
| 11 | 11 | 11 | 11 | | | | | | | |
| 12 | 12 | 12 | 12 | | | | | | | |
| 13 | 13 | 13 | 13 | | | | | | | |
| 14 | 14 | 14 | 14 | | | | | | | |
| 15 | 15 | 16 | 16 | | | | | | | |
| 16 | 16 | 18 | 19 | | | | | | | |
| 17 | 18 | 20 | 20 | | | | | | | |

Card 67----- Heating Equipment Parameters -----

| Heat | Equip | Number | HW Pmp | Energy | Seq | Switch | Hot | Misc. | Demand |
|--------|----------|--------|---------|--------|-------|--------|-------|-------|--------|
| Ref | Code | Of | Full Ld | Cap'y | Rate | Order | over | Acc. | Limit |
| Number | Name | Units | Value | Units | Value | Units | Value | Units | Number |
| 1 | BOILERWT | 1 | 1.12 | KW | 618 | MBH | 850 | MBH | 2 |
| 2 | BOILERWT | 1 | 1.12 | KW | 618 | MBH | 850 | MBH | 4 |
| 3 | BOILERWT | 1 | 0.37 | KW | 109 | MBH | 150 | MBH | |
| 4 | BOILERWT | 1 | .37 | KW | 109 | MBH | 150 | MBH | 1 |
| 5 | BOILERWT | 1 | .37 | KW | 596 | MBH | 820 | MBH | |

Card 67----- Heating Equipment Parameters -----

| Heat Ref | Equip Code | Number Of | HW Pmp Full Ld | Cap'y | Energy Rate | Seq Order | Switch over | Hot Strg | Misc. Acc. | Cogen | Demand Limit |
|----------|------------|-----------|----------------|-------|-------------|-----------|-------------|----------|------------|-------|--------------|
| Number | Name | Units | Value | Units | Value | Units | Value | Units | | | Number |
| 6 | BOILERWT | 1 | .75 | KW | 596 | MBH | 820 | MBH | | | |
| 7 | BOILERWT | 1 | .75 | KW | 596 | MBH | 820 | MBH | | | |
| 8 | EQ2454 | 1 | | | 515.2 | MBH | 53.59 | KW | | | |
| 9 | BOILERWT | 1 | .75 | KW | 596 | MBH | 820 | MBH | | | |
| 10 | BOILERWT | 1 | .75 | KW | 596 | MBH | 820 | MBH | | | |
| 11 | BOILERWT | 1 | .75 | KW | 596 | MBH | 820 | MBH | | | |
| 12 | BOILERWT | 1 | .75 | KW | 1273 | MBH | 1750 | MBH | | | |
| 13 | BOILERWT | 1 | .56 | KW | 327 | MBH | 450 | MBH | | | |
| 14 | BOILERWT | 1 | 1.12 | KW | 145 | MBH | 200 | MBH | | | |
| 15 | EQ2454 | 1 | | | 33 | MBH | 45 | MBH | | | |
| 16 | STEAMBLR | 1 | | | 727 | MBH | 1000 | MBH | | 1 | |
| 17 | STEAMBLR | 1 | | | 727 | MBH | 1000 | MBH | | 2 | |
| 18 | BOILERWT | 1 | .37 | KW | 327 | MBH | 450 | MBH | | | |

Card 71----- Base Utility Parameters -----

| Base Utility Number | Base Utility Description | Hourly Demand Value | Hourly Demand Units | Schedule Code | Energy Type | Equip Reference | Demand Limiting Number | Entering Temp | Leaving Temp |
|---------------------|--------------------------|---------------------|---------------------|---------------|-------------|-----------------|------------------------|---------------|--------------|
| 1 | PIPE-PUMP HT LOS | 1.2 | TONS | FTSAMCLG | CHILL-LD | 1 | | | |
| 2 | PIPE HT LOS | 10.98 | MBH | FTSAMHTG | HOT-LD | 1 | | | |
| 3 | PIPE-PUMP HT LOS | 1.32 | TONS | FTSAMCLG | CHILL-LD | 2 | | | |
| 4 | PIPE HT LOSS | 12.81 | MBH | FTSAMHTG | HOT-LD | 2 | | | |
| 5 | PIPE-PUMP HT LOS | 1.03 | TONS | FTSAMCLG | CHILL-LD | 3 | | | |
| 6 | PIPE HT LOSS | 13.64 | MBH | FTSAMHTG | HOT-LD | 3 | | | |
| 7 | PIPE-PUMP HT LOS | .83 | TONS | FTSAMCLG | CHILL-LD | 4 | | | |
| 8 | PIPE HT LOSS | 10.14 | MBH | FTSAMHTG | HOT-LD | 4 | | | |
| 9 | PIPE-PUMP HT LOS | .89 | TONS | FTSAMCLG | CHILL-LD | 5 | | | |
| 10 | PIPE HT LOSS | 6.67 | MBH | FTSAMHTG | HOT-LD | 5 | | | |
| 11 | PIPE-PUMP HT LOS | 1.4 | TONS | FTSAMCLG | CHILL-LD | 6 | | | |
| 12 | PIPE HT LOS | 10.21 | MBH | FTSAMHTG | HOT-LD | 6 | | | |
| 13 | PIPE-PUMP HT LOS | 1.4 | TONS | FTSAMCLG | CHILL-LD | 7 | | | |
| 14 | PIPE HT LOSS | 10.21 | MBH | FTSAMHTG | HOT-LD | 7 | | | |
| 15 | COMPR HEAT | 1.5 | TONS | FTSAMCLG | CHILL-LD | 9 | | | |
| 16 | REFRIG. HT LOSS | 10.2 | MBH | FTSAMHTG | HOT-LD | 8 | | | |
| 17 | PIPE-PUMP HT LOS | 1.09 | TONS | FTSAMCLG | CHILL-LD | 10 | | | |
| 18 | PIPE HT LOSS | 10.21 | MBH | FTSAMHTG | HOT-LD | 9 | | | |
| 19 | PIPE-PUMP HT LOS | 1.98 | TONS | FTSAMCLG | CHILL-LD | 11 | | | |
| 20 | PIPE HT LOSS | 10.07 | MBH | FTSAMHTG | HOT-LD | 10 | | | |
| 21 | PIPE HT LOSS | 10.07 | MBH | FTSAMHTG | HOT-LD | 11 | | | |
| 22 | PIPE-PUMP HT LOS | 1.14 | TONS | FTSAMCLG | CHILL-LD | 12 | | | |
| 23 | PIPE HT LOSS | 9.12 | MBH | FTSAMHTG | HOT-LD | 12 | | | |
| 24 | PIPE-PUMP HT LOS | .53 | TONS | FTSAMCLG | CHILL-LD | 13 | | | |
| 25 | PIPE HT LOSS | 3.03 | MBH | FTSAMHTG | HOT-LD | 13 | | | |
| 26 | PIPE-PUMP HT LOS | 0.72 | TONS | FTSAMCLG | CHILL-LD | 14 | | | |
| 27 | PIPE HT LOSS | 5.5 | MBH | FTSAMHTG | HOT-LD | 14 | | | |

Card 71----- Base Utility Parameters -----

| Base Utility Number | Base Utility Descrip | Hourly Demand Value | Hourly Demand Units | Schedule Code | Energy Type | Equip Reference Number | Demand Limiting Number | Entering Temp | Leaving Temp |
|---------------------------|----------------------------|---------------------------|---------------------------|------------------|----------------|------------------------------|------------------------------|------------------|-----------------|
| 28 | PIPE HT LOSS | .11 | TONS | FTSAMCLG | CHILL-LD | 15 | | | |
| 29 | PIPE HT LOSS | 1.83 | MBH | FTSAMHTG | HOT-LD | 15 | | | |
| 30 | PIPE-PUMP HT LOS | 3 | TONS | FTSAMCLG | CHILL-LD | 16 | | | |
| 31 | PIPE HT LOSS | 22.8 | MBH | FTSAMHTG | HOT-LD | 16 | | | |
| 32 | PIPE-PUMP HT LOS | .39 | TONS | FTSAMCLG | CHILL-LD | 17 | | | |
| 33 | PIPE HT LOSS | 3.32 | MBH | FTSAMHTG | HOT-LD | 18 | | | |

Card 75----- Miscellaneous Accessory -----

| #1 | | | | | #2 | | | | | #3 | | | | |
|-------------|---------------|-----------------|-----------------|---------------|---------------|-----------------|-----------------|---------------|---------------|-----------------|-----------------|---------------|--|--|
| Misc Ref | Equip Code | Energy Value | Energy Units | Sched Code | Equip Code | Energy Value | Energy Units | Sched Code | Equip Code | Energy Value | Energy Units | Sched Code | | |
| 1 | EQ5240 | 3.73 | KW | | | | | | | | | | | |
| 2 | EQ5020 | 1.12 | KW | | | | | | | | | | | |
| 3 | EQ5001 | 2.24 | KW | | | | | | | | | | | |
| 4 | EQ5020 | 1.12 | KW | | | | | | | | | | | |
| 5 | EQ5001 | 2.24 | KW | | | | | | | | | | | |

----- Equipment Section Alternative #2 -----

Card 59----- Equipment Description / TOD Schedules -----

| Alternative Number | Elec Consump Time of Day Schedule | Elec Demand Time of Day Schedule | Demand Limit Max KW | Alternative Description | Temperature Drift |
|-----------------------|---|--|---------------------------|----------------------------------|----------------------|
| 2 | | | | AIR COOLED SINGLE SCREW CHILLERS | |

Card 60----- Cooling Load Assignment-----

| Load | All Coil | Cooling | | | | | | | | | | |
|----------|-------------------|------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|------------------------|--|
| Asgn Ref | Loads To Cool Ref | Equipment Sizing | -Group 1- Begin End | -Group 2- Begin End | -Group 3- Begin End | -Group 4- Begin End | -Group 5- Begin End | -Group 6- Begin End | -Group 7- Begin End | -Group 8- Begin End | -Group 9- Begin End | |
| 1 | 1 | BLKPLANT | 1 | 20 | | | | | | | | |

Card 62----- Cooling Equipment Parameters -----

| Cool Ref | Equip Code | Num Of | -----COOLING----- | | | | -----HEAT RECOVERY----- | | | | Seq Order | Demand Seq Limit |
|-------------|---------------|-----------|-----------------------|-------|-------|-------|-------------------------|-------|-------|-------|--------------|---------------------|
| | | | --Capacity-- Value | Units | Value | Units | --Capacity-- Value | Units | Value | Units | | |
| 1 | EQ1510 | 1 | 210 | TONS | 240 | KW | | | | | 1 | PAR |
| 2 | EQ1510 | 1 | 210 | TONS | 240 | KW | | | | | 2 | PAR |

Card 63----- Cooling Pumps and References -----
Cool ---CHILLED WATER--- ---CONDENSER--- ---HT REC or AUX--- Switch-
Ref Full Load Full Load Full Load Full Load Full Load Full Load over Cold Cooling Misc.
Num Value Units Value Units Value Units Control Storage Tower Access.
1 22.38 KW 1
2 22.38 KW 1

Card 71----- Base Utility Parameters -----
Base Base Hourly Hourly Equip Demand
Utility Utility Demand Demand Schedule Energy Reference Limiting Entering Leaving
Number Descrip Value Units Code Type Number Number Temp Temp
1 PIPE-PUMP LOSS 18.53 TONS FTSAMCLG CHILL-LD 1

Card 74----- Condenser / Cooling Tower Parameters -----
Cooling Tower Tower Capacity Capacity Energy Energy Number Percent Low Spd Low Spd
Ref Code Value Units Consump Consump Fluid Tower Of Airflow Energy Energy
1 EQ5200 0 KW

----- Equipment Section Alternative #3 -----

Card 59----- Equipment Description / TOD Schedules -----
Elec Consump Elec Demand Demand --- Demand Limit ---
Alternative Time of Day Time of Day Limit Temperature
Number Schedule Schedule Max KW Alternative Description Schedule Drift
3 NATURAL DRAFT WATER TUBE BOILERS

Card 65----- Heating Load Assignment -----
Load All Coil
Assignment Loads To -Group 1- -Group 2- -Group 3- -Group 4- -Group 5- -Group 6- -Group 7- -Group 8- -Group 9-
Reference Heating Ref Begin End Begin End Begin End Begin End Begin End Begin End Begin End Begin End
1 1 1 20

Card 67----- Heating Equipment Parameters -----
Heat Equip Number HW Pmp Energy Seq Switch Demand
Ref Code Of Full Ld Cap'y Rate Order over Hot Misc. Limit
Number Name Units Value Units Value Units Value Units Number Control Strg Acc. Cogen Number
1 BOILERWT 1 7.46 KW 563 MBH 750 MBH 1 1
2 BOILERWT 1 11.19 KW 1250 MBH 1666 MBH 2 1

Card 71----- Base Utility Parameters -----

| Base | Base | Hourly | Hourly | | | Equip | Demand | | |
|---------|--------------|--------|--------|----------|--------|-----------|----------|----------|---------|
| Utility | Utility | Demand | Demand | Schedule | Energy | Reference | Limiting | Entering | Leaving |
| Number | Descrip | Value | Units | Code | Type | Number | Number | Temp | Temp |
| 1 | PIPE HT LOSS | 49.92 | MBH | FTSAMHTG | HOT-LD | 1 | | | |
| 2 | PIPE HT LOSS | 110.89 | MBH | FTSAMHTG | HOT-LD | 2 | | | |

Card 72-- Switchover Controls -----

| | | | Outside | |
|-----------|-------|-------|---------|-------|
| Control | Load | Load | Air | Sched |
| Reference | Value | Units | DB | Code |
| 1 | 750 | MBH | | |

Utility Description Reference Table

Schedules:

FSHBARRL F.S.H. BARRACKS LIGHT/MISC. SCHEDULE
FSHBARRP F.S.H. BARRACKS PEOPLE SCHEDULE
FSHOFFIC F.S.H. OFFICE INTERNAL LOAD SCHEDULE
FTSAMCLG EEAP BOILER/CHILLER STUDY
FTSAMHTG EEAP BOILER/CHILLER STUDY
OFF ALWAYS OFF

System:

MZ MULTIZONE
SZ SINGLE ZONE

Equipment:

Cooling:

100ACREC AREA 100 EXIST AIR COOLED RECIP CHILLR
EQ1161 AIR COOLED COND COMP < 15 TONS
EQ1510 AIR COOLED SERIES R (RTAA)

Heating:

BOILERWT WATERTUBE BOILER
EQ2454 RESIDENTIAL GAS FURNACE WITH FAN
STEAMBLR GAS FIRED STEAM BOILER

Tower:

EQ5200 CONDENSER FANS

Misc:

EQ5001 CHILLED WATER PUMP - CONSTANT VOLUME
EQ5020 HEATING WATER CIRCULATION PUMP
EQ5240 BOILER FORCED DRAFT FAN

**
** TRACE 600 ANALYSIS **
**
** by HUITT & ZOLLARS **
**

030185.04 EEAP BOILER-CHILLER STUDY
FT. SAM HOUSTON - SAN ANTONIO, TX.
CORPS. OF ENGINEERS - FORT WORTH, TX.
HUITT-ZOLLARS INC.

AREA 100

Weather File Code:

Location: SAN ANTONIO, TEXAS
Latitude: 29.0 (deg)
Longitude: 98.0 (deg)
Time Zone: 6
Elevation: 792 (ft)
Barometric Pressure: 29.0 (in. Hg)

Summer Clearness Number: 0.90
Winter Clearness Number: 0.90
Summer Design Dry Bulb: 97 (F)
Summer Design Wet Bulb: 76 (F)
Winter Design Dry Bulb: 30 (F)
Summer Ground Relectance: 0.20
Winter Ground Relectance: 0.20

Air Density: 0.0738 (Lbm/cuft)
Air Specific Heat: 0.2444 (Btu/lbm/F)
Density-Specific Heat Prod: 1.0818 (Btu-min./hr/cuft/F)
Latent Heat Factor: 4,761.9 (Btu-min./hr/cuft)
Enthalpy Factor: 4.4255 (Lb-min./hr/cuft)

Design Simulation Period: June To November
System Simulation Period: January To December
Cooling Load Methodology: TETD/Time Averaging

Time/Date Program was Run: 12:36: 0 6/12/95
Dataset Name: FSH100 .TM

SYSTEM TOTALS LOAD PROFILE - ALTERNATIVE 1
AREA 100 EXISTING SYSTEMS

----- SYSTEM LOAD PROFILE -----

System Totals

| Percent Design Load | ---- Cooling Load ---- | | | ----- Heating Load ----- | | |
|---------------------------|------------------------|--------------|-------|--------------------------|--------------|-------|
| | Cap. (Ton) | Hours (%) | Hours | Capacity (Btuh) | Hours (%) | Hours |
| 0 - 5 | 25.3 | 8 | 360 | -162,580 | 43 | 972 |
| 5 - 10 | 50.5 | 12 | 510 | -325,160 | 29 | 650 |
| 10 - 15 | 75.8 | 11 | 495 | -487,740 | 8 | 176 |
| 15 - 20 | 101.1 | 8 | 347 | -650,319 | 5 | 106 |
| 20 - 25 | 126.3 | 7 | 290 | -812,899 | 3 | 64 |
| 25 - 30 | 151.6 | 7 | 325 | -975,479 | 3 | 68 |
| 30 - 35 | 176.9 | 7 | 298 | -1,138,059 | 3 | 73 |
| 35 - 40 | 202.1 | 8 | 351 | -1,300,639 | 3 | 62 |
| 40 - 45 | 227.4 | 7 | 297 | -1,463,218 | 2 | 53 |
| 45 - 50 | 252.6 | 7 | 298 | -1,625,798 | 1 | 29 |
| 50 - 55 | 277.9 | 4 | 194 | -1,788,378 | 0 | 0 |
| 55 - 60 | 303.2 | 4 | 169 | -1,950,958 | 0 | 0 |
| 60 - 65 | 328.4 | 3 | 149 | -2,113,538 | 0 | 0 |
| 65 - 70 | 353.7 | 4 | 171 | -2,276,118 | 0 | 0 |
| 70 - 75 | 379.0 | 1 | 22 | -2,438,698 | 0 | 0 |
| 75 - 80 | 404.2 | 2 | 86 | -2,601,278 | 0 | 0 |
| 80 - 85 | 429.5 | 0 | 0 | -2,763,858 | 0 | 0 |
| 85 - 90 | 454.8 | 0 | 0 | -2,926,437 | 0 | 0 |
| 90 - 95 | 480.0 | 0 | 0 | -3,089,017 | 0 | 0 |
| 95 - 100 | 505.3 | 0 | 0 | -3,251,597 | 0 | 0 |
| Hours Off | 0.0 | 0 | 4,398 | 0 | 0 | 6,507 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
JE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|----------|---------------------|-------|--------|-------|--------|--------|-------|--------|-------|--------|-------|-------|-----------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 99030 | 89550 | 105452 | 94800 | 102241 | 101222 | 95819 | 105452 | 94800 | 102241 | 94800 | 95819 | 1,181,224 |
| | PK | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 893 | 864 | 893 | 893 | 864 | 893 | 0 | 0 | 5,299 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.2 | 1.2 | 1.2 | 1.2 | 1.2 | 1.2 | 0.0 | 0.0 | 1.2 |
| 2 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 82 | 74 | 82 | 79 | 0 | 0 | 0 | 0 | 0 | 0 | 79 | 82 | 477 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 3 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 982 | 950 | 982 | 982 | 950 | 982 | 0 | 0 | 5,829 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.3 | 1.3 | 1.3 | 1.3 | 1.3 | 1.3 | 0.0 | 0.0 | 1.3 |
| 4 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 95 | 86 | 95 | 92 | 0 | 0 | 0 | 0 | 0 | 0 | 92 | 95 | 556 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | | |
|------------------------------|---------------|---------------------|-----|-----|-----|------|------|------|------|------|------|-----|-----|-------|
| Ref Num | Equip Code | Monthly Consumption | | | | | | | | | | | | Total |
| | | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 5 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 766 | 742 | 766 | 766 | 742 | 766 | 0 | 0 | 4,548 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 6 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 101 | 92 | 101 | 98 | 0 | 0 | 0 | 0 | 0 | 0 | 98 | 101 | 593 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 7 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 618 | 598 | 618 | 618 | 598 | 618 | 0 | 0 | 3,665 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.8 | 0.8 | 0.8 | 0.8 | 0.8 | 0.8 | 0.0 | 0.0 | 0.8 |
| 8 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 75 | 68 | 75 | 73 | 0 | 0 | 0 | 0 | 0 | 0 | 73 | 75 | 440 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 9 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 662 | 641 | 662 | 662 | 641 | 662 | 0 | 0 | 3,930 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.9 | 0.9 | 0.9 | 0.9 | 0.9 | 0.9 | 0.0 | 0.0 | 0.9 |
| 10 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 50 | 45 | 50 | 48 | 0 | 0 | 0 | 0 | 0 | 0 | 48 | 50 | 290 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 11 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 1042 | 1008 | 1042 | 1042 | 1008 | 1042 | 0 | 0 | 6,182 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.4 | 1.4 | 1.4 | 1.4 | 1.4 | 1.4 | 0.0 | 0.0 | 1.4 |
| 12 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 76 | 69 | 76 | 74 | 0 | 0 | 0 | 0 | 0 | 0 | 74 | 76 | 444 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 13 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 1042 | 1008 | 1042 | 1042 | 1008 | 1042 | 0 | 0 | 6,182 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.4 | 1.4 | 1.4 | 1.4 | 1.4 | 1.4 | 0.0 | 0.0 | 1.4 |
| 14 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 76 | 69 | 76 | 74 | 0 | 0 | 0 | 0 | 0 | 0 | 74 | 76 | 444 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 15 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 1116 | 1080 | 1116 | 1116 | 1080 | 1116 | 0 | 0 | 6,624 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 0.0 | 0.0 | 1.5 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|---------------------|-----|-----|-----|------|------|------|------|------|------|-----|-----|-------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 16 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 76 | 69 | 76 | 73 | 0 | 0 | 0 | 0 | 0 | 0 | 73 | 76 | 443 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 17 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 811 | 785 | 811 | 811 | 785 | 811 | 0 | 0 | 4,813 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 | 1.1 |
| 18 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 76 | 69 | 76 | 74 | 0 | 0 | 0 | 0 | 0 | 0 | 74 | 76 | 444 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 19 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 1473 | 1426 | 1473 | 1473 | 1426 | 1473 | 0 | 0 | 8,744 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | 0.0 | 0.0 | 2.0 |
| 20 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 75 | 68 | 75 | 73 | 0 | 0 | 0 | 0 | 0 | 0 | 73 | 75 | 437 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 21 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 75 | 68 | 75 | 73 | 0 | 0 | 0 | 0 | 0 | 0 | 73 | 75 | 437 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 22 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 848 | 821 | 848 | 848 | 821 | 848 | 0 | 0 | 5,034 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 | 1.1 |
| 23 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 68 | 61 | 68 | 66 | 0 | 0 | 0 | 0 | 0 | 0 | 66 | 68 | 396 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 24 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 394 | 382 | 394 | 394 | 382 | 394 | 0 | 0 | 2,340 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.5 | 0.5 | 0.5 | 0.5 | 0.5 | 0.5 | 0.0 | 0.0 | 0.5 |
| 25 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 23 | 20 | 23 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 22 | 23 | 132 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 26 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 536 | 518 | 536 | 536 | 518 | 536 | 0 | 0 | 3,180 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.7 | 0.7 | 0.7 | 0.7 | 0.7 | 0.7 | 0.0 | 0.0 | 0.7 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|------|-----|-----|--------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 27 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 41 | 37 | 41 | 40 | 0 | 0 | 0 | 0 | 0 | 0 | 40 | 41 | 239 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 28 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 82 | 79 | 82 | 82 | 79 | 82 | 0 | 0 | 486 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.1 |
| 29 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 14 | 12 | 14 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 13 | 14 | 79 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 30 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 2232 | 2160 | 2232 | 2232 | 2160 | 2232 | 0 | 0 | 13,248 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 0.0 | 0.0 | 3.0 |
| 31 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 170 | 153 | 170 | 164 | 0 | 0 | 0 | 0 | 0 | 0 | 164 | 170 | 990 |
| | PK | 0.2 | 0.2 | 0.2 | 0.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.2 | 0.2 | 0.2 |
| 32 | | BASE UTILITY | | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 290 | 281 | 290 | 290 | 281 | 290 | 0 | 0 | 1,722 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.4 | 0.4 | 0.4 | 0.4 | 0.4 | 0.4 | 0.0 | 0.0 | 0.4 |
| 33 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 25 | 22 | 25 | 24 | 0 | 0 | 0 | 0 | 0 | 0 | 24 | 25 | 144 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 12971 | 17212 | 21161 | 21472 | 14265 | 5314 | 0 | 0 | 92,395 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 47.5 | 53.0 | 56.9 | 56.3 | 47.8 | 35.0 | 0.0 | 0.0 | 56.9 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1667 | 1613 | 1667 | 1667 | 1613 | 1667 | 0 | 0 | 9,892 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 0.0 | 0.0 | 2.2 |
| 1 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1667 | 1613 | 1667 | 1667 | 1613 | 1667 | 0 | 0 | 9,892 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 0.0 | 0.0 | 2.2 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | |
|------------------------------|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|------|-----|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| Total | | | | | | | | | | | | | |
| 2 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 16071 | 21001 | 25828 | 26166 | 17429 | 6417 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 58.3 | 64.4 | 69.1 | 68.0 | 57.9 | 42.2 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 112,912 |
| | | | | | | | | | | | | | 69.1 |
| 2 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1667 | 1613 | 1667 | 1667 | 1613 | 1667 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 9,892 |
| | | | | | | | | | | | | | 2.2 |
| 2 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | 1.0 |
| 2 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1667 | 1613 | 1667 | 1667 | 1613 | 1667 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 9,892 |
| | | | | | | | | | | | | | 2.2 |
| 3 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1988 | 1982 | 2111 | 2106 | 1941 | 1917 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 28.4 | 29.7 | 30.8 | 30.6 | 28.6 | 26.3 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 12,045 |
| | | | | | | | | | | | | | 30.8 |
| 3 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 833 | 806 | 833 | 833 | 806 | 833 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,946 |
| | | | | | | | | | | | | | 1.1 |
| 3 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | 1.0 |
| 4 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 11076 | 14142 | 17246 | 17487 | 12190 | 4633 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 37.5 | 42.4 | 44.8 | 44.4 | 38.6 | 27.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 76,773 |
| | | | | | | | | | | | | | 44.8 |
| 4 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 833 | 806 | 833 | 833 | 806 | 833 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,946 |
| | | | | | | | | | | | | | 1.1 |
| 4 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | 1.0 |
| 5 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 15584 | 18461 | 21788 | 22374 | 16854 | 8963 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 49.6 | 51.8 | 53.8 | 53.3 | 49.8 | 45.5 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 104,024 |
| | | | | | | | | | | | | | 53.8 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | |
|------------------------------|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|------|-----|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| Total | | | | | | | | | | | | | |
| 5 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 275 | 266 | 275 | 275 | 266 | 275 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.4 | 0.4 | 0.4 | 0.4 | 0.4 | 0.4 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 1,634 |
| | | | | | | | | | | | | | 0.4 |
| 5 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | 1.0 |
| 6 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 16505 | 20599 | 24401 | 25104 | 18009 | 9158 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 61.4 | 66.6 | 71.5 | 72.2 | 62.9 | 49.7 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 113,775 |
| | | | | | | | | | | | | | 72.2 |
| 6 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1667 | 1613 | 1667 | 1667 | 1613 | 1667 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 9,892 |
| | | | | | | | | | | | | | 2.2 |
| 6 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | 1.0 |
| 7 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 16505 | 20599 | 24401 | 25104 | 18009 | 9158 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 61.4 | 66.6 | 71.5 | 72.2 | 62.9 | 49.7 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 113,775 |
| | | | | | | | | | | | | | 72.2 |
| 7 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1667 | 1613 | 1667 | 1667 | 1613 | 1667 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 9,892 |
| | | | | | | | | | | | | | 2.2 |
| 7 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | 1.0 |
| 8 | EQ1161 | AIR COOLED COND COMP < 15 TONS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 0 |
| | | | | | | | | | | | | | 0.0 |
| 8 | EQ5200 | CONDENSER FANS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 0 |
| | | | | | | | | | | | | | 0.0 |
| 8 | EQ5303 | CONTROLS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 0 |
| | | | | | | | | | | | | | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| 9 | EQ1161 | AIR COOLED COND COMP < 15 TONS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 9349 | 11812 | 14056 | 14784 | 10019 | 4806 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 63.6 | 66.4 | 68.8 | 68.3 | 63.8 | 58.9 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 64,825 |
| | | | | | | | | | | | | | 68.8 |
| 9 | EQ5200 | CONDENSER FANS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 910 | 1147 | 1607 | 1421 | 987 | 452 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 4.5 | 4.8 | 6.2 | 6.2 | 4.6 | 3.6 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 6,524 |
| | | | | | | | | | | | | | 6.2 |
| 9 | EQ5303 | CONTROLS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 223 | 216 | 223 | 223 | 216 | 223 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.3 | 0.3 | 0.3 | 0.3 | 0.3 | 0.3 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 1,325 |
| | | | | | | | | | | | | | 0.3 |
| 10 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 15535 | 19517 | 23118 | 23816 | 17025 | 8376 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 59.0 | 64.1 | 68.9 | 69.7 | 60.6 | 47.5 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 107,387 |
| | | | | | | | | | | | | | 69.7 |
| 10 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 833 | 806 | 833 | 833 | 806 | 833 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,946 |
| | | | | | | | | | | | | | 1.1 |
| 10 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | 1.0 |
| 11 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 25325 | 31101 | 37574 | 37169 | 27737 | 11449 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 70.0 | 76.4 | 85.0 | 83.4 | 74.2 | 56.3 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 170,355 |
| | | | | | | | | | | | | | 85.0 |
| 11 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 2775 | 2686 | 2775 | 2775 | 2686 | 2775 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 16,472 |
| | | | | | | | | | | | | | 3.7 |
| 11 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | 1.0 |
| 12 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 16906 | 20372 | 24091 | 24748 | 17920 | 9344 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 60.4 | 65.5 | 70.3 | 70.6 | 61.9 | 49.6 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 113,383 |
| | | | | | | | | | | | | | 70.6 |
| 12 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1109 | 1073 | 1109 | 1109 | 1073 | 1109 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 6,580 |
| | | | | | | | | | | | | | 1.5 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|---------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| 12 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | |
| 13 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 4477 | 5511 | 6556 | 6721 | 4884 | 2466 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 16.1 | 17.3 | 17.9 | 17.8 | 16.6 | 12.9 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 30,616 |
| | | | | | | | | | | | | | |
| 13 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 833 | 806 | 833 | 833 | 806 | 833 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,946 |
| | | | | | | | | | | | | | |
| 13 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | |
| 14 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 6115 | 7877 | 9643 | 9951 | 6902 | 2830 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 21.6 | 23.9 | 26.2 | 26.6 | 22.6 | 16.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 43,319 |
| | | | | | | | | | | | | | |
| 14 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1109 | 1073 | 1109 | 1109 | 1073 | 1109 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 6,580 |
| | | | | | | | | | | | | | |
| 14 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 4,416 |
| | | | | | | | | | | | | | |
| 15 | EQ1161 | AIR COOLED COND COMP < 15 TONS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 1705 | 2262 | 2879 | 2931 | 1893 | 562 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 8.0 | 8.3 | 8.6 | 8.6 | 8.0 | 7.4 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 12,232 |
| | | | | | | | | | | | | | |
| 15 | EQ5200 | CONDENSER FANS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 140 | 184 | 243 | 238 | 157 | 45 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.6 | 0.7 | 0.7 | 0.7 | 0.6 | 0.4 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 1,008 |
| | | | | | | | | | | | | | |
| 15 | EQ5303 | CONTROLS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 223 | 216 | 223 | 223 | 216 | 223 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.3 | 0.3 | 0.3 | 0.3 | 0.3 | 0.3 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 1,325 |
| | | | | | | | | | | | | | |
| 16 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 55068 | 61582 | 70144 | 71148 | 58363 | 30555 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 117.2 | 122.9 | 133.5 | 137.3 | 118.3 | 87.7 | 0.0 | 0.0 |
| | | | | | | | | | | | | | 346,860 |
| | | | | | | | | | | | | | |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | | |
|--|--------|--|-----|-----|-----|------|------|------|------|------|------|-----|-----|--------|--|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | | |
| | | | | | | | | | | | | | | | |
| 16 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 4166 | 4032 | 4166 | 4166 | 4032 | 4166 | 0 | 0 | 24,730 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | 0.0 | 0.0 | 5.6 | |
| 16 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 | |
| 17 | | AREA 100 EXIST AIR COOLED RECIP CHILLR | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 3737 | 5121 | 6202 | 6182 | 3955 | 1429 | 0 | 0 | 26,626 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 13.8 | 15.3 | 16.5 | 16.7 | 14.0 | 9.8 | 0.0 | 0.0 | 16.7 | |
| 17 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 558 | 540 | 558 | 558 | 540 | 558 | 0 | 0 | 3,312 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.8 | 0.8 | 0.8 | 0.8 | 0.8 | 0.8 | 0.0 | 0.0 | 0.8 | |
| 17 | EQ5300 | CONTROL PANEL & INTERLOCKS | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 744 | 720 | 744 | 744 | 720 | 744 | 0 | 0 | 4,416 | |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 1.0 | 0.0 | 0.0 | 1.0 | |
| 1 | | WATERTUBE BOILER | | | | | | | | | | | | | |
| | GAS | 506 | 499 | 160 | 109 | 0 | 0 | 0 | 0 | 0 | 0 | 172 | 481 | 1,928 | |
| | PK | 1.8 | 2.0 | 1.1 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.0 | 1.8 | 2.0 | |
| 1 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | | |
| | ELEC | 678 | 635 | 484 | 403 | 0 | 0 | 0 | 0 | 0 | 0 | 491 | 687 | 3,377 | |
| | PK | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 | 1.1 | |
| 1 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | | |
| | ELEC | 76 | 71 | 54 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 55 | 77 | 377 | |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 | |
| 1 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | | |
| | ELEC | 833 | 753 | 833 | 806 | 0 | 0 | 0 | 0 | 0 | 0 | 806 | 833 | 4,865 | |
| | PK | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 | 1.1 | |
| 2 | | WATERTUBE BOILER | | | | | | | | | | | | | |
| | GAS | 600 | 578 | 184 | 127 | 0 | 0 | 0 | 0 | 0 | 0 | 203 | 571 | 2,263 | |
| | PK | 2.1 | 2.3 | 1.2 | 0.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.2 | 2.1 | 2.3 | |
| 2 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | | |
| | ELEC | 833 | 753 | 833 | 806 | 0 | 0 | 0 | 0 | 0 | 0 | 806 | 833 | 4,865 | |
| | PK | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 | 1.1 | |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|--------|--------------------------------|------|------|------|-----|------|------|-----|-----|-----|------|------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| 2 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 2 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 833 | 753 | 833 | 806 | 0 | 0 | 0 | 0 | 0 | 0 | 806 | 833 |
| | PK | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 |
| 3 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 140 | 126 | 140 | 135 | 0 | 0 | 0 | 0 | 0 | 0 | 135 | 140 |
| | PK | 0.2 | 0.2 | 0.2 | 0.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.2 | 0.2 |
| 3 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 275 | 249 | 275 | 266 | 0 | 0 | 0 | 0 | 0 | 0 | 266 | 275 |
| | PK | 0.4 | 0.4 | 0.4 | 0.4 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.4 | 0.4 |
| 3 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 4 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 480 | 454 | 137 | 100 | 0 | 0 | 0 | 0 | 0 | 0 | 152 | 447 |
| | PK | 1.5 | 1.5 | 0.9 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.9 | 1.5 |
| 4 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 275 | 249 | 275 | 266 | 0 | 0 | 0 | 0 | 0 | 0 | 266 | 275 |
| | PK | 0.4 | 0.4 | 0.4 | 0.4 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.4 | 0.4 |
| 4 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 4 | EQ5240 | BOILER FORCED DRAFT FAN | | | | | | | | | | | |
| | ELEC | 2775 | 2507 | 2775 | 2686 | 0 | 0 | 0 | 0 | 0 | 0 | 2686 | 2775 |
| | PK | 3.7 | 3.7 | 3.7 | 3.7 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 3.7 | 3.7 |
| 5 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 188 | 172 | 78 | 66 | 0 | 0 | 0 | 0 | 0 | 0 | 79 | 175 |
| | PK | 1.3 | 1.4 | 0.3 | 0.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.3 | 1.3 |
| 5 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 212 | 194 | 148 | 133 | 0 | 0 | 0 | 0 | 0 | 0 | 144 | 208 |
| | PK | 0.4 | 0.4 | 0.4 | 0.4 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.4 | 0.4 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | |
|------------------------------|--------|----------------------------------|------|------|------|-----|------|------|-----|-----|-----|------|------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| 5 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 72 | 66 | 50 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 48 | 70 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 6 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 276 | 273 | 119 | 101 | 0 | 0 | 0 | 0 | 0 | 0 | 112 | 245 |
| | PK | 1.7 | 1.8 | 0.8 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.4 | 1.7 |
| 6 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 360 | 338 | 297 | 270 | 0 | 0 | 0 | 0 | 0 | 0 | 290 | 349 |
| | PK | 0.8 | 0.8 | 0.8 | 0.8 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.8 | 0.8 |
| 6 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 60 | 56 | 49 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 48 | 58 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 7 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 276 | 273 | 119 | 101 | 0 | 0 | 0 | 0 | 0 | 0 | 112 | 245 |
| | PK | 1.7 | 1.8 | 0.8 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.4 | 1.7 |
| 7 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 360 | 338 | 297 | 270 | 0 | 0 | 0 | 0 | 0 | 0 | 290 | 349 |
| | PK | 0.8 | 0.8 | 0.8 | 0.8 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.8 | 0.8 |
| 7 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 60 | 56 | 49 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 48 | 58 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 8 | EQ2454 | RESIDENTIAL GAS FURNACE WITH FAN | | | | | | | | | | | |
| | GAS | 85 | 83 | 37 | 26 | 0 | 0 | 0 | 0 | 0 | 0 | 36 | 78 |
| | PK | 0.5 | 0.5 | 0.3 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.3 | 0.5 |
| 8 | EQ5254 | RESIDENTIAL FURNACE FAN | | | | | | | | | | | |
| | ELEC | 5758 | 5157 | 4670 | 4080 | 0 | 0 | 0 | 0 | 0 | 0 | 4624 | 5713 |
| | PK | 11.3 | 11.3 | 11.3 | 11.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 11.3 | 11.3 |
| 9 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 276 | 273 | 119 | 101 | 0 | 0 | 0 | 0 | 0 | 0 | 112 | 245 |
| | PK | 1.7 | 1.8 | 0.8 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.4 | 1.7 |
| 9 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 360 | 338 | 297 | 270 | 0 | 0 | 0 | 0 | 0 | 0 | 290 | 349 |
| | PK | 0.8 | 0.8 | 0.8 | 0.8 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.8 | 0.8 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| EQUIPMENT ENERGY CONSUMPTION | | | | | | | | | | | | | |
|------------------------------|--------|--------------------------------|-----|-----|-----|-----|------|------|-----|-----|-----|-----|-----|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| 9 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 60 | 56 | 49 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 48 | 58 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 10 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 294 | 306 | 103 | 100 | 0 | 0 | 0 | 0 | 0 | 0 | 100 | 258 |
| | PK | 1.5 | 1.6 | 0.3 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.3 | 1.5 |
| 10 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 466 | 415 | 279 | 270 | 0 | 0 | 0 | 0 | 0 | 0 | 270 | 436 |
| | PK | 0.8 | 0.8 | 0.8 | 0.8 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.8 | 0.8 |
| 10 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 78 | 69 | 47 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 45 | 73 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 11 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 294 | 306 | 103 | 100 | 0 | 0 | 0 | 0 | 0 | 0 | 100 | 258 |
| | PK | 1.5 | 1.6 | 0.3 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.3 | 1.5 |
| 11 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 466 | 415 | 279 | 270 | 0 | 0 | 0 | 0 | 0 | 0 | 270 | 436 |
| | PK | 0.8 | 0.8 | 0.8 | 0.8 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.8 | 0.8 |
| 11 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 78 | 69 | 47 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 45 | 73 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 12 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 219 | 207 | 94 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 91 | 190 |
| | PK | 1.5 | 1.5 | 0.5 | 0.4 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.5 | 1.5 |
| 12 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 240 | 235 | 186 | 180 | 0 | 0 | 0 | 0 | 0 | 0 | 180 | 235 |
| | PK | 0.8 | 0.8 | 0.8 | 0.8 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.8 | 0.8 |
| 12 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 40 | 39 | 31 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 30 | 39 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 13 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 93 | 89 | 37 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 38 | 88 |
| | PK | 0.5 | 0.6 | 0.2 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.2 | 0.5 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|--------|----------------------------------|-----|-----|-----|-----|------|------|-----|-----|-----|-----|-----|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| 13 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 225 | 209 | 157 | 134 | 0 | 0 | 0 | 0 | 0 | 0 | 161 | 219 |
| | PK | 0.6 | 0.6 | 0.6 | 0.6 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.6 | 0.6 |
| | | | | | | | | | | | | | |
| 13 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 50 | 47 | 35 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 36 | 49 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 14 | | WATERTUBE BOILER | | | | | | | | | | | |
| | GAS | 261 | 252 | 82 | 55 | 0 | 0 | 0 | 0 | 0 | 0 | 91 | 252 |
| | PK | 1.0 | 1.0 | 0.6 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.6 | 1.0 |
| 14 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | |
| | ELEC | 833 | 753 | 833 | 806 | 0 | 0 | 0 | 0 | 0 | 0 | 806 | 833 |
| | PK | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 |
| 14 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 15 | EQ2454 | RESIDENTIAL GAS FURNACE WITH FAN | | | | | | | | | | | |
| | GAS | 97 | 91 | 29 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 31 | 92 |
| | PK | 0.3 | 0.3 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.2 | 0.3 |
| 15 | EQ5254 | RESIDENTIAL FURNACE FAN | | | | | | | | | | | |
| | ELEC | 540 | 488 | 540 | 523 | 0 | 0 | 0 | 0 | 0 | 0 | 523 | 540 |
| | PK | 0.7 | 0.7 | 0.7 | 0.7 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.7 | 0.7 |
| 16 | | GAS FIRED STEAM BOILER | | | | | | | | | | | |
| | GAS | 350 | 344 | 233 | 226 | 0 | 0 | 0 | 0 | 0 | 0 | 226 | 339 |
| | PK | 2.2 | 2.3 | 0.3 | 0.3 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.3 | 2.1 |
| 16 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 93 | 84 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 93 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |
| 17 | | GAS FIRED STEAM BOILER | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 17 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 1
BASE CASE

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|---------------------------------|-----|-----|-----|-----|------|------|-----|-----|-----|-----|-----|-------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | Total |
| 18 | | WATERTUBE BOILER | | | | | | | | | | | | |
| | GAS | 149 | 150 | 53 | 33 | 0 | 0 | 0 | 0 | 0 | 0 | 61 | 137 | 583 |
| | PK | 0.6 | 0.6 | 0.3 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.3 | 0.6 | 0.6 |
| 18 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 188 | 182 | 152 | 133 | 0 | 0 | 0 | 0 | 0 | 0 | 162 | 191 | 1,008 |
| | PK | 0.4 | 0.4 | 0.4 | 0.4 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.4 | 0.4 | 0.4 |
| 18 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 63 | 61 | 52 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 55 | 65 | 341 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
AIR COOLED SINGLE SCREW CHILLERS

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|----------|--------------------------------------|-------|--------|-------|--------|--------|--------|--------|-------|--------|-------|-------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| Total | | | | | | | | | | | | | |
| 0 | LIGHTS | | | | | | | | | | | | |
| | ELEC | 99030 | 89550 | 105452 | 94800 | 102241 | 101222 | 95819 | 105452 | 94800 | 102241 | 94800 | 95819 |
| | PK | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 |
| | | | | | | | | | | | | | |
| 1 | MISC LD | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | |
| | P HOTH2O | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | |
| | CHILLD | 0 | 0 | 0 | 0 | 13786 | 13342 | 13786 | 13786 | 13342 | 13786 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 18.5 | 18.5 | 18.5 | 18.5 | 18.5 | 18.5 | 0.0 | 0.0 |
| 1 | EQ1510 | AIR COOLED SERIES R (RTAA) | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 78520 | 91045 | 105093 | 105495 | 86547 | 42216 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 210.8 | 234.2 | 240.0 | 240.0 | 221.0 | 187.4 | 0.0 | 0.0 |
| 1 | EQ5200 | CONDENSER FANS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 16651 | 16114 | 16651 | 16651 | 16114 | 16651 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 0.0 | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 2
AIR COOLED SINGLE SCREW CHILLERS

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | |
|--|--------|--------------------------------------|-----|-----|-----|-------|-------|-------|-------|-------|-------|-----|-----|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec |
| 1 | EQ5302 | CONTROLS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 74 | 72 | 74 | 74 | 72 | 74 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 |
| 2 | EQ1510 | AIR COOLED SERIES R (RTAA) | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 27164 | 41842 | 56709 | 61232 | 28981 | 4824 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 210.8 | 234.2 | 240.0 | 240.0 | 221.0 | 147.2 | 0.0 | 0.0 |
| 2 | EQ5001 | CHILLED WATER PUMP - CONSTANT VOLUME | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 4431 | 6624 | 8236 | 8818 | 4476 | 985 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 0.0 | 0.0 |
| 2 | EQ5302 | CONTROLS | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 20 | 30 | 37 | 39 | 20 | 4 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
NATURAL DRAFT WATER TUBE BOILERS

| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|----------|---------------------------------|-------|--------|-------|--------|--------|-------|--------|-------|--------|-------|-------|-----------|
| Ref | Equip | ----- Monthly Consumption ----- | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 0 | LIGHTS | | | | | | | | | | | | | |
| | ELEC | 99030 | 89550 | 105452 | 94800 | 102241 | 101222 | 95819 | 105452 | 94800 | 102241 | 94800 | 95819 | 1,181,224 |
| | PK | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 | 444.1 |
| 1 | MISC LD | | | | | | | | | | | | | |
| | ELEC | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 2 | MISC LD | | | | | | | | | | | | | |
| | GAS | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 3 | MISC LD | | | | | | | | | | | | | |
| | OIL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 4 | MISC LD | | | | | | | | | | | | | |
| | P STEAM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 5 | MISC LD | | | | | | | | | | | | | |
| | P HOTW20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 6 | MISC LD | | | | | | | | | | | | | |
| | P CHILL | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| | PK | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| 1 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 371 | 335 | 371 | 359 | 0 | 0 | 0 | 0 | 0 | 0 | 359 | 371 | 2,169 |
| | PK | 0.5 | 0.5 | 0.5 | 0.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.5 | 0.5 | 0.5 |
| 2 | | BASE UTILITY | | | | | | | | | | | | |
| | HOTLD | 825 | 745 | 825 | 798 | 0 | 0 | 0 | 0 | 0 | 0 | 798 | 825 | 4,817 |
| | PK | 1.1 | 1.1 | 1.1 | 1.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 1.1 | 1.1 | 1.1 |
| 1 | | WATERTUBE BOILER | | | | | | | | | | | | |
| | GAS | 1753 | 1911 | 775 | 479 | 0 | 0 | 0 | 0 | 0 | 0 | 834 | 1807 | 7,559 |
| | PK | 7.5 | 7.5 | 7.2 | 0.7 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 6.2 | 7.5 | 7.5 |
| 1 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 5028 | 4461 | 5550 | 5371 | 0 | 0 | 0 | 0 | 0 | 0 | 5371 | 5021 | 30,802 |
| | PK | 7.5 | 7.5 | 7.5 | 7.5 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 7.5 | 7.5 | 7.5 |

EQUIPMENT ENERGY CONSUMPTION - ALTERNATIVE 3
NATURAL DRAFT WATER TUBE BOILERS


| ----- EQUIPMENT ENERGY CONSUMPTION ----- | | | | | | | | | | | | | | |
|--|--------|--------------------------------|------|-----|-----|-----|------|------|-----|-----|-----|-----|------|-------|
| Ref | Equip | Monthly Consumption | | | | | | | | | | | | Total |
| Num | Code | Jan | Feb | Mar | Apr | May | June | July | Aug | Sep | Oct | Nov | Dec | |
| 1 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 84 | 75 | 93 | 90 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 84 | 516 |
| | PK | 0.1 | 0.1 | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 | 0.1 |
| 2 | | WATERTUBE BOILER | | | | | | | | | | | | |
| | GAS | 1824 | 1665 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1420 | 4,909 |
| | PK | 16.7 | 16.7 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 16.7 | 16.7 |
| 2 | EQ5020 | HEATING WATER CIRCULATION PUMP | | | | | | | | | | | | |
| | ELEC | 1522 | 1623 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1309 | 4,454 |
| | PK | 11.2 | 11.2 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 11.2 | 11.2 |
| 2 | EQ5311 | BOILER CONTROLS | | | | | | | | | | | | |
| | ELEC | 17 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 15 | 50 |
| | PK | 0.1 | 0.1 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.1 | 0.1 |

APPENDIX C
DATA FORMS

APPENDIX C
DATA FORMS

TABLE OF CONTENTS

| | |
|--|------|
| Area 900 - Map | C-1 |
| Area 900 - Building Data Sheets | C-2 |
| Area 900 - HVAC Equipment Lists | C-5 |
| Area 1300 - Map | C-6 |
| Area 1300 - Building Data Sheets | C-7 |
| Area 1300 - HVAC Equipment Lists | C-12 |
| Area 2200 - Map | C-14 |
| Area 2200 - Building Data Sheets | C-15 |
| Area 2200 - HVAC Equipment Lists | C-18 |
| Quadrangle Area - Map | C-19 |
| Quadrangle Area - Building Data Sheet | C-20 |
| Quadrangle Area - HVAC Equipment Lists | C-24 |
| Area 100 - Map | C-26 |
| Area 100 - Building Data Sheets | C-27 |
| Area 100 - HVAC Equipment Lists | C-39 |



BUILDING DESCRIPTION

NAME: Buildings 904, 905, 906, 907, 915, 916, 917, 920, 921, 924, 925, 926, 929, 930, 931, 932

USE: Barracks for single enlisted personnel and attendees of the NCO Academy. Approximately 1 to 3 people per room, and 24 rooms per building. Buildings occupied continuously through the year.

GROSS AREA (SQ.FT.): 11,220 STORIES: 3 DATE OF SURVEY: 11/30 to 12/2/95

DATE OF CONSTRUCTION: 1974

STRUCTURE: Masonry.

EXTERIOR WALLS: Brick

ROOF: Flat built-up roof.

FLOOR CONSTRUCTION: Slab on grade.

FLOOR FINISH: Concrete and Carpet.

CEILINGS: Lay-in acoustical tile in hallways and plaster ceilings in personnel rooms.

WINDOWS: single pane, clear glass.

COOLING EQUIP: Two-pipe, horizontal fan coil units in each room and hallway and vertical fan coil units in lounge areas. Units are mostly located above restroom ceilings. There are approximately 23 room units, 6 lounge units and 6 corridor units per building. Units are served by central chiller in building 902.

HEATING EQUIP: See cooling equipment above. Units served by central boiler in building 902.

LIGHTING: Wall mounted incandescent fixtures in quarters and lounges, with lay-in fluorescent fixtures in hallways.

DOMESTIC WATER HEATING: Heat exchanger and 588 gallon storage tank in basement of each building, served by central boilers in building 902.

OTHER: Combination chilled water/heating water pump in each building.

REMARKS: Poor temperature control, extremely hot during field survey. All mechanical systems appeared to be in a deteriorated state, particularly the HVAC controls and piping distribution system. Leaks and rampant condensation were common throughout all buildings. Corrosion built-up on fan coil units due to placement above restroom ceilings. Also causes accessibility problems for maintenance personnel.

BUILDING DESCRIPTION

NAME: Buildings 908, 919, 922, 928

USE: Buildings 919 & 928 are used for recreation, post office, etc. Average occupancy is 5 persons, between 5 pm till midnight, Monday through Friday, and 9 am till midnight on weekends. Buildings 908 & 922 are used for battalion administration offices, with an average occupancy of 5 persons daily.

GROSS AREA (SQ.FT.): 2,050 STORIES: 1 DATE OF SURVEY: 11/30 to 12/2/95

DATE OF CONSTRUCTION: 1974

STRUCTURE: Masonry.

EXTERIOR WALLS: Brick.

ROOF: Flat built-up roof.

FLOOR CONSTRUCTION: Slab on grade.

FLOOR FINISH: Carpet.

CEILINGS: Lay-in acoustical tile.

WINDOWS: Single pane with tempered glass.

COOLING EQUIP: Each building has a four-pipe, central air handling unit for both heating and cooling. Air handlers typically have a 3 HP fan motor. Units are served by central chiller in building 902.

HEATING EQUIP: See cooling equipment above. Units are served by central boiler in building 902.

LIGHTING: Lay-in fluorescent fixtures in open areas, restrooms and offices and recess incandescent lights in hallways.

DOMESTIC WATER HEATING: Electric water heater in each building, 15 gallon, 1250 W each.

OTHER: Combination chilled water/heating water pump in each building, typically 1-1/2 HP each.

REMARKS: Poor temperature control, extremely hot during field survey, doors were opened to control temperatures. All mechanical systems appeared to be in a deteriorated state, particularly the HVAC controls and piping insulation.

BUILDING DESCRIPTION

NAME: Building 902

USE: Used as administrative offices and classrooms, 7 am until 5 pm, Monday through Friday. Maximum 180 persons when occupied. Other portions used as central boiler and chiller plant for other buildings in the 900 area.

GROSS AREA (SQ.FT.): 23,723 STORIES: 1 DATE OF SURVEY: 11/30 to 12/2/95

DATE OF CONSTRUCTION: 1974

STRUCTURE: Masonry.

EXTERIOR WALLS: Brick.

ROOF: Flat built-up roof.

FLOOR CONSTRUCTION: Slab on grade.

FLOOR FINISH: Carpet

CEILINGS: Lay-in acoustical tile

WINDOWS: Single pane with clear glass.

COOLING EQUIP: Two four-pipe central air handlers with individual return air fans are serving the administrative and classroom areas. Units are served by central chiller in building 902.

HEATING EQUIP: See cooling equipment above. Units are served by central boiler in building 902.

LIGHTING: Lay-in fluorescent fixtures in the admin and classrooms, industrial fluorescent fixtures in the storage area, and recess











DOMESTIC WATER HEATING: Heating water to domestic hot water heat exchanger in central plant, served by central boilers in building 902.

OTHER: Central chiller and boiler equipment, see HVAC Equipment List for descriptions.

REMARKS: Poor temperature control, extremely hot during field survey. All mechanical systems appeared to be in a deteriorated state, particularly the HVAC controls and piping insulation. Exhaust fans appeared to operate while central AHUs were off. Return air grilles appeared to be excessively dirty. Room remodeling has restricted the return air pattern back to the air handling units.

HVAC EQUIPMENT LIST FOR: FORT SAM HOUSTON, AREA 900
JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|----------------------|------|---|-------------|-------------------|--------------|-------------|------|-----|------------|-------|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | York #YTC303C1CJC water cooled, centrifugal, 304 tons, R-11 | Area 900 | 1985 | 225 KW | 24 | 7 | 26 | 444,056 | |
| Chilled Water Pump | 1 | Weinman 720 gpm, 100 ft 25 HP | Area 900 | 1985 | 18.65 KW | 24 | 7 | 26 | 82,358 | |
| Condenser Water Pump | 1 | Weinman 912 gpm, 50 ft 15 HP | Area 900 | 1985 | 11.19 KW | 24 | 7 | 26 | 49,415 | |
| Cooling Tower | 1 | Marley #MC8608 one cell 15 HP fan | Area 900 | 1979 | 11.19 KW | 24 | 7 | 26 | 45,510 | |
| Hot Water Boiler | 3 | Ajax #WG 2250 natural draft, watertube 1665 MBH output | Area 900 | 1979 | 2,250 MBH | 24 | 7 | 26 | | 7,809 |
| Heating Water Pump | 1 | Weinman 200 gpm, 38 ft 5 HP | Area 900 | 1979 | 3.73 KW | 24 | 7 | 26 | 32,675 | |
| Heating Water Pump | 1 | Weinman 115 gpm, 30 ft 5 HP | Area 900 | 1979 | 3.73 KW | 24 | 7 | 26 | 32,675 | |
| Heating Water Pump | 1 | Weinman 115 gpm, 30 ft 2 HP | Area 900 | 1979 | 1.49 KW | 24 | 7 | 26 | 13,052 | |
| Heating Water Pump | 1 | Peerless 1.5 HP | Bldg. 902 | 1979 | 1.12 KW | 24 | 7 | 26 | 9,811 | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |



BUILDING DESCRIPTION

NAME: Building 1350

USE: Barracks, administrative offices, dining and classrooms for single enlisted personnel.
Maximum occupancy of 800 persons with current occupancy of 1550 personnel.

GROSS AREA (SQ.FT.): 261,406 STORIES: 3 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1983

STRUCTURE: Masonry

EXTERIOR WALLS: Both brick and precast panel.

ROOF: Flat built-up roof.

FLOOR CONSTRUCTION: Slab on grade

FLOOR FINISH: Concrete topping, tile, and carpet

CEILINGS: Lay in acoustical tile, plaster, and stucco

WINDOWS: Single pane with glazed, insulating glass.

COOLING EQUIP: Total of seven central multi-zone, variable volume air handling units serving large areas of the building. Approximately 20 two-pipe fan coil units serving cadre rooms. All units are served by central chillers in building 1377.

HEATING EQUIP: See cooling equipment above. Multiple heating/ventilating units serving scrub rooms, toilets and kitchen areas along with heating water convection units serving multiple areas throughout building. All units are served by central boilers in building 1377.

LIGHTING: Lay-in fluorescent fixtures in barracks, admin, classrooms, and dining areas. Surface mounted fluorescent fixtures in kitchen and scattered incandescent fixtures.

DOMESTIC WATER HEATING: Gas fired hot water heaters in building to serve restrooms.

OTHER: 7 ½, ½, ½ HP heating water pumps in building. Steam boilers in building serve kitchen equipment.

REMARKS: Poor temperature control, extremely hot during field survey. Piping leaks are a problem. All other HVAC systems appeared to be in fair condition.

BUILDING DESCRIPTION

NAME: Buildings 1374, 1375, 1379, 1380

USE: Barracks for single enlisted personnel, classrooms and administrative offices. Maximum occupancy of approximately 475 people.

GROSS AREA (SQ.FT.): 111,448 STORIES: 3 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1971

STRUCTURE: Partially exposed structural steel frame

EXTERIOR WALLS: Brick and stucco veneer

ROOF: built-up roof

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: concrete topping and carpet

CEILINGS: Lay-in acoustical tile in building with stucco over exposed areas

WINDOWS: single pane clear and tempered glass

COOLING EQUIP: Approximately six multi-zone, constant volume central air handlers serving barracks and office areas of the buildings. Approximately four cabinet type fan coil units serving classrooms in the buildings. All units served by central chillers in building 1377.

HEATING EQUIP: See cooling equipment above. All units served by central boilers in building 1377.

LIGHTING: Surface mounted incandescent fixtures in exposed areas. Lay-in fluorescent fixtures in admin and barracks areas.

DOMESTIC WATER HEATING: Gas fired hot water boilers in building to serve restrooms.

OTHER: Secondary 7 ½ and 5 HP chilled/heating water pumps in building.

REMARKS: Poor temperature control, extremely hot during field survey. Renovations to building has caused restricted return air flow back to air handling units. All other HVAC systems appeared to be in fair condition.

BUILDING DESCRIPTION

NAME: Building 1382

USE: Barracks for single enlisted personnel, administrative offices. Continuous occupancy of approximately 240 persons.

GROSS AREA (SQ.FT.): 29,390 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1971

STRUCTURE: Masonry

EXTERIOR WALLS: Brick

ROOF: Flat Built-up roof

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and tile

CEILINGS: Gypsum wallboard and acoustical tile

WINDOWS: Single pane clear glass

COOLING EQUIP: Building served by two central multi-zone air handlers. Air handler cooling coils served by central chillers in building 1377.

HEATING EQUIP: See cooling equipment above. Air handler heating coils served by central boilers in building 1377.

LIGHTING: Surface and suspended mounted fluorescent fixtures

DOMESTIC WATER HEATING: Gas fired hot water heaters in building to serve restrooms.

OTHER: Secondary 3/4 HP chilled water and 1/2 HP heating water pumps in building.

REMARKS: Poor temperature control, extremely hot during field survey. All other HVAC systems appeared to be in fair condition. Outside air intake louvers have been blanked off with sheet metal, reducing HVAC loads but also reducing indoor air quality. Building may not meet ASHRAE standards for ventilation.

BUILDING DESCRIPTION

NAME: Building 1385

USE: Administrative services for 232nd Medical Battalion troops. Continuous occupancy of approximately 22 persons.

GROSS AREA (SQ.FT.): 5,072 STORIES: 1 DATE OF SURVEY: 11/30 to 12/2/94

DATE OF CONSTRUCTION: 1971

STRUCTURE: Masonry

EXTERIOR WALLS: Brick

ROOF: Flat built-up roof

FLOOR CONSTRUCTION: Slab on grade

FLOOR FINISH: Concrete and tile

CEILINGS: Acoustical tile and gypsum wallboard

WINDOWS: Single pane clear glass

COOLING EQUIP: Building served by central multi-zone air handler in mechanical room. Air handler cooling coil served by central chiller in building 1377.

HEATING EQUIP: See cooling equipment above. Air handler heating coil served by central boiler in building 1377.

LIGHTING: Recessed and surface mounted fluorescent fixtures in office areas and surface mounted incandescent fixtures in other areas

DOMESTIC WATER HEATING: Electric, 66 gallon, 4500 W hot water heater in building to serve restrooms.

OTHER: Secondary 1/4 HP chilled water and 1/8 HP heating water pumps in building.

REMARKS: Poor temperature control, extremely hot during field survey. All other HVAC systems appeared to be in fair condition. Outside air intake louvers have been blanked off with sheet metal, reducing HVAC loads but also reducing indoor air quality. Building may not meet ASHRAE standards for ventilation.

BUILDING DESCRIPTION

NAME: Building 1377

USE: Kitchen and dining hall in building. Other areas serve as central chiller and boiler plant for buildings in 1300 area. Maximum occupancy of 800 persons on weekdays between 4 am and 9 pm.

GROSS AREA (SQ.FT.): 30,350 STORIES: 1 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1971

STRUCTURE: Masonry

EXTERIOR WALLS: Brick

ROOF: Sloped built-up roof

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and tile

CEILINGS: Acoustical tile, gypsum wallboard, and plaster

WINDOWS: single pane clear glass

COOLING EQUIP: Dining areas served by two, single zone, central air handlers in mechanical room. Air handler cooling coils served by central chiller in building 1377. Kitchen served by two evaporative coolers only.

HEATING EQUIP: See cooling equipment above. Air handler heating coil served by central boiler in building 1377. Evaporative coolers serving kitchen have steam htg coil which is supplied by steam boiler in building 1377.

LIGHTING: Surface mounted fluorescent fixtures

DOMESTIC WATER HEATING: Electric hot water heater in building to serve restrooms.

OTHER: Central chiller and boiler equipment, see HVAC Equipment List for descriptions along with steam boiler to serve bldg. 1377 kitchen equipment..


REMARKS: Poor temperature control, extremely hot during field survey. All mechanical systems appeared to be in a deteriorated state, particularly the HVAC controls and piping insulation. Exhaust fans appeared to operate while central AHUs were off. Return air grilles appeared to be excessively dirty.

HVAC EQUIPMENT LIST FOR: FORT SAM HOUSTON, AREA 1300
JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|----------------------|------|--|---|-------------------|----------------------|-------------|------|-----|------------|--------|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | Trane #PCV-5F-C1D1 water cooled, centrifugal, 600 tons, R-11 | Bldgs. 1374, 1375, 1379, 1380, 1382, 1377, 1385 | 1972 | 564 KW | 24 | 7 | 26 | 1,464,005 | |
| Water Chiller | 1 | Trane #PCV-5F-C1D1 water cooled, centrifugal, 600 tons, R-11 | Bldgs. 1374, 1375, 1379, 1380, 1382, 1377, 1385 | 1972 | 564 KW | 24 | 7 | 26 | 130,286 | |
| Water Chiller | 1 | Carrier #19DK 78942P water cooled, centrifugal, 438 tons, R-11 | Bldg. 1350 | 1983 | 329 KW | 24 | 7 | 26 | 595,685 | |
| Chilled Water Pump | 2 | Aurora 870 gpm, 79 ft 25 HP | Bldgs. 1374, 1375, 1379, 1380, 1382, 1377, 1385 | 1972 | 18.65 KW | 24 | 7 | 26 | 164,716 | |
| Chilled Water Pump | 1 | Allis Chalmers 775 gpm, 114 ft 40 HP | Bldg. 1350 | 1983 | 29.84 KW | 24 | 7 | 26 | 131,830 | |
| Condenser Water Pump | 2 | Aurora 1440 gpm, 70 ft 40 HP | Bldgs. 1374, 1375, 1379, 1380, 1382, 1377, 1385 | 1972 | 29.84 KW | 24 | 7 | 26 | 171,908 | |
| Condenser Water Pump | 1 | Allis Chalmers 1314 gpm, 30 ft 30 HP | Bldg. 1350 | 1983 | 22.38 KW | 24 | 7 | 26 | 98,830 | |
| Cooling Tower | 1 | Marley #324T induced draft, 2-35 HP fans | Bldgs. 1374, 1375, 1379, 1380, 1382, 1377, 1385 | 1972 | 52.22 KW | 24 | 7 | 26 | 210,896 | |
| Cooling Tower | 1 | Marley induced draft, 20 HP fan | Bldg. 1350 | 1983 | 14.92 KW | 24 | 7 | 26 | 60,215 | |
| Hot Water Boiler | 2 | C.B. #CB700X-200 10 HP forced draft, 5912 MBH output | Bldgs. 1374, 1375, 1379, 1380, 1382, 1377, 1385 | 1972 | 8,369 MBH 7.46 KW | 24 | 7 | 26 | 32,406 | 15,611 |
| Hot Water Boiler | 1 | Rite #A750WG natural draft, watertube 5317 MBH output | Bldg. 1350 | 1983 | 7,500 MBH | 24 | 7 | 26 | | 3,140 |
| Hot Water Boiler | 1 | Ajax #WGB 9500 natural draft, watertube 4336 MBH output | Bldg. 1350 | 1983 | 5,800 MBH | 24 | 7 | 26 | | 0 |

JUNE 2, 1995

[illegible]



BUILDING DESCRIPTION

NAME: Building 2263

USE: Administrative offices for post fiscal activities. Maximum occupancy of 250 persons from 6:30 am until 5:15 pm on weekdays.

GROSS AREA (SQ.FT.): 81,065 STORIES: 3 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1970

STRUCTURE: Masonry

EXTERIOR WALLS: Stucco on CMU

ROOF: Pitched shingle roof

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and tile

CEILINGS: Lay-in acoustical tile

WINDOWS: single and double pane clear glass in most of building and insulating glass in corridors.

COOLING EQUIP: Eight, single zone central air handlers serving the general office areas. Fourteen, four-pipe fan coil units serving corridors, stairwells and first floor office areas on the east and west ends. All units are served by the central chiller in building 2265.

HEATING EQUIP: See cooling equipment above. All units are served by the central boilers in building 2265.

LIGHTING: Recessed fluorescent fixtures and scattered incandescent fixtures

DOMESTIC WATER HEATING: Gas fired hot water heaters in building to serve restrooms.

OTHER: Packaged computer room units with outdoor fluid cooler serve the computer room in building. Some rooms in basement served by window units.

REMARKS: Poor temperature control. Extremely hot inside during field visit in mid March. Some inside areas were above 100 degrees F. All HVAC systems appeared to be in good condition with the exception of the temperature controls.

BUILDING DESCRIPTION

NAME: Buildings 2264, 2266

USE: Mainly barracks for single enlisted personnel, with administrative offices and classrooms. Also houses the Academy Museum and band area. Maximum occupancy of 255 persons per building on a continuous basis.

GROSS AREA (SQ.FT.): 98,190 STORIES: 3 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1970

STRUCTURE: Masonry

EXTERIOR WALLS: Plaster on stone

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and tile

CEILINGS: Lay-in acoustical tile

WINDOWS: Single pane clear glass

COOLING EQUIP: Ten, four-pipe multi-zone air handlers serving all areas of the building. Average 3 to 6 zones per unit. All units are served by the central chiller in building 2265.

HEATING EQUIP: See cooling equipment above. All units are served by the central boilers in building 2265.

LIGHTING: Recessed fluorescent fixtures with incandescent fixtures scattered throughout building.

DOMESTIC WATER HEATING: Gas fired hot water heaters in building to serve restrooms.

REMARKS: Poor temperature control. Extremely hot inside during field visit in mid March. All HVAC systems appeared to be in poor condition, especially the temperature controls.

BUILDING DESCRIPTION

NAME: Building 2265

USE: Mainly barracks for single enlisted personnel, with administrative offices and classrooms. Also houses the mess hall and central boiler and chiller plants. Maximum occupancy of 600 persons at meal time, with approximately 200 persons on a continuous basis.

GROSS AREA (SQ.FT.): 105,564 STORIES: 3 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1970

STRUCTURE: Masonry

EXTERIOR WALLS: Plaster on stone wall

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and tile

CEILINGS: Acoustical tile and gypsum wallboard

WINDOWS: single pane clear glass

COOLING EQUIP: Ten, four-pipe multi-zone air handlers serving all areas of the building. Average 2 to 6 zones per unit. All units are served by the central chiller in building.

HEATING EQUIP: See cooling equipment above. All units are served by the central boilers in building behind.

LIGHTING: Recessed fluorescent fixtures with incandescent scattered in building.


DOMESTIC WATER HEATING: Large gas fired boiler located in basement for domestic hot water heating in the building.

OTHER: Central chiller plant equipment in building and central boiler plant equipment in building behind. See HVAC Equipment Lists for descriptions. Steam boilers in basement serve kitchen equipment.

REMARKS: Poor temperature control. Extremely hot inside during field visit in mid March. All HVAC systems appeared to be in poor condition, especially the temperature controls. Boiler (heating water) plant appears in good condition, while chiller plant is aged.

HVAC EQUIPMENT LIST FOR: FORT SAM HOUSTON, AREA 2200
JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|-------------------------|------|---|------------------|-------------------|--------------|-------------|------|-----|------------|-------|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | Chrysler #C2MN779-2 water cooled, centrifugal, 657 tons, R-11 | Area 2200 | 1973 | 595 KW | 24 | 7 | 26 | 994,146 | |
| Chilled Water Pump | 1 | Paco 1526 gpm, 166 ft 100 HP | Area 2200 | 1973 | 74.60 KW | 24 | 7 | 26 | 329,433 | |
| Condenser Water Pump | 1 | Paco 1971 gpm, 63 ft 50 HP | Area 2200 | 1973 | 37.30 KW | 24 | 7 | 26 | 164,717 | |
| Cooling Tower | 1 | Built-up crossflow, 2 cell 2-20HP fans | Area 2200 | 1973 | 29.84 KW | 24 | 7 | 26 | 121,471 | |
| Hot Water Boiler | 3 | Ajax #WGB 4750 natural draft, watertube 2240 MBH output | Area 2200 | 1988 | 3,000 MBH | 24 | 7 | 26 | | 4,949 |
| Heating Water Pump | 3 | Armstrong 207 gpm, 110 ft 15 HP | Area 2200 | 1988 | 11.19 KW | 24 | 7 | 26 | 51,512 | |
| Boiler Circulation Pump | 3 | Armstrong 3/4 HP | Hot Water Boiler | 1988 | 0.56 KW | 24 | 7 | 26 | 24 | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |



BUILDING DESCRIPTION

NAME: Building 4015

USE: Medical logistics training and offices, pharmaceutical storage. Maximum occupancy of 100 persons on weekdays, between 7:30 am and 4:30 pm.

GROSS AREA (SQ.FT.): 14,568 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1956

STRUCTURE: Frame

EXTERIOR WALLS: Stucco

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Slab on grade

FLOOR FINISH: wood covered with linoleum

CEILINGS: suspended metal lathe

WINDOWS: single pane clear glass

COOLING EQUIP: Three multizone air handlers serving the classrooms, offices and storage areas. A 50 ton air cooled reciprocating chiller outside building serves the air handlers. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. A 800 MBH heating water boiler in building serving air handlers. See HVAC Equipment Lists for details.

LIGHTING: Suspended fluorescent fixtures

DOMESTIC WATER HEATING: Gas fired hot water heaters in building to serve restrooms.

OTHER: 5 HP chilled water pump and 2 HP heating water pump serving chiller and boiler. See HVAC Equipment Lists for details.

REMARKS: All HVAC equipment, including controls, appeared to be in fair condition.

BUILDING DESCRIPTION

NAME: Building 56

USE: Administrative offices for post security and pentathlon, classroom areas for training and testing. Maximum occupancy of 65 persons during weekdays, between 7:00 am and 5:00 pm.

GROSS AREA (SQ.FT.): 8,025 STORIES: 1 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1941

STRUCTURE: Frame

EXTERIOR WALLS: Siding and brick

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Slab on grade

FLOOR FINISH: Concrete and carpet

CEILINGS: Acoustical tile

WINDOWS: single pane clear glass

COOLING EQUIP: One multi-zone air handler serving all conditioned areas of the building. Unit served by air cooled reciprocating chiller, approximately 30 tons nominal. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. Steam to heating water generator served from boiler in building 16, furnishing heating water for multizone above. See HVAC Equipment Lists for details.

LIGHTING: Lay-in fluorescent fixtures

DOMESTIC WATER HEATING: Gas fired hot water heaters in building to serve restrooms.

OTHER: 1 HP chilled water pump, and 1/8 HP heating water pump. See HVAC Equipment Lists for details.

REMARKS: Poor temperature control, very hot inside during the field visit. All HVAC equipment appeared to be in fair to poor condition with the exception of new chiller, however most controls were not functioning properly.

BUILDING DESCRIPTION

NAME: Building 16

USE: Headquarters for the 5th Army. Maximum 300 occupants during weekdays between 6:30 am and 6:00 pm.

GROSS AREA (SQ.FT.): 76,102 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1940

STRUCTURE: Masonry

EXTERIOR WALLS: Stone

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Slab on grade

FLOOR FINISH: concrete and carpet

CEILINGS: acoustical tile

WINDOWS: single and double pane clear glass and insulating glass in corridor

COOLING EQUIP: Approximately five, single zone air handlers serving office areas on the first and second floor. Four fan coil units serving the second floor corridor. All units served by two air cooled chillers outside building, total 230 nominal tons capacity. See HVAC Equipment Lists for details.

Also 24 packaged DX cooling units serve the wing areas. DX units served by three evaporative condensers outside building. Computer room units served by air cooled condenser and stand alone compressor in building mechanical room.

HEATING EQUIP: See cooling equipment above. Steam unit heaters serve the wings. All units served by two steam boilers inside building, total 5,800 MBH total output capacity. See HVAC Equipment Lists for details.

LIGHTING: lay-in fluorescent fixtures

DOMESTIC WATER HEATING: Gas fired hot water heaters in building to serve restrooms.

OTHER: Two, 7.5 HP chilled water pumps serving chillers. See HVAC Equipment Lists for details. Condensate pumps scattered through building.

REMARKS: Poor temperature control, portions of building were comfortable while others were very hot during the field visit. All HVAC equipment appeared to be in fair to poor condition, however most controls were not functioning properly

BUILDING DESCRIPTION

NAME: Building 44

USE: Administrative offices for the 5th Army. Maximum occupancy of 350 persons during weekdays between 7:30 am and 4:30 pm.

GROSS AREA (SQ.FT.): 95,332 STORIES: 3 DATE OF SURVEY: 3/13 to 3/17/9

DATE OF CONSTRUCTION: 1956

STRUCTURE: Masonry

EXTERIOR WALLS: Brick and Stucco

ROOF: Flat built-up roof

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and carpet

CEILINGS: Lay-in acoustical tile

WINDOWS: single pane clear glass

COOLING EQUIP: Two dual-duct air handlers serving 1st and 2nd floor offices. Single zone, VAV air handler serving 3rd floor offices. Five single zone air handlers serving 1st floor computer room, 1st floor addition and deli. Most units served by air cooled reciprocating chillers outside with total 255 nominal tons capacity. See HVAC Equipment Lists for details. 1st floor addition and deli unit are DX cooling.

HEATING EQUIP: See cooling equipment above. All units served by 13 steam boilers, total 3440 MBH output capacity. See HVAC Equipment Lists for details.

LIGHTING: Lay in fluorescent fixtures, recessed incandescent scattered in building.

DOMESTIC WATER HEATING: Gas fired hot water heaters in building to serve restrooms.

OTHER: 20 HP chilled water pump serving chillers. See HVAC Equipment Lists for details.

REMARKS: Poor temperature control in building. Extremely hot, especially on the second floor where the lights are on 24 hours/day. Large air handlers and boilers in this building are aging and in appear in poor condition.


HVAC EQUIPMENT LIST FOR: FORT SAM HOUSTON, QUADRANGLE AREA

JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|-----------------------|------|--|-------------------|-------------------|----------------------|-------------|------|-----|------------|-----|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | TSI #CA2CD 75 air cooled, recip. 50 tons, R-22 | Bldg. 4015 | 1983 | 88 KW | 24 | 7 | 26 | 180,278 | |
| Chilled Water Pump | 1 | Paco 5 HP | Bldg. 4015 | 1983 | 3.73 KW | 24 | 7 | 26 | 16,472 | |
| Hot Water Boiler | 1 | Rite #R8-C-05 forced draft, 5 HP blower 741 MBH output | Bldg. 4015 | 1987 | 1,000 MBH 3.73 KW | 24 | 7 | 26 | 4,275 | 120 |
| Heating Water Pump | 1 | N/A 3 HP | Bldg. 4015 | 1987 | 2.24 KW | 24 | 7 | 26 | 1,821 | |
| Water Chiller | 1 | Trane #CDAGC30GACA air cooled, recip. 30 tons | Bldg. 56 | 1993 | 49 KW | 24 | 7 | 26 | 76,755 | |
| Chilled Water Pump | 2 | Armstrong 207 gpm, 110 ft 5 HP | Bldg. 56 | 1993 | 3.73 KW | 24 | 7 | 26 | 32,944 | |
| Water Chiller | 1 | TSI #30AOCM 140 air cooled, recip. 120 tons | Bldg. 16 | 1994 | 194 KW | 24 | 7 | 26 | 393,031 | |
| Water Chiller | 1 | TSI #CA2CM 110 air cooled, recip. 110 tons | Bldg. 16 | 1987 | 190 KW | 24 | 7 | 26 | 122,759 | |
| Chilled Water Pump | 2 | Taco 350 gpm, 50 ft 7.5 HP | Bldg. 16 | 1987 | 5.60 KW | 24 | 7 | 26 | 49,460 | |
| Steam Boiler | 1 | Rite #2255 natural draft, watertube 1614 MBH output | Bldg. 16 | 1979 | 2,250 MBH | 24 | 7 | 26 | | 267 |
| Steam Boiler | 1 | Rite #500 natural draft, watertube 3587 MBH output | Bldg. 16, Bldg 56 | 1979 | 5,000 MBH | 24 | 7 | 26 | | 651 |
| Evaporative Condenser | 1 | Marley - 3 misc. models 2 - 3 HP & 5 HP pumps, 3 - 1/2 HP fans | Bldg. 16 | 1978 | 9.33 KW | 24 | 7 | 26 | 41,201 | |

JUNE 2, 1995

[illegible]



BUILDING DESCRIPTION

NAME: Buildings 122 & 124

USE: Administrative offices - Dir. of Resource Management. Continuous occupancy of approximately 30 people during weekdays, between 7:00 am and 5:00 pm.

GROSS AREA (SQ.FT.): 12,782 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1940

STRUCTURE: Masonry

EXTERIOR WALLS: Brick and stone

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and carpet

CEILINGS: Acoustical tile

WINDOWS: single pane clear glass

COOLING EQUIP: Three multi-zone air handling units serving all conditioned areas of the building. Units served by air cooled reciprocating chiller, approximately 40 tons nominal in bldg. 122 & 50 tons nominal in bldg. 124.. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. Heating water is provided by 850 MBH heating water boiler in basement. See HVAC Equipment Lists for details.

LIGHTING: Lay-in fluorescent fixtures

DOMESTIC WATER HEATING: Gas fired hot water heater in building.

OTHER: 3 HP chilled water pump, and 1-1/2 HP heating water pump. See HVAC Equipment Lists for details.

REMARKS: Poor temperature control, very hot inside during the field visit. Building 124 was being renovated at the time of the site visit. All HVAC equipment appeared to be in fair to poor condition, however most controls were not functioning properly.

BUILDING DESCRIPTION

NAME: Buildings 125, 127, & 135

USE: Administrative offices - Community Operations Div., J. A. office, U.S.M.A. Admin. Field office. Continuous occupancy of approximately 5 people during weekdays, between 7:00 am and 5:00 pm.

GROSS AREA (SQ.FT.): 1,593 STORIES: 1 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1940

STRUCTURE: Masonry

EXTERIOR WALLS: Brick

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and carpet

CEILINGS: Acoustical tile

WINDOWS: Single pane clear glass

COOLING EQUIP: Building 125 is the only one of these buildings that has fan coils. The other two buildings have furnace units with evaporator coils. Bldgs. 125 and 135 are both served by air cooled chillers that also serve adjacent building 124 and 134. Building 127 is served by a 4.5 ton outdoor condensing unit. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. Heating water for bldg. 125 and 135 is provided by a 820 MBH boiler in the basement of buildings 124 and 134. the furnace in Bldg. 127 is served by gas. See HVAC Equipment Lists for details.

LIGHTING: Lay-in fluorescent fixtures

DOMESTIC WATER HEATING: Electric hot water heater in building.

REMARKS: Poor temperature control, very hot inside during the field visit. All HVAC equipment appeared to be in fair to poor condition, however most controls were not functioning properly.

BUILDING DESCRIPTION

NAME: Building 128

USE: Boys & Girls Scouts Offices.

GROSS AREA (SQ.FT.): 14,224 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95 DATE OF CONSTRUCTION: 1940

STRUCTURE: Frame

EXTERIOR WALLS: Brick , stone, and siding

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and carpet

CEILINGS: Acoustical tile

WINDOWS: single pane clear glass

COOLING EQUIP: Air handling units, fan coil units, and several window units serve all conditioned areas of the building. Units served by 40 ton nominal air cooled reciprocating chiller. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. Heating water is provided by 150 MBH heating water boiler in basement See HVAC Equipment Lists for details.

LIGHTING: Lay-in fluorescent fixtures

DOMESTIC WATER HEATING: Electric hot water heater in building.

OTHER: 1-1/2 HP chilled water pump, and 1/2 HP heating water pump. See HVAC Equipment Lists for details.

REMARKS: This building was unavailable to be entered during site visit. Chiller appeared to be in fair condition.

BUILDING DESCRIPTION

NAME: Building 133

USE: Administrative offices - Medical/Pharmaceutical operations. Continuous occupancy of approximately 50 people during weekdays, between 7:00 am and 5:00 pm.

GROSS AREA (SQ.FT.): 13,232 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1940

STRUCTURE: Masonry

EXTERIOR WALLS: Brick and siding

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and carpet

CEILINGS: Acoustical tile

WINDOWS: single pane clear glass

COOLING EQUIP: Multi-zone air handling units and fan coil units serving all conditioned areas of the building. Units served by 25 ton nominal air cooled reciprocating chiller. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. Heating water is provided by 150 MBH heating water boiler in basement. See HVAC Equipment Lists for details.

LIGHTING: Lay-in fluorescent fixtures

DOMESTIC WATER HEATING: Electric hot water heater in building.

OTHER: 1-1/2 HP chilled water pump, and 1/2 HP heating water pump. See HVAC Equipment Lists for details.

REMARKS: Temperature control in good condition. Comfortable inside during the field visit. All HVAC equipment appeared to be in fair condition.

BUILDING DESCRIPTION

NAME: Building 134

USE: Legal offices. Continuous occupancy of approximately 40 people during weekdays, between 7:00 am and 5:00 pm.

GROSS AREA (SQ.FT.): 10,434 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1940

STRUCTURE: Masonry

EXTERIOR WALLS: Brick and stone

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and carpet

CEILINGS: Acoustical tile

WINDOWS: single pane clear glass

COOLING EQUIP: Three multi-zone air handling units serving all conditioned areas of the building. Units served by 30 ton nominal air cooled reciprocating chiller which also serves bldg. 135. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. Heating water is provided by 820 MBH heating water boiler in basement. See HVAC Equipment Lists for details.

LIGHTING: Lay-in fluorescent fixtures

DOMESTIC WATER HEATING: Gas fired hot water heater in building.

OTHER: 1/2 HP chilled and heating water pumps. See HVAC Equipment Lists for details.

REMARKS: Poor temperature control, very hot inside during the field visit especially on second floor near window covered vestibule. All HVAC equipment appeared to be in fair to poor condition, however most controls were not functioning properly.

BUILDING DESCRIPTION

NAME: Buildings 142

USE: Administrative offices - Reg. H.Q. and deferred maintenance.

GROSS AREA (SQ.FT.): 4,735 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1945

STRUCTURE: Masonry

EXTERIOR WALLS: Brick and CMU

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and carpet

CEILINGS: Acoustical tile

WINDOWS: Single pane clear glass

COOLING EQUIP: This building is served by a 10 ton nominal air cooled chiller. See HVAC Equipment Lists for details.

HEATING EQUIP: Heating water for this building is assumed to be provided by a 450 MBH boiler in the basement. See HVAC Equipment Lists for details.

LIGHTING: Lay-in fluorescent fixtures

DOMESTIC WATER HEATING: Electric hot water heater in building.

REMARKS: This building was unavailable to be entered during site visit. Chiller appeared to be in fair condition. This building has it's own electrical meter.

BUILDING DESCRIPTION

NAME: Buildings 143, 144, 145, 146

USE: Administrative offices. Continuous occupancy of approximately 50 people during weekdays, between 7:00 am and 5:00 pm.

GROSS AREA (SQ.FT.): 13,483 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1940

STRUCTURE: Masonry with frame add-on

EXTERIOR WALLS: Brick, stone and wood shingles

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and carpet

CEILINGS: Acoustical tile

WINDOWS: single pane clear glass and tempered glass for enclosed porch

COOLING EQUIP: Bldgs. 143, 144, and 146 are served by multi-zone and single-zone air handling units, and bldg 143 contains packaged window units for cooling. The air handlers in bldg 143, 144, & 146 are served by 45, 45, & 40 ton nominal air cooled reciprocating chillers. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. The air handlers in bldgs. 143, 144, & 146 are served by an 850 MBH heating water boiler in the basements. Warm air furnace provides heating for bldg. 145. See HVAC Equipment Lists for details.

LIGHTING: Lay-in fluorescent fixtures

DOMESTIC WATER HEATING: Gas fired hot water heater in building.

OTHER: 3 HP chilled water pump, and 1 HP heating water pump in bldgs. 143 & 144. 1-1/2 HP chilled water pump and 1 HP heating water pump for bldg. 146. Building 144 also has a 4 ton condensing unit that serves computer room. See HVAC Equipment Lists for details.

REMARKS: Building 143 was empty and awaiting renovation at the time of the site visit. Window units are in poor condition and thus create maintenance problems. All other HVAC equipment appeared to be in fair to poor condition and most controls were not functioning properly.

BUILDING DESCRIPTION

NAME: Buildings 147 & 149

USE: Billeting for Reserves, Family Residence. Continuous occupancy of approximately 50 people during weekdays, between 7:00 am and 5:00 pm.

GROSS AREA (SQ.FT.): 11,522 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1939

STRUCTURE: Masonry

EXTERIOR WALLS: Brick

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and carpet

CEILINGS: Acoustical tile

WINDOWS: single pane clear glass

COOLING EQUIP: One multi-zone air handling unit serves each of these buildings. 50 ton air cooled reciprocating chiller serves both bldg. 147 & 149. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. Heating water is provided by 850 MBH heating water boiler in each bldgs. basement. See HVAC Equipment Lists for details.

LIGHTING: Lay-in fluorescent fixtures and scattered incandescent fixtures.

DOMESTIC WATER HEATING: Gas fired hot water heater in building.

OTHER: 5 HP chilled water pump, and two 1 HP heating water pumps. See HVAC Equipment Lists for details.

REMARKS: All HVAC equipment appeared to be in fair to poor condition. Piping between buildings appears to be deteriorating.

BUILDING DESCRIPTION

NAME: Buildings 197

USE: Headquarter of Fifth Army Band, future 323rd Medical Battalion Supply. Continuous occupancy of approximately 35 people during weekdays, between approximately 7:00 am and 5:00 pm.

GROSS AREA (SQ.FT.): 13,819 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1940

STRUCTURE: Frame

EXTERIOR WALLS: Stucco

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and tile

CEILINGS: Acoustical tile, Plaster

WINDOWS: Single pane clear glass

COOLING EQUIP: Three 4- Pipe, single-zone fan and coil units serve all conditioned areas of the building. Units served by air cooled reciprocating chiller, approximately 50 tons nominal. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. Heating water is provided by 1750 MBH heating water boiler in basement. See HVAC Equipment Lists for details.

LIGHTING: Lay-in and surface mounted fluorescent fixtures

DOMESTIC WATER HEATING: Gas fired hot water heater in building.

OTHER: 2 HP chilled water pump, and 1 HP heating water pump. See HVAC Equipment Lists for details.

REMARKS: Poor temperature control, very hot inside during the field visit. Very old ductwork with dust mold and mildew. Control problems create moisture pockets on furniture and causes moisture problems with computers. All HVAC equipment appeared to be in poor condition, and most controls were not functioning properly.

BUILDING DESCRIPTION

NAME: Building 198

USE: Physical/Medical Evaluation Board. Continuous occupancy of approximately 20 people during weekdays, between 7:00 am and 5:00 pm.

GROSS AREA (SQ.FT.): 5,468 STORIES: 2 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1945

STRUCTURE: Frame

EXTERIOR WALLS: Stucco

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and tile

CEILINGS: Acoustical tile, Plaster

WINDOWS: single pane clear glass

COOLING EQUIP: Two single-zone fan and coil units serving all conditioned areas of the building. Units served by nominal 10 ton air cooled reciprocating chiller. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above and unit heater. Heating water is provided by 450 MBH heating water boiler in basement. See HVAC Equipment Lists for details.

LIGHTING: Surface mounted incandescent fixtures and fluorescent fixtures

DOMESTIC WATER HEATING: Electric water heater in building.

OTHER: 1-1/2 HP chilled water pump, and 3/4 HP heating water pump. See HVAC Equipment Lists for details.

REMARKS: Poor temperature control. Air-side equipment is maintenance intensive. All HVAC equipment appeared to be in poor condition.

BUILDING DESCRIPTION

NAME: Building 199

USE: Band Rehearsal Hall. Intermittent occupancy of approximately 60 people during weekdays, between 7:00 am and 5:00 pm.

GROSS AREA (SQ.FT.): 6,415 STORIES: 1 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION 1940

EXTERIOR WALLS: Stucco

ROOF: Pitched roof with shingles

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete and carpet

CEILINGS: Plaster

WINDOWS: single pane clear glass

COOLING EQUIP: One multi-zone air handling unit serves all conditioned areas of the building. Unit is served by nominal 15 ton air cooled reciprocating chiller. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. Heating water is provided by 200 MBH heating water boiler in basement. See HVAC Equipment Lists for details.

LIGHTING: Recessed and surface mounted fluorescent fixtures

DOMESTIC WATER HEATING: Gas fired hot water heater in building.

OTHER: 2 HP chilled water pump, and 1-1/2 HP heating water pump. See HVAC Equipment Lists for details.

REMARKS: Poor temperature control. Area is critical to humidity control because instruments are susceptible to humidity. All HVAC equipment appeared to be in fair condition, however most controls were not functioning properly.

BUILDING DESCRIPTION

NAME: Building 250

USE: NCO Academy, barracks, and future chef training school. Continuous occupancy of approximately 250 people between 5:00 pm and 7:00 a.m.

GROSS AREA (SQ.FT.): 42,955 STORIES: 3 DATE OF SURVEY: 3/13 to 3/17/95

DATE OF CONSTRUCTION: 1940

STRUCTURE: Masonry

EXTERIOR WALLS: Stucco

ROOF: Flat built-up roof

FLOOR CONSTRUCTION: Pier and beam

FLOOR FINISH: Concrete, tile and carpet

CEILINGS: Acoustical tile, gypsum wallboard, plaster

WINDOWS: single pane clear glass

COOLING EQUIP: Six multi-zone air handling units serve the barracks portion of building and one multi-zone air handling unit serves the future chef school. All units are served by a 100 ton nominal air cooled reciprocating chiller. See HVAC Equipment Lists for details.

HEATING EQUIP: See cooling equipment above. All heating coils in the air handlers are steam. Steam is provided by 1000 MBH steam boiler in basement. See HVAC Equipment Lists for details.

LIGHTING: Lay-in fluorescent fixtures in future chef school, admin, and barracks; surface mounted incandescent and fluorescent fixtures in barracks.

DOMESTIC WATER HEATING: Gas fired hot water heater in building.

OTHER: 7-1/2 HP chilled water pump. See HVAC Equipment Lists for details.

REMARKS: Poor temperature control, very hot inside during the field visit. The air cooled chiller appeared to be in good condition and all other HVAC equipment appeared to be in fair condition.

HVAC EQUIPMENT LIST FOR: FORT SAM HOUSTON, AREA 100
JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|----------------------|------|--|-----------------|-------------------|--------------|-------------|------|-----|------------|-----|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Hot Water Boiler | 1 | Rite #HD-85 watertube 618 MBH output | Bldg. 122 | 1985 | 850 MBH | 24 | 7 | 26 | | 193 |
| Heating Water Pump | 2 | B&G 32 gpm, 50 ft 1.5 HP | Bldg. 122 | 1985 | 1.12 KW | 24 | 7 | 26 | 8,242 | |
| Water Chiller | 1 | Trane #CGABC401AF01FK air cooled. recip. 40 tons | Bldg. 122 | 1985 | 70 KW | 24 | 7 | 26 | 92,395 | |
| Chilled Water Pump | 2 | N/A 3 HP | Bldg. 122 | 1985 | 2.24 KW | 24 | 7 | 26 | 19,784 | |
| Hot Water Boiler | 1 | Ajax natural draft, watertube 618 MBH output | Bldgs. 124, 125 | 1985 | 850 MBH | 24 | 7 | 26 | | 226 |
| Heating Water Pumps | 2 | Amtrol 23 GPM, 50 ft 1.5 HP | Bldgs. 124, 125 | 1985 | 1.12 KW | 24 | 7 | 26 | 9,730 | |
| Water Chiller | 1 | TSI #30-AOCD65 air cooled, recip. 50 tons | Bldgs. 124, 125 | 1985 | 88 KW | 24 | 7 | 26 | 112,912 | |
| Chilled Water Pumps | 2 | Mueller 53 gpm, 71 ft 3 HP | Bldgs. 124, 125 | 1985 | 2.24 KW | 24 | 7 | 26 | 19,784 | |
| Split System Furnace | 1 | RUUD 33 MBH output | Bldg 127 | 1985 | 45 MBH | 24 | 7 | 26 | 3,154 | 36 |
| Condensing Unit | 1 | RUUD #UACC-056JAS 4.5 ton, 7 EER | Bldg 127 | 1985 | 8.48 KW | 24 | 7 | 26 | 13,240 | |
| Hot Water Boiler | 1 | N/A 109 MBH output | Bldg. 128 | 1985 | 150 MBH | 24 | 7 | 26 | | 82 |
| Heating Water Pump | 1 | N/A 1/2 HP | Bldg. 128 | 1985 | 0.37 KW | 24 | 7 | 26 | 1,607 | |

HVAC EQUIPMENT LIST FOR: FORT SAM HOUSTON, AREA 100
JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|--------------------|------|--|----------------|-------------------|--------------------|-------------|------|-----|------------|-----|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | Trane #CGABC403AE00F air cooled, recip. 40 tons | Bldg. 128 | 1985 | 70 KW | 24 | 7 | 26 | 12,045 | |
| Chilled Water Pump | 1 | N/A 1.5 HP | Bldg. 128 | 1985 | 1.12 KW | 24 | 7 | 26 | 4,946 | |
| Hot Water Boiler | 1 | Ajax #WGH-150 forced draft, 5 HP blower 109 MBH output | Bldg. 133 | 1985 | 150 MBH 3.73 KW | 24 | 7 | 26 | 16,203 | 177 |
| Heating Water Pump | 1 | N/A 1/2 HP | Bldg. 133 | 1985 | 0.37 KW | 24 | 7 | 26 | 1,607 | |
| Water Chiller | 1 | Trane #CGABC256AF01FK air cooled, recip. 25 tons | Bldg. 133 | 1985 | 44 KW | 24 | 7 | 26 | 76,773 | |
| Chilled Water Pump | 1 | Aurora 40 gpm, 70 ft 1.5 HP | Bldg. 133 | 1985 | 1.12 KW | 24 | 7 | 26 | 4,946 | |
| Hot Water Boiler | 1 | Thermopak #GWE 825 watertube 596 MBH output | Bldgs 134, 135 | 1985 | 820 MBH | 24 | 7 | 26 | | 116 |
| Heating Water Pump | 1 | Armstrong, close coupled 1/2 HP | Bldgs 134, 135 | 1985 | 0.37 KW | 24 | 7 | 26 | 2,136 | |
| Water Chiller | 1 | Trane #CGACC306KANDD air cooled, recip. 30 tons | Bldgs 134, 135 | 1985 | 53 KW | 24 | 7 | 26 | 104,024 | |
| Chilled Water Pump | 1 | Armstrong, close coupled 63 ft, 1/2 HP | Bldgs 134, 135 | 1985 | 0.37 KW | 24 | 7 | 26 | 1,634 | |
| Hot Water Boiler | 1 | N/A 327 MBH output | Bldg. 142 | 1985 | 450 MBH | 24 | 7 | 26 | | 58 |
| Heating Water Pump | 1 | N/A 1/2 HP | Bldg. 142 | 1985 | 0.37 KW | 24 | 7 | 26 | 1,008 | |

HVAC EQUIPMENT LIST FOR: FORT SAM HOUSTON, AREA 100
JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|-----------------------|------|--|-------------|-------------------|--------------|-------------|------|-----|------------|-----|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | Carrier #30GT-020-500 air cooler, recip. 10 tons | Bldg. 142 | 1985 | 18 KW | 24 | 7 | 26 | 26,626 | |
| Chilled Water Pump | 1 | N/A 1 HP | Bldg. 142 | 1985 | 0.75 KW | 24 | 7 | 26 | 3,312 | |
| Water Chiller | 1 | N/A air cooled, recip. 45 tons | Bldg. 143 | 1985 | 79 KW | 24 | 7 | 26 | 113,775 | |
| Chilled Water Pump | 1 | N/A 3 HP | Bldg. 143 | 1985 | 2.24 KW | 24 | 7 | 26 | 9,892 | |
| Hot Water Boiler | 1 | N/A 596 MBH output | Bldg. 143 | 1985 | 820 MBH | 24 | 7 | 26 | | 76 |
| Heating Water Pump | 1 | N/A 1/2 HP | Bldg. 143 | 1985 | 0.37 KW | 24 | 7 | 26 | 1,039 | |
| Water Chiller | 1 | TSI #CAZCD 45 air cooled, recip. 45 tons | Bldg. 144 | 1985 | 79 KW | 24 | 7 | 26 | 113,775 | |
| Chilled Water Pump | 1 | Aurora 58 gpm, 86 ft 3 HP | Bldg. 144 | 1985 | 2.24 KW | 24 | 7 | 26 | 9,892 | |
| Hot Water Boiler | 1 | Bryan 596 MBH output | Bldg. 144 | 1985 | 820 MBH | 24 | 7 | 26 | | 112 |
| Heating Water Pump | 1 | B&G 1 HP | Bldg. 144 | 1985 | 0.75 KW | 24 | 7 | 26 | 1,904 | |
| Terminal Cooling Unit | 1 | Data Temp #DTA-0532-01 Russell #TD6.5 condenser 4 ton, 9 EER | Bldg. 144 | 1985 | 5.81 KW | 24 | 7 | 26 | 0 | |
| Window A/C Units | 23 | Friedrich #MDD YL 24H3513 2 ton clg, 22.4 MBH htg. 9 EER | Bldg. 145 | 1985 | 2.67 KW | 24 | 7 | 52 | 71,349 | |

HVAC EQUIPMENT LIST FOR: FORT SAM HOUSTON, AREA 100

JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|--------------------|------|---|----------------|-------------------|--------------|-------------|------|-----|------------|-----|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Hot Water Boiler | 1 | Teledyne Laars 596 MBH | Bldg. 146 | 1985 | 820 MBH | 24 | 7 | 52 | | 112 |
| Heating Water Pump | 1 | N/A 1 HP | Bldg. 146 | 1985 | 0.75 KW | 24 | 7 | 52 | 1,904 | |
| Water Chiller | 1 | Trane #CGABC404AF00F air cooled, recip. 40 tons | Bldg. 146 | 1985 | 70 KW | 24 | 7 | 52 | 107,387 | |
| Chilled Water Pump | 1 | Taco 83 gpm, 1.5 HP | Bldg. 146 | 1985 | 1.12 KW | 24 | 7 | 52 | 4,946 | |
| Hot Water Boiler | 1 | Ajax #WG-750-5 596 MBH output | Bldg. 147 | 1985 | 820 MBH | 24 | 7 | 52 | | 112 |
| Heating Water Pump | 1 | Taco 1 HP | Bldg. 147 | 1985 | 0.75 KW | 24 | 7 | 52 | 1,904 | |
| Water Chiller | 1 | McQuay #ALR 040AD air cooled, recip. 50 tons | Bldgs 147, 149 | 1985 | 88 KW | 24 | 7 | 26 | 170,355 | |
| Chilled Water Pump | 1 | Paco 5 HP | Bldgs 147, 149 | 1985 | 3.73 KW | 24 | 7 | 26 | 16,472 | |
| Hot Water Boiler | 1 | Thermopak #GWE 825 596 MBH output | Bldg. 149 | 1985 | 820 MBH | 24 | 7 | 26 | | 116 |
| Heating Water Pump | 1 | Paco 40 gpm, 40 ft 1 HP | Bldg. 149 | 1985 | 0.75 KW | 24 | 7 | 26 | 2,136 | |
| Hot Water Boiler | 1 | Ajax #WG-1750 1400 MBH output | Bldg. 197 | 1985 | 1,750 MBH | 24 | 7 | 26 | | 89 |
| Heating Water Pump | 1 | B&G 1 HP | Bldg. 197 | 1985 | 0.75 KW | 24 | 7 | 26 | 1,257 | |

HVAC EQUIPMENT LIST FOR: FORT SAM HOUSTON, AREA 100

JUNE 2, 1985

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|--------------------|------|---|-------------|-------------------|--------------|-------------|------|-----|------------|-----|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | York #LCHA 50-17A air cooled, recip. 50 tons | Bldg. 197 | 1985 | 88 KW | 24 | 7 | 26 | 113,383 | |
| Chilled Water Pump | 1 | Peerless 2 HP | Bldg. 197 | 1985 | 1.49 KW | 24 | 7 | 26 | 6,580 | |
| Hot Water Boiler | 1 | National #209-7 natural draft 327 MBH output | Bldg. 198 | 1985 | 450 MBH | 24 | 7 | 26 | | 38 |
| Heating Water Pump | 1 | Taco 3/4 HP | Bldg. 198 | 1985 | 0.56 KW | 24 | 7 | 26 | 1,106 | |
| Water Chiller | 1 | Trane #MAUG-C156-B air cooled, recip. 10 tons | Bldg. 198 | 1985 | 18 KW | 24 | 7 | 26 | 30,616 | |
| Chilled Water Pump | 1 | N/A 1.5 HP | Bldg. 198 | 1985 | 1.12 KW | 24 | 7 | 26 | 4,946 | |
| Hot Water Boiler | 1 | Ajax #WG-200-S natural draft 145 MBH output | Bldg. 199 | 1985 | 200 MBH | 24 | 7 | 26 | | 99 |
| Heating Water Pump | 1 | N/A 1.5 HP | Bldg. 199 | 1985 | 1.12 KW | 24 | 7 | 26 | 4,865 | |
| Water Chiller | 1 | RUUD #RAWC 150 CAS air cooled, recip. 15 tons | Bldg. 199 | 1985 | 26 KW | 24 | 7 | 26 | 43,319 | |
| Chilled Water Pump | 1 | N/A 2 HP | Bldg. 199 | 1985 | 1.49 KW | 24 | 7 | 26 | 6,580 | |
| Steam Boiler | 2 | Kewanee #581, series 3X 800 MBH output | Bldg. 250 | 1985 | 1,000 MBH | 24 | 7 | 26 | | 172 |
| | | | | 1985 | | | | | | |

HVAC EQUIPMENT LIST FOR: FORT SAM HOUSTON, AREA 100
JUNE 2, 1995

[illegible]

APPENDIX D
RECOMMENDED ECO CALCULATIONS

APPENDIX D
RECOMMENDED ECO CALCULATIONS

TABLE OF CONTENTS

| | |
|---|------|
| ECO-A, Replace Existing Central Chiller With New Electric Screw Chiller, Area 900 | D-1 |
| ECO-C, Replace Existing Central Chillers With New Electric Centrifugal Chiller, Area 1300 | D-19 |
| ECO-D, Replace Existing Central Boilers With High Efficiency Modular Boilers, Area 1300 | D-38 |
| ECO-E, Replace Existing Central Chiller With New Electric Screw Chiller, Area 2200 | D-44 |
| ECO-I, Replace Existing Individual Building Chillers With Central Chiller Plant, Area 100 | D-62 |

ENERGY CONSERVATION OPPORTUNITY (ECO)

ECO NO: A
DATE: 6/15/95
ECO TITLE: Replace Existing Central Chiller With New Electric Screw Chiller
INSTALLATION: Fort Sam Houston, San Antonio, Texas
LOCATION: Area 900, Building 902

A. Summary:

| | | |
|---------------------------|---------|----------|
| Electrical Energy Savings | 434 | MMBTU/yr |
| Electrical Demand Savings | 2,520 | \$/yr |
| Gas Energy Savings | 0 | MMBTU/yr |
| Total Energy Savings | 434 | MMBTU/yr |
| Total Cost Savings | 17,650 | \$/yr |
| Total Investment | 157,256 | \$ |
| Simple Payback | 8.9 | yrs |
| SIR | 2.08 | |

B. ECO Description:

Remove the existing 300 ton, R-11 centrifugal chiller in building 902 and replace it with a 300 ton, R-134a screw chiller. The existing 25 HP chilled water (CHW) pump, 15 HP condenser water (CND) pump and 15 HP cooling tower will be reused. The new chiller should be connected into the distribution piping at the existing chiller location. All existing controls and electrical services should be reconnected where possible. Specific requirements in these areas should be determined by the design engineer responsible for this project. To meet the current ASHRAE Standard 15, a refrigerant detection and ventilation system should be installed. This project will require engineering drawings and specifications, demolition and removal of the existing chiller and installation of the new chiller, associated wiring and controls.

C. Discussion:

The existing water cooled, centrifugal chiller was installed in 1985 and serves as the primary cooling system for the 21 buildings in the 900 area. It appears to be in fair condition but uses the R-11 refrigerant, which will no longer be manufactured as of January 1, 1996¹. To avoid the anticipated increasing operational costs over the life of this machine, it should either be retrofitted to use an approved refrigerant or replaced with a new machine that operates on one. The existing centrifugal machine can be retrofitted with no loss of capacity by replacing the impeller with one designed for HCFC-123 refrigerant. A company which produces these new impellers for existing R-11 centrifugal machines has provided cost estimates². However, since the machine is already ten years old, it is recommended that the facility replace it instead. A life cycle cost analysis performed on four different types of replacement chillers available determined that a dual screw chiller using R-134a would be the most economical choice over the life of the new machine. Computer simulations of the buildings served by this machine determined that the current installed capacity of 300 tons is required to adequately cool the buildings³. Therefore, no increase or decrease in the current chiller capacity is recommended at this time.

D. Savings Calculations:

1. *Energy Consumption And Savings*

The monthly peak demand and energy consumptions of the existing and proposed alternative chillers and auxiliary equipment were calculated using the Trace 600 computer program⁴. The buildings served by the existing chiller were modeled by the computer to provide a realistic load profile. Field data obtained from the buildings were used to create these computer building models⁵.

The 300 ton chiller alternatives which were compared included an electric centrifugal machine, an electric centrifugal with a variable frequency drive, a dual screw machine and a gas driven centrifugal machine. All proposed machines used R-134a. Full and part load performance data from York International were used in the computer simulations of the new chiller energy usages⁶. Equipment lists of the specific chillers and auxiliaries for each alternative modeled by the computer are shown on pages D-4 to D-7.

Once the computer simulations were completed, the total annual demand cost and energy consumption of each alternative were compared with that of the existing systems to determine the annual savings for each⁷. These savings calculations are shown on pages D-8 and D-9. The demand and energy savings values were used in the life cycle cost analysis for each alternative. The results of these savings calculations were as follows:

| Alternative | Chiller Type | Demand Savings \$/yr | Electrical Savings MMBTU/yr | Gas Savings MMBTU/yr |
|-------------|----------------------------|-------------------------|--------------------------------|-------------------------|
| A1 | Electric Centrifugal | 2,870 | 253 | 0 |
| A2 | Electric Centrifugal & VFD | 3,167 | 529 | 0 |
| A3 | Electric Screw | 2,520 | 434 | 0 |
| A4 | Gas Driven Centrifugal | 10,987 | 1,516 | -3,386 |

2. *Maintenance Cost Savings:*

By installing a new chiller in place of the existing one, the installation will save the cost of retrofitting the machine for the HCFC-123 refrigerant as mentioned previously. The cost of this retrofit was estimated to be \$248,085 on page D-10. This value was used in the life cycle cost analysis as a non-recurring savings for each alternative.

E. Cost Estimates

The total installation costs for each alternative chiller mentioned in this ECO were estimated on pages D-11 through D-14. These costs were used in the life cycle cost analysis for each alternative. The results of the costs estimates were as follows:

| Alternative | Chiller Type | Estimated Cost |
|-------------|----------------------------|----------------|
| A1 | Electric Centrifugal | \$153,242 |
| A2 | Electric Centrifugal & VFD | \$193,215 |
| A3 | Electric Screw | \$157,256 |
| A4 | Gas Driven Centrifugal | \$349,928 |

F. Life Cycle Cost Analysis.

A life cycle cost analysis was performed on each chiller alternative for this ECO using the Life Cycle Cost In Design (LCCID) computer program, and data from the previously mentioned calculations. A summary sheet for each life cycle cost analysis is shown on pages D-15 through D-18. The results of the alternative life cycle cost analysis were as follows:

| Alternative | Chiller Type | Payback Years | SIR |
|-------------|----------------------------|---------------|------|
| A1 | Electric Centrifugal | 9.1 | 2.05 |
| A2 | Electric Centrifugal & VFD | 10.2 | 1.97 |
| A3 | Electric Screw | 8.9 | 2.08 |
| A4 | Gas Driven Centrifugal | 14.6 | 1.11 |

Since the electric screw chiller has the highest SIR, it is recommended as the most economical choice to replace the existing machine. The data from the life cycle cost analysis for this alternative were included in the summary on page D-1.

REFERENCES

1. Per current EPA regulations on CFC refrigerants.
2. See Appendix G for chiller retrofit estimates from Northeastern Research And Engineering Corporation.
3. See Appendix B for Area 900 cooling system load profile.
4. See Appendix B for computer model input assumptions and data, and energy consumption output data.
5. See Appendix C for building field data and existing HVAC system data.
6. See Appendix G for manufacturer's equipment performance data from York International.
7. See Appendix A for utility cost analysis data, used in the savings calculations.

FOR: EC0-A1, FORT SAM HOUSTON, AREA 900
JUNE 2, 1995

[illegible]

JUNE 2, 1995

[illegible]

JUNE 2, 1995

[illegible]

FOR: EC0-A4, FORT SAM HOUSTON, AREA 900
JUNE 2, 1995

[illegible]

900 AREA

| ITEM | EXISTING CENTRAL CHILLER PLANT MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 202.4 | 202.7 | 223.5 | 225.8 | 208.0 | 115.8 | | | 444,056 | |
| CHW Pump | | | | | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | | | 82,358 | |
| CND Pump | | | | | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | | | 49,415 | |
| Cooling Tower | | | | | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | | | 45,510 | |
| Totals | | | | | 243.4 | 243.7 | 264.5 | 266.8 | 249.0 | 156.8 | | | 621,339 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 1,826 | 2,437 | 2,645 | 2,668 | 2,490 | 1,176 | | | | |

Total Demand 13,242 \$/yr

Total Energy 2,121 MMBTU/yr (electric)

Total Energy MMBTU/yr (gas)

| ITEM | ECO-A1: NEW ELECTRIC CENTRIFUGAL CHILLER MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 155.7 | 143.0 | 168.4 | 175.9 | 147.1 | 80.7 | | | 370,072 | |
| CHW Pump | | | | | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | | | 82,358 | |
| CND Pump | | | | | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | | | 49,415 | |
| Cooling Tower | | | | | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | | | 45,441 | |
| Total (KW) | | | | | 196.7 | 184.0 | 209.4 | 216.9 | 188.1 | 121.7 | | | 547,286 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 1,475 | 1,840 | 2,094 | 2,169 | 1,881 | 913 | | | | |

Total Demand 10,372 \$/yr

Demand Savings 2,870 \$/yr

Energy Savings 253 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

| ITEM | ECO-A2: NEW ELECTRIC CENTRIFUGAL CHILLER WITH VFD MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|---|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 144.1 | 138.0 | 166.7 | 175.3 | 141.8 | 69.5 | | | 289,309 | |
| CHW Pump | | | | | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | | | 82,358 | |
| CND Pump | | | | | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | | | 49,415 | |
| Cooling Tower | | | | | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | | | 45,401 | |
| Total (KW) | | | | | 185.1 | 179.0 | 207.7 | 216.3 | 182.8 | 110.5 | | | 466,483 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 1,388 | 1,790 | 2,077 | 2,163 | 1,828 | 829 | | | | |

Total Demand 10,075 \$/yr

Demand Savings 3,167 \$/yr

Energy Savings 529 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

900 AREA

| ITEM | ECO-A3: NEW ELECTRIC SCREW CHILLER MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 163.7 | 150.3 | 176.9 | 184.9 | 154.6 | 76.2 | | | 317,039 | |
| CHW Pump | | | | | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | | | 82,358 | |
| CND Pump | | | | | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | | | 49,415 | |
| Cooling Tower | | | | | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | | | 45,444 | |
| Total (KW) | | | | | 204.7 | 191.3 | 217.9 | 225.9 | 195.6 | 117.2 | | | 494,256 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 1,535 | 1,913 | 2,179 | 2,259 | 1,956 | 879 | | | | |

Total Demand 10,721 \$/yr

Demand Savings 2,520 \$/yr

Energy Savings 434 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

| ITEM | ECO-A4: NEW GAS ENGINE CENTRIFUGAL CHILLER MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | | | | | | | | | | 3,386 |
| CHW Pump | | | | | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | | | 82,358 | |
| CND Pump | | | | | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | | | 49,415 | |
| Cooling Tower | | | | | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | 11.2 | | | 45,352 | |
| Total (KW) | | | | | 41.0 | 41.0 | 41.0 | 41.0 | 41.0 | 41.0 | | | 177,125 | 3,386 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 308 | 410 | 410 | 410 | 410 | 308 | | | | |

Total Demand 2,255 \$/yr

Demand Savings 10,987 \$/yr

Energy Savings 1,516 MMBTU/yr (electric)

Energy Savings -3,386 MMBTU/yr (gas)

ENGINEER'S ESTIMATE OF PROBABLE COST

LOCATION:

AREA 900, BUILDING 902, FORT SAM HOUSTON

PROJECT NO:

03-0185.04

DATE:

BY: PIEPER, C.A.

CHECKED BY:

PROJECT DESCRIPTION: ECO-A - Upgrade Existing R-11 Chiller To Operate With R-123

| ITEM DESCRIPTION | QUANTITY | | LABOR | | MATERIAL | | TOTAL COST |
|--|------------|------------|-------------|---------|----------|------------|------------|
| | # of Units | Unit Meas. | Hrs / Unit | Rate | Total | Unit Price | |
| Retrofit of existing R-11 chiller to use R-123 | 1 | ea | 80.00 | \$28.00 | \$2,240 | \$175,000 | \$177,240 |
| R-123 detection system | 1 | ea | | | | \$5,000 | \$5,000 |
| Chiller 2-speed ventilation fan | 1 | ea | 16.00 | \$25.00 | \$400 | \$1,185 | \$1,585 |
| Chiller ventilation louver | 10 | sqt | 4.00 | \$28.00 | \$1,120 | \$27 | \$1,390 |
| Test & balance | 1 | ea | 4.00 | \$50.00 | \$200 | | \$200 |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | SUBTOTAL | \$3,960 | | | \$185,415 |
| | | | O & P @ 20% | | \$792 | | \$37,083 |
| | | | SUBTOTAL | \$4,752 | | | \$222,498 |
| | | | DESIGN @ 6% | | | | \$13,350 |
| | | | SUBTOTAL | | | | \$235,848 |
| | | | SIOH @ 5.5% | | | | \$12,237 |
| | | | TOTAL | | | | \$248,085 |

HUITT-ZOLLARS, INC.,
ENGINEERS / ARCHITECTS
 512 MAIN STREET, SUITE 1500
 FORT WORTH, TEXAS 76102-3922
 (817) 335-3000 * FAX (817) 335-1025

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
512 MAIN STREET, SUITE 1500
FORT WORTH, TEXAS 76102-3922
(817) 335-3000 * FAX (817) 335-1025

LOCATION:

AREA 900, BUILDING 902, FORT SAM HOUSTON

PROJECT NO:

03-0185.04

DATE:

6/16/95

CHECKED BY: KLK

BY: PIEPER C.A.

PROJECT DESCRIPTION: ECO-A1, Replace Existing Central Chiller With New Centrifugal Chiller

[illegible]

HUITT-ZOLLARS, INC.

ENGINEERS / ARCHITECTS

512 MAIN STREET, SUITE 1500

FORT WORTH, TEXAS 76102-3922

(817) 335-3000 * FAX (817) 335-1025

LOCATION:

AREA 900, BUILDING 902, FORT SAM HOUSTON

PROJECT NO: 03-0185.04

DATE:

6/16/95

BY: PIEPER, C.A.

CHECKED BY:

KLK

PROJECT DESCRIPTION: ECO-A2, Replace Existing Central Chiller With New Centrifugal Chiller And Variable Frequency Drive (VFD)

[illegible]

HUITT-ZOLLARS, INC.

ENGINEERS / ARCHITECTS

5512 MAIN STREET, SUITE 1500

FORT WORTH, TEXAS 76102-3922

(817) 335-3000 * FAX (817) 335-1025

ENGINEER'S ESTIMATE OF PROBABLE COST

LOCATION: AREA 900 , BUILDING 902, FORT SAM HOUSTON
PROJECT NO: 03-0185.04
DATE: 6/16/95
BY: PIEPER, C.A.
CHECKED BY: KLK

PROJECT DESCRIPTION: ECO-A3, Replace Existing Central Chiller With New Water Cooled Dual Screw Chiller

| ITEM DESCRIPTION | QUANTITY | | LABOR | | | MATERIAL | | TOTAL COST |
|---|------------|------------|------------|---------|----------|------------|----------|------------|
| | # of Units | Unit Meas. | Hrs / Unit | Rate | Total | Unit Price | Total | |
| Remove chiller | 1 | EA | 40 | \$24.64 | \$986 | \$500 | \$500 | \$1,486 |
| Install New Chiller 300 ton, water cooled, dual screw, R-134a | 1 | EA | 933 | \$24.64 | \$22,989 | \$81,000 | \$81,000 | \$103,989 |
| Pipe Assembly And Valves | 1 | EA | 42 | \$24.64 | \$1,035 | \$3,300 | \$3,300 | \$4,335 |
| RECONNECT: | | | | | | | | |
| Controls | 1 | JOB | 45 | \$24.64 | \$1,109 | \$100 | \$100 | \$1,209 |
| Electrical | 1 | JOB | 22 | \$24.64 | \$542 | \$200 | \$200 | \$742 |
| Refrigerant Detection System And Ventilation | 1 | JOB | 41 | \$24.64 | \$1,010 | \$4,000 | \$4,000 | \$5,010 |
| Test & Balance and Start-up | 1 | JOB | 20 | \$28.00 | \$560 | \$200 | \$200 | \$760 |

| | | | |
|------------------------|----------|-----------|-----------|
| SUBTOTAL | \$28,231 | \$89,300 | \$117,531 |
| O & P @ 20% | \$5,646 | \$17,860 | \$23,506 |
| SUBTOTAL | \$33,877 | \$107,160 | \$141,037 |
| DESIGN @ 6% | | | \$8,462 |
| SUBTOTAL | | | \$149,499 |
| SIQH @ 5.5% | | | \$7,757 |
| TOTAL | | | \$157,256 |

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
 512 MAIN STREET, SUITE 1500
 FORT WORTH, TEXAS 76102-3922
 (817) 335-3000 * FAX (817) 335-1025

LOCATION:

AREA 900, BUILDING 902, FORT SAM HOUSTON

PROJECT NO:

03-0185.04

DATE:

6/16/95

CHECKED BY:

KLK

PROJECT DESCRIPTION: ECO-A4, Replace Existing Central Chiller With New Gas Engine Driven Chiller

[illegible]

HUITT-ZOLLARS, INC.

ENGINEERS / ARCHITECTS

512 MAIN STREET, SUITE 1500

FORT WORTH, TEXAS 76102-3922

(817) 335-3000 * FAX (817) 335-1025

LIFE CYCLE COST ANALYSIS SUMMARY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: FSH
 INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3
 PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY
 FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-A1
 ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|----|---------|
| A. CONSTRUCTION COST | \$ | 137437. | | |
| B. SIOH | \$ | 7559. | | |
| C. DESIGN COST | \$ | 8246. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 153242. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | | | \$ | 153242. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 253. | \$ 1589. | 15.08 | \$ 23960. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 2870. | 14.88 | \$ 42706. |
| N. TOTAL | | 253. | \$ 4459. | | \$ 66665. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-------|
| A. ANNUAL RECURRING (+/-) | | |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | \$ 0. |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+) COST(-) (4) |
|-------------------|------------------------------|-----------------|------------------------|---|
| 1. REFRIG UPGRADE | \$ 248085. | 0 | 1.00 | 248085. |
| d. TOTAL | \$ 248085. | | | 248085. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 248085.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 16863.

5. SIMPLE PAYBACK PERIOD (1G/4) 9.09 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 314750.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 2.05
 (IF < 1 PROJECT DOES NOT QUALIFY)

** Project does not qualify for ECIP funding; 4,5,6 for information only.

LIFE CYCLE COST ANALYSIS SUMMARY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: FSH
 INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3
 PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY
 FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-A2
 ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|---------|
| A. CONSTRUCTION COST | \$ | 173287. | |
| B. SIOH | \$ | 9531. | |
| C. DESIGN COST | \$ | 10397. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 193215. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | 193215. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 529. | \$ 3322. | 15.08 | \$ 50098. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 3167. | 14.88 | \$ 47125. |
| N. TOTAL | | 529. | \$ 6489. | | \$ 97223. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-------|
| A. ANNUAL RECURRING (+/-) | | |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | \$ 0. |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+) COST(-) (4) |
|-------------------|------------------------------|-----------------|------------------------|---|
| 1. REFRIG UPGRADE | \$ 248085. | 0 | 1.00 | 248085. |
| d. TOTAL | \$ 248085. | | | 248085. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 248085.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 18893.

5. SIMPLE PAYBACK PERIOD (1G/4) 10.23 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 345308.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.79
 (IF < 1 PROJECT DOES NOT QUALIFY)

** Project does not qualify for ECIP funding; 4,5,6 for information only.

LIFE CYCLE COST ANALYSIS SUMMARY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: FSH
 INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3
 PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY
 FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-A3
 ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|---------|
| A. CONSTRUCTION COST | \$ | 141037. | |
| B. SIOH | \$ | 7757. | |
| C. DESIGN COST | \$ | 8462. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 157256. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | 157256. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 434. | \$ 2726. | 15.08 | \$ 41101. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 2520. | 14.88 | \$ 37498. |
| N. TOTAL | | 434. | \$ 5246. | | \$ 78598. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-------|
| A. ANNUAL RECURRING (+/-) | | |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | \$ 0. |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTOR (3) | DISCOUNTED SAVINGS(+) COST(-) (4) |
|-------------------|------------------------------|-----------------|-------------------------|---|
| 1. REFRIG UPGRADE | \$ 248085. | 0 | 1.00 | 248085. |
| d. TOTAL | \$ 248085. | | | 248085. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 248085.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 17650.

5. SIMPLE PAYBACK PERIOD (1G/4) 8.91 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 326683.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 2.08
 (IF < 1 PROJECT DOES NOT QUALIFY)

*** Project does not qualify for ECIP funding; 4,5,6 for information only.

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-A4

ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|--|---------|
| A. CONSTRUCTION COST | \$ | 313837. | | |
| B. SIOH | \$ | 17261. | | |
| C. DESIGN COST | \$ | 18830. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 349928. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | | 349928. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 1516. | \$ 9520. | 15.08 | \$ 143569. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | -3386. | \$ -9007. | 18.58 | \$ -167346. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 10987. | 14.88 | \$ 163487. |
| N. TOTAL | | -1870. | \$ 11501. | | \$ 139710. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|-------|
| A. ANNUAL RECURRING (+/-) | | | |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | \$ 0. |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | | \$ 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTOR (3) | DISCOUNTED SAVINGS(+) COST(-) (4) |
|-------------------|------------------------------|-----------------|-------------------------|---|
| 1. REFRIG UPGRADE | \$ 248085. | 0 | 1.00 | 248085. |
| d. TOTAL | \$ 248085. | | | 248085. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 248085.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 23905.

5. SIMPLE PAYBACK PERIOD (1G/4) 14.64 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 387795.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.11
(IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

ENERGY CONSERVATION OPPORTUNITY (ECO)

ECO NO: C
DATE: 8/13/95
ECO TITLE: Replace Existing Central Chillers With New Electric Centrifugal Chiller
INSTALLATION: Fort Sam Houston, San Antonio, Texas
LOCATION: Area 1300, Building 1377

A. Summary:

| | | |
|---------------------------|---------|----------|
| Electrical Energy Savings | 3,424 | MMBTU/yr |
| Electrical Demand Savings | 13,914 | \$/yr |
| Gas Energy Savings | 0 | MMBTU/yr |
| Total Energy Savings | 3,424 | MMBTU/yr |
| Total Cost Savings | 56,936 | \$/yr |
| Total Investment | 479,191 | \$ |
| Simple Payback | 8.4 | yrs |
| SIR | 1.98 | |

B. ECO Description:

Remove the two 600 ton, R-11 centrifugal chillers in building 1377 which were installed in 1972, and replace them with one R-134 centrifugal chiller, rated at 827 tons. The two existing chilled water pumps and condenser water pumps serving the existing chillers should be removed. Install a new chilled water pump and a new condenser water pump, each rated at 75 HP, to serve the new chiller. The new chiller should be connected into the distribution piping at the existing location. New chilled water supply and return headers should be installed to join together the existing distribution systems serving building 1350 and the other seven buildings in the 1300 area. This will create a single chilled water distribution system to be served by the new chiller and the existing 438 ton chiller which was installed in 1983 to serve building 1350. All existing controls and electrical services should be reconnected where possible. Specific requirements in these areas should be determined by the design engineer responsible for this project. To meet the current ASHRAE Standard 15, a refrigerant detection and ventilation system should be installed. This project will require engineering drawings and specifications, demolition and removal of the existing chillers and pumps, and installation of the new chillers, pumps, associated wiring and controls.

C. Discussion:

There are currently two independent chilled water distribution systems serving the 1300 area, one for building 1350 and the other for seven other buildings. These two systems should be combined into one system to conserve energy in the central plant. This can be accomplished by installing common CHW supply and return headers in the central plant. The existing centrifugal chiller serving building 1350 was installed in 1983, is rated at 438 tons and appears to be in good condition. The two existing centrifugal chillers serving the other seven buildings were installed in 1972, are rated at 600 tons each, and appear to be near the end of their useful life. Also, all three chillers use the R-11 refrigerant, which will no longer be manufactured as of January 1, 1996¹. To avoid the anticipated increasing operational costs over the life of these machines, they should either be retrofitted to use an approved refrigerant or replaced with new machines that operate on one. The existing centrifugal machines can be retrofitted with no loss of capacity by replacing the impellers with new ones designed for HCFC-123 refrigerant. A company which produces these new impellers for existing R-11 centrifugal machines has provided cost estimates². However, since the older machines are already over twenty years old, it is recommended that the facility replace them instead. A life cycle cost analysis performed on four different types of

replacement chillers available determined that a single electric centrifugal chiller using R-134 would be the most economical choice over the life of the machine. Computer simulations of the buildings served by this machine determined that the current installed capacity of 1,638 tons is more than what is required to adequately cool the buildings³. Therefore, the new combined capacity is recommended to be 1,265 tons to more nearly match the building cooling load.

D. Savings Calculations:

1. *Energy Consumption And Savings*

The monthly peak demand and energy consumptions of the existing and proposed alternative chillers and auxiliary equipment were calculated using the Trace 600 computer program⁴. The buildings served by the existing chillers were modeled by the computer to provide a realistic load profile. Field data obtained from the buildings were used to create these computer building models⁵.

The 827 ton chiller alternatives which were compared included an electric centrifugal machine, an electric centrifugal with a variable frequency drive, a dual screw machine and a gas driven centrifugal machine. All proposed machines used R-134. Full load performance data from York International were used in the computer simulations of the new chiller energy usages⁶. Equipment lists of the specific chillers and auxiliaries for each alternative modeled by the computer are shown on pages E-22 to E-25.

Once the computer simulations were completed, the total annual demand cost and energy consumption of each alternative were compared with that of the existing systems to determine the annual savings for each⁷. These savings calculations are shown on pages E-26 through E-28. The demand and energy savings values were used in the life cycle cost analysis for each alternative. The results of these savings calculations were as follows:

| Alternative | Chiller Type | Demand Savings \$/yr | Electrical Savings MMBTU/yr | Gas Savings MMBTU/yr |
|-------------|----------------------------|-------------------------|--------------------------------|-------------------------|
| C1 | Electric Centrifugal | 13,914 | 3,424 | 0 |
| C2 | Electric Centrifugal & VFD | 14,532 | 3,615 | 0 |
| C3 | Electric Screw | 11,345 | 3,250 | 0 |
| C4 | Gas Driven Centrifugal | 38,536 | 6,386 | -8,886 |

2. *Maintenance Cost Savings:*

By installing a new chiller in place of the two oldest existing ones, the installation will save the cost of retrofitting the machines for the HCFC-123 refrigerant as mentioned previously. The cost of this retrofit was estimated to be \$384,882 on page E-29. This value was used in the life cycle cost analysis as a non-recurring savings for each alternative.

E. Cost Estimates

The total installation costs for each alternative chiller mentioned in this ECO were estimated on pages E-30 through E-33. These costs were used in the life cycle cost analysis for each alternative. The results of the costs estimates were as follows:

| Alternative | Chiller Type | Estimated Cost |
|-------------|----------------------------|----------------|
| C1 | Electric Centrifugal | \$479,191 |
| C2 | Electric Centrifugal & VFD | \$633,919 |
| C3 | Electric Screw | \$653,398 |
| C4 | Gas Driven Centrifugal | \$765,561 |

F. Life Cycle Cost Analysis.

A life cycle cost analysis was performed on each chiller alternative for this ECO using the Life Cycle Cost In Design (LCCID) computer program, and data from the previously mentioned calculations. A summary sheet for each life cycle cost analysis is shown on pages E-34 through E-37. The results of the alternative life cycle cost analysis were as follows:

| Alternative | Chiller Type | Payback Years | SIR |
|-------------|----------------------------|---------------|------|
| C1 | Electric Centrifugal | 8.4 | 1.98 |
| C2 | Electric Centrifugal & VFD | 10.7 | 1.54 |
| C3 | Electric Screw | 12.2 | 1.37 |
| C4 | Gas Driven Centrifugal | 10.0 | 1.51 |

Since the electric centrifugal chillers have the highest SIR, they are recommended as the most economical choice to replace the existing machines. The data from the life cycle cost analysis for this alternative were included in the summary on page E-19.

REFERENCES

1. Per current EPA regulations on CFC refrigerants.
2. See Appendix G for chiller retrofit estimates from Northeastern Research And Engineering Corporation.
3. See Appendix B for Area 1300 cooling system load profile.
4. See Appendix B for computer model input assumptions and data, and energy consumption output data.
5. See Appendix C for building field data and existing HVAC system data.
6. See Appendix G for manufacturer's equipment performance data from York International.
7. See Appendix A for utility cost analysis data, used in the savings calculations.

PROPOSED HVAC EQUIPMENT LIST FOR: ECO-C1, FORT SAM HOUSTON, AREA 1300
JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|----------------------|------|--|-------------|-------------------|--------------|-------------|------|-----|------------|-----|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | Carrier #19DK 78942P water cooled, centrifugal, 438 tons, R-11 | Area 1300 | 1983 | 329 KW | 24 | 7 | 26 | 517,565 | |
| Water Chiller | 1 | York, electric water cooled, centrifugal, 827 Tons, R-134a | Area 1300 | New | 479 KW | 24 | 7 | 26 | 867,974 | |
| Chilled Water Pump | 1 | Allis Chalmers 775 gpm, 114 ft 40 HP | Area 1300 | 1983 | 29.84 KW | 24 | 7 | 26 | 85,104 | |
| Chilled Water Pump | 1 | 1670 gpm, 114 ft 75 HP | Area 1300 | New | 55.95 KW | 24 | 7 | 26 | 151,513 | |
| Condenser Water Pump | 1 | Allis Chalmers 1314 gpm, 30 ft 30 HP | Area 1300 | 1983 | 22.38 KW | 24 | 7 | 26 | 63,828 | |
| Condenser Water Pump | 1 | 2785 gpm, 70 ft 75 HP | Area 1300 | New | 55.95 KW | 24 | 7 | 26 | 151,513 | |
| Cooling Tower | 1 | Marley #324T induced draft, 2-35 HP fans | Area 1300 | Exist. | 52.22 KW | 24 | 7 | 26 | 141,358 | |
| Cooling Tower | 1 | Marley induced draft, 20 HP fan | Area 1300 | Exist. | 14.92 KW | 24 | 7 | 26 | 37,204 | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

PROPOSED HVAC EQUIPMENT LIST FOR: ECO-C2, FORT SAM HOUSTON, AREA 1300
JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|----------------------|------|---|-------------|-------------------|--------------|-------------|------|-----|------------|-----|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | Carrier #19DK 78942P water cooled, centrifugal, 438 tons, R-11 | Area 1300 | 1983 | 329 KW | 24 | 7 | 26 | 517,565 | |
| Water Chiller | 1 | York, electric, VFD water cooled, centrifugal, 827 Tons, R-134a | Area 1300 | New | 479 KW | 24 | 7 | 26 | 811,935 | |
| Chilled Water Pump | 1 | Allis Chalmers 775 gpm, 114 ft 40 HP | Area 1300 | 1983 | 29.84 KW | 24 | 7 | 26 | 85,104 | |
| Chilled Water Pump | 1 | 1670 gpm, 114 ft 75 HP | Area 1300 | New | 55.95 KW | 24 | 7 | 26 | 151,513 | |
| Condenser Water Pump | 1 | Allis Chalmers 1314 gpm, 30 ft 30 HP | Area 1300 | 1983 | 22.38 KW | 24 | 7 | 26 | 63,828 | |
| Condenser Water Pump | 1 | 2785 gpm, 70 ft 75 HP | Area 1300 | New | 55.95 KW | 24 | 7 | 26 | 151,513 | |
| Cooling Tower | 1 | Marley #324T induced draft, 2-35 HP fans | Area 1300 | Exist. | 52.22 KW | 24 | 7 | 26 | 141,412 | |
| Cooling Tower | 1 | Marley induced draft, 20 HP fan | Area 1300 | Exist. | 14.92 KW | 24 | 7 | 26 | 37,204 | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

PROPOSED HVAC EQUIPMENT LIST FOR: ECO-C3, FORT SAM HOUSTON, AREA 1300
JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|----------------------|------|--|-------------|-------------------|--------------|-------------|------|-----|------------|-----|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | Carrier #19DK 78942P water cooled, centrifugal, 438 tons, R-11 | Area 1300 | 1983 | 329 KW | 24 | 7 | 26 | 517,565 | |
| Water Chiller | 1 | York, electric water cooled, dual screw 827 Tons, R-134a | Area 1300 | New | 529 KW | 24 | 7 | 26 | 916,945 | |
| Chilled Water Pump | 1 | Allis Chalmers 775 gpm, 114 ft 40 HP | Area 1300 | 1983 | 29.84 KW | 24 | 7 | 26 | 85,104 | |
| Chilled Water Pump | 1 | 1670 gpm, 114 ft 75 HP | Area 1300 | New | 55.95 KW | 24 | 7 | 26 | 151,513 | |
| Condenser Water Pump | 1 | Allis Chalmers 1314 gpm, 30 ft 30 HP | Area 1300 | 1983 | 22.38 KW | 24 | 7 | 26 | 63,828 | |
| Condenser Water Pump | 1 | 2785 gpm, 70 ft 75 HP | Area 1300 | New | 55.95 KW | 24 | 7 | 26 | 151,513 | |
| Cooling Tower | 1 | Marley #324T induced draft, 2-35 HP fans | Area 1300 | Exist. | 52.22 KW | 24 | 7 | 26 | 143,448 | |
| Cooling Tower | 1 | Marley induced draft, 20 HP fan | Area 1300 | Exist. | 14.92 KW | 24 | 7 | 26 | 37,204 | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

PROPOSED HVAC EQUIPMENT LIST FOR: ECO-C4, FORT SAM HOUSTON, AREA 1300
JUNE 2, 1995

| ITEM | QTY. | DESCRIPTION | AREA SERVED | YEAR INSTALLED | FULL LOAD | OPER. TIMES | | | ANNUAL USE | |
|----------------------|------|--|-------------|-------------------|--------------|-------------|------|-----|------------|-------|
| | | | | | | HRS | DAYS | WKS | KWH | MCF |
| Water Chiller | 1 | Carrier #19DK 78942P water cooled, centrifugal, 438 tons, R-11 | Area 1300 | 1983 | 329 KW | 24 | 7 | 26 | 517,565 | |
| Water Chiller | 1 | York, gas fired water cooled, centrifugal 827 Tons, R-134a | Area 1300 | New | 5,127 MBH | 24 | 7 | 26 | | 8,886 |
| Chilled Water Pump | 1 | Allis Chalmers 775 gpm, 114 ft 40 HP | Area 1300 | 1983 | 29.84 KW | 24 | 7 | 26 | 85,104 | |
| Chilled Water Pump | 1 | 1670 gpm, 114 ft 75 HP | Area 1300 | New | 55.95 KW | 24 | 7 | 26 | 151,513 | |
| Condenser Water Pump | 1 | Allis Chalmers 1314 gpm, 30 ft 30 HP | Area 1300 | 1983 | 22.38 KW | 24 | 7 | 26 | 63,828 | |
| Condenser Water Pump | 1 | 2785 gpm, 70 ft 75 HP | Area 1300 | New | 55.95 KW | 24 | 7 | 26 | 151,513 | |
| Cooling Tower | 1 | Marley #324T induced draft, 2-35 HP fans | Area 1300 | Exist. | 52.22 KW | 24 | 7 | 26 | 141,358 | |
| Cooling Tower | 1 | Marley induced draft, 20 HP fan | Area 1300 | Exist. | 14.92 KW | 24 | 7 | 26 | 37,204 | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |
| | | | | | | | | | | |

1300 AREA

| ITEM | EXISTING CENTRAL CHILLER PLANT MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|--------|--------|--------|--------|--------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 524.9 | 541.9 | 549.8 | 556.5 | 540.7 | 371.9 | | | 1,464,005 | |
| Water Chiller | | | | | 165.4 | 210.0 | 305.1 | 347.3 | 234.0 | | | | 130,286 | |
| Water Chiller | | | | | 286.9 | 267.5 | 299.6 | 319.9 | 290.4 | 193.8 | | | 595,685 | |
| CHW Pump | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 131,773 | |
| CHW Pump | | | | | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | | | 82,358 | |
| CHW Pump | | | | | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | 18.6 | | | 82,358 | |
| CND Pump | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 131,773 | |
| CND Pump | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | | 31,153 | |
| CND Pump | | | | | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | | | 98,830 | |
| Cooling Tower | | | | | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | | | 210,817 | |
| Cooling Tower | | | | | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | | | 60,215 | |
| Totals | | | | | 1193.3 | 1235.5 | 1370.6 | 1439.8 | 1281.2 | 752.0 | | | 3,019,253 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 8,950 | 12,355 | 13,706 | 14,398 | 12,812 | 5,640 | | | | |

Total Demand 67,861 \$/yr

Total Energy 10,305 MMBTU/yr (electric)

Total Energy MMBTU/yr (gas)

| ITEM | ECO-C1: NEW ELECTRIC CENTRIFUGAL CHILLER MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|--------|--------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 268.8 | 287.1 | 326.8 | 330.2 | 307.2 | 276.6 | | | 517,565 | |
| Water Chiller | | | | | 437.4 | 453.1 | 475.2 | 479.0 | 446.8 | 373.4 | | | 867,974 | |
| CHW Pump | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 85,104 | |
| CHW Pump | | | | | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | | | 151,513 | |
| CND Pump | | | | | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | | | 63,828 | |
| CND Pump | | | | | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | | | 151,513 | |
| Cooling Tower | | | | | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | | | 37,204 | |
| Cooling Tower | | | | | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | | | 141,358 | |
| Total (KW) | | | | | 937.5 | 971.5 | 1033.3 | 1040.5 | 985.3 | 881.3 | | | 2,016,059 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 7,031 | 9,715 | 10,333 | 10,405 | 9,853 | 6,610 | | | | |

Total Demand 53,947 \$/yr

Demand Savings 13,914 \$/yr

Energy Savings 3,424 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

1300 AREA

| ITEM | ECO-C2: NEW ELECTRIC CENTRIFUGAL CHILLER WITH VFD MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|---|------|------|------|-------|-------|--------|--------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 268.8 | 287.1 | 326.8 | 330.2 | 307.2 | 276.6 | | | 517,565 | |
| Water Chiller | | | | | 419.5 | 441.7 | 472.9 | 479.0 | 437.2 | 340.0 | | | 811,935 | |
| CHW Pump | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 85,104 | |
| CHW Pump | | | | | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | | | 151,513 | |
| CND Pump | | | | | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | | | 63,828 | |
| CND Pump | | | | | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | | | 151,513 | |
| Cooling Tower | | | | | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | | | 37,204 | |
| Cooling Tower | | | | | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | | | 141,412 | |
| Total (KW) | | | | | 919.6 | 960.1 | 1031.0 | 1040.5 | 975.7 | 847.9 | | | 1,960,074 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 6,897 | 9,601 | 10,310 | 10,405 | 9,757 | 6,359 | | | | |

Total Demand 53,329 \$/yr

Demand Savings 14,532 \$/yr

Energy Savings 3,615 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

| ITEM | ECO-C3: NEW ELECTRIC SCREW CHILLER MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|--------|--------|--------|--------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 268.8 | 287.1 | 326.8 | 330.2 | 307.2 | 276.6 | | | 517,565 | |
| Water Chiller | | | | | 483.0 | 500.4 | 524.8 | 529.0 | 493.4 | 412.3 | | | 916,945 | |
| CHW Pump | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 85,104 | |
| CHW Pump | | | | | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | | | 151,513 | |
| CND Pump | | | | | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | | | 63,828 | |
| CND Pump | | | | | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | | | 151,513 | |
| Cooling Tower | | | | | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | | | 37,204 | |
| Cooling Tower | | | | | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | | | 143,448 | |
| Total (KW) | | | | | 983.1 | 1018.8 | 1082.9 | 1090.5 | 1031.9 | 920.2 | | | 2,067,120 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 7,373 | 10,188 | 10,829 | 10,905 | 10,319 | 6,902 | | | | |

Total Demand 56,516 \$/yr

Demand Savings 11,345 \$/yr

Energy Savings 3,250 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

1300 AREA

| ITEM | ECO-C4: NEW GAS ENGINE CENTRIFUGAL CHILLER MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 268.8 | 287.1 | 326.8 | 330.2 | 307.2 | 276.6 | | | 517,565 | |
| Water Chiller | | | | | | | | | | | | | | 8,886 |
| CHW Pump | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 85,104 | |
| CHW Pump | | | | | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | | | 151,513 | |
| CND Pump | | | | | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | | | 63,828 | |
| CND Pump | | | | | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | 56.0 | | | 151,513 | |
| Cooling Tower | | | | | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | | | 37,204 | |
| Cooling Tower | | | | | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | 52.2 | | | 141,358 | |
| Total (KW) | | | | | 500.1 | 518.4 | 558.1 | 561.5 | 538.5 | 507.9 | | | 1,148,085 | 8,886 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 3,751 | 5,184 | 5,581 | 5,615 | 5,385 | 3,809 | | | | |

Total Demand 29,325 \$/yr

Demand Savings 38,536 \$/yr

Energy Savings 6,386 MMBTU/yr (electrical)

Energy Savings -8,886 MMBTU/yr (gas)

LOCATION:

AREA 1300, BUILDING 1377, FORT SAM HOUSTON

PROJECT NO: 03-0185.04

DATE:

8/16/95

CHECKED BY:

KLK

PROJECT DESCRIPTION: ECO-C, Upgrade Two Existing R-11 Chillers To Operate On R-123

[illegible]

HUITT-ZOLLARS, INC.

ENGINEERS / ARCHITECTS

512 MAIN STREET, SUITE 1500

FORT WORTH, TEXAS 76102-3922

(817) 335-3000 * FAX (817) 335-1025

ENGINEER'S ESTIMATE OF PROBABLE COST

LOCATION: AREA 1300 , BUILDING 1377, FORT SAM HOUSTON
PROJECT NO: 03-0185.04
DATE: 8/16/95
BY: PIEPER, C.A.
CHECKED BY: KLK

PROJECT DESCRIPTION: ECO-C1, Replace Existing Central Chillers With New Water Cooled Centrifugal Chiller

| ITEM DESCRIPTION | QUANTITY | | LABOR | | | MATERIAL | | TOTAL COST |
|--|------------|------------|------------|---------|-----------|------------|-----------|------------|
| | # of Units | Unit Meas. | Hrs / Unit | Rate | Total | Unit Price | Total | |
| Remove Pumps | 2 | EA | 6 | \$24.64 | \$296 | | | \$296 |
| Remove chillers | 2 | EA | 40 | \$24.64 | \$1,971 | \$500 | \$1,000 | \$2,971 |
| Install New Chiller 827 ton, water cooled, centrifugal, R-134a | 1 | EA | 2,609 | \$24.64 | \$64,286 | \$226,800 | \$226,800 | \$291,086 |
| Pipe Assembly And Valves | 1 | EA | 168 | \$24.64 | \$4,140 | \$10,000 | \$10,000 | \$14,140 |
| RECONNECT: | | | | | | | | |
| Controls | 1 | JOB | 190 | \$24.64 | \$4,682 | \$400 | \$400 | \$5,082 |
| Electrical | 1 | JOB | 92 | \$24.64 | \$2,267 | \$800 | \$800 | \$3,067 |
| Refrigerant Detection System | 1 | JOB | 20 | \$24.64 | \$493 | \$4,500 | \$4,500 | \$4,993 |
| Water Pump 75 HP | 2 | EA | 132 | \$24.64 | \$6,505 | \$13,500 | \$27,000 | \$33,505 |
| Test & Balance and Start-up | 1 | JOB | 100 | \$28.00 | \$2,800 | \$200 | \$200 | \$3,000 |
| SUBTOTAL | | | | | \$87,440 | | \$270,700 | \$358,140 |
| O & P @ 20% | | | | | \$17,488 | | \$54,140 | \$71,628 |
| SUBTOTAL | | | | | \$104,928 | | \$324,840 | \$429,768 |
| DESIGN @ 6% | | | | | | | | \$25,786 |
| SUBTOTAL | | | | | | | | \$455,554 |
| SIOH @ 5.5% | | | | | | | | \$23,637 |
| TOTAL | | | | | | | | \$479,191 |

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
 512 MAIN STREET, SUITE 1500
 FORT WORTH, TEXAS 76102-3922
 (817) 335-3000 * FAX (817) 335-1025

ENGINEER'S ESTIMATE OF PROBABLE COST

LOCATION: AREA 1300, BUILDING 1377, FORT SAM HOUSTON
PROJECT NO: 03-0185.04
DATE: 8/16/95
BY: PIEPER, C.A.
CHECKED BY: KLK

PROJECT DESCRIPTION: ECO-C2, Replace Existing Central Chiller With New Centrifugal Chiller And Variable Frequency Drive (VFD)

| ITEM DESCRIPTION | QUANTITY | | LABOR | | | MATERIAL | | TOTAL COST |
|--|------------|------------|------------|---------|-----------|------------|-----------|------------|
| | # of Units | Unit Meas. | Hrs / Unit | Rate | Total | Unit Price | Total | |
| Remove Pumps | 2 | EA | 6 | \$24.64 | \$296 | | | \$296 |
| Remove chillers | 2 | EA | 40 | \$24.64 | \$1,971 | \$500 | \$1,000 | \$2,971 |
| Install New Chiller 827 ton, water cooled, centrifugal, R-134a | 1 | EA | 2,609 | \$24.64 | \$64,286 | \$226,800 | \$226,800 | \$291,086 |
| Adder For VFD | 1000 | HP | | | | \$115 | \$115,000 | \$115,000 |
| Pipe Assembly And Valves | 1 | EA | 168 | \$24.64 | \$4,140 | \$10,000 | \$10,000 | \$14,140 |
| RECONNECT: | | | | | | | | |
| Controls | 1 | JOB | 190 | \$24.64 | \$4,682 | \$400 | \$400 | \$5,082 |
| Electrical | 1 | JOB | 118 | \$24.64 | \$2,908 | \$800 | \$800 | \$3,708 |
| Refrigerant Detection System | 1 | JOB | 20 | \$24.64 | \$493 | \$4,500 | \$4,500 | \$4,993 |
| Water Pump 75 HP | 2 | EA | 132 | \$24.64 | \$6,505 | \$13,500 | \$27,000 | \$33,505 |
| Test & Balance and Start-up | 1 | JOB | 100 | \$28.00 | \$2,800 | \$200 | \$200 | \$3,000 |
| SUBTOTAL | | | | | \$88,081 | | \$385,700 | \$473,781 |
| O & P @ 20% | | | | | \$17,616 | | \$77,140 | \$94,756 |
| SUBTOTAL | | | | | \$105,697 | | \$462,840 | \$568,537 |
| DESIGN @ 6% | | | | | | | | \$34,112 |
| SUBTOTAL | | | | | | | | \$602,649 |
| SIOH @ 5.5% | | | | | | | | \$31,270 |
| TOTAL | | | | | | | | \$633,919 |

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
 512 MAIN STREET, SUITE 1500
 FORT WORTH, TEXAS 76102-3922
 (817) 335-3000 * FAX (817) 335-1025

ENGINEER'S ESTIMATE OF PROBABLE COST

LOCATION: AREA 1300 , BUILDING 1377, FORT SAM HOUSTON
PROJECT NO: 03-0185.04
DATE: 8/16/95
BY: PIEPER, C.A.
CHECKED BY: KLK

PROJECT DESCRIPTION: ECO-C3, Replace Existing Central Chillers With New Water Cooled Dual Screw Chillers

| ITEM DESCRIPTION | QUANTITY | | LABOR | | | MATERIAL | | TOTAL COST |
|---|------------|------------|------------|---------|-----------|------------|-----------|------------|
| | # of Units | Unit Meas. | Hrs / Unit | Rate | Total | Unit Price | Total | |
| Remove Pumps | 2 | EA | 6 | \$24.64 | \$296 | | | \$296 |
| Remove chillers | 2 | EA | 40 | \$24.64 | \$1,971 | \$500 | \$1,000 | \$2,971 |
| Install New Chiller 827 ton, water cooled, dual screw, R-134a | 1 | EA | 2,609 | \$24.64 | \$64,286 | \$357,000 | \$357,000 | \$421,286 |
| Pipe Assembly And Valves | 1 | EA | 168 | \$24.64 | \$4,140 | \$10,000 | \$10,000 | \$14,140 |
| RECONNECT: | | | | | | | | |
| Controls | 1 | JOB | 190 | \$24.64 | \$4,682 | \$400 | \$400 | \$5,082 |
| Electrical | 1 | JOB | 92 | \$24.64 | \$2,267 | \$800 | \$800 | \$3,067 |
| Refrigerant Detection System | 1 | JOB | 20 | \$24.64 | \$493 | \$4,500 | \$4,500 | \$4,993 |
| Water Pump 75 HP | 2 | EA | 132 | \$24.64 | \$6,505 | \$13,500 | \$27,000 | \$33,505 |
| Test & Balance and Start-up | 1 | JOB | 100 | \$28.00 | \$2,800 | \$200 | \$200 | \$3,000 |
| SUBTOTAL | | | | | \$87,440 | | \$400,900 | \$488,340 |
| O & P @ 20% | | | | | \$17,488 | | \$80,180 | \$97,668 |
| SUBTOTAL | | | | | \$104,928 | | \$481,080 | \$586,008 |
| DESIGN @ 6% | | | | | | | | \$35,160 |
| SUBTOTAL | | | | | | | | \$621,168 |
| SIQH @ 5.5% | | | | | | | | \$32,230 |
| TOTAL | | | | | | | | \$653,398 |

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
 512 MAIN STREET, SUITE 1500
 FORT WORTH, TEXAS 76102-3922
 (817) 335-3000 * FAX (817) 335-1025

ENGINEER'S ESTIMATE OF PROBABLE COST

LOCATION: AREA 1300 , BUILDING 1377, FORT SAM HOUSTON **PROJECT NO:** 03-0185.04 **DATE:** 8/16/95
BY: PIEPER, C.A. **CHECKED BY:** KLK

PROJECT DESCRIPTION: ECO-C4, Replace Existing Central Chillers With New Gas Engine Driven Chillere

| ITEM DESCRIPTION | QUANTITY | | LABOR | | MATERIAL | | TOTAL COST |
|--|------------|------------|------------|-----------|------------|-----------|------------|
| | # of Units | Unit Meas. | Hrs / Unit | Rate | Unit Price | Total | |
| Remove Pumps | 2 | EA | 6 | \$24.64 | | \$296 | \$296 |
| Remove chillers | 2 | EA | 40 | \$24.64 | \$500 | \$1,000 | \$2,971 |
| Install New Chiller 827 ton, water cooled centrifugal, R-134a, gas fired | 1 | EA | 2,609 | \$24.64 | \$436,800 | \$436,800 | \$501,086 |
| Pipe Assembly And Valves | 1 | EA | 168 | \$24.64 | \$10,000 | \$10,000 | \$14,140 |
| RECONNECT: | | | | | | | |
| Controls | 1 | JOB | 190 | \$24.64 | \$400 | \$400 | \$5,082 |
| Electrical | 1 | JOB | 92 | \$24.64 | \$800 | \$800 | \$3,067 |
| Refrigerant Detection System | 1 | JOB | 20 | \$24.64 | \$4,500 | \$4,500 | \$4,993 |
| Water Pump 75 HP | 2 | EA | 132 | \$24.64 | \$13,500 | \$27,000 | \$33,505 |
| GAS PIPING | 1 | JOB | 62 | \$24.64 | \$2,500 | \$2,500 | \$4,028 |
| Test & Balance and Start-up | 1 | JOB | 100 | \$28.00 | \$200 | \$200 | \$3,000 |
| SUBTOTAL | | | | \$88,968 | | \$483,200 | \$572,168 |
| O & P @ 20% | | | | \$17,794 | | \$96,640 | \$114,434 |
| SUBTOTAL | | | | \$106,762 | | \$579,840 | \$686,602 |
| DESIGN @ 6% | | | | | | | \$41,196 |
| SUBTOTAL | | | | | | | \$727,798 |
| SIOH @ 5.5% | | | | | | | \$37,763 |
| TOTAL | | | | | | | \$765,561 |

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
 512 MAIN STREET, SUITE 1500
 FORT WORTH, TEXAS 76102-3922
 (817) 335-3000 * FAX (817) 335-1025

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-C1

ANALYSIS DATE: 08-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|---------|
| A. CONSTRUCTION COST | \$ | 429768. | |
| B. SIOH | \$ | 23637. | |
| C. DESIGN COST | \$ | 25786. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 479191. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | 479191. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 3424. | \$ 21503. | 15.08 | \$ 324261. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 13914. | 14.88 | \$ 207040. |
| N. TOTAL | | 3424. | \$ 35417. | | \$ 531301. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-----------|
| A. ANNUAL RECURRING (+/-) | | \$ 2275. |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 33852. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+) / COST(-) (4) |
|-------------------|------------------------------|-----------------|------------------------|---|
| 1. REFRIG UPGRADE | \$ 384882. | 0 | 1.00 | 384882. |
| d. TOTAL | \$ 384882. | | | 384882. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+) / COST(-) (3A2+3Bd4) \$ 418734.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 56936.

5. SIMPLE PAYBACK PERIOD (1G/4) 8.42 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 950035.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.98
(IF < 1 PROJECT DOES NOT QUALIFY)

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): 6.59 %

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-C2

ANALYSIS DATE: 08-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|----|---------|
| A. CONSTRUCTION COST | \$ | 568537. | | |
| B. SIOH | \$ | 31270. | | |
| C. DESIGN COST | \$ | 34112. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 633919. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | | | \$ | 633919. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 3615. | \$ 22702. | 15.08 | \$ 342349. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 14532. | 14.88 | \$ 216236. |
| N. TOTAL | | 3615. | \$ 37234. | | \$ 558585. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-----------|
| A. ANNUAL RECURRING (+/-) | | \$ 2275. |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 33852. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) / COST(-) | YR OC | DISCNT FACTOR | DISCOUNTED SAVINGS(+) / COST(-) (4) |
|-------------------|-------------------------|----------|------------------|---|
| | (1) | (2) | (3) | |
| 1. REFRIG UPGRADE | \$ 384882. | 0 | 1.00 | 384882. |
| d. TOTAL | \$ 384882. | | | 384882. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+) / COST(-) (3A2+3Bd4) \$ 418734.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 58753.

5. SIMPLE PAYBACK PERIOD (1G/4) 10.79 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 977319.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.54
(IF < 1 PROJECT DOES NOT QUALIFY)

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): 5.25 %

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-C3

ANALYSIS DATE: 08-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|---------|
| A. CONSTRUCTION COST | \$ | 586008. | |
| B. SIOH | \$ | 32230. | |
| C. DESIGN COST | \$ | 35160. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 653398. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | 653398. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 3250. | \$ 20410. | 15.08 | \$ 307783. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 11345. | 14.88 | \$ 168814. |
| N. TOTAL | | 3250. | \$ 31755. | | \$ 476596. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-----------|
| A. ANNUAL RECURRING (+/-) | | \$ 2275. |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 33852. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTOR (3) | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|-------------------|------------------------------|-----------------|-------------------------|--|
| 1. REFRIG UPGRADE | \$ 384882. | 0 | 1.00 | 384882. |
| d. TOTAL | \$ 384882. | | | 384882. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 418734.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 53274.

5. SIMPLE PAYBACK PERIOD (1G/4) 12.26 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 895330.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.37
(IF < 1 PROJECT DOES NOT QUALIFY)

*** Project does not qualify for ECIP funding; 4,5,6 for information only.

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): N/A

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-C4

ANALYSIS DATE: 08-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|--|
| A. CONSTRUCTION COST | \$ | 686602. | |
| B. SIOH | \$ | 37763. | |
| C. DESIGN COST | \$ | 41196. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 765561. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | 765561. | |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 6386. | \$ 40104. | 15.08 | \$ 604770. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | -8886. | \$ -23637. | 18.58 | \$ -439171. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 38536. | 14.88 | \$ 573416. |
| N. TOTAL | | -2500. | \$ 55003. | | \$ 739014. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-----------|
| A. ANNUAL RECURRING (+/-) | | \$ 2275. |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 33852. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|-------------------|------------------------------|-----------------|------------------------|--|
| 1. REFRIG UPGRADE | \$ 384882. | 0 | 1.00 | 384882. |
| d. TOTAL | \$ 384882. | | | 384882. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 418734.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 76522.

5. SIMPLE PAYBACK PERIOD (1G/4) 10.00 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 1157748.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.51
(IF < 1 PROJECT DOES NOT QUALIFY)

8. ADJUSTED INTERNAL RATE OF RETURN (AIRR): 5.15 %

ENERGY CONSERVATION OPPORTUNITY (ECO)

ECO NO: D
DATE: 6/15/95
ECO TITLE: Replace Existing Central Boilers With High Efficiency Modular Boilers
INSTALLATION: Fort Sam Houston, San Antonio, Texas
LOCATION: Area 1300, Building 1377

A. Summary:

| | | |
|---------------------------|---------|----------|
| Electrical Energy Savings | 712 | MMBTU/yr |
| Electrical Demand Savings | 1,847 | \$/yr |
| Gas Energy Savings | 4,020 | MMBTU/yr |
| Total Energy Savings | 4,732 | MMBTU/yr |
| Total Cost Savings | 17,012 | \$/yr |
| Total Investment | 163,724 | \$ |
| Simple Payback | 9.6 | yrs |
| SIR | 1.79 | |

B. ECO Description:

Remove the two existing watertube boilers and single 40 HP heating water (HW) distribution pump in building 1377, which are serving building 1350. Also remove the two existing firetube boilers and the two 15 HP distribution pumps in building 1377 which serve buildings 1374, 1375, 1379, 1380, 1382, 1377 and 1385. Connect the two separate distribution loops together in building 1377 with new HW supply and return headers to make a single HW distribution system. Install four new modular high efficiency boilers, rated at 1,830 MBH output each and four new 7 ½ HP distribution pumps to serve this single system. The existing electrical service and controls should be reused as much as possible. Specific requirements in these areas should be determined by the design engineer responsible for this project. The boilers and pumps should be sequenced to operate only as needed to maintain the supply water temperature setpoint of approximately 180°F. This project will require engineering drawings and specifications, demolition and removal of the existing boilers and pumps, and installation of the new boilers, pumps, associated wiring and controls.

C. Discussion:

The two existing watertube boilers serving building 1350 were installed in 1983 and are rated at 5,317 MBH and 4,336 MBH output capacity. The single 40 HP pump circulates HW from these boilers through building 1350. The two existing firetube boilers serving the other buildings in the 1300 area were installed in 1972 and are rated at 5,912 MBH output capacity each. Two 15 HP pumps circulate HW from these boilers to the seven other buildings listed above. All these boilers appear to be in fair condition. Computer simulations of the eight buildings served by these boilers determined that the current combined capacity of 21,477 MBH is about three times the amount required to adequately heat the buildings¹. The existing boilers are therefore operating at an inefficient, low load condition most of the time. Also, because of the constant flow rate requirements of the large boilers, excessive pumping energy is expended. By combining the two distribution systems together and staging four new high efficiency modular boilers to operate only as needed, a substantial energy savings can be realized. Also, a decrease in the combined boiler output capacity to 7,320 MBH is recommended to more closely match the heating load in the eight buildings and reduce the associated pumping energy consumption.

D. Savings Calculations:

The monthly peak demand and energy consumptions of the existing and proposed boilers and HW pumps were calculated using the Trace 600 computer program². The buildings served by the existing boilers were modeled by the computer to provide a realistic load profile. Field data obtained from the buildings were used to create these computer building models³.

The four new high efficiency, modular type boilers modeled were rated at 1,830 MBH output each. Full and part load performance data from Aerco International were used in the computer simulations of the new boiler energy usages⁴. An equipment list with specific data on the new boilers and pumps used in the computer simulation is shown on page D-40.

Once the computer simulations of the existing and new boiler systems were completed, the total annual demand cost and energy consumption of the new systems were compared with that of the existing systems to determine the annual savings⁵. These savings calculations are shown on page D-41. The demand and energy savings values were used in the life cycle cost analysis for this ECO. The results of these savings calculations were as follows:

| New Boiler Type | Gas Savings MMBTU/yr | Electrical Savings MMBTU/yr | Demand Savings \$/yr |
|--------------------------|-------------------------|--------------------------------|-------------------------|
| Modular, High Efficiency | 4,020 | 712 | 1,847 |

E. Cost Estimates

The total installation costs for this ECO were estimated on page D-42. These costs were used in the life cycle cost analysis.

F. Life Cycle Cost Analysis.

A life cycle cost analysis was performed on this ECO using the Life Cycle Cost In Design (LCCID) computer program, and data from the previously mentioned calculations. A summary sheet for this life cycle cost analysis is shown on page D-43. The data from the life cycle cost analysis were included in the summary on page D-38.

REFERENCES

1. See Appendix for Area 1300 heating system load profile.
2. See Appendix B for computer model input assumptions and data, and energy consumption output data.
3. See Appendix C for building field data and existing HVAC system data.
4. See Appendix G for manufacturer's equipment performance data from Aerco International.
5. See Appendix A for utility cost analysis data, used in the savings calculations.

PROPOSED HVAC EQUIPMENT LIST FOR: ECO-D, FORT SAM HOUSTON, AREA 1300
JUNE 2, 1995

D-40

1300 AREA

| ITEM | EXISTING CENTRAL BOILER PLANT MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|------------------|---|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Watertube Boiler | | | | | | | | | | | | | | 3,140 |
| Firetube Boiler | 7.5 | 7.5 | 7.5 | 7.5 | | | | | | | 7.5 | 7.5 | 32,406 | 15,611 |
| HW Pump | 29.8 | 29.8 | 29.8 | 29.8 | | | | | | | 29.8 | 29.8 | 129,625 | |
| HW Pump | 11.2 | 11.2 | 11.2 | 11.2 | | | | | | | 11.2 | 11.2 | 48,609 | |
| HW Pump | 11.2 | 11.2 | 11.2 | 11.2 | | | | | | | 11.2 | 11.2 | 48,609 | |
| Totals | 59.7 | 59.7 | 59.7 | 59.7 | | | | | | | 59.7 | 59.7 | 259,249 | 18,751 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | 448 | 448 | 448 | 448 | | | | | | | 448 | 448 | | |

Total Demand 2,687 \$/yr

Total Energy 885 MMBTU/yr (electric)

Total Energy 18,751 MMBTU/yr (gas)

| ITEM | ECO-D: NEW CENTRAL HIGH EFFICIENCY MODULAR BOILERS MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|----------------|--|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Modular Boiler | | | | | | | | | | | | | | 8,632 |
| Modular Boiler | | | | | | | | | | | | | | 3,976 |
| Modular Boiler | | | | | | | | | | | | | | 1,919 |
| Modular Boiler | | | | | | | | | | | | | | 204 |
| HW Pump | 5.6 | 5.6 | 5.6 | 5.6 | | | | | | | 5.6 | 5.6 | 24,326 | |
| HW Pump | 5.6 | 5.6 | 5.6 | 5.6 | | | | | | | 5.6 | 5.6 | 15,742 | |
| HW Pump | 5.6 | 5.6 | 5.6 | | | | | | | | 5.6 | 5.6 | 7,504 | |
| HW Pump | 5.6 | 5.6 | | | | | | | | | | 5.6 | 2,957 | |
| Total (KW) | 22.4 | 22.4 | 16.8 | 11.2 | | | | | | | 16.8 | 22.4 | 50,529 | 14,731 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | 168 | 168 | 126 | 84 | | | | | | | 126 | 168 | | |

Total Demand 840 \$/yr

Demand Savings 1,847 \$/yr

Energy Savings 712 MMBTU/yr (electric)

Energy Savings 4,020 MMBTU/yr (gas)

[illegible]

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
512 MAIN STREET, SUITE 1500
FORT WORTH, TEXAS 76102-3922
(817) 335-3000 * FAX (817) 335-1025

LIFE CYCLE COST ANALYSIS SUMMARY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: FSH
 INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3
 PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY
 FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-D
 ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|----|------------|
| A. CONSTRUCTION COST | \$ | 146838. | | |
| B. SIOH | \$ | 8076. | | |
| C. DESIGN COST | \$ | 8810. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 163724. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | | | | \$ 163724. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 712. | \$ 4471. | 15.08 | \$ 67428. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 4020. | \$ 10693. | 18.58 | \$ 198680. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 1847. | 14.88 | \$ 27483. |
| N. TOTAL | | 4732. | \$ 17012. | | \$ 293591. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|-------|
| A. ANNUAL RECURRING (+/-) | | |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | \$ 0. |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|----------|------------------------------|-----------------|------------------------|--|
| d. TOTAL | \$ 0. | | | 0. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 0.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 17012.

5. SIMPLE PAYBACK PERIOD (1G/4) 9.62 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 293591.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.79
 (IF < 1 PROJECT DOES NOT QUALIFY)

ENERGY CONSERVATION OPPORTUNITY (ECO)

ECO NO: E
DATE: 6/15/95
ECO TITLE: Replace Existing Central Chiller With New Electric Centrifugal Chiller
INSTALLATION: Fort Sam Houston, San Antonio, Texas
LOCATION: Area 2200, Building 2265

A. Summary:

| | | |
|---------------------------|---------|----------|
| Electrical Energy Savings | 1,304 | MMBTU/yr |
| Electrical Demand Savings | 11,822 | \$/yr |
| Gas Energy Savings | 0 | MMBTU/yr |
| Total Energy Savings | 1,304 | MMBTU/yr |
| Total Cost Savings | 37,433 | \$/yr |
| Total Investment | 237,078 | \$ |
| Simple Payback | 6.3 | yrs |
| SIR | 2.73 | |

B. ECO Description:

Remove the existing 675 ton, R-11 centrifugal chiller in building 2265 and replace it with a 555 ton, R-134a centrifugal chiller. The existing 100 HP chilled water (CHW) pump, 50 HP condenser water (CND) pump and 40 HP cooling tower will be reused. The new chiller should be connected into the distribution piping at the existing chiller location. All existing controls and electrical services should be reconnected where possible. Specific requirements in these areas should be determined by the design engineer responsible for this project. To meet the current ASHRAE Standard 15, a refrigerant detection and ventilation system should be installed. This project will require engineering drawings and specifications, demolition and removal of the existing chiller and installation of the new chiller, associated wiring and controls.

C. Discussion:

The existing water cooled, centrifugal chiller was installed in 1973 and serves as the primary cooling system for the four large buildings in the 2200 area. It appears to be in fair condition but uses the R-11 refrigerant, which will no longer be manufactured as of January 1, 1996¹. To avoid the anticipated increasing operational costs over the life of this machine, it should either be retrofitted to use an approved refrigerant or replaced with a new machine that operates on one. The existing centrifugal machine can be retrofitted with no loss of capacity by replacing the impeller with one designed for HCFC-123 refrigerant. A company which produces these new impellers for existing R-11 centrifugal machines has provided cost estimates². However, since the machine is already 22 years old, it is recommended that the facility replace it instead. A life cycle cost analysis performed on four different types of replacement chillers available determined that an electric centrifugal chiller using R-134a would be the most economical choice over the life of the new machine. Computer simulations of the buildings served by this machine determined that the current installed capacity of 657 tons is more than what is required to adequately cool the buildings³. Therefore, the new chiller should only be sized for 555 tons to more closely match the cooling load of the four buildings.

D. Savings Calculations:

1. Energy Consumption And Savings

The monthly peak demand and energy consumptions of the existing and proposed alternative chillers and auxiliary equipment were calculated using the Trace 600 computer program⁴. The buildings served by the existing chiller were modeled by the computer to provide a realistic load profile. Field data obtained from the buildings were used to create these computer building models⁵.

The 555 ton chiller alternatives which were compared included an electric centrifugal machine, an electric centrifugal with a variable frequency drive, a dual screw machine and a gas driven centrifugal machine. All proposed machines used R-134a. Full and part load performance data from York International were used in the computer simulations of the new chiller energy usages⁶. Equipment lists of the specific chillers and auxiliaries for each alternative modeled by the computer are shown on pages D-47 To D-50.

Once the computer simulations were completed, the total annual demand cost and energy consumption of each alternative were compared with that of the existing systems to determine the annual savings for each⁷. These savings calculations are shown on pages D-51 and D-52. The demand and energy savings values were used in the life cycle cost analysis for each alternative. The results of these savings calculations were as follows:

| Alternative | Chiller Type | Demand Savings \$/yr | Electrical Savings MMBTU/yr | Gas Savings MMBTU/yr |
|-------------|----------------------------|-------------------------|--------------------------------|-------------------------|
| E1 | Electric Centrifugal | 11,822 | 1,304 | 0 |
| E2 | Electric Centrifugal & VFD | 12,188 | 1,498 | 0 |
| E3 | Electric Screw | 10,102 | 1,236 | 0 |
| E4 | Gas Driven Centrifugal | 28,597 | 3,394 | -6,578 |

2. Maintenance Cost Savings:

By installing a new chiller in place of the existing one, the installation will save the cost of retrofitting the machine for the HCFC-123 refrigerant as mentioned previously. The cost of this retrofit was estimated to be \$348,435 on page D-53. This value was used in the life cycle cost analysis as a non-recurring savings for each alternative.

E. Cost Estimates

The total installation costs for each alternative chiller mentioned in this ECO were estimated on pages D-54 through D-57. These costs were used in the life cycle cost analysis for each alternative. The results of the costs estimates were as follows:

| Alternative | Chiller Type | Estimated Cost |
|-------------|----------------------------|----------------|
| E1 | Electric Centrifugal | \$237,078 |
| E2 | Electric Centrifugal & VFD | \$277,051 |
| E3 | Electric Screw | \$240,791 |
| E4 | Gas Driven Centrifugal | \$619,177 |

F. Life Cycle Cost Analysis.

A life cycle cost analysis was performed on each chiller alternative for this ECO using the Life Cycle Cost In Design (LCCID) computer program, and data from the previously mentioned calculations. A summary sheet for each life cycle cost analysis is shown on pages D-58 through D-61. The results of the alternative life cycle cost analysis were as follows:

| Alternative | Chiller Type | Payback Years | SIR |
|-------------|----------------------------|---------------|------|
| E1 | Electric Centrifugal | 6.3 | 2.73 |
| E2 | Electric Centrifugal & VFD | 7.1 | 2.42 |
| E3 | Electric Screw | 6.8 | 2.56 |
| E4 | Gas Driven Centrifugal | 12.4 | 1.24 |

Since the electric centrifugal chiller has the highest SIR, it is recommended as the most economical choice to replace the existing machine. The data from the life cycle cost analysis for this alternative were included in the summary on page D-44.

REFERENCES

1. Per current EPA regulations on CFC refrigerants.
2. See Appendix G for chiller retrofit estimates from Northeastern Research And Engineering Corporation.
3. See Appendix B for Area 2200 cooling system load profile.
4. See Appendix B for computer model input assumptions and data, and energy consumption output data.
5. See Appendix C for building field data and existing HVAC system data.
6. See Appendix G for manufacturer's equipment performance data from York International.
7. See Appendix A for utility cost analysis data, used in the savings calculations.

PROPOSED HVAC EQUIPMENT LIST FOR: ECO-E1, FORT SAM HOUSTON, AREA 2200
JUNE 2, 1995

[illegible]

PROPOSED HVAC EQUIPMENT LIST FOR: ECO-E2, FORT SAM HOUSTON, AREA 2200
JUNE 2, 1995

[illegible]

PROPOSED HVAC EQUIPMENT LIST FOR: ECO-E3, FORT SAM HOUSTON, AREA 2200
JUNE 2, 1995

[illegible]

JUNE 2, 1995

[illegible]

2200 AREA

| ITEM | EXISTING CENTRAL CHILLER PLANT MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 481.0 | 522.3 | 568.8 | 596.6 | 535.0 | 368.3 | | | 994,146 | |
| CHW Pump | | | | | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | | | 329,433 | |
| CND Pump | | | | | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | | | 164,717 | |
| Cooling Tower | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 121,471 | |
| Totals | | | | | 622.7 | 664.0 | 710.5 | 738.3 | 676.7 | 510.0 | | | 1,609,767 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 4,670 | 6,640 | 7,105 | 7,383 | 6,767 | 3,825 | | | | |

Total Demand 36,390 \$/yr

Total Energy 5,494 MMBTU/yr (electric)

Total Energy MMBTU/yr (gas)

| ITEM | ECO-E1: NEW ELECTRIC CENTRIFUGAL CHILLER MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 306.9 | 311.1 | 319.4 | 322.0 | 314.8 | 240.0 | | | 611,543 | |
| CHW Pump | | | | | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | | | 329,433 | |
| CND Pump | | | | | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | | | 164,717 | |
| Cooling Tower | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 122,039 | |
| Total (KW) | | | | | 448.6 | 452.8 | 461.1 | 463.7 | 456.5 | 381.7 | | | 1,227,732 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 3,365 | 4,528 | 4,611 | 4,637 | 4,565 | 2,863 | | | | |

Total Demand 24,568 \$/yr

Demand Savings 11,822 \$/yr

Energy Savings 1,304 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

| ITEM | ECO-E2: NEW ELECTRIC CENTRIFUGAL CHILLER WITH VFD MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|---|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 297.8 | 304.5 | 317.9 | 322.0 | 310.5 | 216.8 | | | 554,847 | |
| CHW Pump | | | | | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | | | 329,433 | |
| CND Pump | | | | | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | | | 164,717 | |
| Cooling Tower | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 121,861 | |
| Total (KW) | | | | | 439.5 | 446.2 | 459.6 | 463.7 | 452.2 | 358.5 | | | 1,170,858 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 3,296 | 4,462 | 4,596 | 4,637 | 4,522 | 2,689 | | | | |

Total Demand 24,202 \$/yr

Demand Savings 12,188 \$/yr

Energy Savings 1,498 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

2200 AREA

| ITEM | ECO-E3: NEW ELECTRIC SCREW CHILLER MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 338.4 | 343.0 | 352.2 | 355.0 | 347.1 | 264.5 | | | 631,571 | |
| CHW Pump | | | | | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | | | 329,433 | |
| CND Pump | | | | | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | | | 164,717 | |
| Cooling Tower | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 122,031 | |
| Total (KW) | | | | | 480.1 | 484.7 | 493.9 | 496.7 | 488.8 | 406.2 | | | 1,247,752 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 3,601 | 4,847 | 4,939 | 4,967 | 4,888 | 3,047 | | | | |

Total Demand 26,288 \$/yr

Demand Savings 10,102 \$/yr

Energy Savings 1,236 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

| ITEM | ECO-E4: NEW GAS ENGINE CENTRIFUGAL CHILLER MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | | | | | | | | | | 6,578 |
| CHW Pump | | | | | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | 74.6 | | | 329,433 | |
| CND Pump | | | | | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | 37.3 | | | 164,717 | |
| Cooling Tower | | | | | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | 29.8 | | | 121,172 | |
| Total (KW) | | | | | 141.7 | 141.7 | 141.7 | 141.7 | 141.7 | 141.7 | | | 615,322 | 6,578 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 1,063 | 1,417 | 1,417 | 1,417 | 1,417 | 1,063 | | | | |

Total Demand 7,794 \$/yr

Demand Savings 28,597 \$/yr

Energy Savings 3,394 MMBTU/yr (electric)

Energy Savings -6,578 MMBTU/yr (gas)

[illegible]

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
512 MAIN STREET, SUITE 1500
FORT WORTH, TEXAS 76102-3922
(817) 335-3000 * FAX (817) 335-1025

LOCATION: PROJECT NO: 03-0185.04 DATE: 6/16/95

AREA 2200, BUILDING 2265, FORT SAM HOUSTON

DATE: 6/16/95

03-0185.04

PROJECT NO:

LOCATION:

LOCATION:

CHECKED BY: KLK

BY: PIEPER, C.A.

[illegible]

PROJECT DESCRIPTION: ECO-E1, Replace Existing Central Chiller With New Centrifugal Chiller

[illegible]

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
512 MAIN STREET, SUITE 1500
FORT WORTH, TEXAS 76102-3922
(817) 335-3000 * FAX (817) 335-1025

| | | |
|--|-------------------------------|------------------------|
| LOCATION: AREA 2200, BUILDING 2265, FORT SAM HOUSTON | PROJECT NO: 03-0185.04 | DATE: 6/16/95 |
| BY: PIEPER, C.A. | | CHECKED BY: KLK |

| | | |
|--|-------------------------------|------------------------|
| LOCATION: AREA 2200, BUILDING 2265, FORT SAM HOUSTON | PROJECT NO: 03-0185.04 | DATE: 6/16/95 |
| BY: PIEPER, C.A. | | CHECKED BY: KLK |

ANEA Z200, BUILDING Z200, FORT CAMM HOSPITAL
BY: PIEPER, C.A.
CHECKED BY: KKK

[illegible]

HUITT-ZOLLARS, INC.,
ENGINEERS / ARCHITECTS
512 MAIN STREET, SUITE 1500
FORT WORTH, TEXAS 76102-3922
(817) 335-3000 * FAX (817) 335-1025

| | | |
|--|----------------------------------|---------------------------|
| LOCATION: AREA 2200, BUILDING 2265, FORT SAM HOUSTON | PROJECT NO: 03-0185.04 | DATE: 6/16/95 |
| BY: PIEPER, C.A. | | CHECKED BY: KLK |

PROJECT DESCRIPTION: ECO-E3, Replace Existing Central Chiller With Water Cooled, Dual Screw Chiller

[illegible]

D-56

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-E1

ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|---------|--|
| A. CONSTRUCTION COST | \$ | 212626. | | |
| B. SIOH | \$ | 11694. | | |
| C. DESIGN COST | \$ | 12758. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 237078. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | 237078. | |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 1304. | \$ 8189. | 15.08 | \$ 123492. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 11822. | 14.88 | \$ 175911. |
| N. TOTAL | | 1304. | \$ 20011. | | \$ 299403. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|----|
| A. ANNUAL RECURRING (+/-) | | \$ | 0. |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) | YR OC | DISCNT FACTOR | DISCOUNTED SAVINGS(+) COST(-) |
|-------------------|-----------------------|----------|------------------|-------------------------------------|
| | (1) | (2) | (3) | (4) |
| 1. REFRIG UPGRADE | \$ 348435. | 0 | 1.00 | 348435. |
| d. TOTAL | \$ 348435. | | | 348435. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 348435.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 37433.

5. SIMPLE PAYBACK PERIOD (1G/4) 6.33 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 647838.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 2.73
(IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-E2

ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|----|------------|
| A. CONSTRUCTION COST | \$ | 248476. | | |
| B. SIOH | \$ | 13666. | | |
| C. DESIGN COST | \$ | 14909. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 277051. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | | | | \$ 277051. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 1498. | \$ 9407. | 15.08 | \$ 141864. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 12188. | 14.88 | \$ 181357. |
| N. TOTAL | | 1498. | \$ 21595. | | \$ 323222. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|----|
| A. ANNUAL RECURRING (+/-) | | \$ | 0. |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) | YR OC | DISCNT FACTR | DISCOUNTED SAVINGS(+) COST(-) |
|-------------------|-----------------------|----------|-----------------|-------------------------------------|
| | (1) | (2) | (3) | (4) |
| 1. REFRIG UPGRADE | \$ 348435. | 0 | 1.00 | 348435. |
| d. TOTAL | \$ 348435. | | | 348435. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 348435.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 39017.

5. SIMPLE PAYBACK PERIOD (1G/4) 7.10 YEAF

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 671657.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 2.42
(IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: FSH
 INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3
 PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY
 FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-E3
 ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|--|
| A. CONSTRUCTION COST | \$ | 215956. | |
| B. SIOH | \$ | 11878. | |
| C. DESIGN COST | \$ | 12957. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 240791. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | 240791. | |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 1236. | \$ 7762. | 15.08 | \$ 117052. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 10102. | 14.88 | \$ 150318. |
| N. TOTAL | | 1236. | \$ 17864. | | \$ 267370. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|----|
| A. ANNUAL RECURRING (+/-) | | \$ | 0. |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|-------------------|------------------------------|-----------------|------------------------|--|
| 1. REFRIG UPGRADE | \$ 348435. | 0 | 1.00 | 348435. |
| d. TOTAL | \$ 348435. | | | 348435. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 348435.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 35286.

5. SIMPLE PAYBACK PERIOD (1G/4) 6.82 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 615805.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 2.56
 (IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-E4

ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|--|
| A. CONSTRUCTION COST | \$ | 555316. | |
| B. SIOH | \$ | 30542. | |
| C. DESIGN COST | \$ | 33319. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 619177. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | 619177. | |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 3394. | \$ 21314. | 15.08 | \$ 321420. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | -6578. | \$ -17497. | 18.58 | \$ -325103. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 28597. | 14.88 | \$ 425523. |
| N. TOTAL | | -3184. | \$ 32414. | | \$ 421840. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|----|
| A. ANNUAL RECURRING (+/-) | | \$ | 0. |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) | YR OC | DISCNT FACTR | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|-------------------|-----------------------|----------|-----------------|--|
| | (1) | (2) | (3) | |
| 1. REFRIG UPGRADE | \$ 348435. | 0 | 1.00 | 348435. |
| d. TOTAL | \$ 348435. | | | 348435. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 348435.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 49836.

5. SIMPLE PAYBACK PERIOD (1G/4) 12.42 YEAR.

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 770275.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.24
 (IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

ENERGY CONSERVATION OPPORTUNITY (ECO)

ECO NO: I
DATE: 6/15/95
ECO TITLE: Replace Existing Individual Building Chillers With Central Chiller Plant
INSTALLATION: Fort Sam Houston, San Antonio, Texas
LOCATION: Area 100, Building 250

A. Summary:

| | | |
|---------------------------|---------|----------|
| Electrical Energy Savings | 2,816 | MMBTU/yr |
| Electrical Demand Savings | 19,781 | \$/yr |
| Gas Energy Savings | 0 | MMBTU/yr |
| Total Energy Savings | 2,816 | MMBTU/yr |
| Total Cost Savings | 64,465 | \$/yr |
| Total Investment | 556,559 | \$ |
| Simple Payback | 8.6 | yrs |
| SIR | 1.73 | |

B. ECO Description:

Remove the 14 existing air cooled, reciprocating chillers serving buildings 122, 124, 125, 128, 133, 134, 135, 142, 143, 144, 146, 147, 149, 197, 198, 199 and 250. Install 6" chilled water supply and return piping loop between the buildings in this area and terminate loop behind building 250, near the existing air cooled chiller installation. Install two new 210 ton, air cooled screw chillers behind building 250. Install two new 30 HP chilled water distribution pumps to circulate water from new chillers through new distribution loop. The existing chilled water pumps that serve buildings where chillers were removed will be reused to circulate chilled water from the new loop through the buildings. These existing pumps should be connected into the new distribution piping at the existing chiller locations. All new controls and electrical services should be installed at building 250 to serve the new chillers and pumps. Other specific requirements should be determined by the design engineer responsible for this project. This project will require engineering drawings and specifications, demolition and removal of the existing chiller and installation of the new chiller, associated wiring and controls.

C. Discussion:

The 14 existing air cooled, reciprocating chillers in the 100 area were installed in 1985 and serves as the primary cooling systems for 17 buildings. They generally appear to be in fair condition at this time. However, the cost of maintaining so many chillers is excessive and difficult for the maintenance staff. It is recommended that a central chiller plant, consisting of two air cooled screw machines be installed to serve all these buildings. This will not only save energy but will also greatly reduce the maintenance costs to the installation. Computer simulations of the buildings in this area determined that the current installed capacity of 540 tons is more than is required to adequately cool the buildings¹. Therefore, it is recommended that the two new chillers be rated at a combined 420 tons to more closely match the cooling load of the buildings.

D. Savings Calculations:

1. *Energy Consumption And Savings*

The monthly peak demand and energy consumptions of the existing and proposed chillers and pumps were calculated using the Trace 600 computer program². The buildings served by the existing chillers were modeled by the computer to provide a realistic load profile. Field data obtained from the buildings were used to create these computer building models³.

The 210 ton air cooled screw chillers which were modeled by the computer had better part load performance ratings than reciprocating machines and were chosen for that reason. Full and part load performance data from McQuay Incorporated were used in the computer simulations of the new chiller energy usages. An equipment list of the specific chillers and pumps modeled for the new central plant are shown on page D-64.

Once the computer simulations of the existing and new chiller plants were completed, the total annual demand cost and energy consumption of the new central plant was compared with that of the existing individual systems to determine the annual savings for this ECO⁴. These savings calculations are shown on pages D-65 and D-66. These demand and energy savings values were used in the life cycle cost analysis.

2. *Maintenance Cost Savings:*

Maintenance cost estimates were obtained from a local maintenance contractor and were used to estimate the maintenance savings from reducing the total number of air cooled chillers in this area from fourteen down to two⁵. Based on an annual maintenance cost of \$2,250 per chiller, the total maintenance cost savings from this ECO is estimated to be \$27,000 per year. This figure was used in the life cycle cost analysis.

E. Cost Estimates

The total installation costs for the new central chiller plant were estimated on page D-67. These costs were used in the life cycle cost analysis.

F. Life Cycle Cost Analysis.

A life cycle cost analysis was performed on this ECO using the Life Cycle Cost In Design (LCCID) computer program, and data from the previously mentioned calculations. A summary sheet for this life cycle cost analysis is shown on page D-68. The data from the summary sheet were presented in the ECO summary on page D-62.

REFERENCES

1. See Appendix B for Area 100 cooling system load profile.
2. See Appendix B for computer model input assumptions and data, and energy consumption output data.
3. See Appendix C for building field data and existing HVAC system data.
4. See Appendix A for utility cost analysis data, used in the savings calculations.
5. See Appendix G for maintenance contractor cost estimates for air cooled chillers.

PROPOSED HVAC EQUIPMENT LIST FOR: ECO-I, FORT SAM HOUSTON, AREA 100
JUNE 2, 1995

[illegible]

100 AREA

| ITEM | EXISTING INDIVIDUAL CHILLER PLANTS MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|------------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 47.5 | 53.0 | 56.9 | 56.3 | 47.8 | 35.0 | | | 92,395 | |
| Water Chiller | | | | | 58.3 | 64.4 | 69.1 | 68.0 | 57.9 | 42.2 | | | 112,912 | |
| Water Chiller | | | | | 28.4 | 29.7 | 30.8 | 30.6 | 28.6 | 26.3 | | | 12,045 | |
| Water Chiller | | | | | 37.5 | 42.4 | 44.8 | 44.4 | 38.6 | 27.0 | | | 76,773 | |
| Water Chiller | | | | | 49.6 | 51.8 | 53.8 | 53.3 | 49.8 | 45.5 | | | 104,024 | |
| Water Chiller | | | | | 61.4 | 66.6 | 71.5 | 72.2 | 62.9 | 49.7 | | | 113,775 | |
| Water Chiller | | | | | 61.4 | 66.6 | 71.5 | 72.2 | 62.9 | 49.7 | | | 113,775 | |
| Water Chiller | | | | | 59.0 | 64.1 | 68.9 | 69.7 | 60.6 | 47.5 | | | 107,387 | |
| Water Chiller | | | | | 70.0 | 76.4 | 85.0 | 83.4 | 74.2 | 56.3 | | | 170,355 | |
| Water Chiller | | | | | 60.4 | 65.5 | 70.3 | 70.6 | 61.9 | 49.6 | | | 113,383 | |
| Water Chiller | | | | | 16.1 | 17.3 | 17.9 | 17.8 | 16.6 | 12.9 | | | 30,616 | |
| Water Chiller | | | | | 21.6 | 23.9 | 26.2 | 26.6 | 22.6 | 16.0 | | | 43,319 | |
| Water Chiller | | | | | 117.2 | 122.9 | 133.5 | 137.3 | 118.3 | 87.7 | | | 346,860 | |
| Water Chiller | | | | | 13.8 | 15.3 | 16.5 | 16.7 | 14.0 | 9.8 | | | 26,626 | |
| CHW Pump | | | | | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | | 9,892 | |
| CHW Pump | | | | | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | | 9,892 | |
| CHW Pump | | | | | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | | 9,892 | |
| CHW Pump | | | | | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | | 9,892 | |
| CHW Pump | | | | | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | | | 4,946 | |
| CHW Pump | | | | | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | | | 4,946 | |
| CHW Pump | | | | | 0.4 | 0.4 | 0.4 | 0.4 | 0.4 | 0.4 | | | 1,634 | |
| CHW Pump | | | | | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | | 9,892 | |
| CHW Pump | | | | | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | 2.2 | | | 9,892 | |
| CHW Pump | | | | | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | | | 4,946 | |
| CHW Pump | | | | | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | | 16,472 | |
| CHW Pump | | | | | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | | | 6,580 | |
| CHW Pump | | | | | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | | | 4,946 | |
| CHW Pump | | | | | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | | | 6,580 | |
| CHW Pump | | | | | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | | | 24,730 | |
| CHW Pump | | | | | 0.8 | 0.8 | 0.8 | 0.8 | 0.8 | 0.8 | | | 3,312 | |
| Air Cooled Comp. | | | | | 8.0 | 8.3 | 8.6 | 8.6 | 8.0 | 7.4 | | | 12,232 | |
| Compressor Fans | | | | | 0.6 | 0.7 | 0.7 | 0.7 | 0.6 | 0.4 | | | 1,008 | |
| Air Cooled Comp. | | | | | 63.6 | 66.4 | 68.8 | 68.3 | 63.8 | 58.9 | | | 64,825 | |
| Compressor Fans | | | | | 4.5 | 4.8 | 6.2 | 6.2 | 4.6 | 3.6 | | | 6,524 | |
| Totals | | | | | 810.0 | 871.2 | 932.1 | 934.0 | 824.8 | 656.6 | | | 1,687,278 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 6,075 | 8,712 | 9,321 | 9,340 | 8,248 | 4,925 | | | | |

Total Demand 46,621 \$/yr

Total Energy 5,759 MMBTU/yr (electric)

Total Energy MMBTU/yr (gas)

100 AREA

| ITEM | ECO-I: NEW CENTRAL AIR COOLED SCREW CHILLERS MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 210.8 | 234.2 | 240.0 | 240.0 | 221.0 | 187.4 | | | 508,916 | |
| Water Chiller | | | | | 210.8 | 234.2 | 240.0 | 240.0 | 221.0 | 147.2 | | | 220,753 | |
| CHW Pump | | | | | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | | | 98,830 | |
| CHW Pump | | | | | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | | | 33,570 | |
| Total (KW) | | | | | 466.4 | 513.2 | 524.8 | 524.8 | 486.8 | 379.4 | | | 862,069 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 3,498 | 5,132 | 5,248 | 5,248 | 4,868 | 2,846 | | | | |

Total Demand 26,840 \$/yr

Demand Savings 19,781 \$/yr

Energy Savings 2,816 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

ENGINEER'S ESTIMATE OF PROBABLE COST

LOCATION: AREA 100, FORT SAM HOUSTON
PROJECT NO: 03-0185.04
DATE: 6/16/95
BY: PIEPER, C.A.
CHECKED BY: KLK

PROJECT DESCRIPTION: ECO-1, Replace Existing Individual Building Chillers With Central Chiller Plant

| ITEM DESCRIPTION | QUANTITY | | LABOR | | | MATERIAL | | TOTAL COST |
|--|------------|------------|------------|---------|-----------|------------|-----------|------------|
| | # of Units | Unit Meas. | Hrs / Unit | Rate | Total | Unit Price | Total | |
| Remove chiller | 14 | EA | 40 | \$24.64 | \$13,798 | \$500 | \$7,000 | \$20,798 |
| Install New Chiller 210 ton, air-cooled, single screw R-22 | 2 | EA | 650 | \$23.64 | \$30,732 | \$73,500 | \$147,000 | \$177,732 |
| Install New Chilled Water Pump 30 HP | 2 | EA | 20 | \$24.64 | \$986 | \$3,957 | \$7,914 | \$8,900 |
| REconnect Pump to Site Distribution | 16 | EA | 6 | \$24.64 | \$2,365 | \$800 | \$12,800 | \$15,165 |
| Pipe Assembly And Valves Chiller Assembly | 2 | EA | 60 | \$24.64 | \$2,957 | \$3,300 | \$6,600 | \$9,557 |
| Prefabricated Conduit 6" Trench & backfill | 2950 | LF | 1 | \$24.64 | \$72,688 | \$17 | \$50,150 | \$122,838 |
| Controls | 1 | JOB | 390 | \$24.64 | \$9,610 | \$26,000 | \$26,000 | \$35,610 |
| Electrical | 1 | JOB | 192 | \$24.64 | \$4,731 | \$13,800 | \$13,800 | \$18,531 |
| E equipment Yard Pads | 1 | JOB | 120 | \$15.60 | \$1,872 | \$1,400 | \$1,400 | \$3,272 |
| Test & Balance and Start-up | 1 | JOB | 120 | \$28.00 | \$3,360 | \$200 | \$200 | \$3,560 |
| SUBTOTAL | | | | | \$143,099 | | \$272,864 | \$415,963 |
| O & P @ 20% | | | | | \$28,620 | | \$54,573 | \$83,193 |
| SUBTOTAL | | | | | \$171,719 | | \$327,437 | \$499,156 |
| DESIGN @ 6% | | | | | | | | \$29,949 |
| SUBTOTAL | | | | | | | | \$529,105 |
| SIQH @ 5.5% | | | | | | | | \$27,454 |
| TOTAL | | | | | | | | \$556,559 |

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
 512 MAIN STREET, SUITE 1500
 FORT WORTH, TEXAS 76102-3922

LIFE CYCLE COST ANALYSIS SUMMARY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: FSH
 INSTALLATION & LOCATION: FSH REGION NOS. 6 LCCID FY95 (92)
 PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY
 FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-I
 ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|--|
| A. CONSTRUCTION COST | \$ | 499156. | |
| B. SIOH | \$ | 27454. | |
| C. DESIGN COST | \$ | 29949. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 556559. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | 556559. | |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 2816. | \$ 17684. | 15.08 | \$ 266682. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 19781. | 14.88 | \$ 294341. |
| N. TOTAL | | 2816. | \$ 37465. | | \$ 561023. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|------------|
| A. ANNUAL RECURRING (+/-) | | \$ 27000. |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 401760. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|----------|------------------------------|-----------------|------------------------|--|
| d. TOTAL | \$ 0. | | | 0. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 401760.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 64465.

5. SIMPLE PAYBACK PERIOD (1G/4) 8.63 YEAR

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 962783.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.73
 (IF < 1 PROJECT DOES NOT QUALIFY)

APPENDIX E
NON-RECOMMENDED ECO CALCULATIONS

APPENDIX E
NON-RECOMMENDED ECO CALCULATIONS

TABLE OF CONTENTS

| | |
|---|------|
| ECO-B, Replace Existing Central Boilers With High Efficiency Modular Boilers, Area 900 | E-1 |
| ECO-F, Replace Existing Central Boilers With High Efficiency Modular Boilers, Area 2200 | E-7 |
| ECO-G, Replace Existing Individual Building Chillers With Central Chiller Plant, Quadrangle | E-13 |
| ECO-H, Replace Existing Individual Building Boilers With Central Boiler Plant, Quadrangle | E-19 |
| ECO-J, Replace Existing Individual Building Boilers With Central Boiler Plant, Area 100 | E-25 |

ENERGY CONSERVATION OPPORTUNITY (ECO)

ECO NO: B
DATE: 6/15/95
ECO TITLE: Replace Existing Central Boilers With High Efficiency Modular Boiler
INSTALLATION: Fort Sam Houston, San Antonio, Texas
LOCATION: Area 900, Building 902

A. Summary:

| | | |
|---------------------------|--------|----------|
| Electrical Energy Savings | 0 | MMBTU/yr |
| Electrical Demand Savings | 0 | \$/yr |
| Gas Energy Savings | 1,235 | MMBTU/yr |
| Total Energy Savings | 1,235 | MMBTU/yr |
| Total Cost Savings | 3,285 | \$/yr |
| Total Investment | 50,591 | \$ |
| Simple Payback | 15.4 | yrs |
| SIR | 1.21 | |

B. ECO Description:

Remove the three existing watertube boilers in building 902 which are serving the 21 buildings in the 900 area. Install one new modular high efficiency boiler, rated at 1,830 MBH output in place of the existing boilers. Connect the new boiler to the existing distribution headers at the existing boiler location. The four existing heating water distribution pumps in building 902 should be reused. The existing electrical service and controls should be reused as much as possible. Other specific requirements in these areas should be determined by the design engineer responsible for this project. This project will require engineering drawings and specifications, demolition and removal of the existing boilers, and installation of the new boilers, associated wiring and controls.

C. Discussion:

The three existing watertube boilers serving the 900 area buildings were installed in 1985 and are rated at 1,665 MBH output capacity each. The four existing pumps in 902 circulate HW from these boilers through the buildings. All these boilers and pumps appear to be in fair condition. Computer simulations of the 21 buildings served by these boilers determined that the current combined capacity of 4,995 MBH is about 2 ½ times the amount required to adequately heat the buildings¹. The existing boilers are therefore operating at an inefficient, low load condition most of the time. The new high efficiency modular boiler is designed to maintain extremely high efficiencies even at very low load conditions and is therefore recommended to replace the existing boilers. The decrease in the boiler output capacity to 1,830 MBH is recommended to more closely match the heating load in the buildings.

D. Savings Calculations:

The monthly peak demand and energy consumptions of the existing and proposed boilers and HW pumps were calculated using the Trace 600 computer program². The buildings served by the existing boilers were modeled by the computer to provide a realistic load profile. Field data obtained from the buildings were used to create these computer building models³.

The new high efficiency, modular type boiler modeled was rated at 1,830 MBH output. Full and part load performance data from Aerco International were used in the computer simulations of the new boiler energy usage⁴. An equipment list with specific data on the new boiler and existing pumps used in the

computer simulation is shown on page E-3.

Once the computer simulations of the existing and new boiler systems were completed, the total annual demand cost and energy consumption of the new systems were compared with that of the existing systems to determine the annual savings⁵. These savings calculations are shown on page E-4. The demand and energy savings values were used in the life cycle cost analysis for this ECO.

E. Cost Estimates

The total installation costs for this ECO were estimated on page E-5. These costs were used in the life cycle cost analysis.

F. Life Cycle Cost Analysis.

A life cycle cost analysis was performed on this ECO using the Life Cycle Cost In Design (LCCID) computer program, and data from the previously mentioned calculations. A summary sheet for this life cycle cost analysis is shown on page E-6. The data from the life cycle cost analysis were included in the summary on page E-1.

REFERENCES

1. See Appendix B for Area 900 heating system load profile.
2. See Appendix B for computer model input assumptions and data, and energy consumption output data.
3. See Appendix C for building field data and existing HVAC system data.
4. See Appendix G for manufacturer's equipment performance data from Aerco International.
5. See Appendix A for utility cost analysis data, used in the savings calculations.

PROPOSED HVAC EQUIPMENT LIST FOR: ECO-B, FORT SAM HOUSTON, AREA 900
JUNE 2, 1995

[illegible]

900 AREA

| ITEM | EXISTING CENTRAL BOILER PLANT MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|------------------|---|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Watertube Boiler | | | | | | | | | | | | | | 7,809 |
| HW Pump | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 32,675 | |
| HW Pump | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 32,675 | |
| HW Pump | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 13,052 | |
| HW Pump | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 9,811 | |
| Totals | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 88,213 | 7,809 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | 75 | 75 | 75 | 75 | 75 | 100 | 100 | 100 | 100 | 75 | 75 | 75 | | |

Total Demand 1,000 \$/yr

Total Energy 301 MMBTU/yr (electric)

Total Energy 7,809 MMBTU/yr (gas)

| ITEM | ECO-B: NEW CENTRAL HIGH EFFICIENCY BOILER MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|----------------|---|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Modular Boiler | | | | | | | | | | | | | | 6,574 |
| HW Pump | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 32,675 | |
| HW Pump | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 32,675 | |
| HW Pump | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 1.5 | 13,052 | |
| HW Pump | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 1.1 | 9,811 | |
| Total (KW) | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 10.0 | 88,213 | 6,574 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | 75 | 75 | 75 | 75 | 75 | 100 | 100 | 100 | 100 | 75 | 75 | 75 | | |

Total Demand 1,000 \$/yr

Demand Savings \$/yr

Energy Savings MMBTU/yr (electric)

Energy Savings 1,235 MMBTU/yr (gas)

ENGINEER'S ESTIMATE OF PROBABLE COST

LOCATION:

AREA 900 , BUIDING 902, FORT SAM HOUSTON

PROJECT NO:

03-0185.04

DATE:

195

BY: PIEPER, C.A.

CHECKED BY:

KLK

PROJECT DESCRIPTION: ECO-B, Replace Existing Central Boilers With New High Efficiency Modular Boiler

[illegible]

HUITT-ZOLLARS, INC.

ENGINEERS / ARCHITECTS

512 MAIN STREET, SUITE 1500

FORT WORTH, TEXAS 76102-3922

(817) 335-3000 * FAX (817) 335-1025

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-B

ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|--------|--|
| A. CONSTRUCTION COST | \$ | 45373. | |
| B. SIOH | \$ | 2496. | |
| C. DESIGN COST | \$ | 2722. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 50591. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | 50591. | |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 0. | \$ 0. | 15.08 | \$ 0. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 1235. | \$ 3285. | 18.58 | \$ 61037. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 0. | 14.88 | \$ 0. |
| N. TOTAL | | 1235. | \$ 3285. | | \$ 61037. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|----|
| A. ANNUAL RECURRING (+/-) | | \$ | 0. |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTOR (3) | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|----------|------------------------------|-----------------|-------------------------|--|
| d. TOTAL | \$ 0. | | | 0. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 0.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 3285.

5. SIMPLE PAYBACK PERIOD (1G/4) 15.40 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 61037.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.21
(IF < 1 PROJECT DOES NOT QUALIFY)

ENERGY CONSERVATION OPPORTUNITY (ECO)

ECO NO: F
DATE: 6/15/95
ECO TITLE: Replace Existing Central Boilers With High Efficiency Modular Boilers
INSTALLATION: Fort Sam Houston, San Antonio, Texas
LOCATION: Area 2200, Building 2265

A. Summary:

| | | |
|---------------------------|--------|----------|
| Electrical Energy Savings | 38 | MMBTU/yr |
| Electrical Demand Savings | 378 | \$/yr |
| Gas Energy Savings | 910 | MMBTU/yr |
| Total Energy Savings | 948 | MMBTU/yr |
| Total Cost Savings | 3,037 | \$/yr |
| Total Investment | 78,553 | \$ |
| Simple Payback | 25.8 | yrs |
| SIR | 0.69 | |

B. ECO Description:

Remove the three existing watertube boilers and three 15 HP heating water (HW) distribution pumps in building 2265, which are serving four large buildings in the 2200 area. Install two new modular high efficiency boilers, rated at 1,830 MBH and 915 MBH output, and two new HW distribution pumps, one rated at 7 1/2 HP and the other at 5 HP. Connect the new boilers and pumps to the distribution piping at the existing boiler and pump locations. The existing electrical service and controls should be reused as much as possible. Specific requirements in these areas should be determined by the design engineer responsible for this project. The boilers and pumps should be sequenced to operate only as needed to maintain the supply water temperature setpoint of approximately 180°F. This project will require engineering drawings and specifications, demolition and removal of the existing boilers and pumps, and installation of the new boilers, pumps, associated wiring and controls.

C. Discussion:

The three existing watertube boilers serving the 2200 area buildings were installed in 1988 and are rated at 2,240 MBH output capacity each. The three 15 HP pumps circulate HW from these boilers through buildings 2263, 2264, 2265 and 2266. All these boilers appear to be in fair condition. Computer simulations of the four buildings served by these boilers determined that the current combined capacity of 6,720 MBH is over two times the amount required to adequately heat the buildings⁶. The existing boilers are therefore operating at an inefficient, low load condition most of the time. Also, because of the constant flow rate requirements of the boilers, excessive pumping energy is expended. By staging two new high efficiency modular boilers to operate only as needed, a substantial energy savings can be realized. Also, a decrease in the combined boiler output capacity to 2,745 MBH is recommended to more closely match the heating load in the buildings and reduce the associated pumping energy consumption.

D. Savings Calculations:

The monthly peak demand and energy consumptions of the existing and proposed boilers and HW pumps were calculated using the Trace 600 computer program⁷. The buildings served by the existing boilers were modeled by the computer to provide a realistic load profile. Field data obtained from the buildings were used to create these computer building models⁸.

The two new high efficiency, modular type boilers modeled were rated at 1,830 MBH and 915 MBH output. Full and part load performance data from Aerco International were used in the computer simulations of the new boiler energy usages⁹. An equipment list with specific data on the new boilers and pumps used in the computer simulation is shown on page E-9.

Once the computer simulations of the existing and new boiler systems were completed, the total annual demand cost and energy consumption of the new systems were compared with that of the existing systems to determine the annual savings¹⁰. These savings calculations are shown on page E-10. The demand and energy savings values were used in the life cycle cost analysis for this ECO. The results of these savings calculations were as follows:

| New Boiler Type | Gas Savings MMBTU/yr | Electrical Savings MMBTU/yr | Demand Savings \$/yr |
|--------------------------|----------------------------|-----------------------------------|----------------------------|
| Modular, High Efficiency | 910 | 38 | 378 |

E. Cost Estimates

The total installation costs for this ECO were estimated on page E-11. These costs were used in the life cycle cost analysis.

F. Life Cycle Cost Analysis.

A life cycle cost analysis was performed on this ECO using the Life Cycle Cost In Design (LCCID) computer program, and data from the previously mentioned calculations. A summary sheet for this life cycle cost analysis is shown on page E-12. The data from the life cycle cost analysis were included in the summary on page E-7.

REFERENCES

6. See Appendix B for Area 2200 heating system load profile.
7. See Appendix B for computer model input assumptions and data, and energy consumption output data.
8. See Appendix C for building field data and existing HVAC system data.
9. See Appendix G for manufacturer's equipment performance data from Aerco International.
10. See Appendix A for utility cost analysis data, used in the savings calculations.

JUNE 2, 1995

[illegible]

2200 AREA

| ITEM | EXISTING CENTRAL BOILER PLANT MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|------------------|---|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Watertube Boiler | | | | | | | | | | | | | | 4,936 |
| Watertube Boiler | | | | | | | | | | | | | | 13 |
| HW Pump | 11.2 | 11.2 | 11.2 | 11.2 | | | | | | | 11.2 | 11.2 | 48,609 | |
| HW Pump | 0.6 | 0.6 | 0.6 | 0.6 | | | | | | | 0.6 | 0.6 | 2,433 | |
| HW Pump | 11.2 | 11.2 | | | | | | | | | | 11.2 | 470 | |
| HW Pump | 0.6 | 0.6 | | | | | | | | | | 0.6 | 24 | |
| Totals | 23.6 | 23.6 | 11.8 | 11.8 | | | | | | | 11.8 | 23.6 | 51,536 | 4,949 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | 177 | 177 | 89 | 89 | | | | | | | 89 | 177 | | |

Total Demand 797 \$/yr

Total Energy 176 MMBTU/yr (electric)

Total Energy 4,949 MMBTU/yr (gas)

| ITEM | ECO-F: NEW CENTRAL HIGH EFFICIENCY MODULAR BOILERS MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|----------------|--|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Modular Boiler | | | | | | | | | | | | | | 3,983 |
| Modular Boiler | | | | | | | | | | | | | | 56 |
| HW Pump | 5.6 | 5.6 | 5.6 | 5.6 | | | | | | | 5.6 | 5.6 | 24,326 | |
| HW Pump | 3.7 | 3.7 | 3.7 | 3.7 | | | | | | | 3.7 | 3.7 | 16,203 | |
| Total (KW) | 9.3 | 9.3 | 9.3 | 9.3 | | | | | | | 9.3 | 9.3 | 40,529 | 4,039 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | 70 | 70 | 70 | 70 | | | | | | | 70 | 70 | | |

Total Demand 419 \$/yr

Demand Savings 378 \$/yr

Energy Savings 38 MMBTU/yr (electric)

Energy Savings 910 MMBTU/yr (gas)

| | | | |
|--|--|----------------------------------|-------------------------|
| LOCATION: AREA 2200, BUILDING 2265, FORT SAM HOUSTON | | PROJECT NO: 03-0185.04 | DATE: 6/16/95 |
| BY: PIEPER C.A. | | CHECKED BY: KLK | |

PROJECT DESCRIPTION: ECO-F, Replace Existing Central Boilers With High Efficiency Modular Boilers

| ITEM DESCRIPTION | QUANTITY | | LABOR | | | MATERIAL | | TOTAL COST |
|---|------------|------------|-------------|----------|----------|-------------|----------|------------|
| | # of Units | Unit Meas. | Hrs / Unit | Rate | Total | Unit Price | Total | |
| Remove Boiler | 3 | EA | 60.00 | \$24.64 | \$4,435 | \$500.00 | \$1,500 | \$5,935 |
| Remove Pump | 3 | EA | 6.00 | \$24.64 | \$444 | | | \$444 |
| Install New Boiler | 1 | EA | 81.00 | \$24.64 | \$1,996 | \$18,001.00 | \$18,001 | \$19,997 |
| AERCO # KC 2000 GWB Natural Draft , Water Tube 1830 MBH | 1 | EA | 40.00 | \$24.64 | \$986 | \$12,000.00 | \$12,000 | \$12,986 |
| AERCO # KC 1000 GWB Natural Draft , Water Tube 915 MBH | 1 | EA | 11.00 | \$24.64 | \$271 | \$1,669.00 | \$1,669 | \$1,940 |
| Install New Pump 7.5 Hp | 1 | EA | 10.00 | \$24.64 | \$246 | \$1,600.00 | \$1,600 | \$1,846 |
| Install New Pump 5.0 HP | 1 | JOB | 42.00 | \$24.64 | \$1,035 | \$3,600.00 | \$3,600 | \$4,635 |
| Pipe Assembly & valves Boiler | 2 | EA | 9.00 | \$24.64 | \$444 | \$350.00 | \$700 | \$1,144 |
| Pipe Assembly & valves Pump | 40 | LF | 2.00 | \$24.64 | \$1,971 | \$147.00 | \$5,880 | \$7,851 |
| Boiler Breaching Stainless steel | 1 | JOB | 20.00 | \$24.64 | \$493 | \$55.00 | \$55 | \$548 |
| Reconnect Controls | 1 | JOB | 16.00 | \$24.64 | \$394 | \$200.00 | \$200 | \$594 |
| Reconnect Electrical | 1 | JOB | 10.00 | \$24.64 | \$246 | \$50.00 | \$50 | \$296 |
| Reconnect Chemical system | | | | | | | | |
| Test , Balance & Start-up | 1 | LS | 20.00 | \$24.64 | \$493 | | | \$493 |
| | | | | | | | | |
| | | | | SUBTOTAL | \$13,454 | | \$45,255 | \$58,709 |
| | | | O & P @ 20% | | \$2,691 | | \$9,051 | \$11,742 |
| | | | SUBTOTAL | | \$16,145 | | \$54,306 | \$70,451 |
| | | | DESIGN @ 6% | | | | | \$4,227 |
| | | | SUBTOTAL | | | | | \$74,678 |
| | | | SIQH @ 5.5% | | | | | \$3,875 |
| | | | TOTAL | | | | | \$78,553 |

HUITT-ZOLLARS, INC.,
ENGINEERS / ARCHITECTS
512 MAIN STREET, SUITE 1500
FORT WORTH, TEXAS 76102-3922
(817) 335-3000 * FAX (817) 335-1025

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
512 MAIN STREET, SUITE 1500
FORT WORTH, TEXAS 76102-3922
(817) 335-3000 * FAX (817) 335-1025

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-F

ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|--------|--------|
| A. CONSTRUCTION COST | \$ | 70451. | |
| B. SIOH | \$ | 3875. | |
| C. DESIGN COST | \$ | 4227. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 78553. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | 78553. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 38. | \$ 239. | 15.08 | \$ 3599. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 910. | \$ 2421. | 18.58 | \$ 44975. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 378. | 14.88 | \$ 5625. |
| N. TOTAL | | 948. | \$ 3037. | | \$ 54198. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|----|
| A. ANNUAL RECURRING (+/-) | | \$ | 0. |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 0. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+) COST(-) (4) |
|----------|------------------------------|-----------------|------------------------|---|
| d. TOTAL | \$ 0. | | | 0. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 0.

4. FIRST YEAR DOLLAR SAVINGS 2N3+3A+(3Bd1/(YRS ECONOMIC LIFE)) \$ 3037.

5. SIMPLE PAYBACK PERIOD (1G/4) 25.86 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 54198.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= .69
(IF < 1 PROJECT DOES NOT QUALIFY)

ENERGY CONSERVATION OPPORTUNITY (ECO)

ECO NO: G
DATE: 6/15/95
ECO TITLE: Replace Existing Individual Building Chillers With Central Chiller Plant
INSTALLATION: Fort Sam Houston, San Antonio, Texas
LOCATION: Quadrangle Area

A. Summary:

| | | |
|---------------------------|---------|----------|
| Electrical Energy Savings | 2,212 | MMBTU/yr |
| Electrical Demand Savings | 14,116 | \$/yr |
| Gas Energy Savings | 0 | MMBTU/yr |
| Total Energy Savings | 2,212 | MMBTU/yr |
| Total Cost Savings | 39,257 | \$/yr |
| Total Investment | 824,178 | \$ |
| Simple Payback | 20.9 | yrs |
| SIR | 0.71 | |

B. ECO Description:

Remove the seven existing air cooled, reciprocating chillers serving buildings 4015, 56, 16 and 44. Install a chilled water supply and return piping loop between the buildings in this area and terminate loop behind building 56, near the existing air cooled chiller installation. Install two new 275 ton, air cooled screw chillers in that location. Install two new 30 HP chilled water distribution pumps by new chillers to circulate water from new chillers through new distribution loop. Construct 10' high stone wall around new chiller plant to match local historical architecture. The existing chilled water pumps that serve buildings where chillers were removed will be reused to circulate chilled water from the new loop through the buildings. These existing pumps should be connected into the new distribution piping at the existing chiller locations. All new controls and electrical services should be installed at building 56 to serve the new central chillers and pumps. Other specific requirements should be determined by the design engineer responsible for this project. This project will require engineering drawings and specifications, demolition and removal of the existing chillers and installation of the new chillers, associated wiring and controls.

C. Discussion:

The seven existing air cooled, reciprocating chillers in the Quadrangle area were installed between 1983 and 1994. They serve as the primary cooling systems for the four historically significant buildings. They generally appear to be in fair condition at this time. However, the cost of maintaining so many chillers is excessive and difficult for the maintenance staff. It is recommended that a central chiller plant, consisting of two air cooled screw machines be installed to serve all these buildings. This will not only save energy but will also reduce the maintenance costs to the installation. Computer simulations of the buildings in this area determined that the current installed capacity of 565 tons is slightly more than is required to adequately cool the buildings¹. Therefore, it is recommended that the two new chillers be rated at a combined 550 tons to more closely match the cooling load of the buildings.

D. Savings Calculations:

1. *Energy Consumption And Savings*

The monthly peak demand and energy consumptions of the existing and proposed chillers and pumps were calculated using the Trace 600 computer program². The buildings served by the existing chillers were modeled by the computer to provide a realistic load profile. Field data obtained from the buildings were used to create these computer building models³.

The 275 ton air cooled screw chillers which were modeled by the computer had better part load performance ratings than reciprocating machines and were chosen for that reason. Full and part load performance data from McQuay Incorporated were used in the computer simulations of the new chiller energy usages. An equipment list of the specific chillers and pumps modeled for the new central plant are shown on page E-15.

Once the computer simulations of the existing and new chiller plants were completed, the total annual demand cost and energy consumption of the new central plant was compared with that of the existing individual systems to determine the annual savings for this ECO⁴. These savings calculations are shown on page E-16. These demand and energy savings values were used in the life cycle cost analysis.

2. *Maintenance Cost Savings:*

Maintenance cost estimates were obtained from a local maintenance contractor and were used to estimate the maintenance savings from reducing the total number of air cooled chillers in this area from seven down to two⁵. Based on an annual maintenance cost of \$2,250 per chiller, the total maintenance cost savings from this ECO is estimated to be \$11,250 per year. This figure was used in the life cycle cost analysis.

E. Cost Estimates

The total installation costs for the new central chiller plant were estimated on page E-17. These costs were used in the life cycle cost analysis.

F. Life Cycle Cost Analysis.

A life cycle cost analysis was performed on this ECO using the Life Cycle Cost In Design (LCCID) computer program, and data from the previously mentioned calculations. A summary sheet for this life cycle cost analysis is shown on page E-18. The data from the summary sheet were presented in the ECO summary on page E-13.

REFERENCES

1. See Appendix B for Quadrangle Area cooling system load profile.
2. See Appendix B for computer model input assumptions and data, and energy consumption output data.
3. See Appendix C for building field data and existing HVAC system data.
4. See Appendix A for utility cost analysis data, used in the savings calculations.
5. See Appendix G for maintenance contractor cost estimates for air cooled chillers.

JUNE 2, 1995

E-15

QUADRANGLE AREA

| ITEM | EXISTING INDIVIDUAL CHILLER PLANTS MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|-----------------|--|------|------|------|-------|-------|--------|--------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 83.1 | 86.8 | 90.0 | 89.3 | 83.4 | 76.9 | | | 180,278 | |
| Water Chiller | | | | | 36.9 | 40.4 | 43.9 | 44.1 | 37.5 | 27.4 | | | 76,755 | |
| Water Chiller | | | | | 159.0 | 185.9 | 188.5 | 189.2 | 166.5 | 157.2 | | | 393,031 | |
| Water Chiller | | | | | 155.6 | 170.6 | 184.6 | 185.3 | 160.4 | 119.9 | | | 122,759 | |
| Water Chiller | | | | | 98.2 | 106.1 | 113.6 | 115.1 | 103.4 | 93.6 | | | 296,194 | |
| Water Chiller | | | | | 143.1 | 155.5 | 166.4 | 168.7 | 151.4 | 137.2 | | | 243,230 | |
| Water Chiller | | | | | 143.1 | 155.5 | 166.4 | 168.7 | 151.4 | 121.0 | | | 104,234 | |
| CHW Pump | | | | | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | | 16,472 | |
| CHW Pump | | | | | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | | 16,472 | |
| CHW Pump | | | | | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | | 16,472 | |
| CHW Pump | | | | | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | | | 24,730 | |
| CHW Pump | | | | | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | 5.6 | | | 24,730 | |
| CHW Pump | | | | | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | 14.9 | | | 65,887 | |
| CHW Pump | | | | | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | | 7,822 | |
| CHW Pump | | | | | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | 3.7 | | | 3,036 | |
| Evap. Condenser | | | | | 9.3 | 9.3 | 9.3 | 9.3 | 9.3 | 9.3 | | | 41,201 | |
| Totals | | | | | 872.9 | 954.7 | 1007.3 | 1014.3 | 907.9 | 787.1 | | | 1,633,303 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 6,547 | 9,547 | 10,073 | 10,143 | 9,079 | 5,903 | | | | |

Total Demand 51,292 \$/yr

Total Energy 5,574 MMBTU/yr (electric)

Total Energy MMBTU/yr (gas)

| ITEM | ECO-G: NEW CENTRAL AIR COOLED SCREW CHILLERS MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|---------------|--|------|------|------|-------|-------|-------|-------|-------|-------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Water Chiller | | | | | 287.6 | 328.3 | 351.0 | 351.0 | 306.5 | 271.9 | | | 607,003 | |
| Water Chiller | | | | | 287.6 | 328.3 | 351.0 | 351.0 | 306.5 | 216.4 | | | 253,553 | |
| CHW Pump | | | | | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | | | 98,830 | |
| CHW Pump | | | | | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | 22.4 | | | 25,759 | |
| Total (KW) | | | | | 620.0 | 701.4 | 746.8 | 746.8 | 657.8 | 533.1 | | | 985,145 | |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | | | | | 4,650 | 7,014 | 7,468 | 7,468 | 6,578 | 3,998 | | | | |

Total Demand 37,176 \$/yr

Demand Savings 14,116 \$/yr

Energy Savings 2,212 MMBTU/yr (electric)

Energy Savings MMBTU/yr (gas)

ENGINEER'S ESTIMATE OF PROBABLE COST

LOCATION: QUAD AREA, FORT SAM HOUSTON
PROJECT NO: 03-0185.04
DATE: 6/16/95
BY: PIEPER, C.A./KOTHMANN, K.
CHECKED BY: WHW

PROJECT DESCRIPTION: ECO-G, Replace Existing Individual Building Chillers With Central Chiller Plant

| ITEM DESCRIPTION | QUANTITY | | LABOR | | | MATERIAL | | TOTAL COST |
|--|------------|------------|------------|---------|-----------|-------------|-----------|------------|
| | # of Units | Unit Meas. | Hrs / Unit | Rate | Total | Unit Price | Total | |
| Prefabricated Insulated ConduitSCH 40 Blk Stl Pipe W/ PVC Jacket | | | | | | | | |
| 6" | 2556 | LF | 1.28 | \$24.64 | \$60,614 | \$17.88 | \$45,701 | \$126,315 |
| 4" | 500 | LF | 1.04 | \$24.64 | \$12,813 | \$15.96 | \$7,980 | \$20,793 |
| 2-1/2" | 588 | LF | 0.94 | \$24.64 | \$13,619 | \$12.54 | \$7,374 | \$20,993 |
| Chiller Yard Enclosure 40' X 40' W/ Steel Gate 10'-0" High | 1 | JOB | | \$24.64 | \$11,291 | | \$38,707 | \$49,998 |
| Stone Vent Wall (12" X 12" X 18") Historically Correct | | | | | | | | |
| Water Chiller Air Cooled 275 TON Single Screw w/ Pipe Assembly | 2 | EA | 1420.00 | \$24.64 | \$69,978 | \$99,000.00 | \$198,000 | \$267,978 |
| Chilled Water Pump 660 GPM X 120' 30 HP W/ Pipe Assembly | 2 | EA | 27.50 | \$24.64 | \$1,355 | \$3,300.00 | \$6,600 | \$7,955 |
| Connect to Existing Hydronic System | 4 | BLDG | 75.00 | \$24.64 | \$7,392 | \$2,800.00 | \$11,200 | \$18,592 |
| Controls / Test & Balance | 1 | JOB | 90.00 | \$24.64 | \$2,218 | \$6,500.00 | \$6,500 | \$8,718 |
| Remove Chiller & CW pump (50 Ton) BLDG 4015 | 1 | JOB | 80.00 | \$24.64 | \$1,971 | \$100.00 | \$100 | \$2,071 |
| Remove Chiller & CW pump (30 Ton) BLDG 56 | 1 | JOB | 48.00 | \$24.64 | \$1,183 | \$100.00 | \$100 | \$1,283 |
| Remove Chiller & CW pump (110 Ton) BLDG 16 | 1 | JOB | 150.00 | \$24.64 | \$3,696 | \$200.00 | \$200 | \$3,896 |
| Remove Chiller & CW pump (120 Ton) BLDG 16 | 1 | JOB | 150.00 | \$24.64 | \$3,696 | \$200.00 | \$200 | \$3,896 |
| Remove Chiller & CW pump BLDG 44 | 255 | TON | 1.49 | \$24.64 | \$9,362 | \$1.50 | \$383 | \$9,745 |
| Remove Condenser Pump Bldg 16 | 3 | EA | 6.00 | \$24.64 | \$444 | \$100.00 | \$300 | \$744 |
| Electrical | 1 | JOB | | | | | \$73,000 | \$73,000 |
| SUBTOTAL | | | | | \$219,632 | | \$396,345 | \$615,977 |
| O & P @ 20% | | | | | \$43,926 | | \$79,269 | \$123,195 |
| SUBTOTAL | | | | | \$263,558 | | \$475,614 | \$739,172 |
| DESIGN @ 6% | | | | | | | | \$44,350 |
| SUBTOTAL | | | | | | | | \$783,522 |
| SIQH @ 5.5% | | | | | | | | \$40,654 |
| TOTAL | | | | | | | | \$824,176 |

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
 512 MAIN STREET, SUITE 1500
 FORT WORTH, TEXAS 76102-3922
 (817) 335-3000 * FAX (817) 335-1025

LIFE CYCLE COST ANALYSIS SUMMARY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: FSH
 INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3
 PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY
 FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-G
 ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | |
|--|----|---------|---------|
| A. CONSTRUCTION COST | \$ | 739172. | |
| B. SIOH | \$ | 40655. | |
| C. DESIGN COST | \$ | 44351. | |
| D. TOTAL COST (1A+1B+1C) | \$ | 824178. | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | 824178. |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | 2212. | \$ 13891. | 15.08 | \$ 209482. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | 0. | \$ 0. | 18.58 | \$ 0. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 14116. | 14.88 | \$ 210046. |
| N. TOTAL | | 2212. | \$ 28007. | | \$ 419528. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | |
|---------------------------------------|-------|------------|
| A. ANNUAL RECURRING (+/-) | | \$ 11250. |
| (1) DISCOUNT FACTOR (TABLE A) | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ 167400. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTR (3) | DISCOUNTED SAVINGS(+) COST(-) (4) |
|----------|------------------------------|-----------------|------------------------|---|
| d. TOTAL | \$ 0. | | | 0. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 167400.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 39257.

5. SIMPLE PAYBACK PERIOD (1G/4) 20.99 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 586928.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= .71
 (IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

ENERGY CONSERVATION OPPORTUNITY (ECO)

ECO NO: H
DATE: 6/15/95
ECO TITLE: Replace Existing Individual Building Boilers With Central Boiler Plant
INSTALLATION: Fort Sam Houston, San Antonio, Texas
LOCATION: Quadrangle Area, Building 16

A. Summary:

| | | |
|---------------------------|---------|----------|
| Electrical Energy Savings | -12 | MMBTU/yr |
| Electrical Demand Savings | 122 | \$/yr |
| Gas Energy Savings | -434 | MMBTU/yr |
| Total Energy Savings | -446 | MMBTU/yr |
| Total Cost Savings | 5,542 | \$/yr |
| Total Investment | 394,910 | \$ |
| Simple Payback | 71.2 | yrs |
| SIR | 0.20 | |

B. ECO Description:

Remove twelve existing steam boilers in building 44, which serve as the primary heating source for that building. Install a new condensate receiver, pump and buried piping to return condensate to the new central boiler plant in building 16. Provide new electrical connections as required for the new condensate pump.

Remove one 741 MBH hot water boiler from building 4015 which serves as the primary heating source for that building. Install a new 250 MBH steam to hot water generator in place of the boiler. The existing 3 HP distribution pump will remain to circulate heating water from the new generator through the building. Install a new condensate receiver, pump and buried piping to return condensate from the new generator to the new central boiler plant in building 16. Provide new electrical connections as required for the new condensate pump.

Remove one 1,614 MBH steam boiler from building 16, which serves only that building. The 3,587 MBH steam boiler in building 16 which serves it and building 56 shall remain and be used as a new central steam boiler for buildings 16, 56, 44 and 4015. Install a new condensate receiver and pump in the location where the other boiler was removed, and install new condensate return piping from there to the new central steam boiler plant in the building

Install new buried steam distribution piping from the new central steam boiler in the building out to buildings 4015, 44 and the area in building 16 where the other boiler was removed.. Connect existing steam distribution piping in buildings 44 and 16 to the new central steam distribution piping. Connect the new steam to hot water generator in building 4015 to the new central steam distribution piping.

C. Discussion:

The twelve existing steam boilers in building 44 were installed in 1970 and are rated at a combined 2,902 MBH output capacity. The single hot water boiler in building 4015 was installed in 1983, and the two steam boilers in building 16 were installed in 1979. All of these boilers appear to be in fair to poor condition. Computer simulations of the four buildings in the Quadrangle area determined that the current combined capacity of 8,970 MBH is over two times the amount required to adequately heat the buildings¹. The existing boilers are therefore operating at an inefficient, low load condition most of the

time. By eliminating the extra boilers in the area, maintenance cost savings can be realized. Also, a decrease in the combined boiler output capacity to 3,587 MBH is recommended to more closely match the heating load in the buildings.

D. Savings Calculations:

1. *Energy Savings:*

The monthly peak demand and energy consumptions of the existing and proposed boilers and HW pump were calculated using the Trace 600 computer program². The buildings served by the existing boilers were modeled by the computer to provide a realistic load profile. Field data obtained from the buildings were used to create these computer building models³. An equipment list with specific data on the new central boiler system used in the computer simulation is shown on page E-21.

Once the computer simulations of the existing and new boiler systems were completed, the total annual demand cost and energy consumption of the new systems were compared with that of the existing systems to determine the annual savings⁴. These savings calculations are shown on page E-22. The demand and energy savings values were used in the life cycle cost analysis for this ECO.

2. *Maintenance Savings:*

Since the total number of boilers is being reduced from fifteen down to one, there will be a substantial savings in maintenance costs. Maintenance cost estimates were obtained from a local contractor and used to estimate these savings for the installation⁵. Based on a cost annual maintenance cost of \$475 per boiler, the total estimated maintenance cost savings for this ECO is \$6,650. This figure was used in the life cycle cost analysis.

E. Cost Estimates

The total installation costs for this ECO were estimated on page E-23. These costs were used in the life cycle cost analysis.

F. Life Cycle Cost Analysis.

A life cycle cost analysis was performed on this ECO using the Life Cycle Cost In Design (LCCID) computer program, and data from the previously mentioned calculations. A summary sheet for this life cycle cost analysis is shown on page E-24. The data from the life cycle cost analysis were included in the summary on page E-19.

REFERENCES

1. See Appendix B for Quadrangle Area heating system load profile.
2. See Appendix B for computer model input assumptions and data, and energy consumption output data.
3. See Appendix C for building field data and existing HVAC system data.
4. See Appendix A for utility cost analysis data, used in the savings calculations.
5. See Appendix G for maintenance contractor cost estimates.

QUADRANGLE AREA

| ITEM | EXISTING INDIVIDUAL BOILER PLANTS MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|-----------------|---|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Steam Boiler | | | | | | | | | | | | | | 651 |
| Steam Boiler | | | | | | | | | | | | | | 267 |
| Steam Boiler | | | | | | | | | | | | | | 103 |
| Steam Boiler | | | | | | | | | | | | | | 66 |
| Steam Boiler | | | | | | | | | | | | | | 3 |
| Firetube Boiler | 3.7 | 3.7 | 3.7 | | | | | | | | 3.7 | 3.7 | 4,275 | 120 |
| HW Pump | 2.2 | 2.2 | 2.2 | | | | | | | | 2.2 | 2.2 | 1,821 | |
| Totals | 5.9 | 5.9 | 5.9 | | | | | | | | 5.9 | 5.9 | 6,096 | 1,210 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | 44 | 44 | 44 | | | | | | | | 44 | 44 | | |

Total Demand 221 \$/yr

Total Energy 21 MMBTU/yr (electric)

Total Energy 1,210 MMBTU/yr (gas)

| ITEM | ECO-H: NEW CENTRAL BOILER PLANT MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|--------------|---|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Steam Boiler | | | | | | | | | | | | | | 1,644 |
| HW Pump | 2.2 | 2.2 | 2.2 | 2.2 | | | | | | | 2.2 | 2.2 | 9,731 | |
| Total (KW) | 2.2 | 2.2 | 2.2 | 2.2 | | | | | | | 2.2 | 2.2 | 9,731 | 1,644 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | 17 | 17 | 17 | 17 | | | | | | | 17 | 17 | | |

Total Demand 99 \$/yr

Demand Savings 122 \$/yr

Energy Savings -12 MMBTU/yr (electric)

Energy Savings -434 MMBTU/yr (gas)

ENGINEER'S ESTIMATE OF PROBABLE COST

LOCATION: QUAD AREA, FORT SAM HOUSTON
PROJECT NO: 03-0185.04
DATE: 6/16/95
BY: PIEPER, C.A. / KOTHMANN, K.
CHECKED BY: WHW

PROJECT DESCRIPTION: ECO-H, Replace Existing Individual Building Boilers With Central Boiler Plant

| ITEM DESCRIPTION | QUANTITY | | LABOR | | MATERIAL | | TOTAL COST |
|---|------------|------------|------------|---------|------------|-----------|------------|
| | # of Units | Unit Meas. | Hrs / Unit | Rate | Unit Price | Total | |
| Condinsate Rreciever Pump Combo Unit with Pipe Assembly & Valves | | | | | | | |
| 6 GPM, 60 psi, 640 lb BLDG 44 | 1 | EA | 33.00 | \$24.64 | \$4,600.00 | \$4,600 | \$5,413 |
| 1.5 GPM, 30psi, 245lb / hr, BLDG 4015 | 1 | EA | 16.60 | \$24.64 | \$2,700.00 | \$2,700 | \$3,109 |
| 6 GPM, 60 psi, 640 lb / hr. BLDG 16 | 1 | EA | 33.00 | \$24.64 | \$4,600.00 | \$4,600 | \$5,413 |
| Electrcal Connections & Motor Feeders | 1 | JOB | 81.00 | \$24.64 | \$1,800.00 | \$1,800 | \$3,796 |
| Prefabricated Insulated Conduit sch 80 STL Carrier 2" insul. PVC Jacket | | | | | | | |
| 2-1/2" with Fittings Trench & Backfill | 2375 | LF | 0.94 | \$24.64 | \$15.70 | \$37,288 | \$92,297 |
| 1-1/2" with Fittings Trench & Backfill | 250 | LF | 0.84 | \$24.64 | \$13.60 | \$3,400 | \$8,574 |
| 1" with Fittings Trench & Backfill | 100 | LF | 0.79 | \$24.64 | \$12.75 | \$1,275 | \$3,222 |
| Connect to Existing Hydronic System | 4 | BLDG | 40.00 | \$24.64 | \$2,150.00 | \$8,600 | \$12,542 |
| Prefabricated Insulated Conduit sch 40 STL Carrier 1" insul. PVC Jacket | | | | | | | |
| 2" with Fittings Trench & Backfill | 2,375 | LF | 0.81 | \$24.64 | \$11.75 | \$27,906 | \$75,307 |
| 1-1/2" with Fittings Trench & Backfill | 250 | LF | 0.78 | \$24.64 | \$10.54 | \$2,635 | \$7,440 |
| 1" with Fittings Trench & Backfill | 100 | LF | 0.76 | \$24.64 | \$9.37 | \$937 | \$2,810 |
| Reuse 3 HP Hot Water Pump Bldg 4015 | 1 | EA | 13.20 | \$24.64 | \$345.00 | \$345 | \$670 |
| Steam to Hot Water Generator, 250 MBH, bldg 4015 | 1 | EA | 15.65 | \$24.64 | \$1,500.00 | \$1,500 | \$1,886 |
| Remove Boiler & Piping | 15 | EA | 137.00 | \$24.64 | \$225.00 | \$3,375 | \$54,010 |
| Controls and Test & Balance | 5 | BLDG | 50.00 | \$24.64 | \$2,500.00 | \$12,500 | \$18,660 |
| SUBTOTAL | | | | | | \$181,688 | \$295,149 |
| O & P @ 20% | | | | | | \$36,338 | \$59,030 |
| SUBTOTAL | | | | | | \$218,026 | \$354,179 |
| DESIGN @ 6% | | | | | | | \$21,251 |
| SUBTOTAL | | | | | | | \$375,430 |
| SIQH @ 5.5% | | | | | | | \$19,480 |
| TOTAL | | | | | | | \$394,910 |

HUITT-ZOLLARS, INC.
ENGINEERS / ARCHITECTS
 512 MAIN STREET, SUITE 1500
 FORT WORTH, TEXAS 76102-3922
 (817) 335-3000 * FAX (817) 335-1025

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: FSH

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FSH REGION NOS. 6 CENSUS: 3

PROJECT NO. & TITLE: 03018504 EEAP BOILER CHILLER STUDY

FISCAL YEAR 96 DISCRETE PORTION NAME: ECO-H

ANALYSIS DATE: 06-16-95 ECONOMIC LIFE 20 YEARS PREPARED BY: PIEPER

1. INVESTMENT

| | | | | |
|--|----|---------|---------|--|
| A. CONSTRUCTION COST | \$ | 354179. | | |
| B. SIOH | \$ | 19480. | | |
| C. DESIGN COST | \$ | 21251. | | |
| D. TOTAL COST (1A+1B+1C) | \$ | 394910. | | |
| E. SALVAGE VALUE OF EXISTING EQUIPMENT | \$ | 0. | | |
| F. PUBLIC UTILITY COMPANY REBATE | \$ | 0. | | |
| G. TOTAL INVESTMENT (1D - 1E - 1F) | \$ | | 394910. | |

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

| FUEL | UNIT COST \$/MBTU(1) | SAVINGS MBTU/YR(2) | ANNUAL \$ SAVINGS(3) | DISCOUNT FACTOR(4) | DISCOUNTED SAVINGS(5) |
|-------------------|-------------------------|-----------------------|-------------------------|-----------------------|--------------------------|
| A. ELECT | \$ 6.28 | -12. | \$ -75. | 15.08 | \$ -1136. |
| B. DIST | \$.00 | 0. | \$ 0. | 18.57 | \$ 0. |
| C. RESID | \$.00 | 0. | \$ 0. | 21.02 | \$ 0. |
| D. NAT G | \$ 2.66 | -434. | \$ -1154. | 18.58 | \$ -21449. |
| E. COAL | \$.00 | 0. | \$ 0. | 16.83 | \$ 0. |
| F. PPG | \$.00 | 0. | \$ 0. | 17.38 | \$ 0. |
| M. DEMAND SAVINGS | | | \$ 122. | 14.88 | \$ 1815. |
| N. TOTAL | | -446. | \$ -1108. | | \$ -20771. |

3. NON ENERGY SAVINGS(+) / COST(-)

| | | | |
|---------------------------------------|--|-------|--------|
| A. ANNUAL RECURRING (+/-) | | \$ | 6650. |
| (1) DISCOUNT FACTOR (TABLE A) | | 14.88 | |
| (2) DISCOUNTED SAVING/COST (3A X 3A1) | | \$ | 98952. |

B. NON RECURRING SAVINGS(+) / COSTS(-)

| ITEM | SAVINGS(+) COST(-) (1) | YR OC (2) | DISCNT FACTOR (3) | DISCOUNTED SAVINGS(+)/ COST(-) (4) |
|----------|------------------------------|-----------------|-------------------------|--|
| d. TOTAL | \$ 0. | | | 0. |

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-) (3A2+3Bd4) \$ 98952.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 5542.

5. SIMPLE PAYBACK PERIOD (1G/4) 71.26 YEAR

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 78181.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= .20
(IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

ENERGY CONSERVATION OPPORTUNITY (ECO)

ECO NO: J
DATE: 6/15/95
ECO TITLE: Replace Existing Individual Building Boilers With Central Boiler Plant
INSTALLATION: Fort Sam Houston, San Antonio, Texas
LOCATION: Area 100, Building 250

A. Summary:

| | | |
|---------------------------|---------|----------|
| Electrical Energy Savings | 186 | MMBTU/yr |
| Electrical Demand Savings | 680 | \$/yr |
| Gas Energy Savings | 680 | MMBTU/yr |
| Total Energy Savings | 866 | MMBTU/yr |
| Total Cost Savings | 11,483 | \$/yr |
| Total Investment | 273,951 | \$ |
| Simple Payback | 23.8 | yrs |
| SIR | 0.66 | |

B. ECO Description:

Remove fourteen existing hot water boilers in buildings 122, 124, 128, 133, 134, 142, 143, 144, 146, 147, 149, 197, 198 and 199 which serve as the primary heating source for those buildings. Remove the two existing steam boilers in building 250. Install two new central hot water boilers rated at 563 MBH and 1250 MBH output. Locate these new boilers outside of building 250, near existing air cooled chiller installation. Install new 3 1/2 inch hot water supply and return piping between the buildings in the 100 area and terminate loop at the new boiler locations behind building 250. Install new 10 HP and 15 HP heating water pumps at that location to circulate HW from the new central boilers through the new distribution loop. Reconnect individual building HW pumps to new central HW distribution piping at existing boiler locations and reuse pumps to circulate HW from loop through buildings. Provide new electrical service for new boilers as required. Other specifications in these areas should be determined by the design engineer responsible for this project. This project will require engineering drawings and specifications, demolition and removal of the existing boilers and installation of the new boilers, pumps, distribution loop, associated electrical services and controls.

C. Discussion:

The sixteen existing boilers in Area 100 were installed in 1985 and are rated at a combined 8,829 MBH output capacity. All of these boilers appear to be in fair condition. Computer simulations of the 100 Area buildings determined that the current combined capacity is nearly five times the amount required to adequately heat the buildings¹. The existing boilers are therefore operating at an inefficient, low load condition most of the time. By eliminating the extra boilers in the area, energy and maintenance cost savings can be realized. Also, a decrease in the combined boiler output capacity to 1,813 MBH is recommended to more closely match the heating load in the buildings.

D. Savings Calculations:

1. Energy Savings:

The monthly peak demand and energy consumptions of the existing and proposed boilers and HW pumps were calculated using the Trace 600 computer program². The buildings served by the existing boilers were modeled by the computer to provide a realistic load profile. Field data obtained from the

buildings were used to create these computer building models³. An equipment list with specific data on the new central boiler system used in the computer simulation is shown on page E-27.

Once the computer simulations of the existing and new boiler systems were completed, the total annual demand cost and energy consumption of the new systems were compared with that of the existing systems to determine the annual savings⁴. These savings calculations are shown on pages E-28 through E-29. The demand and energy savings values were used in the life cycle cost analysis for this ECO.

2. Maintenance Savings:

Since the total number of boilers is being reduced from sixteen down to two, there will be a substantial savings in maintenance costs. Maintenance cost estimates were obtained from a local contractor and used to estimate these savings for the installation⁵. Based on a cost annual maintenance cost of \$475 per boiler, the total estimated maintenance cost savings for this ECO is \$6,650. This figure was used in the life cycle cost analysis.

E. Cost Estimates

The total installation costs for this ECO were estimated on page E-30. These costs were used in the life cycle cost analysis.

F. Life Cycle Cost Analysis.

A life cycle cost analysis was performed on this ECO using the Life Cycle Cost In Design (LCCID) computer program, and data from the previously mentioned calculations. A summary sheet for this life cycle cost analysis is shown on page E-31. The data from the life cycle cost analysis were included in the summary on page E-25.

REFERENCES

1. See Appendix B for 100 Area heating system load profile.
2. See Appendix B for computer model input assumptions and data, and energy consumption output data.
3. See Appendix C for building field data and existing HVAC system data.
4. See Appendix A for utility cost analysis data, used in the savings calculations.
5. See Appendix G for maintenance contractor cost estimates.

100 AREA

| ITEM | EXISTING INDIVIDUAL BOILER PLANTS MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|------------------|---|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Watertube Boiler | | | | | | | | | | | | | | 193 |
| Watertube Boiler | | | | | | | | | | | | | | 226 |
| Watertube Boiler | | | | | | | | | | | | | | 82 |
| Firetube Boiler | 3.7 | 3.7 | 3.7 | 3.7 | | | | | | | 3.7 | 3.7 | 16,203 | 177 |
| Watertube Boiler | | | | | | | | | | | | | | 76 |
| Watertube Boiler | | | | | | | | | | | | | | 190 |
| Watertube Boiler | | | | | | | | | | | | | | 112 |
| Watertube Boiler | | | | | | | | | | | | | | 112 |
| Watertube Boiler | | | | | | | | | | | | | | 116 |
| Watertube Boiler | | | | | | | | | | | | | | 116 |
| Watertube Boiler | | | | | | | | | | | | | | 89 |
| Watertube Boiler | | | | | | | | | | | | | | 38 |
| Watertube Boiler | | | | | | | | | | | | | | 99 |
| Steam Boiler | | | | | | | | | | | | | | 172 |
| Watertube Boiler | | | | | | | | | | | | | | 58 |
| HW Pump | 1.1 | 1.1 | 1.1 | 1.1 | | | | | | | 1.1 | 1.1 | 3,377 | |
| HW Pump | 1.1 | 1.1 | 1.1 | 1.1 | | | | | | | 1.1 | 1.1 | 4,865 | |
| HW Pump | 1.1 | 1.1 | 1.1 | 1.1 | | | | | | | 1.1 | 1.1 | 4,865 | |
| HW Pump | 1.1 | 1.1 | 1.1 | 1.1 | | | | | | | 1.1 | 1.1 | 4,865 | |
| HW Pump | 0.4 | 0.4 | 0.4 | 0.4 | | | | | | | 0.4 | 0.4 | 1,607 | |
| HW Pump | 0.4 | 0.4 | 0.4 | 0.4 | | | | | | | 0.4 | 0.4 | 1,607 | |
| HW Pump | 0.4 | 0.4 | 0.4 | 0.4 | | | | | | | 0.4 | 0.4 | 1,039 | |
| HW Pump | 0.8 | 0.8 | 0.8 | 0.8 | | | | | | | 0.8 | 0.8 | 1,904 | |
| HW Pump | 0.8 | 0.8 | 0.8 | 0.8 | | | | | | | 0.8 | 0.8 | 1,904 | |
| HW Pump | 0.8 | 0.8 | 0.8 | 0.8 | | | | | | | 0.8 | 0.8 | 1,904 | |
| HW Pump | 0.8 | 0.8 | 0.8 | 0.8 | | | | | | | 0.8 | 0.8 | 2,136 | |
| HW Pump | 0.8 | 0.8 | 0.8 | 0.8 | | | | | | | 0.8 | 0.8 | 2,136 | |
| HW Pump | 0.8 | 0.8 | 0.8 | 0.8 | | | | | | | 0.8 | 0.8 | 1,257 | |
| HW Pump | 0.6 | 0.6 | 0.6 | 0.6 | | | | | | | 0.6 | 0.6 | 1,106 | |
| HW Pump | 1.1 | 1.1 | 1.1 | 1.1 | | | | | | | 1.1 | 1.1 | 4,865 | |
| HW Pump | 0.4 | 0.4 | 0.4 | 0.4 | | | | | | | 0.4 | 0.4 | 1,008 | |
| Gas Furnace | 11.3 | 11.3 | 11.3 | 11.3 | | | | | | | 11.3 | 11.3 | 30,002 | 35 |
| Gas Furnace | 0.7 | 0.7 | 0.7 | 0.7 | | | | | | | 0.7 | 0.7 | 3,154 | 36 |
| Totals | 28.2 | 28.2 | 28.2 | 28.2 | | | | | | | 28.2 | 28.2 | 89,804 | 1,927 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | 212 | 212 | 212 | 212 | | | | | | | 212 | 212 | | |

Total Demand 1,269 \$/yr

Total Energy 307 MMBTU/yr (electric)

Total Energy 1,927 MMBTU/yr (gas)

100 AREA

| ITEM | ECO-J: NEW CENTRAL BOILER PLANT MONTHLY PEAK DEMAND (KW) | | | | | | | | | | | | ANNUAL ENERGY USAGE (KWH) | ANNUAL ENERGY USAGE (MCF) |
|------------------|---|------|------|------|------|-------|-------|-------|-------|------|------|------|------------------------------------|------------------------------------|
| | Jan | Feb | Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | | |
| Watertube Boiler | | | | | | | | | | | | | | 756 |
| Watertube Boiler | | | | | | | | | | | | | | 491 |
| HW Pump | 7.5 | 7.5 | 7.5 | 7.5 | | | | | | | 7.5 | 7.5 | 30,802 | |
| HW Pump | 11.2 | 11.2 | | | | | | | | | | 11.2 | 4,454 | |
| Total (KW) | 18.7 | 18.7 | 7.5 | 7.5 | | | | | | | 7.5 | 18.7 | 35,256 | 1,247 |
| Rate (\$/KW) | 7.50 | 7.50 | 7.50 | 7.50 | 7.50 | 10.00 | 10.00 | 10.00 | 10.00 | 7.50 | 7.50 | 7.50 | | |
| Cost (\$) | 140 | 140 | 56 | 56 | | | | | | | 56 | 140 | | |

Total Demand 590 \$/yr

Demand Savings 680 \$/yr

Energy Savings 186 MMBTU/yr (electric)

Energy Savings 680 MMBTU/yr (gas)

APPENDIX F

(EEAP) BOILER AND CHILLER STUDY
SCOPE OF WORK AND
REVIEW COMMENTS

CESAM-EN-DM

January 1995

GENERAL SCOPE OF WORK
FOR A
LIMITED ENERGY STUDY

Performed as part of the
ENERGY ENGINEERING ANALYSIS PROGRAM (EEAP)

SCOPE OF WORK
FOR A
LIMITED ENERGY STUDY

TABLE OF CONTENTS

1. BRIEF DESCRIPTION OF WORK
2. GENERAL
3. PROJECT MANAGEMENT
4. SERVICES AND MATERIALS
5. PROJECT DOCUMENTATION
 - 5.1 ECIP Projects
 - 5.2 Non-ECIP Projects
 - 5.3 Nonfeasible ECOs
6. DETAILED SCOPE OF WORK
7. WORK TO BE ACCOMPLISHED
 - 7.2 Perform a Limited Site Survey
 - 7.4 Evaluate Selected ECOs
 - 7.5 Combine ECOs into Recommended Projects
 - 7.6 Submittals, Presentations and Reviews

ANNEXES

- A - DETAILED SCOPE OF WORK
- B - EXECUTIVE SUMMARY GUIDELINE
- C - REQUIRED DD FORM 1391 DATA

1. BRIEF DESCRIPTION OF WORK: The Architect-Engineer (AE) shall:

1.2 Perform a limited site survey of specific buildings or areas to collect all data required to evaluate the specific ECOs included in this study.

1.4 Evaluate specific ECOs to determine their energy savings potential and economic feasibility.

1.5 Provide project documentation for recommended ECOs as detailed herein.

1.6 Prepare a comprehensive report to document all work performed, the results and all recommendations.

2. GENERAL

2.1 This study is limited to the evaluation of the specific buildings, systems, or ECOs listed in Annex A, DETAILED SCOPE OF WORK.

2.2 The information and analysis outlined herein are considered to be minimum requirements for adequate performance of this study.

2.3 For the buildings, systems or ECOs listed in Annex A, all methods of energy conservation which are reasonable and practical shall be considered, including improvements of operational methods and procedures as well as the physical facilities. All energy conservation opportunities which produce energy or dollar savings shall be documented in this report. Any energy conservation opportunity considered infeasible shall also be documented in the report with reasons for elimination.

2.4 The study shall consider the use of all energy sources applicable to each building, system, or ECO.

2.5 The "Energy Conservation Investment Program (ECIP) Guidance", described in letter from DAIM-FDF-U, dated 10 Jan 1994 (including current updates) establishes criteria for ECIP projects and shall be used for performing the economic analyses of all ECOs and projects. The program, Life Cycle Cost In Design (LCCID), has been developed for performing life cycle cost calculations in accordance with ECIP guidelines and is referenced in the ECIP Guidance. If any program other than LCCID is proposed for life cycle cost analysis, it must use the mode of calculation specified

in the ECIP Guidance. The output must be in the format of the ECIP LCCA summary sheet, and it must be submitted for approval to the Contracting Officer.

2.6 Computer modeling will be used to determine the energy savings of ECOs which would replace or significantly change an existing heating, ventilating, and air-conditioning (HVAC) system. The requirement to use computer modeling applies only to heated and air-conditioned or air-conditioned-only buildings which exceed 8,000 square feet or heated-only buildings in excess of 20,000 square feet. Modeling will be done using a professionally recognized and proven computer program or programs that integrate architectural features with air-conditioning, heating, lighting and other energy-producing or consuming systems. These programs will be capable of simulating the features, systems, and thermal loads of the building under study. The program will use established weather data files and may perform calculations on a true hour-by-hour basis or may condense the weather files and the number of calculations into several "typical" days per month. The Detailed Scope of Work, Annex A, will list programs that are acceptable to the Contracting Officer. If the AE desires to use a different program, it must be submitted for approval with a sample run, an explanation of all input and output data, and a summary of program methodology and energy evaluation capabilities.

2.7 Energy conservation opportunities determined to be technically and economically feasible shall be developed into projects acceptable to installation personnel. This may involve combining similar ECOs into larger packages which will qualify for ECIP or FEMP funding, and determining in coordination with installation personnel the appropriate packaging and implementation approach for all feasible ECOs.

2.7.1 Projects which qualify for ECIP funding shall be identified, separately listed, and prioritized by the Savings to Investment Ratio (SIR).

2.7.2 All feasible non-ECIP projects shall be ranked in order of highest to lowest SIR.

2.7.3 At some installations Energy Conservation and Management (ECAM) funding will be used instead of ECIP funding. The criteria for each program is the same. The Director of Public Works will indicate which program is used at this installation. This Scope of Work mentions only ECIP, however, ECAM is also meant.

2.8 Metric Reporting Requirements: In this study, the analyses of the ECOs may be performed using English or Metric units as long as they are consistent throughout the report. The final results of energy savings for individual recommended projects and for the overall study will be reported in units of MegaBTU per year and in MegaWatts per year. Paragraph 7.6.2 details requirements for the contents of the final submittal.

3. PROJECT MANAGEMENT

3.1 Project Managers. The AE shall designate a project manager to serve as a point of contact and liaison for work required under this contract. Upon award of this contract, the individual shall be immediately designated in writing. The AE's designated project manager shall be approved by the Contracting Officer prior to commencement of work. This designated individual shall be responsible for coordination of work required under this contract. The Contracting Officer will designate a project manager to serve as the Government's point of contact and liaison for all work required under this contract. This individual will be the Government's representative.

3.2 Installation Assistance. The Commanding Officer or authorized representative at the installation will designate an individual to assist the AE in obtaining information and establishing contacts necessary to accomplish the work required under this contract. This individual will be the installation representative.

3.3 Public Disclosures. The AE shall make no public announcements or disclosures relative to information contained or developed in this contract, except as authorized by the Contracting Officer.

3.4 Meetings. Meetings will be scheduled whenever requested by the AE or the Contracting Officer for the resolution of questions or problems encountered in the performance of the work. The AE's project manager and the Government's representative shall be required to attend and participate in all meetings pertinent to the work required under this contract as directed by the Contracting Officer. These meetings, if necessary, will be in addition to the presentation and review conferences.

3.5 Site Visits, Inspections, and Investigations. The AE shall visit and inspect/investigate the site of the project as necessary and required during the preparation and accomplishment of the work.

3.6 Records

3.6.1 The AE shall provide a record of all significant conferences, meetings, discussions, verbal directions, telephone conversations, etc., with Government representative(s) relative to this contract in which the AE and/or designated representative(s) thereof participated. These records shall be dated and shall identify the contract number, and modification number if applicable, participating personnel, subject discussed and conclusions reached. The AE shall forward to the Contracting Officer within ten calendar days, a reproducible copy of the records.

3.6.2 The AE shall provide a record of requests for and/or receipt of Government-furnished material, data, documents, information, etc., which if not furnished in a timely manner, would significantly impair the normal progression of the work under this

contract. The records shall be dated and shall identify the contract number and modification number, if applicable. The AE shall forward to the Contracting Officer within ten calendar days, a reproducible copy of the record of request or receipt of material.

3.7 Interviews. The AE and the Government's representative shall conduct entry and exit interviews with the Director of Public Works before starting work at the installation and after completion of the field work. The Government's representative shall schedule the interviews at least one week in advance.

3.7.1 Entry. The entry interview shall describe the intended procedures for the survey and shall be conducted prior to commencing work at the facility. As a minimum, the interview shall cover the following points:

- a. Schedules.
- b. Names of energy analysts who will be conducting the site survey.
- c. Proposed working hours.
- d. Support requirements from the Director of Public Works.

3.7.2 Exit. The exit interview shall be held when the field work is essentially complete; it shall briefly describe the items surveyed and probable areas of energy conservation. The interview shall also solicit input and advice from the Director of Public Works.

4. SERVICES AND MATERIALS. All services, materials (except those specifically enumerated to be furnished by the Government), labor, supervision, and travel necessary to perform the work and render the data required under this contract are included in the lump sum price of the contract.

5. PROJECT DOCUMENTATION. All energy conservation opportunities which the AE has considered shall be included in one of the following categories and presented in the report as such:

5.1 ECIP Projects. To qualify as an ECIP project, an ECO, or several ECOs which have been combined, must have a construction cost estimate greater than \$300,000, a Savings to Investment Ratio (SIR) greater than 1.25 and a simple payback period of less than ten years. The overall project and each discrete part of the project shall have an SIR greater than 1.25. All projects meeting the above criteria shall be arranged as specified in paragraph 2.7.1 and shall be provided with programming documentation. Programming documentation shall consist of a DD Form 1391 and life cycle cost analysis (LCCA) summary sheet(s) (with necessary backup data to verify the numbers presented). A life cycle cost analysis summary sheet shall be developed for each ECO and for the overall project when more than one ECO are combined. The energy savings for projects consisting of multiple ECOs must take into account

the synergistic effects of the individual ECOs.

5.2 Non-ECIP Projects. Projects which do not meet ECIP criteria with regard to cost estimate, but which have an SIR greater than 1.25 shall be documented. Projects or ECOs in this category shall be arranged as specified in paragraph 2.7.2 and shall be provided with the following documentation: the life cycle cost analysis (LCCA) summary sheet completely filled out, a description of the work to be accomplished, backup data for the LCCA (energy savings calculations and cost estimate), and the simple payback period. The energy savings for projects consisting of multiple ECOs must take into account the synergistic effects of the individual ECOs. In addition these projects shall have the necessary documentation prepared, as required by the Government's representative, for one of the following categories:

a. Federal Energy Management Program (FEMP) Projects. A FEMP (or O&M Energy) project is one that results in needed maintenance or repair to an existing facility, or replaces a failed or failing existing facility, and also results in energy savings. The criteria are similar to the criteria for ECIP projects, ie, $SIR \geq 1.25$, and simple payback period of less than ten years. Projects with a construction cost estimate up to \$1,000,000 shall be documented as outlined in par 5.2 above; projects over \$1,000,000 shall be documented on 1391s. In the FEMP program, a system may be defined as "failed or failing" if it is inefficient or technically obsolete. However, if this strategy is used to justify a proposed project, the equipment to be replaced must have been in use for at least three years.

b. Low Cost/No Cost Projects. These are projects which the Director of Public Works (DPW) can perform using his resources. Documentation shall be as required by the DPW.

5.3 Nonfeasible ECOs. All ECOs which the AE has considered but which are not feasible, shall be documented in the report with reasons and justifications showing why they were rejected.

6. DETAILED SCOPE OF WORK. The Detailed Scope of Work is contained in Annex A.

7. WORK TO BE ACCOMPLISHED.

7.2 Perform a Limited Site Survey. The AE shall obtain all necessary data to evaluate the ECOs or projects by conducting a site survey. However, the AE is encouraged to use any data that may have been documented in a previous study. The AE shall document his site survey on forms developed for the survey, or on

standard forms, and submit these completed forms as part of the report. All test and/or measurement equipment shall be properly calibrated prior to its use.

7.4 Evaluate Selected ECOs. The AE shall analyze the ECOs listed in Annex A. These ECOs shall be analyzed in detail to determine their feasibility. Savings to Investment Ratios (SIRs) shall be determined using current ECIP guidance. The AE shall provide all data and calculations needed to support the recommended ECO. All assumptions and engineering equations shall be clearly stated. Calculations shall be prepared showing how all numbers in the ECO were figured. Calculations shall be an orderly step-by-step progression from the first assumption to the final number. Descriptions of the products, manufacturers catalog cuts, pertinent drawings and sketches shall also be included. A life cycle cost analysis summary sheet shall be prepared for each ECO and included as part of the supporting data.

7.5 Combine ECOs Into Recommended Projects. During the Interim Review Conference, as outlined in paragraph [7.6.1], the AE will be advised of the DEH's preferred packaging of recommended ECOs into projects for implementation. Some projects may be a combination of several ECOs, and others may contain only one. These projects will be evaluated and arranged as outlined in paragraphs 5.1, 5.2, and 5.3. Energy savings calculations shall take into account the synergistic effects of multiple ECOs within a project and the effects of one project upon another. The results of this effort will be reported in the Final Submittal per par [7.6.2].

7.6 Submittals, Presentations and Reviews. The work accomplished shall be fully documented by a comprehensive report. The report shall have a table of contents and shall be indexed. Tabs and dividers shall clearly and distinctly divide sections,

subsections, and appendices. All pages shall be numbered. Names of the persons primarily responsible for the project shall be included. The AE shall give a formal presentation of the interim submittal to installation, command, and other Government personnel. Slides or view graphs showing the results of the study to date shall be used during the presentation. During the presentation, the personnel in attendance shall be given ample opportunity to ask questions and discuss any changes deemed necessary to the study. A review conference will be conducted the same day, following the presentation. Each comment presented at the review conference will be discussed and resolved or action items assigned. It is anticipated that the presentation and review conference will require approximately one working day. The presentation and review conference will be at the installation on the date agreeable to the Director of Public Works, the AE and the Government's representative. The Contracting Officer may require a resubmittal of any document(s), if such document(s) are not approved because they are determined by the Contracting Officer to be inadequate for the intended purpose.

7.6.1 Interim Submittal. An interim report shall be submitted for review after the field survey has been completed and an analysis has been performed on all of the ECOs. The report shall indicate the work which has been accomplished to date, illustrate the methods and justifications of the approaches taken and contain a plan of the work remaining to complete the study. Calculations showing energy and dollar savings, SIR, and simple payback period of all the ECOs shall be included. The results of the ECO analyses shall be summarized by lists as follows:

a. All ECOs eliminated from consideration shall be grouped into one listing with reasons for their elimination as discussed in par 5.3.

b. All ECOs which were analyzed shall be grouped into two listings, recommended and non-recommended, each arranged in order of descending SIR. These lists may be subdivided by building or area as appropriate for the study.

The AE shall submit the Scope of Work and any modifications to the Scope of Work as an appendix to the report. A narrative summary describing the work and results to date shall be a part of this submittal. At the Interim Submittal and Review Conference, the Government's and AE's representatives shall coordinate with the Director of Public Works to provide the AE with direction for packaging or combining ECOs for programming purposes and also indicate the fiscal year for which the programming or implementation documentation shall be prepared. The survey forms completed during this audit shall be submitted with this report. The survey forms only may be submitted in final form with this submittal. They should be clearly marked at the time of submission that they are to be retained. They shall be bound in a standard three-ring binder which will allow repeated disassembly and reassembly of the material contained within.

7.6.2 Final Submittal. The AE shall prepare and submit the final report when all sections of the report are 100% complete and all comments from the interim submittal have been resolved. The AE shall submit the Scope of Work for the study and any modifications to the Scope of Work as an appendix to the submittal. The report shall contain a narrative summary of conclusions and recommendations, together with all raw and supporting data, methods used, and sources of information. The report shall integrate all aspects of the study. The recommended projects, as determined in accordance with paragraph 5, shall be presented in order of priority by SIR. The lists of ECOs specified in paragraph [7.6.1] shall also be included for continuity. The final report and all appendices shall be bound in standard three-ring binders which will allow repeated disassembly and reassembly. The final report shall be arranged to include:

a. An Executive Summary to give a brief overview of what was accomplished and the results of this study using graphs, tables and charts as much as possible (See Annex B for minimum requirements).

b. The narrative report describing the problem to be studied, the approach to be used, and the results of this study.

c. Documentation for the recommended projects (includes LCCA Summary Sheets).

d. Appendices to include as a minimum:

- 1) Energy cost development and backup data
- 2) Detailed calculations
- 3) Cost estimates
- 4) Computer printouts (where applicable)
- 5) Scope of Work

ANNEX A

DETAILED SCOPE OF WORK
CONTRACT NO. DACAC63-94-D-0015
DELIVERY ORDER NO. 000

1. The Architect-Engineer (A-E) shall furnish all services, material, supplies, plant, labor, equipment, investigations, studies, superintendence and travel as required in connection with the below identified project for design in accordance with the original basic contract and this Detailed Scope of Work. Appendix "A" of the basic contract shall be followed for performance requirements for A-E services. Where this Detailed Scope of Work conflicts with Appendix "A", this Detailed Scope of Work shall govern.

INSTALLATION

PROJECT TITLE

Fort Sam Houston, TX

Boiler/Chiller Study (EEAP)

2. The work and other related data and services required in this Delivery Order shall be accomplished within the time schedule required, in accordance with the subject stated above and scope of work described in paragraph 3 below. The schedule for delivery of data to the Contracting Officer is in calendar days as follows:

DELIVERY SCHEDULE

- | | |
|---|--|
| a. Interim Submittal and related data for studies (See Annex B for number of copies) | 60 calendar days after receipt of Delivery Order |
| b. Pre-Final Submittal(s) | 90 calendar days after approval of Interim submittal |
| c. Final Submittal (original and all data developed under this submittal) | 90 calendar days after approval of the pre-final |

3. The items of work included in this Delivery Order shall be in accordance with criteria furnished at the Scoping conference held 29 June 1994 at Fort Sam Houston. The services to be provided shall include, but not be limited to, the following Scope of Work.

a. Items of Work:

(1) 2200 Area. Evaluate the feasibility and economic impacts of modifying the existing cooling and heating plant in Building 2265. This plant provides heating hot water and chilled water to Buildings 2263, 2264, 2265 and 2266. The feasibility study will consider chiller replacement or retrofit and boiler

upgrade or replacement. A limited survey of the four existing buildings served by this plant will be performed to permit a qualitative verification that the existing plant capacities are adequate. The survey will also reveal constraining requirements such as year-round cooling requirements which may influence the recommendations. Chiller replacement/retrofit recommendations will consider refrigerants 123 or 134a only, gas vs. electrical driven compressors, drive configuration (i.e., open-drive vs. hermetic), operating efficiency (i.e., compressor type: screw vs. centrifugal part load and full load capacities and variable speed drive) and maintainability. The cost effects of the new design criteria from the Uniform Mechanical code which requires a partition be provided between the chiller and boiler shall be investigated. As the thermal load history for the plant is not available, a generalized load profile will be assumed and used to analyze the benefits of energy saving options and equipment selections. Recommendations will be supported by life cycle cost analyses which will include initial purchase and installation costs, energy consumption costs, and maintenance costs extended over the useful life of the equipment.

(2) 2200 Area (item 1 must be performed in conjunction with this item). Evaluate buildings 2263, 2264, 2265, and 2266 and model each building to develop a probable annual thermal load profile. Receive as-built drawings on the buildings from Fort Sam Houston and perform a survey of the buildings to collect information necessary to more accurately develop the annual thermal profile of each.

(3) 2200 Area (items 1 or 1a must be performed in conjunction with this item). Evaluate the use of four-pipe heating and cooling distribution from the central plant. Recommendations will be supported by life cycle cost analyses which will include initial purchase and installation costs, energy consumption costs, and maintenance costs extended over the useful life of the equipment. Based on the current type of building occupancy, a determination will be provided on whether a single mode of plant operation will suit the air conditioning requirements for the group of buildings tied into the plant, as will occur in a two pipe system. Also, considering the constant changing use of the Army facilities, the firm performing the study shall provide their own engineering judgement on whether locking a facility into a particular type of occupancy (i.e., loss of flexibility) makes sense, as will also occur in a two pipe system. The fact that a complete system shut down is needed in order to perform maintenance in a two pipe system, will be addressed in the engineering judgement decision.

(4) 1300 Area. Evaluate the feasibility and economic impacts of modifying the existing cooling and heating plant in Building 1377. This plant provides heating hot water and chilled water to Buildings 1350, 1374, 1375, 1379, 1380, 1382, and 1385. The feasibility study will consider chiller replacement or retrofit and boiler upgrade or replacement. A limited survey of the seven existing buildings served by this plant will be performed to permit a qualitative verification that the existing plant capacities are adequate. The survey will also reveal constraining requirements such as year-round cooling requirements which may influence the recommendations. Chiller replacement/retrofit recommendations will consider refrigerants 123 or 134a only, gas vs. electrical driven compressors, drive configuration (i.e., open-drive vs. hermetic), operating efficiency (i.e., compressor type: screw vs. centrifugal part load and full load capacities and variable speed drive) and maintainability. The cost effects of the new design criteria from the Uniform Mechanical code which requires a partition be provided between the chiller and boiler shall be investigated. As the thermal load history for the plant is not available, a generalized load profile will be assumed and used to analyze the benefits of energy saving options and equipment selections. Recommendations will be supported by life cycle cost analyses which will include initial purchase and installation costs, energy consumption costs, and maintenance costs extended over the useful life of the equipment.

(5) 1300 Area (item 2 must be performed in conjunction with this item). Evaluate Buildings 1350, 1374, 1375, 1379, 1380, 1382 and 1385 and model each building to develop a probable annual thermal load profile. Receive as-built drawings on the buildings from Fort Sam Houston and perform a survey of the buildings to collect information necessary to more accurately develop the annual thermal profile of each. Evaluate the optimum size and configuration for the central plant.

(6) 900 Area. Evaluate the feasibility and economic impacts of modifying the existing cooling and heating plant in Building 902. This plant provides heating hot water and chilled water to Buildings 902, 904, 905, 906, 907, 908, 916, 917, 919, 920, 921, 922, 924, 925, 926, 928, 929, 930, and 931. The feasibility study will consider chiller replacement or retrofit or refrigerant upgrade and boiler upgrade or modification or replacement. A limited survey of the nineteen existing buildings served by this plant will be performed to permit a qualitative verification that the existing plant capacities are adequate. The survey will also reveal constraining requirements such as year-round cooling requirements which may influence the recommendations. Chiller replacement/retrofit recommendations will consider refrigerants 123 or 134a only, gas vs. electrical

driven compressors, drive configuration (i.e., open-drive vs. hermetic), operating efficiency (i.e., compressor type: screw vs. centrifugal part load and full load capacities and variable speed drive) and maintainability. The cost effects of the new design criteria from the Uniform Mechanical code which requires a partition be provided between the chiller and boiler shall be investigated. As the thermal load history for the plant is not available, a generalized load profile will be assumed and used to analyze the benefits of energy saving options and equipment selections. Recommendations will be supported by life cycle cost analyses which will include initial purchase and installation costs, energy consumption costs, and maintenance costs extended over the useful life of the equipment.

(7) 900 Area (item 3 must be performed in conjunction with this item. Evaluate Buildings 902, 904, 905, 906, 907, 908, 916, 917, 919, 920, 921, 922, 924, 925, 926, 928, 929, 930, and 931 and model each building to develop a probable annual thermal load profile. Receive as-built drawings on the buildings from Fort Sam Houston and perform a survey of the buildings to collect information necessary to more accurately develop the annual thermal profile of each. Evaluate the optimum size and configuration for the central plant.

(8) 100 Area. Review the existing design manual and construction documents prepared in 1986 to provide a central plant at building 250 to serve Buildings 122, 124, 125, 127, 128, 132, 133, 134, 135, 142, 143, 144, 145, 146, 147, 149, 197, 198, 199, and 250. A limited survey of the twenty existing buildings served by this plant will be performed to permit a qualitative verification that the plant capacities established in 1986 are adequate. The survey will also reveal constraining requirements such as year-round cooling requirements which may influence the recommendations. Make recommendations to modify the equipment selections developed with that design and develop a conceptual cost estimate for its implementation. Recommendations will be supported by life cycle cost analyses which will include initial purchase and installation costs, energy consumption costs, and maintenance costs extended over the useful life of the equipment.

(9) 100 Area (item 4 must be performed in conjunction with this item). Evaluate Buildings 122, 124, 125, 127, 128, 132, 133, 134, 135, 142, 143, 144, 145, 146, 147, 149, 197, 198, 199, and 250 and model each building to develop a probable annual thermal load profile. Receive as-built drawings on the buildings from Fort Sam Houston and perform a survey of the buildings to collect information necessary to more accurately develop the annual thermal profile of each. Evaluate the optimum size and configuration for the central plant.

(10) Quadrangle. Evaluate the feasibility and economic impacts of providing a new cooling and heating plant adjacent to the Quadrangle. This plant would provide heating hot water and chilled water to buildings 16, 44, T-56, and 4015. Receive as-built drawings on the buildings from Fort Sam Houston and model each building to develop a probable annual thermal load profile. Evaluate the optimum size and configuration for the central plant. Develop recommendations for a central plant configuration and location which will complement the historic nature of the Quadrangle. Evaluate the use of 2-pipe versus 4-pipe thermal distribution. Recommendations will be supported by life cycle cost analyses which will include initial purchase and installation costs, energy consumption costs, and maintenance costs extended over the useful life of the equipment.

c. Special Requirements: Distribution of submittal documents are as follows:

- (1) Three copies of all documents shall be mailed to:

Commander
U.S. Army Engineer District, Fort Worth
819 Taylor Street/P.O. Box 17300
ATTN: CESWF-ED-MR/Champagne
Fort Worth, Texas 76102-0300

- (2) Ten copies of all documents, field survey data and one disk shall be mailed to:

Commander
ATTN: AFZG-PW-ESB/Mr. De La Pena
Department of Army
HQ, Fort Sam Houston
Fort Sam Houston, TX 78234

ANNEX B

EXECUTIVE SUMMARY GUIDELINE

1. Introduction.
2. Building Data (types, number of similar buildings, sizes, etc.)
3. Present Energy Consumption of Buildings or Systems Studied.
 - o Total Annual Energy Used.
 - o Source Energy Consumption.
 - Electricity - KWH, Dollars, BTU
 - Fuel Oil - GALS, Dollars, BTU, MWH
 - Natural Gas - THERMS, Dollars, BTU, MWH
 - Propane - GALS, Dollars, BTU, MWH
 - Other - QTY, Dollars, BTU, MWH
4. Reevaluated Projects Results.
5. Energy Conservation Analysis.
 - o ECOs Investigated.
 - o ECOs Recommended.
 - o ECOs Rejected. (Provide economics or reasons)
 - o ECIP Projects Developed. (Provide list)*
 - o Non-ECIP Projects Developed. (Provide list)*
 - o Operational or Policy Change Recommendations.
 - * Include the following data from the life cycle cost analysis summary sheet: the cost (construction plus SIOH), the annual energy savings (type and amount), the annual dollar savings, the SIR, the simple payback period and the analysis date.
6. Energy and Cost Savings.
 - o Total Potential Energy and Cost Savings.
 - o Percentage of Energy Conserved.
 - o Energy Use and Cost Before and After the Energy Conservation Opportunities are Implemented.

ANNEX C

REQUIRED DD FORM 1391 DATA

To facilitate ECIP project approval, the following supplemental data shall be provided:

- a. In title block clearly identify projects as "ECIP."
- b. Complete description of each item of work to be accomplished including quantity, square footage, etc.
- c. A comprehensive list of buildings, zones, or areas including building numbers, square foot floor areas.
- (11) Latest MCP Index, essential for projecting costs for project documentation.
- (12) The following items are important and should be provided to the AE to the extent to which they are available:
 - (a) As-built drawings of applicable buildings, equipment, or systems
 - (b) Handbooks or SOPs relating to the operation of applicable equipment or systems.
 - (c) Applicable records of energy or fuel usage.
 - (d) Copies of bills for electrical penetration assumptions before and after improvements.
 - (4) Include source of expertise and demonstrate savings claimed. Identify any special or critical environmental conditions such as pressure relationships, exhaust or outside air quantities, temperatures, humidity, etc.
- e. Claims for boiler efficiency improvements must identify data to support present properly adjusted boiler operation and future expected efficiency. If full replacement of boilers is indicated, explain rejection of alternatives such as replace burners, nonfunctioning controls, etc. Assessment of the complete existing installation is required to make accurate determinations of required retrofit actions.
- f. Lighting retrofit projects must identify number and type of fixtures, and wattage of each fixture being deleted and installed. New lighting shall be only of the level to meet current criteria. Lamp changes in existing fixtures is not considered an ECIP type project.

g. An ECIP life cycle cost analysis summary sheet as shown in the ECIP Guidance shall be provided for the complete project and for each discrete part included in the project. The SIR is applicable to all segments of the project. Supporting documentation consisting of basic engineering and economic calculations showing how savings were determined shall be included.

h. The DD Form 1391 face sheet shall include, for the complete project, the annual dollar and MBTU savings, SIR, simple amortization period and a statement attesting that all buildings and retrofit actions will be in active use throughout the amortization period.

i. The calendar year in which the cost was calculated shall be clearly shown on the DD Form 1391.

j. For each temporary building included in a project, separate documentation is required showing (1) a minimum 10-year continuing need, based on the installation's annual real property utilization survey, for active building retention after retrofit, (2) the specific retrofit action applicable and (3) an economic analysis supporting the specific retrofit.

k. Nonappropriated funded facilities will not be included in an ECIP project without an accompanying statement certifying that utility costs are not reimbursable.

l. Any requirements required by ECIP guidance dated 10 Jan 1994 and any revisions thereto. Note that unescalated costs/savings are to be used in the economic analyses.

m. The five digit category number for all ECIP projects except for Family Housing is 80000. The category code number for Family Housing projects is 71100.

INTERIM SUBMITTAL REVIEW COMMENTS - HQ FORSCOM

7/6/95

PG 1 of 2

REVIEW COMMENTS FOR INTERIM SUBMITTAL :

EEAP CHILLER AND BOILER PLANT STUDY AT FORT SAM HOUSTON, TX

REVIEWER: NARESH K.KAPUR, P.E. DATED: 6 JULY 95
ORGANIZATION: HQ FORSCOM
ADDRESS: ATTN: AFPI-ENO/KAPUR TEL: 404-669-5327, FAX 7751
 BLDG 200,
FORT MCPHERSON, GA 30330-6000

1. THE INTERIM REPORT IS WELL ORGANIZED. IT WOULD BE NICE TO HAVE ONE OR TWO PAGE WRITEUP TO PROVIDE A GIST OF THIS STUDY. SOME OF THE ITEMS TO BE ADDRESSED IN THIS ARE: PURPOSE & SCOPE; ALTERNATIVES CONSIDERED; METHODS OF ANALYSIS AND ASSUMPTIONS; RECOMMENDED ECOS AND THEIR LCC INFO.

2. GENERAL. FOR MANY BUILDINGS, LACK OF HVAC CONTROLS LEAD TO OCCUPIED AREAS VERY HOT. REQUEST PROVIDE A SUGGESTED SOLUTION BASED ON YOUR FIELD OBSERVATIONS.

3. GENERAL. DISCUSS VARIOUS OPTIONS FOR SELECTING CHILLERS AND BOILERS FOR ECOS. MENTION PROS AND CONS OF EACH, INCLUDING COST FACTORS, ENERGY EFFICIENCIES, POSSIBLE CHILLER WITH INTEGRAL HEATING UNIT, AND EASE OF MAINTENANCE ETC.

4. GENERAL. FROM ENVIRONMENTAL CONSIDERATIONS, IT IS DESIRABLE TO AVOID OZONE DEPLETING CHEMICALS (ODC) TYPE REFRIGERENTS FOR NEW CHILLERS. NATURAL GAS ABSORPTION CHILLERS (SEE ENCLOSED INFO) ARE AVAILABLE IN MANY VARIETIES AND USE NON-ODC REFRIGERENT. PL DISCUSS POSSIBILITIES. BY USING NON-ODC REFRIGERENT IN NEW CHILLERS WE CAN POSSIBLY HAVE RECURRING SAVINGS DUE TO SOME AVOIDED MAINTENANCE COST.

5. GENERAL. PER YOUR SITE VISIT OBSERVATIONS, MOST OF THE AREAS WERE EXCESSIVELY WARM AND HVAC CONTROLS POOR. HOW DOES THIS AFFECT THE LCC ANALYSIS?

6. PG 6. PROVIDE A RECOMMENDED ACTION PLAN TO ADEQUATELY MAINTAIN HVAC SYSTEMS IN VIEW OF EVER DIMINISHING MAINTENANCE PERSONNEL WHO ARE NOT WELL TRAINED.

7. GENERAL. IN A CENTRAL PLANT SITUATION, THERE ARE TRANSMISSION LOSSES AND OTHER INHERENT INEFFICIENCIES WHEN THE OCCUPANCY OF BUILDINGS IS NOT UNIFORM. CONSIDER DOING A SAMPLE LCC ANALYSIS CONSIDERING SELECTIVE DECENTRALIZING HEATING AND COOLING EQUIPMENT. IN SMALLER UNITS, WE EXPECT EASIER CONTROLS/ MAINTENANCE. SMALLER UNITS CAN BE SHUTDOWN DURING WEEKENDS/ HOLIDAYS AND NON-WORKING HOURS.

8. GENERAL. PL ADDRESS THE FOLLOWINGS:
- A. WHAT ARE DOMESTIC HOT WATER REQUIREMENTS DURING HEATING AND COOLING SEASON? HOW ARE THESE REQUIREMENTS CURRENTLY MET? ADDRESS THIS ISSUE IN EACH ALTERNATIVE AS APPROPRIATE.
 - B. ARE THERE SIGNIFICANT ENERGY REQUIREMENTS RELATED TO COOKING? PL DISCUSS.
 - C. ANY SIGNIFICANT COOLING LOADS DURING HEATING SEASON/ PL DISCUSS.
 - D. PL DISCUSS 4 PIPE V/S 2PIPE SYSTEM AS RELATED TO FT SAM HOUSTON SITUATION.

INTERIM SUBMITTAL REVIEW COMMENTS - USAED MOBILE

7/6/95

| MOBILE DIST. OFFICE PROJECT REVIEW COMMENTS | | DATE: 5 July 95 | P.3-3 PAGE 1 of 1 |
|---|-------------------------|--|----------------------|
| TO: Army Corps of Engineers Fort Worth Division | | FROM: (Section): EN-DM (Reviewer): Robert S. Woodruff | |
| PROJECT: Boiler and Chiller Study LOCATION: Fort Sam Houston | | Year: | Line Item No.: |
| Type of Action: Interim Report | | | |
| Item No. | Drawing No. Or Par. No. | COMMENTS | Review Action |
| 1. | Page 1 | The first sentence of the third paragraph should be reworded. | |
| 2. | Page 2 Para. B.1. | Buildings 915 and 932 should be added to the list of 900 area buildings studied. The actual study data indicates that these two building were studied (see page C-2). | |
| 3. | Page 2 Para. B.2. | Building 1377 should be added to the list of 1300 area buildings. This building was part of the actual study (see page C-11). | |
| 4. | Page 5 Para. 1 | The type of refrigerant used in each of the chillers serving the quadrangle buildings should be listed. | |
| 5. | General | The operating schedules used in the Traca studies appear to be reasonable. It should be pointed out in the study report that if the existing controls were repaired and set properly the energy savings would be even greater than those predicted by the study. | |
| 6. | General | The replacement chiller for the 1300 area appears very close to meeting the criteria for approval. Are there any ways that this SCO could be modified to make it feasible? | |

INTERIM SUBMITTAL REVIEW COMMENTS - FORT SAM HOUSTON, TX

7/10/95

| ENGINEERING REVIEW COMMENTS | | ACTIVITY AF26-PW-ESA | DATE 7/10/95 |
|--|-------------|---|--------------------------------|
| TYPE OF REVIEW <input type="checkbox"/> PRELIMINARY <input checked="" type="checkbox"/> FINAL | | AREA OF REVIEW 1. <input type="checkbox"/> CIVIL 3. <input type="checkbox"/> STRUCTURAL 5. <input type="checkbox"/> ELECTRICAL 2. <input type="checkbox"/> ARCHITECTURAL 4. <input checked="" type="checkbox"/> MECHANICAL 6. <input type="checkbox"/> OTHER | |
| PROJECT Boiler/Chiller Central Plant Study | ITEM NUMBER | DESIGNED BY F. CARBONELL | |
| LEGEND: A - Concur D - Do not concur E - Exception, see comment X - Delete comment | | | |
| GRAPHIC NO. OR PAR. NO. | COMMENT NO. | COMMENT (TYPE OR PRINT) | ACTION BY REVIEWER (ENCLOSURE) |
| 3, 4, 5 | 1. | Do NOT CONSIDER REDUCING CAPACITIES SINCE EXISTING CAPACITIES WERE FOUND TO BE MORE THAN WHAT IS NEEDED IN MOST CASES. | |
| 5 | 2 | A CENTRAL PLANT FOR THE QUADRANGLE AREA WOULD REQUIRE MUCH MORE THAN A "HISTORICALLY CORRECT" WALL TO HIDE EQUIPMENT. THE CENTRAL PLANT WOULD EITHER HAVE TO BE UNDERGROUND OR IN ONE OF THE EXISTING BUILDINGS SURROUNDING THE QUADRANGLE. THIS WOULD REQUIRE A VERY | |

ESH FORM 847* THOROUGH AND CAREFUL CHECKING REQUIRED

7/10/95

15:34 NO.008 P.04 047- ESH AUG 02.95

9095177.017:BT

RESPONSES TO INTERIM SUBMITTAL REVIEW COMMENTS

7/10/95

A. FORSCOM Comments:

1. Executive summary in final report will summarize the study as requested.
2. Additional maintenance recommendations will be added to study which will address the repair of HVAC controls in the buildings.
3. Additional text will be added which will describe the selection of new equipment to be used in the analysis in this study.
4. Gas absorption cooling systems would eliminate the concerns over refrigerant types to be used in the new chillers. However, analysis of these types of cooling systems is beyond the scope of this study. (See pages F-11 through F-15)
5. An underlying assumption in all ECOs in this study is that the building controls remain as-is, and the new central cooling and heating systems merely save central plant heating and cooling energy, rather than improve building temperature control. Therefore, the LCC analysis of each ECO is valid whether the building HVAC controls are repaired or not. However, it is acknowledged that additional energy savings are possible if these controls are repaired. But analysis of these savings is beyond the scope of this study. (See pages F-11 through F-15)
6. An underlying assumption in the maintenance and operations recommendations made in this study is that the installation has adequate resources to implement them. It is beyond the scope of this study to determine the installations maintenance capabilities and provide maintenance strategies based on them.
7. Because of the apparent shortage of HVAC maintenance manpower at this installation, it is felt that centralization of the primary heating and cooling equipment is the best strategy to pursue. Consideration of unitized primary heating and cooling equipment is beyond the scope of this study. (See pages F-11 through F-15)
- 8(A). Descriptions of all domestic hot water heating systems can be found in the building data sheets in Appendix C. All DHW systems, except for the 900 area, are unitized by building, and separate from the heating system. It is assumed that DHW demand is directly related to building occupancy rather than outside weather conditions. In area 900, the DHW demand used in the study was taken from a 12 month metered gas profile for building 902. This amounted to boiler base load of 565 BTUH, as described on page B-3, item E (5). This load was constant throughout the year, due to the nearly constant occupancy of the barracks buildings in the 900 area.
- 8(B). Only buildings 1377 and 2265 have small boilers which are used for cooking loads. These cooking energy demands were assumed to be small as compared to the heating and cooling demands of all buildings in the study. Therefore, any ECO performed on these cooking boilers would have very long paybacks of greater than 10 years.
- 8(C). Because of the physical size of the buildings studied, and the types of internal heat sources present within them, the only significant cooling loads possible during the heating season would be in areas which house central computer equipment. The areas which fit this description were

generally served by unitary cooling equipment which could operate independently of the central HVAC systems, therefore providing cooling during the heating season if required. Building 2263 however has large computer areas without unitized cooling systems. In almost all cases, the analyst feels that the lack of operable HVAC controls along with the apparent over sizing of the central boiler systems is the cause of the high temperatures within the buildings during the heating season. However, operable windows are available in many cases to offset the lack of temperature controls.

- 8(D). The evaluation of two-pipe vs. Four-pipe systems at the installation was determined by the contracting officer to be beyond the scope of this study. Therefore, it was omitted.

B. MOBILE

1. Sentence reworded as requested.
2. Buildings added to list as requested.
3. Building added to list as requested.
4. Refrigeration types added to description as requested.
5. Statement added to Maintenance & Operations Recommendations as requested.
6. The area 1300 chiller replacement (ECO-C) was reevaluated, leaving the 1983 chiller in place and only replacing the two 1972 chillers with a single new chiller. The new payback is 8.4 years and this ECO is now recommended.

C. FORT SAM HOUSTON

1. Over sizing of the new boiler and chiller equipment in the study would cause the ECO paybacks to be over 10 years and therefore unacceptable. Therefore, new equipment was sized to closely match the heating and cooling load profiles given in Appendix B.
2. ECO-G, the central chiller plant for the Quadrangle area, was evaluated to have a 20.9 year payback and was therefore not recommended for implementation. Increasing the implementation cost of this ECO by adding funds for architectural aesthetics would not improve the payback time. Therefore, no changes were made to this ECO.
3. Words replaced as requested.

APPENDIX G
SAMPLE PRODUCTS

APPENDIX G
SAMPLE PRODUCTS

TABLE OF CONTENTS

| | |
|--|------|
| Maintenance Cost Estimate Data | G-1 |
| Chiller Retrofit Cost Data For R-11 To HCFC-123 Upgrades | G-3 |
| York International Data On Chiller Performance | G-5 |
| Aerco International Data On Modular Boiler Performance | G-9 |
| Area 100 New Central Boiler Data | G-12 |

DYNASERVICE

RECEIVED

MAR 01 1995

HZ

FEBRUARY 27, 1995

MR. WALTER WILLIAMS, III P.E.
HUITT-ZOLLARS, INC.
512 MAIN STREET SUIT 1500
FORT WORTH, TX 76102

Walter,

I have projected maintenance cost for equipment you have noted broken down to per unit per visit on AHU, FCU, Fans, etc. Recommended at four (4) visits per year normal conditions. Severe conditions may require more frequent visits. To obtain heating and cooling season costs just divide visits in half and omit items such as water heater and exhaust fans if you do not want them included in heating and cooling costs.

NOTES: Boilers: one (1) visit per year annual inspection
Chillers: four (4) visits per year. Three (3) routine checks and one (1) annual winter service.
GeoTherm Wells: not applicable
Cooling Towers: one (1) visit per year complete annual clean and service

*Annual switch from heat to cool is per season per building.

Attached list shows breakdown of costs. If you have any questions, please call.

Sincerely,



David J. Recca
Customer Relations &
Sales

DR/als huitt

A DIVISION OF
DYNA TEN
CORPORATION
7466 Dogwood Park
Fort Worth
Texas 76118
817.585.4423
Metro
817.589.9511
FAX
817.589.0200



DYNASERVICE

PAGE FOUR OF FIVE
HUITT ZOLLARS
PAGE THREE OF BREAKDOWN
PREVENTIVE MAINTENANCE

B. CENTRAL PLANT EQUIPMENT

1. Cooling Equipment

All of the below alternatives include a new chilled water pump (25 hp) and cooling tower.

- a. Existing Chiller retrofit to R-123 refrigerant, includes checking room sensors* \$2275/yr
 - b. New Water Cooled Centrifugal Chiller R-22* \$2275/yr
 - c. New Water Cooled Centrifugal Chiller R-123* \$2275/yr
 - d. New Water Cooled Centrifugal Chiller R-134A* \$2275/yr
 - e. New Water Cooled Screw Chiller* \$2275/yr
 - f. New Water Cooled Centrifugal Chiller with VFD Compressor motor and inlet vanes* \$2275/yr
 - g. New Engine Driven Chiller - Natural Gas fired combustion engine. Similar to York CAT engine drive chiller. Jacket water will be utilized to heat domestic hot water during the summer months* \$3075/yr
- *Oil test only, no oil change

All of the below alternatives include a new chilled water pump (25 hp)

- a. New air cooled reciprocating chiller* \$2250/yr
 - b. New air cooled screw chiller* \$2250/yr
 - c. Chilled Water Pump (25 hp) \$25**
- *Assume 300 ton size equipment
**per visit

2. Heating Equipment

All of the below alternatives include a new heating water pump (20 hp)

- a. New standard firetube boilers 2 \$475*
 - b. New vertical fired high efficiency firetube boilers 4 \$475*
 - c. New cast iron boilers 2 \$475*
 - d. Hot water pump (20 hp) \$25**
- *One visit per year.
**Price per visit.

**NORTHERN RESEARCH
AND ENGINEERING CORPORATION**

NREC

39 Olympia Avenue - Woburn, MA 01801-2073 USA
Telephone: (617) 935-9050 - Telefax: (617) 935-9052
Telex: 466328 NOR RES WOB UD

June 16, 1995

Mr. John Carter
Huitt-Zollars
512 Main Street, Suite 1500
Forth Worth, TX 76102

| | | | | | |
|-------------------|----------------|------|---------|--------------|---|
| Post-it® Fax Note | 7671 | Date | 6/16 | # of Pages | 4 |
| To | John Carter | | From | Jimmy Tang | |
| Co. Name | Huitt-Zollars | | Co. | NREC | |
| Phone # | | | Phone # | 617-937-4668 | |
| Fax # | (817) 335-1025 | | Fax # | 617-935-9052 | |

Dear Mr. Carter:

We are pleased to provide our Preliminary and Budgetary Quotation No. 950-2381 describing the design and manufacture of replacement impellers for returning original capacity to various chillers described in your fax of June 14, 1995.

Based on our past experience, we believe that any capacity loss resulting from the conversion from CFC-11 refrigerant to HCFC-123 can be rectified by changing the impellers. This option will retain original operating conditions, including driving speed, and will avoid the need to change other system components such as the condenser. This presumes that the evaporator and condenser are adequately sized for the added HCFC-123 flow rates.

NREC proposes to design and supply new compressor impellers which will provide the pressure ratios and flow rates required by the use of the new refrigerant. NREC predicts that the present capacity of the systems using CFC-11 can be achieved using our high performance impellers with negligible increases in power consumption. However, we reserve the possibility of up to a 5 percent increase in power consumption.

This proposal assumes that we will work with a contractor of Huitt-Zollars's choice to perform the entire conversion of the machines for the customer. NREC will be responsible for:

- measuring compressor internals,
- designing and fabricating new impellers,
- balancing the impellers,
- supporting the contractor during the installation, conversion, completion, and operational testing of the converted system.

The selected contractor would be responsible for:

- removing and reinstalling the impeller,
- providing all other on-site support and conversion tasks.

NREC will retain overall responsibility for the satisfaction of the performance requirements. The impellers will be designed and manufactured to operate within the

Mr. John Carter
June 16, 1995
Page 2

specified original equipment. The impellers will be individually balanced, spin-tested, and assembled to the original rotor shaft.

Listed below are the preliminary and budgetary prices for the chillers you outlined in your request:


| | | | | |
|---------------|-------------|-----------|-----------|------------|
| Area: | 900 | 2200 | 1300 | 1350 |
| Manufacturer: | York | Chrysler | Trane | Carrier |
| Make: | TurboPak HT | Airtemp | Centravac | |
| Model: | YTC3D3C1CJC | C2MN7792 | PCV5FC1D1 | 19DK7894CP |
| Quantity: | One (1) | One (1) | Two (2) | One (1) |
| Budget Price: | \$175,000 | \$250,000 | \$275,000 | \$35,000 |

Since NREC have not yet designed impellers for the specific York, Chrysler, and Trane compressors above, a significant non-recurring engineering and tooling effort is included in the budget price. NREC is currently evaluating market potentials and, within six months, may develop a design and production plan for the York TurboPak and Trane Centravac chillers. This new position could possibly reduce the costs for the replacement TurboPak and Centravac impellers.

This proposal is subject to the standard "Products Sales" Terms and Conditions of our parent company, Ingersoll-Rand. A copy of these Terms and Conditions is attached. If you have any questions about the quotation, please feel free to contact me at (617) 937-4668 or Mel Mitnick, Senior Applications Engineer, at (617) 937-4655.

Sincerely,

NORTHERN RESEARCH AND ENGINEERING
CORPORATION


Chi-Wu (Jimmy) Tang
Sales Engineer

CJT/ph
Enclosure

2361HUIT.DOC

**CHILLER STUDY
FT. SAM HOUSTON**

Prepared For:

Mr. John T. Carter

HUITT-ZOLLARS, INC.

512 Main Street

Suite 1500

Ft. Worth, Texas 76102

Project # 03-0185-04

Prepared By:

TOM McGREAL

YORK INTERNATIONAL

12901 Nicholson Road #260

Dallas, Texas 75234

(214) 620-8830

February 2, 1995

February 2, 1995

Huitt-Zollars, Inc.
512 Main Street
Suite 1500
Ft. Worth, Texas 76102

Attention: Mr. John T. Carter

Re: **Chiller Study - Ft. Sam Houston
Huitt-Zollars Project 03-0185-04**

Dear John,

Per your request, we are pleased to provide you with the following information concerning the study you are doing on the above referenced project:

Overview

900 Area - Served by (1) - 300 ton R-11 York YT Model
1300 Area - Served by (2)-500 ton R-11 chillers and (1)-440 ton R-11 Chiller

Some initial thoughts about the existing chillers:

Since the York chiller serving the 900 Area is "open" drive, it can be retrofitted quite inexpensively to R-123 (cost of approximately \$20,000). However, there will be a tonnage deration and loss of efficiency (see attached chiller rating).

The units serving the 1300 Area will be hermetic chillers, and converting them to R-123 would be cost prohibitive, as the units would require total motor rework to become compatible with R-123. Replacement may be the only solution for this area, with the only exception being York "Codekits", new Open Drive Motor/Compressor Assemblies, field mounted. If the shells and tubes are in good shape, this option may make some sense.

- For the energy evaluation of electric centrifugal chiller full and part load performance, the curve you have will be excellent for the centrifugal chillers. As a baseline for full load efficiencies, use the following:

R-123 Model YT Tonnage Range 150 - 800 tons

150 - 250 tons use .62 KW/Ton
250 - 350 tons use .59 KW/Ton
350 - 675 tons use .56 KW/Ton
675 - 800 tons use .58 KW/Ton

R-22 Model YK Tonnage Range 350 - 2100 Tons

350 - 600 tons use .62 KW/Ton
600 - 1200 tons use .58 KW/Ton
1200 - 1700 tons use .60 KW/Ton
1700 - 2000 tons use .62 KW/Ton

12901 Nicholson, Suite 260, Dallas, Texas 75234
Telephone (214) 620-8830 • Fax (214) 484-7689



Huitt-Zollars
Ft. Sam Houston Project

R-134a Model YK Tonnage Range 350 - 2100 Tons

| | |
|----------------------|------------|
| 350 - 600 tons use | .62 KW/Ton |
| 600 - 1200 tons use | .58 KW/Ton |
| 1200 - 1700 tons use | .60 KW/Ton |
| 1700 - 2000 tons use | .62 KW/Ton |

- For the Gas Engine Drive Chillers, utilize the R-134a selections (only refrigerant available on CAT Engine Drive Chillers), and use the following:

R-134a Model YG Tonnage Range 400 - 2100 Tons

| |
|---|
| 6.6 MBH per ton (full load) from 350 - 700 Tons |
| 6.2 MBH per ton (full load) above that |

The part load curve will be slightly better than the centrifugal curve, but it will conservatively show the savings offered by gas.

- For the Water Cooled Screw Chillers, the part load curve will also be slightly better than the centrifugal, particularly through the 25% to 50% range. I've attached a "Marked Up" part load curve which should be used for the screw chillers. The full load efficiency base line should be:


R-22 Model YS Tonnage Range 125 - 675 tons, 1000 - 1200 tons

| | |
|--------------------|------------|
| 125 - 200 tons use | .64 KW/Ton |
| 200 - 280 tons use | .62 KW/Ton |
| 280 - 375 tons use | .62 KW/Ton |
| 375 - 675 tons use | .64 KW/Ton |

- For Air Cooled and Water Cooled Reciprocating Chillers, the full and part load points are attached.
- For the Gas Fired Absorption Chillers, utilize the attached curve and 12 MBH per ton for full load energy consumption.

We appreciate your interest in York products. Please feel free to call me if you have any questions.

Sincerely,




Thomas J. McGreal
Systems Consultant

C:\WPWIN60\TOM\SAMHOUST

Water Cooled Screw Chiller

TYPICAL CODEPAK PART LOAD PERFORMANCE*



*Based on 2.4 GPM/Ton of 44°F leaving chilled water temperature; 3 GPM/Ton of condenser water; 0.0005 FF on both circuits.;

AERCO KC Gas Fired Hot Water Boiler System


The AERCO KC Water Boiler is a true industry advance that meets the needs of today's energy and environmental concerns. Designed for application in any closed loop hydronic system, it relates energy input directly to fluctuating system load, yielding *seasonal efficiencies as high as 95%*. The boiler can be used singly or in *modular arrangements for inherent standby with minimum space requirements*. Venting flexibility permits installation without normal restrictions.

The advanced electronics of each boiler module offer selectable modes of operation. The options available include:

- Constant Temperature Internal Setpoint
- Indoor/Outdoor Reset
- 4-20ma Linear Signal Response
- AERCO Boiler Management System Integration
- AERCO Combination Domestic Water/Boiler Plant

Regardless of the mode of operation, the load tracking capability of every unit delivers the ultimate in energy control through energy input modulation with a 14:1 ratio while meeting all load demands.

With condensing capability, the KC Boiler is ideally suited for modern low temperature as well as conventional heating systems. Because of the compact design with direct or conventional venting, the KC Boiler system is applicable to either new construction or retrofit application with the same excellent results. Efficiently, reliability, and longevity make the KC Boiler System a true step forward in heating system design.



KC1000 FEATURES

- Natural Gas or Propane
- 14:1 Turndown Ratio
- Direct Vent or Conventional Vent Capabilities
- ASME 150 PSIG Working Pressure Certified
- UL, ULC Listed, FM Approved, ASME Coded
- UL, ULC Listed for Alcove Installation on Combustible Flooring
- Quiet Operation throughout Firing Range
- Internal Low Water Cutoff and Dual Over Temperature Protection
- Compact Space Efficient Design
- Precise Temperature Control $\pm 2^\circ\text{F}$
- Optional Sealed Combustion

KC-1000 Specifications

| | |
|-------------------------------|---|
| BTU Input | 1,000,000 BTU/Hr† |
| Net Output @ full input | 860,000-915,000 BTU/Hp* |
| ASME Working Pressure | 150 PSIG |
| Electrical Requirement | 120/1/60 20 Amp |
| Gas Requirements | 8.5" W.C. Minimum @ Full Load 14" W.C. Maximum |
| Vent Size | 6" Diameter |
| Water Connections | 4" Flanged 150 lb. ANSI |
| Gas Connection | 1-1/4" NPT |

| | |
|-------------------------------------|-------------------|
| Minimum Water Flow | 25 GPM |
| Maximum Water Flow | 150 GPM |
| Water Pressure Drop | 0.23 Ft. 100 GPM |
| Water Volume | 23 Gallons |
| Control Range | 50F to 220F |
| Standard Listings & Approvals | UL, ULC, FM, ASME |
| Optional Approval | IRI |
| Weight, Installed | 1200 lbs. |

*Output is dependent upon return water temp. and firing rate—see efficiency curves on reverse.

†Up to 2000 Altitude.



AERCO INTERNATIONAL INC.
KC HEATING BOILERS
PERFORMANCE COMPARISON

Case Date: Feb 13, 1995

Project Name:
BOILER JOB 1

Rep Firm: AERCO International, Inc.
Salesperson: Javier Piraneque
Design Firm:

Design Information:

Facility: MILITARY BASE
Square Footage: 000
BIN City Data: DALLAS

Design Heat Loss 2,500,000 BTU/H TYPICAL
Outdoor Design Temp: 10 F FOR ANY
Temp Differential: 20 F LOAD
Supply Water Temp @ Design: 180 F
Indoor Design Temp: 70 F
of KC-1000 Boilers: 3
With an Efficiency of 86.2%

Competition: BURNHAM FIRETUBE
Fuel Consumed: Natural Gas
Its Max Known Thermal Effy: 80.0%

Energy Units Consumption


| Outdoor AirTemp | ASHRAE BIN Hours | BURNHAM Effy % | FIRETUBE Energy | AERCO Boilers Effy % | Energy | Difference Energy Units |
|--------------------|---------------------|-------------------|--------------------|-------------------------|--------|----------------------------|
| 70 | 1,400 | 50.0 | 0 | 93.0 | 0 | 0 |
| 65 | 1,200 | 52.5 | 4,762 | 99.7 | 2,509 | 2,253 |
| 60 | 1,000 | 55.0 | 7,576 | 99.5 | 4,191 | 3,385 |
| 55 | 900 | 57.5 | 9,783 | 98.9 | 5,692 | 4,091 |
| 50 | 800 | 60.0 | 11,111 | 97.9 | 6,816 | 4,295 |
| 45 | 770 | 62.5 | 12,833 | 93.9 | 8,550 | 4,284 |
| 40 | 499 | 65.0 | 9,596 | 91.0 | 6,861 | 2,735 |
| 35 | 350 | 67.5 | 7,562 | 89.6 | 5,699 | 1,863 |
| 30 | 250 | 70.0 | 5,952 | 89.0 | 4,682 | 1,271 |
| 25 | 150 | 72.5 | 3,879 | 88.8 | 3,168 | 711 |
| 20 | 59 | 75.0 | 1,639 | 86.8 | 1,417 | 221 |
| 15 | 30 | 77.5 | 887 | 86.5 | 796 | 91 |
| 10 | 15 | 80.0 | 469 | 86.2 | 435 | 33 |

TOTALS: 76,049 EU 50,817 EU 25,232 EU

If BURNHAM FIRETUBE equipment is selected for this project, the INCREASE in energy usage over Aerco International KC Boilers will be approximately 49.7% MORE per year.

AERCO International reserves the right to revise any information contained within this program in accordance to the written legal agreement as stated in the pages of our users manual dated 5/94

Dimensions KC-1000 Boiler



Ratings and Dimensions


| Modules | Model | Mbh Input | MBH Output | Length | Depth | Height | Weight |
|-----------|-----------|-----------|-----------------|--------|-------|--------|----------|
| | (a) | (b) | (b) (c) | | | | |
| One (1) | KC-1000 | 1000mbh | 860mbh-915mbh | 1'10" | 4'9" | 6'8" | 1200lbs. |
| Two (2) | KC-1000-2 | 2000mbh | 1720mbh-1830mbh | 5'10" | 4'9" | 6'8" | 2400lbs. |
| Three (3) | KC-1000-3 | 3000mbh | 2580mbh-2745mbh | 9'8" | 4'9" | 6'8" | 3600lbs. |
| Four (4) | KC-1000-4 | 4000mbh | 3440mbh-3660mbh | 13'6" | 4'9" | 6'8" | 4800lbs. |
| Five (5) | KC-1000-5 | 5000mbh | 4300mbh-4575mbh | 17'4" | 4'9" | 6'8" | 6000lbs. |
| Six (6) | KC-1000-6 | 6000mbh | 5160mbh-5490mbh | 21'2" | 4'9" | 6'8" | 7200lbs. |
| Seven (7) | KC-1000-7 | 7000mbh | 6020mbh-6405mbh | 25' | 4'9" | 6'8" | 8400lbs. |
| Eight (8) | KC-1000-8 | 8000mbh | 6880mbh-7320mbh | 28'10" | 4'9" | 6'8" | 9600lbs. |

(a) Style to be Determined by Individual Application Requirement


(b) Altitude below 2,000'. Apply Altitude Correction Factor above 2,000.

(c) Output dependent upon application-see efficiency curves.

Efficiency Curves



Programmable Modes of Operation



Represented by:

GFB-1 BBC 08/93 5M

HEAT EXCHANGES • WATER HEATERS • BOILERS


CONTROL VALVES • STEAM GENERATORS

AERCO


HOT WATER SYSTEMS

AERCO INTERNATIONAL, INC. • 159 PARIS AVE., P.O. BOX 128
NORTHVALE, N.J. 07647-0128 • (201) 768-2400 • FAX 201-768-7789


Series H hydronic boilers are packaged compact outdoor and slimline indoor units that fit in smaller places than conventional boilers—and do it without compromising or sacrificing performance. They are ideal for installation in multiples to meet almost any volume needs.



Type HQ
Indoor



Type HJ
Outdoor



Type HK
Indoor version shown.
Available with
vent cap for
outdoor use

 **TELEDYNE LAARS**

Dimensions and Technical Data

Series H copper tube hydronic boilers are designed for closed system heating applications. All models are design-certified by AGA for natural or propane gas.
Note: Two-stage with outdoor reset available.

| Model | Boiler Ratings' Natural & Propane Gas | | | Gas Connection' | | | | | Air' Supply (Sq. Ft.) | Dimensions'—see drawings below | | | | | | | Water Piping Conn. | Ship- ping Wt. |
|-------|--|-----------------------------------|------------------------------------|--------------------------|------|------------------------|------|-------------------------|-----------------------------|--------------------------------|-----|-----|-----|-------------|------------------------------|-----------------------------|--------------------------|----------------------|
| | BTU Input x 1000 | BTU Output x 1000 Indoor | BTU Output x 1000 Outdoor | Mechanical Modulation | | On/Off or Two Stage | | Motorized Modulation | | A | B | C | D | V (Dia.) | Indoor Draft Hood G | Outdoor Vent Cap H | | |
| | | | | Nat. | Pro. | Nat. | Pro. | | | | | | | | | | | |
| 250 | 250 | 200 | 188 | ¾ | ½ | — | — | — | .5 | 22½ | 32½ | 15½ | 11½ | 7 | 27 | 23 | 2 | 251 |
| 325 | 325 | 260 | 244 | ¾ | ½ | — | — | — | .6 | 26¾ | 36½ | 17½ | 11¾ | 8 | 27¾ | 23½ | 2 | 316 |
| 400 | 400 | 320 | 300 | ¾ | ½ | — | — | — | .8 | 31¾ | 41½ | 20½ | 11¾ | 9 | 29¾ | 26½ | 2 | 371 |
| 500 | 500 | 400 | 375 | — | — | 1 | ¾ | 1 | .9 | 30½ | 36½ | 20 | 6 | 10 | — | — | 2 | 407 |
| 625 | 625 | 500 | 469 | — | — | 1 | ¾ | 1 | 1.0 | 36½ | 42½ | 23 | 7 | 12 | — | — | 2 | 562 |
| 750 | 750 | 600 | 563 | — | — | 1 | ¾ | 1½ | 1.3 | 42½ | 48½ | 25½ | 8 | 14 | — | — | 2 | 603 |
| 925 | 925 | 740 | 694 | — | — | 1 | 1 | 1½ | 1.6 | 50½ | 56½ | 30 | 8 | 14 | — | — | 2 | 798 |
| 1100 | 1100 | 880 | 825 | — | — | 1½ | 1 | 1½ | 1.9 | 58½ | 64½ | 34½ | 9 | 16 | — | — | 2½ | 863 |
| 1266 | 1266 | 1013 | 950 | — | — | 1½ | 1 | 1½ | 2.0 | 66½ | 72½ | 38 | 9 | 16 | — | — | 2½ | 933 |
| 1466 | 1466 | 1173 | 1100 | — | — | 1½ | 1½ | 1½ | 2.5 | 76 | 81½ | 42½ | 10 | 18 | — | — | 2½ | 1004 |
| 1666 | 1666 | 1333 | 1250 | — | — | 1½ | 1½ | 1½ | 2.9 | 85½ | 91½ | 47½ | 10 | 18 | — | — | 2½ | 1146 |

Boiler standard with 2-stage firing on Models 500 through 1666.


Notes:

- All dimensions nominal. Dimensions not shown in table are given in drawings below. Where measurements are critical request certified drawing.
- The design of all models has been certified by AGA for natural and propane gases.
All models conform to ASME Boiler Code for 160 PSI working pressure.
Derate propane ratings for outdoor boilers by 10%.


Derate BTU input and output 4% for every 1000 ft. installation is above sea level. No derating necessary up to 2000 ft. elevation. Ex. At 4000 ft. elevation derate BTU input and output 16%.

For other boiler ratings:
IBR Net BTU = $\frac{\text{Output}}{1.15}$
EDR (Sq. Ft.) = $\frac{\text{Output}}{150}$
IBR (Sq. Ft.) = $\frac{\text{Net IBR BTU}}{150}$


- Area indicated is for each of two openings, one at floor and one at ceiling, communicating directly through a wall to outside air. For all other conditions refer to American National Standards Bulletin Z223.1—1974 Section 1.3.4.
Check tower manufacturers for Net Free Area of tower. Correct screen resistance to net Free Area screen used.
- Size shown is the connection at the boiler. For correct sizing of the gas supply piping and gas supply pressure see Document 1010.



Type HK
Indoor/Outdoor
Stacktop
250-400



Type HJ
Outdoor Only
500-1666



Type HQ—Slimline
Integral Draft Hood
Indoor Only
500-1666